

LEE COUNTY ORDINANCE NO. 75-5

AN ORDINANCE RELATING TO ALCOHOLIC BEVERAGES; REPEALING SPECIAL ACT, LAWS OF FLORIDA, CHAPTER 18651 (1937); REPEALING THE COMPLIANCE REQUIRED; REPEALING THE APPLICATION FOR LICENSE REQUIRED FOR SALES FOR CONSUMPTION ON THE PREMISES; REPEALING THE PETITION OF ELECTORS TO ACCOMPANY APPLICATIONS AND REQUIREMENTS FOR PETITION; REPEALING THE CONTENTS OF APPLICATION AND ACTION BY COUNTY; REPEALING THE POWERS OF MUNICIPALITIES IN COUNTY; REPEALING THE RESTRICTIONS ON PERSONS SELLING ALCOHOLIC BEVERAGES IN MUNICIPALITIES; REPEALING THE CERTAIN WINES EXCEPTED FROM PROVISIONS; AND PROVIDING FOR AN EFFECTIVE DATE.

BE IT ORDAINED BY THE BOARD OF COUNTY COMMISSIONERS OF LEE COUNTY, FLORIDA:

SECTION 1. REPEALED LAW

THAT PART OF FLORIDA LAWS, CHAPTER 18651 §1 KNOWN AS §4-11 OF CODE OF LAWS AND ORDINANCE OF LEE COUNTY, FLORIDA, RELATING TO THE COMPLIANCE REQUIRED, IS HEREBY REPEALED,

SECTION 2. REPEALED LAW

THAT PART OF FLORIDA LAWS, CHAPTER 18651 §2 KNOWN AS §4-12 OF CODE OF LAWS AND ORDINANCE OF LEE COUNTY, FLORIDA, RELATING TO THE APPLICATION FOR LICENSE REQUIRED FOR SALES FOR CONSUMPTION ON THE PREMISES, IS HEREBY REPEALED.

SECTION 3. REPEALED LAW

THAT PART OF FLORIDA LAWS, CHAPTER 18651 §3 KNOWN AS §4-13 OF CODE OF LAWS AND ORDINANCE OF LEE COUNTY, FLORIDA, RELATING TO THE PETITION OF ELECTORS TO ACCOMPANY APPLICATION AND THE REQUIREMENTS FOR PETITION, IS HEREBY REPEALED.

SECTION 4. REPEALED LAW

THAT PART OF FLORIDA LAWS, CHAPTER 18651 §4 KNOWN AS §4-14 OF CODE OF LAWS AND ORDINANCE OF LEE COUNTY, FLORIDA, RELATING TO THE CONTENTS OF APPLICATION AND ACTION BY THE COUNTY, IS HEREBY REPEALED.

SECTION 5. REPEALED LAW

THAT PART OF FLORIDA LAWS, CHAPTER 18651 §5 KNOWN AS §4-15 OF CODE OF LAWS AND ORDINANCE OF LEE COUNTY, FLORIDA, RELATING TO THE POWER OF MUNICIPALITIES IN COUNTY, IS HEREBY REPEALED.

SECTION 6. REPEALED LAW

THAT PART OF FLORIDA LAWS, CHAPTER 18651 §6 KNOWN AS §4-16 OF CODE OF LAWS AND ORDINANCE OF LEE COUNTY, FLORIDA, RELATING TO THE RESTRICTIONS ON PERSONS SELLING ALCOHOLIC BEVERAGES IN MUNICIPALITIES, IS HEREBY REPEALED.

SECTION 7. REPEALED LAW

THAT PART OF FLORIDA LAWS, CHAPTER 18651 §7 KNOWN AS §4-17 OF CODE OF LAWS AND ORDINANCE OF LEE COUNTY, FLORIDA, RELATING TO CERTAIN WINES EXCEPTED FROM PROVISIONS, IS HEREBY REPEALED.

SECTION 8. EFFECTIVE DATE

THIS ORDINANCE TAKES EFFECT IMMEDIATELY UPON RECEIPT OF THE OFFICIAL ACKNOWLEDGMENT FROM THE OFFICE OF THE SECRETARY OF STATE OF FLORIDA THAT THIS ORDINANCE HAS BEEN FILED WITH SAID OFFICE.


DULY PASSED AND ADOPTED THIS 26TH DAY OF MARCH, 1975.

ATTEST:
SAL GERACI, CLERK

BY Bretchen Young
DEPUTY CLERK

BOARD OF COUNTY COMMISSIONERS
LEE COUNTY, FLORIDA

BY James Sweeney, Jr.
JAMES M. SWEENEY, JR.,
CHAIRMAN



Approved as to Form & Legal Sufficiency
Office of the County Attorney

By James G. Geiger
28 March 1975

LEE COUNTY ORDINANCE NO. 76-9

AN ORDINANCE ENTITLED: AN ORDINANCE ESTABLISHING AND REGULATING THE HOURS FOR THE SALE, CONSUMPTION, SERVICE OR PERMITTING TO BE SERVED, OF ALCOHOLIC BEVERAGES AND INTOXICATING LIQUORS WITHIN THE UNINCORPORATED AREA OF LEE COUNTY BY PLACES HOLDING A LICENSE UNDER THE STATE BEVERAGE DEPARTMENT OF FLORIDA; PROVIDING THAT NO ALCOHOLIC BEVERAGES OR INTOXICATING LIQUORS OF ANY KIND MAY BE SOLD, CONSUMED, SERVED, OR PERMITTED TO BE SERVED OR CONSUMED DURING THE WEEK HOURS (TO INCLUDE SUNDAYS) OF 2:00 A.M. AND 7:00 A.M. OF THE SAME DAY; PROVIDING FOR THE PROHIBITION OF THE ON-PREMISE CONSUMPTION OF ALCOHOLIC BEVERAGES OF ANY KIND WITHIN FIVE HUNDRED (500') FEET OF A CHURCH OR SCHOOL UNLESS A SPECIAL PERMIT IS FIRST OBTAINED; PROVIDING A STANDARD TO MEASURE THE FIVE HUNDRED (500') FEET DISTANCE REQUIREMENT; PROVIDING FOR THE REPEAL OF ANY ORDINANCE OR RESOLUTION IN CONFLICT HEREWITH, REPEALING A 2,500 FEET REQUIREMENT FROM A CHURCH OR SCHOOL; PROVIDING FOR CIVIL AND CRIMINAL PENALTIES; PROVIDING AN EFFECTIVE DATE.

WHEREAS, Florida Statutes 125(0) allows county governments to establish and enforce regulations for the sale of alcoholic beverages in the unincorporated areas of the county, pursuant to general law; and,

WHEREAS, the Board of County Commissioners of Lee County, Florida, has determined that it will be in the best interest, public safety and welfare of the citizens of Lee County, Florida, to have uniform hours in which alcoholic beverages and intoxicating liquors may be sold, consumed or served, or permitted to be served or consumed.

NOW, THEREFORE, BE IT RESOLVED BY THE BOARD OF COUNTY COMMISSIONERS OF LEE COUNTY, FLORIDA, that:

SECTION ONE.

No alcoholic beverage or intoxicating liquor of any

kind shall be sold, consumed or served, or permitted to be served or consumed, in any place holding a license under the State Beverage Department of Florida within the unincorporated area of the county, except during the following hours:

All places or establishments within the unincorporated area of the county and lawfully licensed by the State Beverage Department of Florida, may sell or serve, or permit to be sold, served or consumed, any type of alcoholic beverage of any kind whatsoever for consumption both on or off the premises only during the hours of 7:00 a.m. and 2:00 a.m. of the following morning every day of the week, including Sundays.

SECTION TWO.

The on-premise consumption of alcoholic beverages of any kind is prohibited within Five Hundred (500') feet of a church or school, unless a special permit allowing such on-premise consumption is first obtained from the Board of County Commissioners.

The Five Hundred (500') feet requirement within which a special permit is required hereunder shall be measured from the main entrance of the establishment desiring to have on-premise consumption of alcoholic beverages and the main entrance of the church or school.

SECTION THREE.

All ordinances, resolutions or reports of ordinances and resolutions in conflict herewith are hereby repealed. A resolution which prohibited the on-premise consumption of alcoholic beverages of any kind within 2,500 feet of a church or school is hereby repealed.

SECTION FOUR.

It is intended that if any section, sub-section, sentence, clause or provision contained herein is held invalid, the remainder shall not be affected.

SECTION FIVE.

PENALTIES

Any person convicted of violation of any of the provisions of this Ordinance shall be punished by a fine not to exceed Five Hundred (\$500.00) Dollars or by imprisonment in the County Jail for a period not to exceed sixty (60) days, or both, such fine and imprisonment for each such offense.

SECTION SIX.

The Board of County Commissioners may institute in any Court of competent jurisdiction action to prevent, restrain, correct or abate any violation of this ordinance or of any order or regulation made in connection with its administration or enforcement, and the Court shall adjudge to the Plaintiff such relief by way of injunction or otherwise, to include mandatory injunction, as may be proper under all the facts and circumstances of the case in order to fully effectuate the ordinance and regulations made pursuant thereto.

SECTION SEVEN.

EFFECTIVE DATE.

A certified copy of this ordinance shall be filed in the office of the Secretary of State by the County Administrator within ten (10) days after enactment, and this Ordinance shall take effect upon receipt of an official acknowledgement from that office that this ordinance has been filed.


DONE AND ADOPTED in regular session this 16th day of June, A. D. 1976.

ATTEST:
SAL GERACI, CLERK

BOARD OF COUNTY COMMISSIONERS
OF LEE COUNTY, FLORIDA

By: Mary Amenthornt
Deputy Clerk

By: L. H. Whan
L. H. "Bob" Whan,
Chairman



APPROVED AS TO FORM
& LEGAL SUFFICIENCY

By: James G. Yeager
OFFICE OF COUNTY CLERK
June 21, 1976

LEE COUNTY ORDINANCE NO. 79-1

AN ORDINANCE ENTITLED: AN ORDINANCE AMENDING LEE COUNTY ORDINANCE NO. 76-9, AS CONTAINED IN THE LEE COUNTY CODE, SEC. 4-2; RELATING TO THE SALE, CONSUMPTION AND SERVICE OF ALCOHOLIC BEVERAGES; RELATING TO SPECIAL PERMITS FOR ON-PREMISE CONSUMPTION OF ALCOHOLIC BEVERAGES AND PROHIBITION OF SAME WITHIN 500 FEET OF A CHURCH OR SCHOOL AND PROVIDING FOR MEASUREMENT CRITERIA FOR SAID DISTANCES; AMENDING THE MEASUREMENT REQUIREMENT TO PROVIDE SAME ON A STRAIGHT-LINE FROM THE MAIN ENTRANCE OF ON-PREMISE CONSUMPTION ESTABLISHMENT TO THE PROPERTY LINE OF CHURCH OR SCHOOL, PROVIDING FOR AN EFFECTIVE DATE.

NOW, THEREFORE, BE IT RESOLVED BY THE BOARD OF COUNTY COMMISSIONERS OF LEE COUNTY, FLORIDA:

SECTION ONE

Sec. 4-2(b) of the Code of Ordinances of Lee County, Florida, as it pertains to Ordinance No. 76-9, Section Two is hereby amended to read as follows:

(b) The on-premise consumption of alcoholic beverages of any kind is prohibited within five hundred feet (500') of a church or school, unless a special permit allowing such on-premise consumption is first obtained from the Board of County Commissioners. The five hundred feet (500') requirement within which a special permit is required hereunder shall be measured by a straight-line from the main entrance of the establishment desiring to have on-premise consumption of alcoholic beverages and the nearest property line of a church or school.

SECTION TWO

Except as amended above, all other sections and provisions of Ordinance No. 76-9 as codified in Sec. 4-2 of the Code of ordinances of Lee County, Florida, shall remain in full force and effect.

SECTION THREE

EFFECTIVE DATE

A certified copy of this ordinance shall be filed in the office of the Secretary of State by the County Administrator within ten (10) days after enactment, and this Ordinance shall take effect upon receipt of an official acknowledgment from that office that this ordinance has been filed.

DONE AND ADOPTED in regular session this 24th day of January, A.D. 1979.

ATTEST:
SAL GERACI, CLERK

BOARD OF COUNTY COMMISSIONERS
OF LEE COUNTY, FLORIDA

By: Mary Ammendt
Deputy Clerk

By: X.L. Steele
Chairman



APPROVED AS:
TO FORM
BY: James Gager
COUNTY ATTORNEY

LEE COUNTY ORDINANCE NO. 80-4

AN EMERGENCY ORDINANCE PROHIBITING THE COUNTY PERMIT APPROVAL OF ALL NEW ON-PREMISE CONSUMPTION OF ALCOHOLIC BEVERAGES WITHIN ALL COMMERCIAL ZONING CLASSIFICATIONS; DECLARING A PUBLIC EMERGENCY EXISTS, PROVIDING SEVERABILITY; PROVIDING FOR A VARIANCE; PROVIDING EFFECTIVE DATE.

WHEREAS, the Board of County Commissioners is concerned about the increasing number of premises providing the sale of alcoholic beverage for consumption on-premise in commercially-zoned properties; and;

WHEREAS, the present permitted sale of alcoholic beverages for consumption on the premises in commercially zoned areas detracts from the enjoyment of surrounding residential uses and such use may not be compatible with surrounding land uses and the criteria established in Lee County Zoning Ordinance Section 402.1(e)(2); and,

WHEREAS, the Board of County Commissioners has established the date of February 28, 1980 for a public hearing to discuss the Amendment, Section 500.5(b) to amend the Lee County Zoning Ordinance to require the sale of alcoholic beverages and consumption on the premises to be allowed only as a special exception in the zoning districts rather than as a permitted use; and,

WHEREAS, the continued permitting of on-premise consumption of alcoholic beverages without meeting the Zoning criteria of Section 402.1(e)(2) of the Lee County Zoning Ordinance constitutes a public emergency threatening the health, welfare and safety of the citizens of Lee County.

NOW, THEREFORE, BE IT ORDAINED BY THE BOARD OF COUNTY COMMISSIONERS OF LEE COUNTY, FLORIDA:

SECTION ONE

The foregoing recitation is hereby incorporated into this ordinance.

SECTION TWO

The County issuance and approval of all newly applied for State alcoholic beverage permits for the sale of alcoholic beverages for consumption on the premises within all commercial zones is hereby prohibited except as provided in Section Five.

SECTION THREE

If any section, subsection, sentence, clause or provision of this ordinance is held invalid, the remainder of this ordinance shall not be affected by such invalidity.

SECTION FOUR

This ordinance is passed as an emergency measure and the Board does by the vote by which this ordinance is passed, hereby declare that an emergency exists, which makes it imperative that this ordinance shall become effective forthwith in order that the public health, welfare and safety might most effectively be provided for. The Notice requirements of Section 125.66, Fla. Sta., are hereby waived.

SECTION FIVE

The requisite County approval of State alcoholic beverage permits for the sale of alcoholic beverages for consumption on the premises within commercially-zoned properties as now exist within Lee County may be obtained upon the granting of a variance from Section Two of this Ordinance by the Board of County Commissioners. The Board of County Commissioners shall consider whether:

- A. The special conditions and circumstances that exist which involve a hardship to the Applicant.
- B. The request for the on-premise consumption permit approval is compatible with surrounding land uses and otherwise meet the applicable provisions of Lee County Zoning Ordinance Section 402.1(e)(2).
- C. The Division of Community Development has reviewed the request.

SECTION SIX

A certified copy of this ordinance shall be filed in the Office of the Department of State by the Clerk of the Board of County Commissioners as soon after enactment by the Board as is practicable. Such filing shall be accomplished by depositing such certified copy of this ordinance with postal authorities of the Government of the United States, for special delivery by registered mail, to the Department of State and this ordinance shall take effect when such copy has been so accepted by the postal authorities of the Government of the United States and shall remain in full force and effect until the earlier of either February 28, 1980 or the effective date of Lee County Ordinance Amendment pertaining hereto adopted by the Board of County Commissioners of Lee County, at which time it shall be deemed repealed.

DULY PASSED AND ADOPTED this 23rd day of January, 1980.

ATTEST:
SAL GERACI, CLERK

BOARD OF COUNTY COMMISSIONERS
OF LEE COUNTY, FLORIDA

By: Louis Kurtz
Deputy Clerk

By: T. L. Steele
Chairman



APPROVED AS
TO FORM
BY James Yeager
COUNTY ATTORNEY

AN ORDINANCE AMENDING THE LEE COUNTY ZONING REGULATIONS, GENERAL PROVISIONS SECTION 500.5.B. ALCOHOLIC BEVERAGES, CONSUMPTION ON THE PREMISES AND AMENDING THE LEE COUNTY ZONING REGULATIONS SECTION 500.29 SUBSECTION D.3., SETBACKS FROM SECTION LINES VARIANCE; PROVIDING FOR SEVERABILITY; PROVIDING FOR AN EFFECTIVE DATE.

BE IT ORDAINED BY THE BOARD OF COUNTY COMMISSIONERS OF LEE COUNTY, FLORIDA, THAT:

SECTION ONE

Section 500.5.B., Alcoholic Beverages Relating to Consumption on the Premises, of the Lee County Zoning Regulations, is amended to read:

B. CONSUMPTION ON THE PREMISES.

The sale of alcoholic beverages for consumption on the premises shall be allowed only as a ~~special exception~~ special permit issued by the Board of County Commissioners in Zoning Districts classified as:

- CC COMMUNITY COMMERCIAL
 - CT TOURIST COMMERCIAL
 - CG GENERAL COMMERCIAL
 - CS SPECIALIZED COMMERCIAL
 - CM-1 MARINE COMMERCIAL
 - CM-2 MARINE COMMERCIAL
 - C 1A COMMERCIAL DISTRICT
 - C-1 COMMERCIAL DISTRICT
 - C-2 COMMERCIAL DISTRICT
 - RM2 RESIDENTIAL MULTIPLE FAMILY DISTRICT-
- Consumption on the premises shall be permitted only in restaurants or lounges in RM2 districts which were converted pursuant to Section 600 from a zoning classification which permitted same and only where said facility was in existence upon the effective date of the Lee County Zoning Regulations or where a commercial use such as a lounge or restaurant is granted a special exception in RM-2, and subject to all of the limitations and regulations of the zoning districts in which the use is located, and further subject to the property owner or his agent being granted a special permit issued by the Board of County Commissioners or its designee, pursuant to the following:

- (a) Appropriate application to the Board of County Commissioners or its designee,
- (b) Advertisement on the County Agenda of said application,
- (c) Appearance at a regularly scheduled meeting of said Board by the property owner or his agent.

SECTION TWO

Section 500.29, Subsection D.3., is amended to read as follows:

D. SETBACKS FROM SECTION LINES.

1. Setbacks from section lines shall be a minimum of seventy-five (75) feet.
2. Setbacks from half section lines shall be a minimum of sixty (60) feet.
3. Variance. ~~(See Section 401.6)~~ A variance from these setbacks may be granted from the Board of County Commissioners of Lee County, Florida, pursuant to:
 - (a) Appropriate application to the Board of County Commissioners, or its designee.
 - (b) Advertisement on the County Agenda of said application.
 - (c) Appearance at a regularly scheduled meeting of said Board by the property owner or his agent.

SECTION THREE - SEVERABILITY

It is declared to be the legislative intent that if any section, subsection, sentence, clause or provision of this ordinance is held invalid, the remainder of the ordinance shall not be affected.


SECTION FOUR - EFFECTIVE DATE

The provisions of this ordinance shall become effective as prescribed by law.

DULY PASSED AND ADOPTED this 23rd day of September, 1981.

ATTEST:

SAL GERACI, CLERK

BOARD OF COUNTY COMMISSIONERS
OF LEE COUNTY, FLORIDABy: *Ernest C. Wall*
Vice- ChairmanBy: *Sal Geraci*
Deputy Clerk

Approved
James Greger

TOWN OF FORT MYERS BEACH
ORDINANCE NO. 96-05

AN ORDINANCE OF THE TOWN OF FORT MYERS BEACH,
FLORIDA, TO BE KNOWN AS THE TOWN OF FORT MYERS
BEACH OPEN ALCOHOLIC BEVERAGE CONTAINER
ORDINANCE; PROVIDING AUTHORITY; TITLE AND
CITATION; DEFINITIONS; CONSUMPTION OR
POSSESSION OF ALCOHOLIC BEVERAGES ON A
SEMI-PUBLIC PARKING LOT, PUBLIC WAY PARKING
LOT, OR BEACH; EXEMPTIONS; SEVERABILITY;
REPEALING CLAUSE; AND EFFECTIVE DATE.

IT IS HEREBY ORDAINED BY THE TOWN OF FORT MYERS BEACH, FLORIDA as follows:

SECTION ONE: Authority

This Ordinance is enacted pursuant to the provisions of Chapter 95-494, Laws of Florida, Chapter 166, Florida Statutes, and other applicable provisions of law.

SECTION TWO: Title and Citation

This ordinance shall be known and cited as the "Town of Fort Myers Beach Open Alcoholic Beverage Container Ordinance"

SECTION THREE: Definitions

For the purpose of this Ordinance the following terms, phrases, words and their derivations shall have the meaning given herein. When not inconsistent with the context, words used in the present tense include the future, words in the plural include the singular and words in the singular include the plural. The words "shall" and "will" are mandatory and not discretionary.

A. "Alcoholic beverages" shall mean all beverages containing more than one percent (1%) of alcohol by weight.

B. "Semi-public parking lot" shall include any area wherein motor vehicles are parked by the public in conjunction with any business, enterprise, commercial establishment, office building, or apartment building.

C. "Package " shall include, but is not limited to, any can, bottle, carton, or other container of alcoholic beverages.

D. "Public beach" shall mean any beach which (1) is below the mean high water lines; or (2) is owned by the Town or Lee County; or (3) has arisen upon it a right of customary use by the public; or (4) has arisen upon it a public easement, prescriptive or otherwise; or (5) is the fore shore of tidal navigable waters, that is the land

between the high and low water marks, and is owned by the State of Florida.

SECTION FOUR: Consumption or Possession of Alcoholic Beverages on a Semi-public Parking Lot, Public Way Parking Lot, or Beach

It shall be unlawful and punishable as provided herein to:

A. Drink or consume any alcoholic beverage on a semi-public parking lot, or a public street, sidewalk, parkway, beach, or parking lot located in the Town of Fort Myers Beach.

B. Transport, carry, or possess any alcoholic beverage, except in the original package and with the seal unbroken, on a semi-public parking lot, or a public street, sidewalk, parkway, beach, or parking lot located in the Town of Fort Myers Beach.

C. Possess an open container of an alcoholic beverage while operating a vehicle or while a passenger in or on a vehicle being operated.

SECTION FIVE: Exemptions

This ordinance shall not apply to:

A. Any person engaged in picking up empty beverage containers for the purpose of collecting the deposit or value of the bottle or can itself, nor to any person taking part in a litter control campaign;

B. The transportation of any open container of alcoholic beverage by any licensed distributor or licensed vendor of alcoholic beverages provided that such alcoholic beverage is being transported solely for commercial purposes;

C. Any wine in the possession of a minister, pastor, priest or rabbi which is to be used solely during religious services;

D. The transportation of any open container of alcoholic beverage in any motor vehicle provided that such container is in a compartment of the vehicle such as a locked glove compartment, trunk, container or other non-passenger area of the motor vehicle;

E. Any carrier which has a valid license to sell alcoholic beverages issued by the State of Florida.

SECTION SIX: Penalty

Any person convicted of violation of SECTION THREE, Subsection A. or B. of this Ordinance shall be punished by a fine not to exceed Five Hundred Dollars (\$500.00) or by imprisonment in the County Jail for a period not to exceed sixty (60) days, or both, such fine and imprisonment for each such offense.

Any person who violates any of the provisions of SECTION THREE, Subsection C. of this ordinance shall be guilty of a non-criminal moving traffic violation as provided by Florida Statute Section 316.193.

SECTION SEVEN: Severability

If any one of the provisions of this ordinance should be held contrary to any express provision of law of contrary to the policy of express law, although not expressly prohibited, or against public policy, or shall for any reason whatsoever be held invalid, then such provision shall be null and void and shall be deemed separate from the remaining provisions of this ordinance, and in no way affect the validity of all other provisions of this ordinance.

SECTION EIGHT: Repealing Clause

All ordinances or parts thereof in conflict with the provisions herein contained are, to the extent of such conflict, hereby superseded and repealed.

SECTION NINE: Effective Date

This ordinance shall become effective September 30, 1996.

The foregoing ordinance was enacted by the Town Council upon a motion by Council Member CERECEDA and seconded by Council Member Reynolds and, upon being put to a

vote, the result was as follows:

Anita T. Cereceda	<u>aye</u>
Ted FitzSimons	<u>aye</u>
William (Rusty) Isler	<u>aye</u>
Garr Reynolds	<u>aye</u>
Ray Murphy	<u>aye</u>

DULY PASSED AND ENACTED this 1st day of July, 1996.

ATTEST:

By: Marsha Segal-George
Marsha Segal-George, Town Clerk

TOWN OF FORT MYERS BEACH

By: Anita T. Cereceda
Anita T. Cereceda, Mayor

Approved as to form by:

Richard V.S. Roosa
Richard V.S. Roosa, Town Attorney

LEE COUNTY ORDINANCE NO. 96-08

A REVISER'S ORDINANCE AMENDING APPLICABILITY AND JURISDICTIONAL EFFECTIVENESS OF STATED LEE COUNTY ORDINANCES; PROVIDING THAT CERTAIN LEE COUNTY ORDINANCES SHALL BE APPLICABLE TO AND BE EFFECTIVE WITHIN THE TOWN LIMITS OF THE TOWN OF FORT MYERS BEACH, FLORIDA; AMENDING THOSE LEE COUNTY ORDINANCES TO PROVIDE APPLICABILITY TO AND EFFECTIVENESS WITHIN THE TOWN OF FORT MYERS BEACH RESPECTIVELY, TO-WIT: LEE COUNTY ORDINANCE NO. 75-09, AS AMENDED BY LEE COUNTY ORDINANCES NO. 76-09 AND 79-01, RELATING TO THE SALE, CONSUMPTION AND SERVICE OF ALCOHOLIC BEVERAGES AND THE EXPOSURE OF PRIVATE PARTS OR FEMALE BREASTS IN AN ESTABLISHMENT AT WHICH ALCOHOLIC BEVERAGES ARE OFFERED FOR SALE OR CONSUMPTION ON THE PREMISES; LEE COUNTY ORDINANCE NO. 84-01, AS AMENDED BY LEE COUNTY ORDINANCES NO. 84-11 AND 93-06, RELATING TO THE PROHIBITION OF ANY PERSON FROM TRANSPORTING, CARRYING OR POSSESSING ALCOHOLIC BEVERAGES IN AN OPEN CONTAINER; LEE COUNTY ORDINANCE NO. 90-51, AS AMENDED BY LEE COUNTY ORDINANCES NO. 90-63 AND 91-16, RELATING TO VESSEL CONTROL AND WATER SAFETY, AREAS OF ENFORCEMENT, PROHIBITED WATER ACTIVITY AND PERSONAL WATERCRAFT RENTALS AND FLOATING VENDOR'S REGULATIONS; LEE COUNTY ORDINANCE NO. 90-03, AS AMENDED BY LEE COUNTY ORDINANCE 91-24, RELATING TO THE ESTABLISHMENT AND ENFORCEMENT OF THE WATER SHORTAGE PLAN; LEE COUNTY ORDINANCE 95-14, RELATING TO RECONSTRUCTION AND MITIGATION ACTIVITIES FOLLOWING A MAJOR OR CATASTROPHIC DISASTER; LEE COUNTY ORDINANCE NO. 88-24, RELATING TO MINIMUM STANDARDS OF HYGIENE FOR FOOD ESTABLISHMENTS AND FOOD VENDORS; LEE COUNTY ORDINANCE NO. 91-01, RELATING TO MANDATORY CONNECTION OF ON-SITE SEWAGE DISPOSAL SYSTEMS TO WASTEWATER COLLECTION SYSTEMS; LEE COUNTY ORDINANCE NO. 93-10, RELATING TO REMOVAL OF RECYCLABLE MATERIALS FROM COUNTY CONTAINERS FOR COLLECTION; LEE COUNTY ORDINANCE NO. 93-23, RELATING TO NUISANCE GRASSES AND WEEDS AND ENFORCING AUTHORITY; LEE

COUNTY ORDINANCE NO. 93-39, RELATING TO THE REGULATION AND DISPOSAL OF GARBAGE, REFUSE, TRASH, RUBBISH, LOST OR ABANDONED PROPERTY OR INOPERABLE VEHICLES, PROHIBITIONS ON DUMPING AND PROVIDING FOR REMOVAL; LEE COUNTY ORDINANCE NO. 95-08, AS AMENDED BY LEE COUNTY ORDINANCE NO. 95-19, RELATING TO GARBAGE AND SOLID WASTE COLLECTION AND DISPOSAL, CREATING MANDATORY SOLID WASTE COLLECTION AND DISPOSAL UNITS FOR SERVICE AREA, PROVIDING FOR RESIDENTIAL AND COMMERCIAL COLLECTION AND DISPOSAL, MANDATING SERVICES AND PAYMENT, LEVYING SPECIAL ASSESSMENTS AND COLLECTION; LEE COUNTY ORDINANCE NO. 95-10, AS AMENDED BY LEE COUNTY ORDINANCE NO. 95-20, RELATING TO LEE COUNTY GARBAGE AND SOLID WASTE DISPOSAL FACILITIES, CREATING A MUNICIPAL SERVICE BENEFIT UNIT WITHIN LEE COUNTY FOR COMMERCIAL SOLID WASTE SERVICE CUSTOMER DISPOSAL FACILITIES COSTS, ESTABLISHING THE GOVERNING BODY WITH POWERS AND DUTIES, LEVYING CERTAIN SPECIAL ASSESSMENTS FOR COSTS OF LEE COUNTY SOLID WASTE DISPOSAL FACILITIES FROM COMMERCIAL SOLID WASTE SERVICE PROPERTIES; LEE COUNTY ORDINANCE NO. 91-07, REGULATING SOLID WASTE TRANSPORTATION, REGULATION AND ENFORCEMENT; LEE COUNTY ORDINANCE NO. 88-54, RELATING TO ESCORT SERVICE BUSINESSES, DISCLOSURES AND PERMIT; LEE COUNTY ORDINANCE NO. 85-07, AS AMENDED BY LEE COUNTY ORDINANCE 88-17, RELATING TO THE LICENSING OF TRANSIENT MERCHANTS, PROHIBITIONS, PERMIT CRITERIA, REVIEW BOARD CREATION AND INVESTIGATION, CURRENT COMMERCIAL USE OF RIGHTS-OF-WAY; LEE COUNTY ORDINANCE NO. 94-32, RELATING TO THE SALE OF FIREWORKS, PROHIBITING FIREWORKS FROM BEING DISTRIBUTED, STORED OR SOLD AT ROADSIDE STANDS, PROVIDING FOR OUTDOOR DISPLAYS; LEE COUNTY ORDINANCE NO. 95-13, RELATING TO PERSONAL WATERCRAFT RENTAL VENDOR AND PARASAILING LICENSE, RELATING TO THE UNLICENSED RENTAL OF PERSONAL WATERCRAFT OR PARASAILING, PROVIDING FOR FEES, LICENSE AND LICENSE CONDITIONS, AREAS AND MEANS OF ENFORCEMENT; LEE COUNTY ORDINANCE

91-29, RELATING TO UNIFORM TRAFFIC CONTROL, COUNTY PARKING REGULATIONS, PROHIBITED VEHICULAR ACTIVITIES IN SPECIFIED PLACES, DISABLED PERSONS PARKING, POSTING OF SIGNS, VIOLATIONS AND ENFORCEMENT; LEE COUNTY ORDINANCE NO. 94-27, PERTAINING TO THE TOWING OF VEHICLES PARKED ON PRIVATE PROPERTY, TOWING AND REMOVAL OF VEHICLES FROM PRIVATE PROPERTY WITHOUT CONSENT OF THE OWNER, REGULATION OF SERVICE RATES AND INSURANCE REGULATIONS; LEE COUNTY ORDINANCE NO. 93-15, AS AMENDED BY ORDINANCE 94-17, RELATING TO NOISE CONTROL, PROVIDING FOR CRITERIA FOR MAXIMUM PERMISSIBLE SOUND LEVELS, RELATING TO SPECIFIC PROHIBITIONS DURING CERTAIN HOURS FOR SOUNDS FROM RADIOS, TELEVISIONS, LOUDSPEAKERS, SOUND AMPLIFIERS AND OTHER MECHANICAL DEVICES OR INSTRUMENTS WHICH ARE PLAINLY AUDIBLE AND CRITERIA THEREFOR; LEE COUNTY ORDINANCE NO. 85-04, RELATING TO SLEEPING ON PUBLIC BEACHES, TERRITORIAL SCOPE, ENFORCEMENT AND REGULATION; LEE COUNTY ORDINANCE NO. 91-26, RELATING TO SPECIAL EVENTS AND REGULATING OUTDOOR ENTERTAINMENT EVENTS, LICENSING AND COMPLAINTS; LEE COUNTY ORDINANCE NO. 91-11, RELATING TO THE LEE COUNTY WELL CODE, PERMITTING CRITERIA, CONSTRUCTION, REPAIR AND PLUGGING OF WATER WELLS, ESTABLISHING A WELL CONSTRUCTION ADVISORY BOARD, TESTING AND ABANDONMENT OF WATER WELLS AND LICENSES; LEE COUNTY ORDINANCE NO. 95-18, RELATING TO SEXUALLY ORIENTED BUSINESS REGULATIONS, RELATING TO CLASSIFICATION OF BUSINESSES, PERMIT CRITERIA, ESTABLISHING PERMIT FEES AND INSPECTION OF SEXUALLY ORIENTED BUSINESSES, JUDICIAL REVIEW, PROHIBITING BACK ROOM LINGERIE MODELING, PROHIBITIONS REGARDING MINORS, ADVERTISING REGULATIONS, HOURS OF OPERATION, EXEMPTIONS AND PENALTIES, PROHIBITING STRADDLE DANCING AND OTHER SEXUAL ACTIVITIES AT SEXUALLY ORIENTED BUSINESSES, NOTICE REQUIREMENTS AND PENALTIES; PROVIDING FOR ORDINANCE FINDINGS, INTENT, SEVERABILITY, EFFECTIVE DATE AND SUNSET TERMINATION.

WHEREAS, Lee County has duly adopted county ordinances for the public's health, welfare, safety and benefit that apply to the unincorporated area of the county; and

WHEREAS, the area presently encompassed within the corporate limits of the Town of Fort Myers Beach was subject to said ordinances prior to the incorporation of the Town's area pursuant to Chapter 95-494, Laws of Florida (1995); and

WHEREAS, the Town presently has limited administrative and fiscal resources by which to implement and enforce as town ordinances those prior legislative acts of the county, found to be necessary to protect the public health, safety and welfare; and

WHEREAS, F.S. §165.093 provides that a county is to provide that assistance which is reasonably necessary in the formation and implementation of new municipalities; and

WHEREAS, the Town has requested and consented to the County amending said ordinances to continue county ordinance applicability and jurisdiction within the Town limits in order to provide necessary public health, safety and welfare legislation to the Town citizens as citizens of Lee County;

NOW, THEREFORE, BE IT ORDAINED BY THE BOARD OF COUNTY COMMISSIONERS OF LEE COUNTY FLORIDA:

SECTION ONE: FINDINGS.

The above referenced statements in the preamble are hereby confirmed and incorporated herein as if set out further in this section at length. There is hereby found to be a public need to amend those county ordinances as provided herein to provide

continued applicability and effectiveness of same within the Town limits of the Town of Fort Myers Beach, Florida, as said town is legally described and set forth in Chapter 95-494, Laws of Florida, (1995).

SECTION TWO: INTENT.

It is the intent of the Lee County Board of County Commissioners to amend each and every ordinance as set out in the following sections to set forth and provide for ordinance applicability, effectiveness and enforcement within the town limits of the Town of Fort Myers Beach as such is described in Chapter 95-494, Laws of Florida (1995), to the same extent and in the same manner as if such Town area was within the unincorporated area of Lee County. Upon adoption of this ordinance, all such stated county ordinances will be applicable to, effective and enforceable within the Town limits for the period as further provided for herein.

SECTION THREE: GENERAL AMENDMENT

The Lee County ordinances as stated by number, style and general subject description set forth in the following sections are hereby amended to extend the ordinance coverage, applicability, effectiveness and enforcement to the Town of Fort Myers Beach, Florida, as created by Chapter 95-494, laws of Florida.

SECTION FOUR:

Lee County Ordinance No. 75-9, an ordinance prohibiting the exposure of private parts or female breasts in an establishment at which alcoholic beverages are offered for sale for consumption on the premises; prohibiting the use of any device or covering which simulates private parts or female breasts in an establishment at which alcoholic

beverages are offered for sale for consumption on the premises; prohibiting any person owning, maintaining, or operating an establishment at which alcoholic beverages are offered for sale for consumption on the premises from suffering or permitting, on the premises of said establishment, the exposure of private parts or female breasts or the use of any device or covering which simulates private parts or female breasts; legislative authorization; providing for penalties;

As amended by Lee County Ordinance No. 76-09, entitled an ordinance establishing and regulating the hours for the sale, consumption, service or permitting to be served, of alcoholic beverages and intoxicating liquors within the unincorporated areas of lee county by places holding a license under the state beverage department of Florida; providing that no alcoholic beverages or intoxicating liquors of any kind may be sold, consumed, served, or permitted to be served or consumed during the week hours (to include Sundays) of 2:00 a.m. and 7:00 a.m of the same day; providing for the prohibition of the on-premise consumption of alcoholic beverages of any kind within five hundred (500') feet of a church or school unless a special permit is first obtained; providing a standard to measure the five hundred (500') feet distance requirement; providing for the repeal of any ordinance or resolution in conflict herewith; repealing a 2,500 feet distance requirement from a church or school; providing for civil and criminal penalties; and

As amended by Lee County Ordinance No. 79-1, entitled an ordinance amending Lee County Ordinance No. 76-9; relating to the sale, consumption and service of alcoholic beverages; relating to special permits for on-premise consumption of alcoholic

beverages and prohibition of same within 500 feet of a church or school and providing for measurement criteria for said distances; amending the measurement requirement to provide same on a straight-line from the main entrance of on-premise consumption establishment to the property line of church or school; are hereby amended to include the Town of Fort Myers Beach and to be effective therein. SECTION FIVE:

Lee County Ordinance No. 84-1, an ordinance to prohibit any person from drinking or consuming alcoholic beverages on a semi-public parking lot or public way, parking lot, or beach and to prohibit the transporting, carrying, or possession of alcoholic beverages, except in the original package and with the seal unbroken, on a semi-public parking lot or public way, parking lot, or beach in the unincorporated area of Lee County; providing for exemption; providing for penalty;

As amended by Lee County Ordinance No. 84-11, an ordinance amending Lee County Ordinance No. 84-01 relating to drinking alcoholic beverages or possessing alcoholic beverages in public; amending definition of alcoholic beverage; providing exemptions; and

As amended by Lee County Ordinance No. 93-06, an ordinance amending Lee County Ordinance No. 84-01 relating to the prohibition of any person from transporting, carrying or possessing alcoholic beverages in an open container; providing that open container of alcoholic beverage while operating a vehicle shall be punishable, under F.S. Sec. 316.1936 as a non-criminal moving traffic violation; amending penalty section, are hereby amended to include the Town of Fort Myers Beach and to be effective therein.

SECTION SIX:

Lee County Ordinance No. 90-51, an ordinance relating to vessel control and water safety; providing for title, purpose and authority; providing for definitions; providing for areas of enforcement and means of enforcement; providing for vessel regulation including speed, careful and prudent operation required, areas of prohibited water activity, areas of special management and regulations for operation of personal watercraft; providing for regulations for personal watercraft rentals; providing for procedures to designate areas; providing exemptions; providing for penalty; providing for repealer, conflicts,

As amended by Lee County Ordinance No. 90-63, an ordinance amending Lee County vessel control and water safety Ordinance No. 90-51, so as to clarify certain section of the ordinance and readopt Section Six F. Relating to prohibited personal watercraft activity within waters of the Captiva Island shoreline; providing for amendments to Section Three C, Definition of Floating Vendor; Section Five, Means of Enforcement; Section Six C, Areas of Prohibited Water Activity; Section Six F, Areas of Prohibited Personal Watercraft Activity; and Section Nine C, Exemption for Commercial Vessels; and

As amended by Lee County Ordinance No. 91-16, an ordinance amending Lee County Vessel Control and Water Safety Ordinance No. 90-51, as amended, so as to clarify regulations for personal watercraft rentals and to regulate personal watercraft floating vendors; providing for amendments to Section Three, Definitions and Section Seven, Regulations and Locations for Personal Watercraft Rentals, are hereby amended to include the Town of Fort Myers Beach and to be effective therein.

SECTION SEVEN:

Lee County Ordinance No. 90-03, an ordinance providing for local enforcement of the water shortage plan of the South Florida Water Management District; providing definitions; providing for application of ordinance; providing for enforcement and penalties;

As amended by Lee County Ordinance 91-24, which establishes local enforcement of the water shortage plan of the South Florida Water Management District; providing for a title; providing for amendments to definitions; creating permanent water restrictions, providing for amendments to declaration of water shortage, are hereby amended to include the Town of Fort Myers Beach and to be effective therein.

SECTION EIGHT:

Lee County Ordinance No. 95-14, an ordinance repealing and replacing Lee County Ordinance No. 90-61 to better manage recovery, reconstruction and mitigation activities following a major or catastrophic disaster within the unincorporated areas of Lee County, Florida; providing for the purpose and intent of the ordinance; providing for jurisdiction; providing definitions; providing for the creation, composition, duties and responsibilities, duration, and chair of a disaster advisory council; providing for the creation, duration, duties and responsibilities of a post-disaster recovery task force and certain members thereof; providing for the composition and duties of an emergency review board; providing priorities for post-disaster redevelopment; providing priorities for essential services and facilities restoration; providing debris clearance, removal and disposal strategies; providing for determination of damage; providing for implementation

of a build back policy; providing for a declaration of an initial building moratorium and establishing related moratoria pertaining to building permit inspections, development orders and site plans providing provisions for moratoria; providing for emergency repairs; providing for an emergency permitting system; providing policies for economic redevelopment; providing guidelines for acquiring damaged property; providing for authority; and providing penalties is hereby amended to include the Town of Fort Myers Beach and to be effective therein.

SECTION NINE:

Lee County Ordinance 88-24, an ordinance repealing and replacing Ordinance No. 74-11, relating to minimum standards of hygiene for food establishments and food vendors, stating the purpose of the ordinance, adopting sections of the Florida Administrative Code, setting forth definitions and permit requirements providing for non-transferability of permits, approval of plans, providing for a food hygiene certification program, providing for inspections, approval, revocation of permits, closing of establishments, control of unsafe food and drink, mobile and roadside food vendors; establishing a hearing review board; providing for appeal from orders, enforcement and penalties, is hereby amended to include the Town of Fort Myers Beach and to be effective therein.

SECTION TEN:

Lee County Ordinance 91-01, an ordinance providing for the mandatory connection of on-site sewage disposal systems to publicly owned or investor-owned wastewater collection systems after notice that such a system is available; providing for

definitions; providing for an administrative waiver of the mandatory connection, providing for penalties, is hereby amended to include the Town of Fort Myers Beach and to be effective therein.

SECTION ELEVEN:

Lee County Ordinance No. 93-10, an ordinance relating to removal of recyclable materials from county containers for collection; providing for definitions; providing for prohibitions; providing for penalties, is hereby amended to include the Town of Fort Myers Beach and to be effective therein.

SECTION TWELVE:

Lee County Ordinance No. 93-23, an ordinance repealing and replacing Lee County Ordinance No. 86-05, as amended by Lee County Ordinance No. 88-42, relating to nuisance grasses and weeds; providing for repealer, providing for short title and territorial scope; providing for definitions, providing for nuisance declared; providing for prohibitions; providing for designation of investigating and enforcing authority; providing for procedures for implementation; providing for budget of funds; providing for civil remedies; and providing for conflict, are hereby amended to include the Town of Fort Myers Beach and to be effective therein.

SECTION THIRTEEN:

Lee County Ordinance No. 93-39, an ordinance amending and restating Lee County Ordinance No. 88-43, governing the regulation and disposal of garbage, refuse, trash, rubbish, lost or abandoned property or inoperable vehicles by prohibiting the

dumping of such material on private property; providing for removal of accumulations of refuse, trash, rubbish, lost or abandoned property or inoperable vehicles; amending the definition of nuisance accumulation; providing for a definition of inoperable vehicle; providing for prosecution before a hearing examiner; and providing for penalties, are hereby amended to include the Town of Fort Myers Beach and to be effective therein.

SECTION FOURTEEN:

Lee County Ordinance No. 95-08, as amended by Lee County Ordinance No. 95-19, an ordinance amending and restating Lee County Ordinance No. 86-14, as amended, relating to garbage and solid waste collection and disposal for Lee County; creating certain municipal service benefit units within Lee County to be known as mandatory solid waste collection and disposal units for service area; providing for the purpose of disposing of solid waste within their boundaries; establishing the governing body with powers and duties; providing for residential and commercial collection and disposal; mandating services and payment for same; levying special assessments and collection; prohibiting unlawful disposal; and penalties, is hereby amended to include the Town of Fort Myers Beach and to be effective therein.

SECTION FIFTEEN:

Lee County Ordinance No. 95-10, as amended by Lee County Ordinance No. 95-20, an ordinance relating to Lee County Garbage and solid waste disposal facilities; creating a municipal service benefit unit within Lee County for commercial solid waste service customer disposal facilities costs; establishing the governing body with powers

and duties; levying certain special assessments for costs of Lee County solid waste disposal facilities from commercial solid waste service properties; providing for penalties, severability, supplemental authority, repeal of provisions of inconsistent ordinances, and effective date, is hereby amended to include the Town of Fort Myers Beach and to be effective therein.

SECTION SIXTEEN:

Lee County Ordinance No. 91-07, an ordinance regulating solid waste transportation within Lee County, Florida, providing for purpose and authority; providing for definitions; providing for regulation and enforcement; and providing for penalties, is hereby amended to include the Town of Fort Myers Beach and to be effective therein.

SECTION SEVENTEEN:

Lee County Ordinance No. 88-54, an ordinance relating to escort service businesses, providing for definitions, providing for county permit to conduct business, providing for disclosure of escort service business records, providing for age limitation, providing for county license to be employed as an escort; and providing for penalties, is hereby amended to include the Town of Fort Myers Beach and to be effective therein.

SECTION EIGHTEEN:

Lee County Ordinance No. 85-07, an ordinance relating to the licensing of transient merchants within Lee County; providing definitions; providing prohibition; providing exemptions; providing for a permit; providing for the content of applications; providing for a fee; permit not transferable; bond required; providing for service of process; background investigation required; creating the licensing review board;

providing for issuance or denial; providing for revocation of permit and criteria; providing one year duration of permit; requiring the display of permits; providing enforcement; and providing a penalty;

As amended by Lee County Ordinance No. 88-17, an ordinance amending the transient merchant ordinance, to provide for proper reference to the current commercial use of rights-of-way Ordinance, No. 88-11, as may be amended or replaced; to provide for conflict, are hereby amended to include the Town of Fort Myers Beach and to be effective therein.

SECTION NINETEEN:

Lee County Ordinance No. 94-32, an ordinance amending and restating Lee County Ordinance No. 94-16, relating to fireworks and sparklers; providing a short title, applicability and purpose; providing for sale of fireworks; providing for definitions; prohibiting fireworks from being distributed, stored or sold at roadside stands; providing for outdoor display of fireworks, providing for pyrotechnic displays before a proximate ordinance; providing for penalties, is hereby amended to include the Town of Fort Myers Beach and to be effective therein.

SECTION TWENTY:

Lee County Ordinance No. 95-13, an ordinance creating a personal watercraft rental vendor and parasailing license ordinance; providing for title, purpose and authority; providing definitions; prohibiting unlicensed rental of personal watercraft or parasailing; providing for application and regulatory fee; providing for annual license fee; providing for renewal and display of license; providing for conditions of licensing use by personal

watercraft vendors or parasailing operators; providing for transferability of the vendor license and a grandfather clause; providing for insurance, regulatory penalties and exemptions; providing for areas of enforcement and means of enforcement, is hereby amended to include the Town of Fort Myers Beach and to be effective therein.

SECTION TWENTY-ONE:

Lee County Ordinance No. 91-29, an ordinance relating to uniform traffic control enacting county parking regulations; providing for title; providing for definitions; providing for prohibited stopping, standing and/or parking in specified places; providing for parallel and angle parking regulations; providing for parking for certain purposes prohibited; providing for disabled persons parking; providing for posting of no parking signs in certain designated areas; providing for violations, enforcement, penalties; providing exercise of police power; establishing criteria in issuance of summons; providing for application; providing non-liability of county; providing for inclusion in the code; repealing Lee County ordinances 81-36, 86-03 and 90-20, is hereby amended to include the Town of Fort Myers Beach and to be effective therein.

SECTION TWENTY-TWO:

Lee County Ordinance No. 94-27, an ordinance of Lee County, Florida, pertaining to the towing of vehicles parked on private property; relating to the towing and removal of vehicles from private property without the consent of the registered owner or other person in control of the vehicle; providing for supplemental authority to F.S. §715.07, regulation of maximum service rates and minimum insurance regulations; definitions, intent and non-solicitation; and penalty, is hereby amended to include the Town of Fort

Myers Beach and to be effective therein.

SECTION TWENTY-THREE:

Lee County Ordinance No. 93-15, an ordinance amending and restating in its entirety the Lee County Noise Control Ordinance No. 82-32, as amended, so as to provide clarification and provide for various amendments; amending Section Three, Definitions; amending Section Six, Exceptions, to clarify that the sheriff's department may charge individuals with breach of the peace; adding Section Eight, Enforcement, to empower the sheriff's department with the enforcement of the ordinance; and amending Section Nine, Penalties;

As amended by Lee County Ordinance No. 94-17; an ordinance amending the Lee County Noise Control Lee County Ordinance No. 93-15, so as to revise the criteria for maximum permissible sound levels; to provide specific prohibitions during certain hours from sounds emanating from radios, televisions, loudspeakers, sound amplifiers and other mechanical devices or instruments which are plainly audible; and set forth criteria for plainly audible sound, are hereby amended to include the Town of Fort Myers Beach and to be effective therein.

SECTION TWENTY-FOUR:

Lee County Ordinance No. 85-04, an ordinance relating to sleeping on public beaches; providing territorial scope; providing for means of enforcement; providing for legislative intent; providing for regulation of sleeping on beaches being prohibited except between certain times; and providing for penalty, is hereby amended to include the Town of Fort Myers Beach and to be effective therein.

SECTION TWENTY-FIVE:

Lee County Ordinance No. 91-26, an ordinance creating the Lee County special events ordinance regulating outdoor entertainment events; providing for repealer; defining outdoor entertainment events; establishing license requirements and application procedures; requiring proof of insurance and proof of a bond; providing for the filing of complaints; providing for revocation of licenses; providing for enforcement, is hereby amended to include the Town of Fort Myers Beach and to be effective therein.

SECTION TWENTY-SIX:

Lee County Ordinance No. 91-11, an ordinance repealing Ordinance No. 87-7 and restating and establishing the Lee County Well Code; relating to administration, permitting standards, construction, repair, and plugging of water wells; establishing a well construction advisory board; providing permitting procedures; providing regulations relating to test wells, testing reports and inspections, water well permits, construction and abandonment of water wells; providing for licensing; providing for supplemental regulations; providing for specialty licenses; providing for penalties, is hereby amended to include the Town of Fort Myers Beach and to be effective therein.

SECTION TWENTY-SEVEN:

Lee County Ordinance No. 95-18, an ordinance of the Board of County Commissioners of Lee County, Florida, to be entitled the "Lee County Sexually Oriented Businesses Regulation Ordinance; providing for purpose and intent; providing for applicability to the unincorporated areas of Lee County, Florida; providing for definitions; providing for classification of sexually oriented businesses; providing for the requirement

of a permit for operating sexually oriented businesses; providing for investigation of applications for permits; providing procedures for the issuance or denial of permits; providing for an annual permit fee; providing for inspection of the premises of sexually oriented businesses; providing for expiration of permits; providing for suspension of permits; providing for revocation of permits; providing for judicial review of permit denial, suspension or revocation; providing for restrictions regarding the transfer of permits; prohibiting back room lingerie modeling; providing for prohibitions regarding minors and sexually oriented businesses; providing for advertising regulations; providing for hours of operation; prohibiting "straddle dancing" and other sexual activities at sexually oriented businesses; providing for exemptions; providing for criminal penalties and additional equitable and injunctive relief; providing for consent by permittees to the provisions of this ordinance and to county, federal, state and municipal regulations; providing for immunity from prosecution; providing for notice requirements under this ordinance; and providing for severability, is hereby amended to include the Town of Fort Myers Beach and to be effective therein.

SECTION TWENTY-EIGHT: SEVERABILITY

The provisions of this ordinance are severable and it is the legislative intention to confer upon the whole or any part of the ordinance the powers herein provided for. If any of the provisions of this ordinance shall be held unconstitutional by any court of competent jurisdiction, the decision of such court shall not affect or impair any remaining provisions of the ordinance. It is hereby declared to be the legislative intent that this ordinance would have been adopted had such unconstitutional provision not been included herein.

SECTION TWENTY-NINE: CONFLICTS OF LAW

Whenever the requirements or provisions of this ordinance are in conflict with the requirements or provisions of any other lawfully adopted Lee County ordinance or Florida Law or Statute, the more restrictive will apply.

SECTION THIRTY: CODIFICATION, INCLUSION IN CODE AND SCRIVENER'S ERRORS

It is the intention of the Board of County Commissioners that the provisions of this ordinance shall become and be made a part of the Lee County Code; and that sections of this ordinance may be renumbered or relettered and that the word "ordinance" may be changed to "section," "article," or such other appropriate word or phrase in order to accomplish such intention; and regardless of whether such inclusion in the code is accomplished, sections of this ordinance may be renumbered or relettered and typographical errors which do not affect the intent may be authorized by the County Administrator, or his designee, without need of public hearing, by filing a corrected or recodified copy of same with the Clerk of Circuit Court.

SECTION THIRTY-ONE: SUNSET PROVISION/REPEALER

This Reviser's Ordinance amendment specifically amending existing Lee County Ordinances to provide applicability to the Town of Fort Myers Beach, Florida, shall be deemed repealed and of no further force or effect as of October 1, 1996. This provision shall not affect the continued applicability or effectiveness of said county ordinances to the unincorporated area of Lee County, and said ordinances shall remain in full force and effect as to unincorporated Lee County.

SECTION THIRTY-TWO: EFFECTIVE DATE

This ordinance shall take effect immediately upon "filing" \$125.66 as revised with the Secretary of State of Florida.

The foregoing Ordinance was offered by Commissioner Ray Judah, who moved its adoption. The motion was seconded by Commissioner John Manning and, being put to a vote, the vote was as follows:

JOHN E. MANNING	<u>AYE</u>
DOUGLAS ST. CERNY	<u>AYE</u>
RAY JUDAH	<u>AYE</u>
ANDREW W. COY	<u>AYE</u>
JOHN E. ALBION	<u>AYE</u>

DULY PASSED AND ADOPTED this 3rd day of April, 1996.

CHARLIE GREEN, CLERK
LEE COUNTY, FLORIDA

By: Shirley E. Rast
Deputy Clerk

BOARD OF COUNTY COMMISSIONERS

By: [Signature]
Chairman

LEE COUNTY ATTORNEY'S OFFICE
APPROVED AS TO FORM:

By: James Jaeger
County Attorney

Charlie Green
Clerk Of Circuit Court
Lee County, Florida


STATE OF FLORIDA

COUNTY OF LEE

I, Charlie Green, Clerk of Circuit Court, Lee County, Florida, and ex-Officio Clerk to the Board of County Commissioners, Lee County, Florida, do hereby certify that acknowledgment has been received from the Department of State advising that Ordinance No. 96-08 was filed in that office on the 10th day of April, 1996. Said Ordinance was adopted by the Board of Lee County Commissioners at their meeting held on the 3rd day of April, 1996, and same filed in the Clerk's Office.

Given under my hand and seal, at Fort Myers, Florida, this 12th day of April, 1996.

CHARLIE GREEN,
Clerk of Circuit Court
Lee County, Florida

By 
Deputy Clerk

TOWN OF FORT MYERS BEACH
ORDINANCE NO. 96-06

COPY

AN ORDINANCE OF THE TOWN OF FORT MYERS BEACH
FLORIDA, TO BE KNOWN AS THE TOWN OF FORT MYERS
BEACH LIQUOR LICENSE RESTRICTION ORDINANCE
PROVIDING AUTHORITY; TITLE AND CITATION; HOURS
RESTRICTION; LOCATION RESTRICTION; PENALTIES;
SEVERABILITY; REPEALING CLAUSE AND EFFECTIVE
DATE

IT IS HEREBY ORDAINED BY THE TOWN OF FORT MYERS BEACH, FLORIDA as follows:

SECTION ONE: Authority

This Ordinance is enacted pursuant to the provisions of Chapter 95-494, Laws of Florida, Chapter 166, Florida Statutes, and other applicable provisions of law.

SECTION TWO: Title and Citation

This ordinance shall be known and cited as the "TOWN OF FORT MYERS BEACH LIQUOR LICENSE RESTRICTION ORDINANCE."

SECTION THREE: Hours Restriction

No alcoholic beverage or intoxicating liquor of any kind shall be sold, consumed or served, or permitted to be served or consumed, in any place holding a license under the State Beverage Department of Florida within the Town of Fort Myers Beach, except during the hours of 7:00 a.m. and 2:00 a.m. of the following morning every day of the week, including Sundays.

SECTION FOUR: Location Restriction

The on-premise consumption of alcoholic beverages of any kind is prohibited within Five Hundred (500') feet of a church or school, unless a special permit allowing such on premise consumption is first obtained from the Town Council. The Five Hundred (500') feet requirement within which a special permit is required hereunder shall be measured by a straight-line from the main entrance of the establishment desiring to have on premise consumption of alcoholic beverages and the nearest property line of the church or school.

SECTION FIVE: Penalties

Any person who shall violate any section of this ordinance shall be guilty of a misdemeanor punishable by a fine not to exceed \$500.00 or imprisonment in the county jail not to exceed sixty (60)

days, or both.

SECTION SIX: Severability

If any one of the provisions of this ordinance should be held contrary to any express provision of law or contrary to the policy of express law, although not expressly prohibited, or against public policy, or shall for any reason whatsoever be held invalid, then such provision shall be null and void and shall be deemed separate from the remaining provisions of this ordinance, and in no way affect the validity of all other provisions of this ordinance.

SECTION SEVEN: Repealing Clause

All ordinances or parts thereof in conflict with the provisions herein contained are, to the extent of such conflict, hereby superseded and repealed.

SECTION EIGHT: Effective Date

This ordinance shall become effective September 30, 1996.

The foregoing ordinance was enacted by the Town Council upon a motion by Council Member CERECEDA and seconded by Council Member Reynolds and, upon being put to a vote, the result was as follows:

Anita T. Cereceda	<u>aye</u>
Ted FitzSimons	<u>aye</u>
William (Rusty) Isler	<u>aye</u>
Garr Reynolds	<u>aye</u>
Ray Murphy	<u>aye</u>

DULY PASSED AND ENACTED this 1st day of July, 1996.

ATTEST:

By: Marsha Segal-George
Marsha Segal-George, Town Clerk

TOWN OF FORT MYERS BEACH

By: Anita T. Cereceda
Anita T. Cereceda, Mayor

Approved as to form by:

Richard V.S. Roosa
Richard V.S. Roosa, Town Attorney

ORDINANCE NO. 96-~~20~~

AN ORDINANCE ADOPTING THE FORT MYERS BEACH CORE AREA OVERLAY ZONING DISTRICT TO PROVIDE FOR OPTIONAL DEVELOPMENT STANDARDS WITHIN THE DISTRICT; PROVIDING FOR PURPOSE AND INTENT, ELEMENTS OF THE REDEVELOPMENT OVERLAY DISTRICT, MASTER PLAN, LIMITATIONS ON APPROVALS, MODIFIED DEVELOPMENT REGULATIONS, PROCEDURES FOR APPROVAL, ~~AND FOR~~ APPEALS OF ADMINISTRATIVE DECISIONS, ~~MAP LEGAL~~ DESCRIPTION OF OVERLAY DISTRICT, MASTER SITE PLAN, STORM WATER MANAGEMENT PLAN, PROVIDING FOR SEVERABILITY, CONFLICTS, CODIFICATION, INCLUSION IN THE LAND DEVELOPMENT CODE, SCRIVENER'S ERRORS, AND PROVIDING FOR AN EFFECTIVE DATE

WHEREAS, prior to the incorporation of the Town of Fort Myers Beach, Lee Plan Policy 2.7.1 provided that community redevelopment activities would be conducted by the Lee County Community Redevelopment ~~Advisory Committee Agency~~ within approved redevelopment areas according to adopted redevelopment plans; and

WHEREAS, Lee Plan Policy 110.4.10. provided that the Lee County Community Redevelopment ~~Advisory Committee Agency~~ would continue local revitalization efforts in the County's redevelopment areas to leverage private investment activities through public investment and community development and infrastructure improvements; and

WHEREAS, prior to the incorporation of the Town of Fort Myers Beach, Lee County's Community Redevelopment ~~Advisory Committee Agency~~ authorized the Fort Myers Beach Core Area Overlay Zoning Master Plan to be prepared hereinafter called the Master Plan; ~~and; and~~

WHEREAS, Chapter 34 of the Fort Myers Beach Land Development Code provides for the establishment of a redevelopment overlay district also referred to as the Downtown District encompassing Districts One through Four as shown on 3 maps attached hereto, incorporated herein and labeled as follows: Map 1- Proposed Land Use by District-Fort Myers Beach Core Area Overlay Zoning Master Plan; Map 2- Storm Water Management Plan-Fort Myers Beach Core Area Overlay Zoning Master Plan; Map 3- Illustrative Master Plan; to recognize and provide for the unique requirements of redevelopment which cannot be adequately addressed through existing regulations; and

WHEREAS, the purpose of a redevelopment overlay district is to create favorable conditions for the revitalization of redevelopment areas by establishing a procedure through which such areas *may* be master planned; and

WHEREAS, master plans may include development guidelines and standards which, to the extent covered, are intended to provide an incentive driven alternative to the standard zoning and other land development regulations; and

WHEREAS, it is the express policy of the Town Council that development consistent with an approved master plan be *voluntary*; and

WHEREAS, the ~~Master Plan~~ Fort Myers Beach Master Plan/Overlay was unanimously approved by the Estero Island Local Redevelopment Planning Committee and the Lee County Community

Development Advisory Committee on September 14 and November 2, 1995 respectively; and

WHEREAS, Lee County Department of Community Development staff, and the Fort Myers Beach staff have reviewed the proposed ~~Fort Myers Beach~~ Master Plan and have recommended adoption of ~~the Fort Myers Beach Redevelopment Overlay District~~; and

WHEREAS, the ~~Fort Myers Beach Lee County~~ Local Planning Agency held a Public Hearing on July 30, 1996 on the ~~reviewed the proposed Fort Myers Beach Master Plan Overlay on January _____, Plan 1995~~ and found the master plan consistent with the Lee Plan; and

WHEREAS, the ~~Fort Myers Beach Local Planning Agency~~ recommends to the Town Council that ~~this ordinance be adopted~~; and

WHEREAS, the ~~Fort Myers Beach Town Council~~ has reviewed and accepts the recommendation of the ~~Local Planning Agency Lee County Board of Commissioners~~ desire to adopt the ~~Fort Myers Beach Master Plan/Overlay~~ as set forth below.

NOW THEREFORE, BE IT ORDAINED BY THE TOWN COUNCIL BOARD OF COUNTY COMMISSIONERS OF FORT MYERS BEACH LEE COUNTY, FLORIDA THAT:

SECTION ONE: AMENDMENT TO THE LAND DEVELOPMENT CODE

The ~~Fort Myers Beach Lee County~~ Land Development Code is hereby amended to add Subdivision VI to Chapter 34, Division 11, to read as follows:

Subdivision VI. The Fort Myers Beach Overlay District

Sec. 34-1141~~33~~ Purpose and intent.

(a) *Purpose and affected area.* This redevelopment overlay district is designed to stimulate the revitalization of the original commercial district on Estero Island. This district is known as the Downtown of Times Square and Fort Myers Beach and is described in a set of maps attached hereto and incorporated herein by reference, ~~encompasses several city blocks spanning from Matanzas Pass to the Gulf of Mexico and on each side of Estero Boulevard to the Diamondhead Resort property. A legal description of the boundaries is set forth in Section 34-1139.~~

(b) *Scope.* The revitalization of the Fort Myers Beach Downtown District ~~business district~~ will include the renovation and re-use of existing buildings and the construction of new buildings. It will also include the installation of public works, including plazas, sidewalks, changes in vehicular circulation, public and shared parking, and other street- scape improvements.

(c) *Optional nature of these regulations.* Individual landowners may choose to build or rebuild in full compliance with the provisions of this redevelopment overlay district, or may choose to follow all existing ~~Fort Myers Beach Lee County~~ regulations. However, should a landowner elect to use any of the modified development regulations in Section 34-1145~~37~~ below, he or she must comply with all of the requirements of this redevelopment overlay district on that property.

(d) *Authority.* The Fort Myers Beach Downtown~~business~~ District lies at the heart of the pre-incorporation Estero Island community redevelopment area. This redevelopment overlay district is consistent with and helps to implement the adopted component redevelopment plan for Estero Island. This redevelopment overlay district also complies with all requirements for such districts found in Section 34-1122 through 34-1132 of the Fort Myers Beach~~Lee County~~ Land Development Code.

Sec. 34-1142~~34~~ **Elements of the redevelopment overlay district.**

This redevelopment overlay district includes two distinct elements. The first is the Master Plan itself (Section 34-1143~~35~~), which depicts the desired redevelopment plan for the Fort Myers Beach Downtown District~~business district~~ including public and private improvements. The second is a set of modified development regulations (Section 34-1145~~37~~) which enable and encourage private landowners to rehabilitate existing buildings or construct new buildings. Both elements of the redevelopment overlay district are needed to ensure the redevelopment of the business district in the old Florida/Caribbean~~Caribbean~~ style as shown in the Master Plan.

Sec. 34-1143~~35~~ **The master plan.**

The master plan for the Fort Myers Beach Downtown ~~business~~ District contains three separate components as described in the following subsections.

(a) *Master site plan.* A reduced copy of the master site plan for the Fort Myers Beach Downtown~~business~~ District is included in Appendix L. Full-sized copies of this drawing are available at the Town Hall, ~~from the Lee County Community Redevelopment Agency in downtown Fort Myers.~~

(b) *Storm Water management master plan.* A reduced copy of the storm- water management master plan for the Fort Myers Beach Downtown ~~business~~ District is included in Appendix L. Surface water flows will continue to be directed away from Old San Carlos Drive and Estero Boulevard and towards Matanzas Pass under this plan, but water quality treatment and minimal storm attenuation will be added. Necessary facilities, to retrofit the existing storm sewer system for a regional exfiltration system are included in the future phases of the Master Plan implementation, and discussed in Section 34-1137(I) below. Full-sized copies of this drawing and the remainder of the plan are available from the Town Hall, ~~Lee County Community Redevelopment Agency in downtown Fort Myers.~~

(c) *Design guidelines.* Design guidelines for the Fort Myers Beach Downtown~~business~~ District are being adopted by administrative code. These guidelines provide technical and design assistance for exterior commercial building renovations and new construction. They are designed to encourage owners and tenants to preserve and improve the unique character of the business district, and to stimulate creative design solutions while promoting a sense of relatedness among properties. These guidelines are not regulations that control land-use decisions, and they contain no mandatory review process. They are designed simply to encourage the proper maintenance and improvement of the visual character of the Fort Myers Beach Downtown~~business~~ District as a pedestrian-oriented retail and community center.

Sec. 34-1144~~36~~ **Limitations on approvals.**

(a) **Record-keeping.** The staff of the ~~Town of Fort Myers Beach~~~~Lee County Community Redevelopment Agency~~ shall maintain detailed records of development and redevelopment that is approved using the modified development regulations in Section 34-1145~~37~~ below. These records shall include cumulative totals of square footage of new commercial space and the resulting number of parking spaces (both the number required by general ~~Town~~~~Lee County~~ regulations and the number actually being provided by those developing and redeveloping land in the Fort Myers Beach ~~Downtown~~~~business~~ ~~D~~istrict).

(b) **New development prior to public improvements.** ~~Lee County's~~ ~~The~~ Community Redevelopment Agency is ~~constructing~~~~planning~~ major public improvements in the Fort Myers Beach ~~Downtown~~~~business~~ ~~D~~istrict that ~~were planned and funded prior to incorporation and~~ will include substantial pedestrian and automobile infrastructure improvements. If actual development activity recorded pursuant to Section 34-1144~~36~~ (a) exceeds a cumulative total of 25,000 square feet of commercial space or a reduction of 100 parking spaces below general ~~Town~~~~Lee County~~ regulations prior to the letting of contracts to construct on-street parking and the core surface ~~water~~ management system, then the ~~Town~~~~Community Redevelopment Agency~~ shall immediately undertake an analysis of actual demand for these public facilities in the Fort Myers Beach ~~Downtown~~~~business~~ ~~D~~istrict. The results of this analysis shall be presented to the ~~Town Council~~~~Board of County Commissioners~~, which shall decide whether to initiate the public improvements or to repeal or modify these redevelopment overlay regulations so that adequate public facilities will be available when needed by new development. However, this provision shall not be interpreted to supersede the general concurrency requirements of Chapter 2 of the Land Development Code.

Sec. 34-1145~~37~~ Modified development regulations.

(a) **Optional nature of this section.** All landowners in the Fort Myers Beach ~~Downtown~~~~business~~ ~~D~~istrict are encouraged to develop or redevelop their property in conformance with the overall ~~M~~aster ~~P~~lan and the detailed design guidelines ~~referred to~~~~found~~ in Section 34-1143~~35~~ (c). Should a landowner choose to avail himself of the modified development regulations contained ~~here~~ in ~~this~~ Section ~~34-1137~~, then compliance with all applicable portions of the redevelopment overlay district will be mandatory for that property and for any abutting lot(s) or adjacent building(s) under the same ownership or control, for a period of 10 years. Nothing in this ordinance shall require any landowner to participate in any of its provisions unless that landowner elects to do so. A landowner's decision to use these regulations shall be made in writing on a form supplied by ~~the~~ ~~Town~~~~Lee County~~. This form shall acknowledge that this decision runs with the land for the stated period. ~~Fort Myers Beach~~~~Lee County~~ shall record this form in ~~the~~~~its~~ Official Record books ~~of~~ Lee County.

(b) **Modified development regulations.** The remainder of the provisions of this ordinance assume that a landowner in the Fort Myers Beach ~~Downtown~~~~business~~ ~~D~~istrict has elected in writing to comply in full with this redevelopment overlay district. All ~~Fort Myers Beach~~~~Lee County~~ regulations shall remain in effect except as explicitly modified through this ordinance.

(c) **Permitted uses.** The permitted uses of land are normally determined by its zoning classification. At present, the district is zoned C-1, CPD and RM-2. Regardless of these underlying zoning classifications, the permitted uses of land in this redevelopment overlay district shall be in accordance with Table 1. ~~The land uses that are permitted in the C-1 zone throughout Lee County as of August 16, 1995, are shown on Table 1 for informational purposes only.~~ The table then shows those

specific uses that are permitted in the Fort Myers Beach ~~Downtownbusiness~~ District on the ground floor and/or outdoors facing the primary walking zone (facing the rights-of-way of Old San Carlos Boulevard).

- (1) The terminology and the numbered notes used in this table are the same as contained in Table 34-843 of the Land Development Code, including the letter “P” to indicate a permitted use, “SE” for a use only by special exception, “SP” for a use only by special permit, “-” for a use that is not permitted in this district, “EO” for existing uses only, “TP” for temporary permit, “AA” for administrative approval, etc. (see Section 34-621(b) for details). Terms that are defined in Section 34-2 of the Land Development Code are specifically noted in this table.
- (2) Land uses that are not specifically included nor excluded by Table 1 or the Land Development Code may be permitted only by application and review pursuant to the special permit process as provided by Section 34-232 (c) of the Fort Myers Beach Land Development Code. ~~if they are no more intense than the most similar listed use, considering impacts such as noise, hours of operation, traffic generation, compatibility with the purposes of this overlay district, and similar factors.~~
- (3) All land uses are subject to the supplementary district regulations that are found in Article VII of Chapter 34 of the Land Development Code, except as explicitly modified herein.
- (4) ~~(4) ——— Under no circumstances shall Drive-in or drive-through lanes~~ may be permitted only by application and review pursuant to the special permit process as provided by Section 34-232 (c) of the Fort Myers Beach Land Development Code. ~~be provided for any land uses.~~
- (5) Outdoor restaurant seating is specifically encouraged in the Fort Myers Beach ~~Downtownbusiness~~ District. Music or other entertainment for any patrons seated outdoors must not be audible at a distance of 200 feet from the outdoor seating. ~~*****~~ (potential conflict with noise ordinance which needs to be worked out after noise ordinance adopted)
- (6) In addition to the land uses shown in Table 1, certain temporary uses such as farmers’ markets and portable carts selling food or crafts may be permitted in Times Square or on public rights-of-way. Such uses of public property are regulated by Town Ordinance and Lee County Ordinance on county property: Ordinance No. 88-11 (as amended by No. 90-42) which regulates commercial activities on road rights-of-way; Ordinance No. 90-56 which regulates activities in public parks and certain adjoining rights-of-way; and Administrative Code AC-8-1 (formerly known as D-0015) which regulates certain functions held on county property or within the county road system.

TABLE 1

LAND USES	SPECIAL NOTES OR REGULATIONS	<i>OLD SAN CARLOS DRIVE</i>	<i>TIMES SQUARE</i>	<i>CRESCENT STREET</i>	<i>ESTER BLVD. BEACH FRON.</i>
-----------	------------------------------	-----------------------------	---------------------	------------------------	--------------------------------

Accessory apartment		P	P	P	P
Administrative offices (defined term)		P	P	P	P
Adult congregate living facility (defined term)		P	-	P	-
Amusement park, less than ten acres (defined term)		-	-	-	-
Animals:	34-1321 et seq.				
Clinic (defined term)		P	-	-	P
Kennel (defined term)		-	-	-	-
Control center (including Humane Society)		P	-	-	P
ATM (automatic teller machine) (defined term)		P	P	-	P
Auto parts store: (defined term)					
No installation service		P	-	-	P
With installation service		-	-	-	P
Automobile service station (defined term)		-	-	-	P
Auto Repair and service (34-622(c)(2)):					
Group I		-	-	-	P
Group II		-	-	-	-
Bait and tackle shop		P	-	-	P
Banks and financial establishments (34-622(c)(3)):					
Group I		P	-	-	P
Group II		P	-	-	P
Bar or cocktail lounge (defined term)	34-1261 et seq.	P	P	-	P
Bed-and-breakfast establishments		P	P-(e)	P-(e)	P
Boarding house (defined term)		P	P	P	P
Boats: (defined term)					
Boat parts store (defined term)		-	-	-	P
Boat rental		-	-	-	P
Boat repair and service (defined term)	34-1352, 34-3001 et seq.	-	-	-	-
Boat sales		-	-	-	P
Boat storage, dry, not exceeding two tiers or 18 feet above natural grade		-	-	-	P
Boat storage, dry, exceeding two tiers or 18 feet above natural grade		-	-	-	SE
Broadcast studio, commercial radio and television	34-1441 et seq.	P	-	-	-
Building materials sales (34-622(c)(4))		-	-	-	-
Business services (34-622(c)(5)):					
Group I		P	P	-	P
Group II		-	-	-	P
Bus station/depot (defined term)	34-1381 et seq.	-	-	-	-
Caretaker's residence		SE	SE	-	SE
Car wash (defined term)		-	-	-	-
Cleaning and maintenance services (34-622(c)(7))		-	-	-	P
Clothing stores, general (34-622(c)(8))		P	P	P	P
Clubs:	34-2111				
Country (defined term)		-	-	-	-
Commercial (defined term)		-	-	-	-
Fraternal (defined term)		P	P	-	P
Membership organization (defined term)		P	P	-	P
Private (defined term)		P	P	-	P
Community residential home (defined term)		P	P	P	P
Consumption on premises	34-1261 et seq.	AA/SP	AA/SP	AA/SP	AA/SP
Contractors and builders (34-622(c)(9)):					
Group I		P	-	P	-
Group II		P	-	-	-

Group III		-	-	-	
Convenience food and beverage store (defined term)		P1	<i>P1</i>	<i>P</i>	<i>P</i>
Cultural facilities (34-622(c)(10))		P	<i>P</i>	-	<i>P</i>
Day care center, adult, child (defined term)		P	<i>P</i>	<i>SE</i>	<i>P</i>
Department store (defined term)		P2	<i>P2</i>	-	<i>P</i>
Dormitory (defined term)		-	-	-	-
Drive-through facility for any permitted use (defined term)	Note (9)	-	-	-	-
Drive-in theater (defined term)		-	-	-	-
Drugstore, pharmacy (defined term)		P	<i>P</i>	-	<i>P</i>
Dwelling unit: (defined term)		-	-	-	<i>P</i>
Duplex (defined term)		<i>P</i>	<i>P</i>	<i>P</i>	<i>P</i>
Single-family (defined term)		<i>P</i>	<i>P</i>	<i>P</i>	<i>P</i>
Two-family attached (defined term)		<i>P</i>	<i>P</i>	<i>P</i>	-
Townhouse (defined term)		<i>P</i>	<i>P</i>	<i>P</i>	-
Mobile home (defined term)		<i>P</i>	<i>P</i>	<i>P</i>	<i>P</i>
Multiple-family building (defined term)		<i>P</i>	<i>P</i>	<i>P</i>	<i>P</i>
Entrance gates and gatehouse (defined term)	34-1749	P	<i>P</i>	<i>P</i>	<i>P</i>
Emergency medical service (ambulance station)		EO	<i>EO</i>	<i>EO</i>	<i>EO</i>
Emergency operations center		-	-	-	<i>P</i>
Essential services (defined term)	34-1611 et seq.				
Essential service facilities (34-622(c)(13)):					
Group I	34-1611 et seq.	SE	<i>SE</i>	<i>SE</i>	<i>SE</i>
Group II	34-1611 et seq.	SE	<i>SE</i>	<i>SE</i>	<i>SE</i>
Excavation:					
Mining		-	-	-	-
Water retention		-	-	-	-
Oil or gas	34-1651 et seq.	<i>P</i>	<i>P</i>	<i>P</i>	<i>SP</i>
Fire station		P	<i>P</i>	-	<i>SP</i>
Flea market:					
Open (defined term)		SE3	<i>SE3</i>	-	<i>SE3</i>
Indoor (defined term)		<i>P</i>	<i>P</i>	-	<i>P</i>
Food and beverage service, limited (defined term)		SE	<i>SE</i>	-	<i>SE</i>
Food stores (34-622(c)(16)):					
Group I		<i>P</i>	<i>P</i>	-	<i>P</i>
Group II		<i>P</i>	<i>P</i>	-	<i>P</i>
Forestry tower		-	-	-	<i>P</i>
Fraternity house (defined term)		-	-	-	-
Funeral home or mortuary:					
No cremation		SE	<i>SE</i>	-	<i>P</i>
With cremation		-	-	-	-
Gasoline dispensing system, special (defined term)		-	-	-	-
Government maintenance facility		-	-	-	<i>P</i>
Hardware store (defined term)		P2	<i>P2</i>	-	<i>P</i>
Health care facility (34-622(c)(20)):					
Group I		<i>P</i>	-	-	-
Group II		<i>P</i>	-	-	-
Group III		<i>P</i>	-	-	<i>P</i>
Group IV		-	-	-	-
Heliport or helistop (defined terms)	34-1231 et seq.	SP	<i>SP</i>	-	<i>SP</i>

Hobby, toy, game shops (34-622(c)(21))		P2	P2	-	P
Home care facility (defined term)		P	-	P	P
Home occupation: (defined term) No outside help With outside help	34-1771 et seq. 34-1771 et seq.	P P	P P	P AA	P AA
Hotel/motel: Efficiency (defined term) Business (defined term)	34-1801 et seq.	P P	P P	P4 P4	P P
Household and office furnishings (34-622(c)(22)): Group I Group II Group III		P P -	P P -	- - -	P P -
Insurance companies (34-622(c)(23))		P	P	-	P
Laundromat (defined term)		P	P	-	P
Laundry or dry cleaning (34-622(c)(24)): Group I Group II		P -	P -	- -	P P
Lawn and garden supply store (defined term)	34-2081	P	-	-	P
Library		P	P	-	P
Marina (defined term)	34-1862	P	P	P	P
Marina, ancillary uses (defined term)		P	-	-	EO
Mass transit depot or maintenance facility (government-operated)		-	-	-	P
Medical office (defined term)		P	P	-	P
Mini-warehouse (defined term)		-	-	-	-
Model: (defined term) Home Unit Display center	34-1951 et seq. 34-1951 et seq. 34-1951 et seq.	P P P	- - -	- - -	P P P
Multislip docking facility (defined term)		P	-	-	P
Nonstore retailers (34-622(c)(30)), all groups		P	P	-	P
Package store (defined term)	34-1261 et	P	P	-	P
Paint, glass and wallpaper (defined term)		P	P	-	P
Parks (34-622(c)(32)), public or private, groups I and II (defined term)		P	P	P	P
Parking lot: Accessory (defined term) Commercial (defined term) Garage, public parking (defined term), Temporary (defined term)	34-3049 34-2022	P P P P	P SE SE P	P - - P	P SE SE P
Personal services (34-622(c)(33)): Group I Group II Group III Group IV		P P P P	P ⁽ⁿ⁾ ^(p) P ^(q) - -	P 5 ⁽ⁿ⁾ ^(p) P 5 ^(q) P -	
Pet services (defined term)		P	P	P-	P
Pet shop (defined term)		P	P	-	P
Pharmacy (defined term)		P	P	-	P

Place of worship (defined term)	34-2051	P	<i>PEO</i>	-	<i>P</i>
Plant nursery (defined term)	34-2081	P	<i>P</i>	-	<i>P</i>
Police or sheriff's station		P	<i>P</i>	-	<i>P</i>
Pool or billiard halls		P	<i>P</i>	-	<i>P</i>
Post office		<u>P</u>	<u>P</u>	=	<u>P</u>
Printing and Publishing	34-622 (c)	=	=	=	=
Real Estate Sales Office		<u>P</u>	<u>P</u>	<u>P</u>	<u>P</u>
Recreation, commercial (34-622(c)(38)):					
Group I		P	<i>P</i>	-	<i>P</i>
Group II		P	<i>P</i>	-	<i>P</i>
Group III		P	<i>P</i>	-	<i>P</i>
Group IV		P	<i>P</i>	-	<i>P</i>
Recreational facilities: (defined term)					
Commercial (defined term)	(34-622(c)(38))	P	<i>P</i>	-	-
Private or public: (defined terms)		P	<i>P</i>	-	-
Indoor only		P	<i>P</i>	-	-
Indoor or outdoor		P	<i>P</i>	-	-
Religious facilities (defined term)	34-2051 et	-	-	-	-
Rental or leasing establishments (34-622(c)(39)):					
Group I	34-1201 et seq.	P	<i>P</i>	-	<i>P</i>
Group II	34-1352	P	<i>P</i>	-	<i>P</i>
Group III	34-3001 et seq.	P	<i>P</i>	-	<i>P</i>
Group IV		P	<i>P</i>	-	<i>P</i>
Repair shops (34-622(c)(40)):					
Group I		P	<i>P</i>	-	<i>P</i>
Group II		P	<i>P</i>	-	<i>P</i>
Group III		P	<i>P</i>	-	<i>P</i>
Group IV		-	-	-	-
Group V		-	-	-	-
Research and development laboratories (34-622(c)(41)):					
Group II		-	-	-	-
Group IV		-	-	-	-
Residential accessory uses (34-622(c)(42))		P	<i>P</i>	-	<i>P</i>
Resort, see Hotel/motel (defined term)		-	-	-	
Restaurant, fast food (defined term)		P	<i>P</i>	-	<i>P</i>
Restaurants (34-622(c)(43)): (defined term)					
Group I		P	<i>P</i>	-	<i>P</i>
Group II		P	<i>P</i>	-	<i>P</i>
Group III		P	<i>P</i>	-	<i>P</i>
Group IV		P	<i>P</i>	-	<i>P</i>
Roadside stand (defined term)	34-1714	TP	<i>TP</i>	<i>TP</i>	<i>TP</i>
Rooming house (defined term)		P	<i>P</i>	<i>P</i>	<i>P</i>
Schools, commercial (34-622(c)(45))	34-2381	P	<i>P</i>	-	<i>P</i>
Self-service fuel pumps (defined term)		-	-	-	<i>SE</i>
Self-service fuel pump station (defined term)		-	-	-	<i>SE</i>
Signs in accordance with chapter 30		P6	<i>P6</i>	-	<i>P</i>
Social services (34-622(c)(46)):					
Group I		P	<i>P</i>	-	<i>P</i>
Group II		-	-	-	-
Group III		-	-	-	-
Group IV		-	-	-	-
Specialty retail shop (34-622(c)(47)):					

Group I		P	P	P7	P
Group II		P	P	P7	P
Group III		P	P	P7	P
Group IV		P	P	P7	P
Storage: (defined terms)					
Indoor only	34-3001 et seq.	P	P	-	P
Storage, open	34-3001 et seq.	-	-	-	P
Studios (34-622(c)(49))		P	P	P	P
Supermarket (defined term)		P	P2	P 2	P
Temporary uses	34-3041 et seq.	P	P	P	P
Theater:					
Indoor	34-2471 et seq.	P	P	-	P
Drive-in	34-2471 et seq.	-	-	-	-
Towers, communication, (defined term) only when accessory to a permitted use:					
100 feet or less in height	34-1441 et seq.	-	-	-	-
Over 100 feet in height	34-1441 et seq.	-	-	-	-
Transportation services (34-622(c)(53)):					
Group I		-	-	-	
Group II		P8	P8	-	
Group III		-	-	-	
Group IV		-	-	-	
Unit of high impact, includes time-share units (defined term)	34-3071 et seq.	P	P	P	SE
Used merchandise stores (34-622(c)(54)):					
Group I		P	P	-	P
Group II		-	-	-	P
Group III		-	-	-	P
Group IV		-	-	-	P
Variety store (defined term)		P	P	P	P
Vehicle and equipment dealers (34-622(c)(55)):					
Group I	34-1352	-	-	-	P
Group II	34-1352	P	P	-	P
Group III	34-1352	P	P	-	P
Group IV	34-1352	-	-	-	P
Group V	34-1352	-	-	-	P
Warehouse:					
Mini-warehouse (defined term)		-	-	-	-
Private (defined term)		-	-	-	-
Public (defined term)		-	-	-	-
Wholesale establishment (34-622(c)(56)):					
Group I		-	-	-	-
Group II		-	-	-	-
Group III		-	-	-	P9
Group IV		-	-	-	P9

Original notes from Table 34-843843: [reprinted here only when referenced above]

- (1) Permitted only when accessory to a lawfully permitted single-family dwelling unit.
- ~~(2)~~ Only permitted where clearly subordinate and incidental to a specified principal use, only when accessory to a lawfully permitted single-family dwelling unit.
- (3) Permitted only if completely enclosed within a building.
- (4) Subject to limitations for commercial uses set forth in section 34-937.
- ~~(4)~~(5) Limited to 500 square feet when in conjunction with one dwelling unit on the same premises.
- ~~(6)~~ Use only permitted when clearly incidental to a hotel or motel. Excluding fast food restaurants for which drive-through facilities are permitted by right.
- ~~(7)~~(5) Uses anticipated include boat rentals (inflatables, sailboats, jet skis, windsurfers and the like) food stands, rental of cabanas and beach furniture, outdoor amusements including balloonist, seaplane rides, ski tows and

- similar activities, fishing and sight-seeing piers and towers. Limited to those commodities and products which are permitted to be sold at retail, provided that parking meets the requirements for retail sales.
- (8) Bail bonding, blood banks, blood donor stations and caterers permitted only by a special exception.
 - (9) Drive-through, drive-in lanes require approval through a special permit process provided in Section 34-232 (c) of the Fort Myers Beach Land Development Code.
 - (10) The total square footage of the residential uses shall not exceed the total square footage of all existing and proposed commercial uses on the subject property, and the total number of residential units shall not exceed the number of units permitted by the Fort Myers Beach Land Use Plan, which ever is less.
 - ~~(8)-(11)~~ (11) Not permitted within 500 feet of the nearest residence.

Notes applying to the Fort Myers Beach business district only:

- ~~(a)~~ *The 500-foot spacing requirements in Section 34-1264 of the Land Development Code are hereby reduced to 0 feet. However, bars or cocktail lounges shall not be permitted within 100 feet of the right-of-way of Felts Ave. (measured from any public entrance or exit of the establishment to any part of the right-of-way). The Executive Director of the Community Redevelopment Agency shall advise the Department of Community Development on all requests for on-premise consumption of alcoholic beverages.*
- ~~(b)~~ *Restaurants may serve alcoholic beverages from a cocktail lounge (or directly at dining tables) without regard to any spacing requirements and without separate administrative approval or special permit, provided that there is no indication from the outside of the restaurant that alcoholic beverages are served there.*
- ~~(c)~~ *Bed and breakfast establishments provide paying guests with overnight accommodations and a morning meal in a dwelling unit.*
- ~~(d)~~ *Excluding boats with engines larger than 10 horsepower.*
- ~~(e)~~ *Excluding bail bonding, blood banks, blood donor stations, check exchanges, collection agencies, and employment agencies.*
- ~~(f)~~ *Limited to bus stations/depots that provide scheduled intercity service in Fort Myers Beach.*
- ~~(g)~~ *Limited to dwelling units or housing units that are located on the second or third floor of a building that also contains other permitted uses.*
- ~~(h)~~ *Fuel pumps may not be approved under any circumstances.*
- ~~(i)~~ *Department stores, drugstores, hardware stores, supermarkets, and hobby, toy and game shops (defined terms) are permitted up to a maximum gross floor area of 10,000 square feet.*
- ~~(k)~~ *Limited to the sale and/or repair of antique merchandise, meaning objects of an earlier period such as furniture, jewelry, stamps, coins, miniaturized replicas, works of art, or other decorative articles that are collected primarily because of their age, history, beauty, or expectation of increasing value.*
- ~~(l)~~ *Limited to one employee who is not a resident of the dwelling unit.*
- ~~(m)~~ *Individual sleeping rooms must be located outside the primary walking zone.*
- ~~(n)~~ *Excluding coin-operated laundries for self-service laundering or dry cleaning.*
- ~~(o)~~ *Accessory parking lots (defined term) that serve land uses in the primary walking zone must be located behind the primary walking zone (see also Sections 34-1135 and 34-1137(e)).*
- ~~(p)~~ *Excluding drive-through lanes for ATMs.*
- ~~(q)~~ *Limited to health and beauty clubs or spas only.*
- ~~(r)~~ *Limited to establishments providing indoors seating for up to 150 patrons; additional seating may be provided outdoors (see also Sections 34-1137(e)(5) and 34-1137(e)(3)).*
- ~~(s)~~ *Temporary permits for roadside stands may be renewed beyond the normal two-week maximum upon the favorable written recommendation of the Executive Director of the Community Redevelopment Agency.*
- ~~(t)~~ *Must be in accordance with Section 34-1137(g) below.*
- ~~(u)~~ *Limited to water taxis only.*
- ~~(v)~~ *Also including the sale of clothing on consignment.*

(de) Property development regulations. In the same manner as for Table 1, new property development regulations for the Fort Myers Beach Downtown Business District are shown in Table 2. The terminology and notes used in this table are the same as contained in Table 34-844 of the Land Development Code, except as specifically noted.

TABLE 2

DIMENSIONAL	SPECIAL NOTES OR	C-1 ZONING	FORT MYERS BEACH
-------------	---------------------	---------------	---------------------

REGULATIONS	REGULATIONS	DISTRICT	<i>DowntownBUSINESS DISTRICT (ALL PORTIONS)</i>
Maximum density	34-2142, 2221 &22	Note (1)	Note (1)
Minimum lot area and dimensions: Minimum lot size: Residential uses (square feet): First two units in same building Each add'l unit in same building Nonresidential uses (square feet): Corner lot Interior lot Minimum lot width (feet) Minimum lot depth (feet)		7,500 3,000 7,500 7,500 75 100	7,500 3,000 5,000 2,500 25 100
Minimum setbacks: Street (feet)	34-2191 et seq. Note (3)	Variable according to the functional classification of the street or road (see Section 34-2192)	<i>All buildings shall about the "build-to" line as defined in Appendix I (a), (b), (c)</i>
Side yard (feet)	Note (5)	15	0 (d), (e)
Rear yard (feet)		25	25
Water body (feet): Gulf of Mexico Other (feet)	34-2194(a), (c)	N/A 25	N/A 25
Maximum height (feet)	34-2171 et seq.	40 35	40 35 (f)
Maximum lot coverage (percent of total lot area)		40%	60% (g)

Original notes from Table 34-8444: [reprinted here only when referenced above]

- (1) Residential development shall not exceed that density permitted by the Lee Plan for the land use category in which the property is located.
- (3) Modifications to required setbacks for arterial or collector streets, or for solar or wind energy purposes, are permitted only by special permit. See section 34-2191 et seq.
- (5) No side yard setback is required from common lot line for two-family attached or townhouse.

Notes applying to the Fort Myers Beach Downtownbusiness District only:

- (a) *Maximum bonus density allowed for multifamily residential use with the additional density for affordable housing only. However, no portion of a building or structure may materially obstruct visibility from vehicles crossing or turning onto Old San Carlos Drive. Visibility must be maintained on northwest or southeast corner lots within the triangular space bounded by the outer edges of the existing or proposed through travel lanes and a straight line connecting the two edges 50 feet from their intersection. Visibility across this triangular space must be maintained between two feet and seven feet above the average grade of each street. (These requirements supersede the vehicle visibility requirements found in Section 34-3131.)*
- (b) *Setback may be covered by a roof or built as an arcade with building above. Projections of any character projecting over or upon public property (such as doors, windows, awnings, canopies, overhangs, etc.) must comply with the requirements of the Standard Building Code for use of public property, except that fixed awnings or canopies may project over public property at the same clearances allowed for movable awnings.*
- (c) *Existing structures may be expanded at grade to the street right-of-ways without providing additional parking. Expansion above the ground level requires parking to code. Instead of placing the front wall of a building up to the "build-to" line, a landowner may construct a patio which provides outdoor seating for a permitted use in the space between the building and the "build-to" line.*
- (d) *30 feet from front setback at grade, 50 feet from front setback above grade. Where side setbacks are less than 5 feet, satisfactory evidence must be presented that the landowner will be able to maintain the exterior wall, for example through a maintenance easement granted by the adjoining landowner.*
- (e) *Minimum 5 feet one side with 50% lot width total setback required. The exterior walls of buildings must meet the fire protection requirements of Table 600 of the Standard Building Code; these requirements vary based on the amount of horizontal separation from the side lot line.*
- (f) *Above Base Flood Elevation. The additional permitted height over 35 feet that is allowed by Section 34-2171(a) does not apply in the Bonita Springs Town Center redevelopment overlay district.*
- (g) *(g) Additional height allowance for greater setbacks (sec. 34-2174 (a)) This lot coverage percentage applies to buildings only and not to storm water detention areas or hard surfaces such as parking areas, pedestrian ways, and patios.*

- | |
|---|
| <p>(h) <u>Refer to special provision for towers</u></p> <p>(i) <u>Parking garage exempt</u></p> <p>(g) (j) <u>Governed by setback requirements</u></p> |
|---|

(e) **Off-street parking.** Off-street parking is generally required in accordance with Section 34-2011 et seq. of the Land Development Code. Those requirements assume that patrons of each land use will arrive in a private automobile that will be parked in a private lot on the same premises. The Fort Myers Beach ~~Downtownbusiness~~ ~~District~~ district differs in several ways from most conventional development: its location on Estero Island allows some arrivals on foot or by bicycle, trolley, or boat; the proposed intensity of related uses will increase the number of destinations for each automobile trip; shared parking lots are encouraged by this overlay district; and some on-street parking will be provided. In response to these conditions, the following modifications to the Land Development Code shall apply:

- (1) *Location of off-street parking spaces.* Off-street parking spaces shall not be placed between the principal building and the street. This parking shall be provided in parking lots located generally behind the principal building, in order to de-emphasize the visual effect of large parking lots and to allow the front walls of buildings to become an integral part of the pedestrian-oriented streetscape being created through the master plan.
- (2) *Access, location, and design of parking spaces.* Notwithstanding any conflicting provisions of Section 34-2013 and 34-2015 of the Land Development Code:
 - a. Parking lots may be accessed by alleys, and parking spaces may be directly accessed from alleys, provided such alleys are improved in accordance with ~~this~~ ~~Section~~ ~~34-1137(j)~~ herein.
 - b. Distinct parking lot entrances to streets or alleys shall be at least 12 feet wide for one-way entrances and 20 feet wide for two-way entrances.
- (3) *Required number of parking spaces.* The number of off-street parking spaces required for any given land use by Section 34-2020 shall be reduced by one-third. Area used for outdoor restaurant seating shall not be counted in the total floor area when calculating parking requirements.
- (4) *Joint use of off-street parking lots.* Notwithstanding any conflicting provisions of Section 34-2018 of the Land Development Code:
 - a. Joint or shared use of off-street parking is specifically encouraged in the Fort Myers Beach ~~Downtownbusiness~~ ~~District~~ district. To this end, joint-use parking may be approved administratively by the Town Manager ~~Lee County Community Redevelopment Agency~~ as an alternative to; the special permit process found in Section 34-203(g)(5), in accordance with the following provisions of this sub-section (4).
 - b. Joint or shared parking lots must be located on the same block as the land uses they serve. Signs shall be placed to inform motorists of the allowable use of shared lots. Applicants are also encouraged to include joint space for off-street loading in these lots.

- c. In joint or shared lots, the same parking space may fully satisfy the off-street parking requirement for two different land uses provided their peak parking demands clearly occur at different times. When the peak demands do not clearly occur at different times, each two parking spaces can replace three parking spaces that would otherwise be required by the combined uses (after the reduction found in subsection (3) above).
- d. ~~Town~~CRA administrative approval for joint or shared use of off-street parking can be granted only when all users of the shared lot have chosen to be governed by this redevelopment overlay district in accordance with Sections 34-1137 (a), and (b) above. Requests for administrative approval shall include the following:
 - 1. A notarized statement from all property owners involved indicating the use of each property and to what extent the activities of each separate building or use which create a demand for parking shall occur at different times.
 - 2. Written agreements, covenants, contracts and the like, acceptable to the ~~Town~~CRA, which ensure that the parking area is to be used jointly and establish the responsibility for maintenance.
- e. Administrative approvals granted by the ~~Town~~CRA shall be recorded in the same manner as other administrative approvals granted under the Land Development Code.

(f) **Off-street loading.** Space for off-street loading is generally required in accordance with Section 34-1981 et seq. of the Land Development Code. Conventional development is designed so that the unloading of products or materials from large trucks occurs entirely off-street, often in space earmarked for that purpose. The Fort Myers Beach ~~Downtown~~business ~~D~~istrict differs from conventional development by eliminating large retailers and industrial uses, both of which usually require a separate area for off-street loading to or from large trucks. In addition, the more intense clustering of commercial uses along street frontages precludes a separate loading space for each use. Accordingly, and notwithstanding any conflicting provisions of Section 34-1981 et seq. of the Land Development Code:

- (1) *Off-street loading area.* Off-street loading areas shall not be placed between the principal building and the street right-of-way line. A separate loading area is not required, but when provided, the surfaced portions of loading areas are not required to be set back from side or rear lot lines.
- (2) *Interference with parking areas.* Establishments are encouraged to schedule deliveries before or after their normal business hours. Deliveries that are made during normal hours may not obstruct parking aisles or parking entrances.

(g) **Sandwich signs.** ~~The Town's~~Lee-County's sign regulations are found in Chapter 30 of the Land Development Code, and additional guidance is provided through the design guidelines discussed in Section 34-114337(ee) above. With certain exceptions, signs in ~~Fort Myers Beach~~Lee-County must be placed on private property. In light of the urban character of the Fort Myers Beach ~~Downtown~~ District, signs may be placed in the ~~Downtown~~business ~~D~~istrict abutting or extending over public property such as sidewalks despite the general prohibition in Section 30-5 of sandwich-board signs, "A" signs, or other types of portable signs which are portable and readily movable from place to place. Single- or double-

faced sandwich signs may be placed on the same premises or on sidewalks directly in front of the premises provided that the sign is placed indoors after business hours, is not illuminated, and, if placed on a public sidewalk, does not exceed 24 inches in width.

(h) **Development standards.** In a similar manner as for Tables 1 and 2, new development standards for the Fort Myers Beach Downtown Business District are shown in Table 3. The terminology in this table follows that in Chapter 10 of the Land Development Code, except as specifically noted.

TABLE 3

TYPE OF DEVELOPMENT STANDARD	FOUND WHERE IN LAND DEVELOPMENT CODE	SUBSTANCE OF CURRENT REGULATIONS	FORT MYERS BEACH <u>Downtown Business District</u> (ALL PORTIONS)
Open space: small developments large developments	10-413(b)	20% 30%	Note (a) Note (a)
Minimum required buffering: commercial adjoining existing residential development commercial adjoining street rights-of-way	10-414(a)	15-foot buffer and 8-foot-high fence, wall or berm	None
	10-415(b)	10-foot-wide landscaped strip	Note (b)
Storm water detention Intersection separation	10-321 et seq. 10-285	Required for each individual parcel Arterials: 660 ft. Collectors: 330 ft. Local streets: 125 ft. Access roads or access ways: 60 ft.	See Section 5(I) below <u>Esteros Blvd. Old 41:</u> note (c) Other streets: note (d) Note (e)
<p>Notes applying to the Fort Myers Beach business district only:</p> <p>(a) There is no minimum open space requirement comparable to that required by Section 10-413.</p> <p>(b) There is no minimum buffer requirement adjoining rights-of-way comparable to that required by Section 10-414(f).</p> <p>(c) Vehicular access to private parking spaces shall be via the side streets (see Section 34-1137(j) below). No new access points shall be allowed directly to Old San Carlos Drive, and existing access points (other than</p>			

existing alleys) shall be removed when parking areas are reconfigured to conform to these regulations.
(d) *Vehicular access to parking spaces shall be via the side streets wherever possible (see Section 34-1137(j) below). New access points shall be allowed to streets other than Old San Carlos Drive only where side street access is not shown in the master plan (see Section 34-1135), or where side street access is not feasible or inferior to the circulation pattern shown in the master plan (as determined by the Town Manager-Executive Director of the Community Redevelopment Agency).*

~~(d) **Storm water management.** This redevelopment overlay district contains an integral water management plan for the entire Fort Myers Beach business district. Surface water flows will continue to be directed away from Old San Carlos Drive and Estero Boulevard and towards Matanzas Pass under this plan, but water quality treatment and minimal storm attenuation will be added. Retention facilities, control structures, and outfalls will be constructed by the Lee County Community Redevelopment Agency. The construction of inlets and drainage piping within each block is the responsibility of landowners on that block at the time of development or redevelopment, and must be sized to serve the entire block. Storm water runoff west of Old 41 will be directed into exfiltration trenches; runoff east of Old 41 will flow into a detention lake, or as the surface water management plan may be amended from time to time. The engineering details for all facilities constructed by private owners in conjunction with development activity shall be subject to the review and approval of the Development Services director.~~

(i) **Building Height Limitations.** Building Heights are limited to 40' above Base Flood Elevation allowing a maximum of a three story building. Additional building heights in return for greater setbacks is not an available option under the Master Plan.

~~(k) **Building regulations.** The purpose of this subsection is to encourage the continued use or reuse of existing buildings in the Fort Myers Beach Downtown business District and to encourage the creation of awnings and canopies over sidewalks and pedestrian walkways.- Accordingly, and notwithstanding any conflicting provisions of Chapter 6 of the Land Development Code:~~

(1) *Existing uses.* Existing buildings may continue their existing use, provided such buildings are maintained in a safe and sanitary condition and such use was legal at the time of adoption of this ~~ordinance~~ resolution. Buildings left vacant for a time period exceeding 2 years shall be analyzed prior to reoccupancy for structural strength, stability, sanitation, adequate light and indoor air quality, adequate plumbing, mechanical, gas, and electrical systems, and safety to life and property from fire and other hazards affecting the safe use and occupancy of the building. The Building Official may waive one or more of the above requirements based upon the type occupancy being requested. Findings of the analysis shall be submitted to the Building Official as a part of the application for a permit to reoccupy the building.

(2) *Alterations, Repairs, and Rehabilitation.* Alterations, repairs, or rehabilitation work may be made to any existing building without requiring the building to comply with all the requirements of the building codes provided that the alteration, repair, or rehabilitation work conforms to the requirements of the Building, Plumbing, Mechanical, Gas, and Electrical Codes for new construction. The Building Official shall determine the extent to which the remainder of the building shall be made to conform to the requirements of these codes for existing construction, consistent with the purposes of this subsection.

(3) *Change of a building's use or occupant.* When a new use is proposed for an existing building, or a new occupant wishes to occupy an existing building, the following shall apply:

a. If the occupancy classification of an existing building or structure is changed to a more hazardous occupancy (based on the life safety and fire hazard involved), the building, electrical, gas, mechanical, and plumbing systems shall be made to conform to the intent of the technical codes as required by the Building Official.

b. If a new use falls within the same occupancy classification as the previous use, the requirement in subsection a. shall not apply.

c. The mere change of occupant within the same occupancy classification, or the upgrading of a certificate of compliance to a certificate of occupancy, shall not cause the requirement in subsection a. to apply.

(4) *Awnings and canopies.* The installation of awnings and canopies over sidewalks and pedestrian walkways is specifically encouraged, (see design guidelines referred to in Section 34-1135 (e) above). Awnings and canopies that extend over public property are regulated by Chapter 22 of the Standard Building Code. In order to allow and encourage the implementation of the master plan, landowners may construct fixed awnings and canopies that extend over public property to the same extent as allowed by the Standard Building Code for movable awnings, notwithstanding the limitations found in Section 34-2191 of the Land Development Code.

Sec. 34-1146~~38~~ Procedures for approval and for appeals of administrative decisions.

(a) *Approval process.* In order to minimize the time required for review of permit requests in the Fort Myers Beach ~~Downtown~~business District, all staff any review conducted by the Community Redevelopment Agency staff shall occur simultaneously with review by other county agencies. County agencies shall be responsible for notifying the Community Redevelopment Agency staff immediately upon receipt of relevant permit applications. The Community Redevelopment Agency staff shall be responsible for conducting its review within the same time period as allotted to those agencies. Permit applicants are encouraged to consult with permitting departments and the Community Redevelopment Agency staff prior to submitting applications.

(b) *Appeals of administrative decisions.* Administrative decisions may be appealed in accordance with existing procedures for such appeals.

Sec. 34-1139 ~~Legal Description of Overlay District~~

The Fort Myers Beach Redevelopment Overlay District is legally described as follows:

A tract or parcel of land lying on Estero Island, Plat Book 3 at Page 26 and Heitman's Bonita Springs Townsite, Plat Book 6 at Page 24, Lee County Records in Section 35, Township 47 South, Range 25 East, Bonita Springs, Lee County, Florida which tract or parcel is described as follows: Beginning at the intersection of the center lines of Abernathy Street and Felts Avenue as shown on said Plat of Bonita Springs and run Westerly along the centerline of said Abernathy Street, across Old 41 Road and continue along the centerline of Abernathy Street (Fifth Street, as shown on said Plat of Heitman's Bonita Springs Townsite) to the centerline of Front Street; thence run Northerly along said centerline to the centerline of Childers Street, thence run Westerly and Southwesterly along the centerline of Pennsylvania Avenue to an intersection with a southerly prolongation of the centerline of East Drive; thence run Northerly along said prolongation and said centerline to the southerly shore of Imperial River; thence run Easterly along said southerly shore to an intersection with said centerline of Felts Avenue; thence run Southerly along said centerline to the Point of Beginning.

SECTION TWO:—_AMENDMENTS TO LAND DEVELOPMENT CODE APPENDIX

There is hereby created Appendix LI to the Land Development Code. This Appendix will include a reduced copy of three maps that pictorially describe the boundaries of the Downtown District identified as Map 1-Proposed Land Use by District-Fort Myers Beach Core Area Overlay Zoning Master Plan; Map 2-Storm Water Management Plan-Fort Myers Beach Core Area Overlay Zoning Master Plan; Map 3-Illustrative Master Plan ~~the Fort Myers Beach Master Site Plan and Surface Water Management Plan-Fort Myers Beach Core Area Overlay Zoning Master Plan.~~

SECTION THREE:—_SEVERABILITY

It is the legislative intent that if any section, subsection, sentence, clause or provision of this Ordinance is held to be invalid or unconstitutional by any court of competent jurisdiction, such portion will be deemed a separate provision and the remaining provisions of this ordinance will not be affected. It is the legislative intent of the Town Council ~~Board of County Commissioners~~ that this ordinance would have been adopted had such unconstitutional provision not be included therein.

SECTION FOUR: CONFLICTS OF LAW

Whenever the requirements or provisions of this Ordinance are in conflict with the requirements or provisions of any other lawfully adopted ordinance or statute, the most restrictive requirements will apply.

SECTION FIVE:—_CODIFICATION, INCLUSION IN CODE AND SCRIVENER'S ERRORS

The Town Council ~~Board of County Commissioners~~ intends for the provisions of this ordinance to become and be made a part of the Fort Myers Beach Lee County Land Development Code; and that sections of this ordinance may be renumbered or relettered and that the word "ordinance" may be changed to "section," "article," or such other appropriate word or phrase in order to accomplish such intention; and

regardless of whether such inclusion in the code is accomplished, sections of this ordinance may be renumbered or relettered and typographical errors which do not affect the intent may be authorized by the Town Manager~~County Administrator~~, or his designee, without need of public hearing.

SECTION SIX: ———EFFECTIVE DATE

This ordinance will take effect immediately upon adoption~~receipt~~ by the ~~Board of County Commissioners of Lee County, Florida, of the official acknowledgment from the Secretary of State of Florida that it has been filed with that office.~~

THE FOREGOING ORDINANCE was offered by ~~Councilmember~~~~Commissioner~~ Ray Judah ~~—————~~ Cereceda who moved its adoption. The motion was seconded by ~~Councilmember~~~~Commissioner~~ John Manning ~~—————~~ Murphy and, being put to a vote, the vote was as follows:

	<u>Anita Cereceda</u>	<u>aye</u>	<u>JOHN E. ALBION</u>	<u>Aye</u>
	<u>Ted Fitzsimons</u>	<u>aye</u>	<u>RAY JUDAH</u>	
<u>Aye</u>	<u>Rusty Isler</u>	<u>aye</u>	<u>DOUGLAS R. ST. CERNY</u>	<u>Aye</u>
	<u>Garr Reynolds</u>	<u>aye</u>	<u>JOHN E. MANNING</u>	<u>Aye</u>
	<u>Ray Murphy</u>	<u>aye</u>	<u>ANDREW W. COY</u>	<u>Aye</u>

DULY PASSED AND DATED THIS 3rd~~16th~~ DAY OF AUGUST~~September~~, 1996~~5~~.

ATTEST:
OF COUNTY COMMISSIONERS
~~CHARLIE G~~
Marsha Segal-George~~REEN~~, CLERK
FLORIDA

Town Council of Fort Myers Beach, Florida~~BOARD~~

OF LEE COUNTY,

By: _____
Clerk~~Deputy Clerk~~

By: _____
Mayor~~Chairman~~

APPROVED AS TO FORM BY:

Attorney

Town Attorney~~Office of the County~~

ORDINANCE No. 98-13

COPY

AN ORDINANCE AMENDING THE TOWN OF FORT MYERS BEACH CODE OF ORDINANCES CHAPTER 62, TOWN OF FORT MYERS BEACH OPEN ALCOHOLIC BEVERAGE CONTAINER ORDINANCE; SECTION SIX: PENALTY; PROVIDING AUTHORITY; AMENDMENT TO CHAPTER 62, SECTION SIX: PENALTY; SEVERABILITY. AND EFFECTIVE DATE.

IT IS HEREBY ORDAINED BY THE TOWN OF FORT MYERS BEACH AS FOLLOWS:

SECTION 1. Authority. This Ordinance is enacted pursuant to the provisions of Chapter 95-494, Laws of Florida, Chapter 166, Florida Statutes, and other applicable provisions of law.

SECTION 2. Amendment To CHAPTER 62. CHAPTER 62. SECTION SIX: Penalty, of the "Town of Fort Myers Beach Open Alcoholic Beverage Container Ordinance" is hereby amended to read as follows:

62. SECTION SIX: Penalty

Any person convicted of violation of SECTION ~~FOUR THREE~~, Subsection A. or B. of this Ordinance shall be punished by a fine not to exceed Five Hundred Dollars (\$500.00) or by imprisonment in the County Jail for a period not to exceed sixty (60) days, or both, such fine and imprisonment for each such offense.

Any person who violates any of the provisions of SECTION ~~FOUR THREE~~, Subsection C. of this ordinance shall be guilty of a non-criminal moving traffic violation as provided by Florida Statute Section 316.193.

SECTION 3. Severability. If any one of the provisions of this ordinance should be held contrary to any express provision of law or contrary to the policy of express law, although not expressly prohibited, or against public policy, or shall for any reason whatsoever be held invalid, then such provision shall be null and void and shall be deemed separate from the remaining provisions of this ordinance, and in no way affect the validity of all other provisions of this ordinance.

SECTION 4. Effective Date. This ordinance shall become effective immediately upon its adoption.

The foregoing ordinance was enacted by the Town Council upon a motion by Council Member Murphy and seconded by Council Member Reynolds and, upon being put to a vote, the result was as follows:

Anita T. Cereceda	aye
Daniel Hughes	aye
John Mulholland	aye
Garr Reynolds	aye
Ray Murphy	aye

DULY PASSED AND ENACTED this 2nd day of November, 1998.

ATTEST:

TOWN OF FORT MYERS BEACH

By: _____
Marsha Segal-George, Town Clerk

By: _____
Anita T. Cereceda, Mayor

Approved as to form by:

Richard V.S. Roosa, Town Attorney

COPY

TOWN OF FORT MYERS BEACH, FLORIDA

ORDINANCE NO. 98-14

AN ORDINANCE ENTITLED "ADOPTION OF THE FORT MYERS BEACH COMPREHENSIVE PLAN," REPLACING IN ITS ENTIRETY THE TRANSITIONAL COMPREHENSIVE PLAN OF THE TOWN OF FORT MYERS BEACH, FLORIDA, IN ORDER TO CONTROL FUTURE LAND USE, GUIDE PUBLIC FACILITIES, AND PROTECT NATURAL RESOURCES PURSUANT TO THE LOCAL GOVERNMENT COMPREHENSIVE PLANNING AND LAND DEVELOPMENT REGULATION ACT (CHAPTER 163, PART II, *FLORIDA STATUTES*). THIS COMPREHENSIVE PLAN IS CONTAINED WITHIN A SINGLE VOLUME THAT INCLUDES:

- CHAPTER 1, INTRODUCTION
- CHAPTER 2, "ENVISIONING TOMORROW'S FORT MYERS BEACH"
- CHAPTER 3, COMMUNITY DESIGN ELEMENT
- CHAPTER 4, FUTURE LAND USE ELEMENT
- CHAPTER 5, COASTAL MANAGEMENT ELEMENT
- CHAPTER 6, CONSERVATION ELEMENT
- CHAPTER 7, TRANSPORTATION ELEMENT
- CHAPTER 8, UTILITIES ELEMENT
- CHAPTER 9, STORMWATER MANAGEMENT ELEMENT
- CHAPTER 10, RECREATION ELEMENT
- CHAPTER 11, CAPITAL IMPROVEMENTS ELEMENT
- CHAPTER 12, HOUSING ELEMENT
- CHAPTER 13, HISTORIC PRESERVATION ELEMENT
- CHAPTER 14, INTERGOVERNMENTAL COORDINATION ELEMENT
- CHAPTER 15, PROCEDURES AND MONITORING

THIS ORDINANCE ALSO DEFINES ITS PURPOSE AND INTENT; IDENTIFIES THE TITLE AND CONTENTS OF THE NEW COMPREHENSIVE PLAN; REPEALS THE TRANSITIONAL COMPREHENSIVE PLAN; AND PROVIDES FOR APPLICABILITY, CONFLICTS, CODIFICATION, SEVERABILITY, AND AN EFFECTIVE DATE.

WHEREAS, Chapter 166, *Florida Statutes*, empowers the Town Council of the Town of Fort Myers Beach to prepare and enforce a comprehensive plan for the future development of the town; and

WHEREAS, Sections 163.3161 through 163.3217, *Florida Statutes*, empower and require the Town Council to: (a) plan for the town's future development and growth; (b) adopt a comprehensive plan to guide the future growth and development within the town; (c) implement the adopted comprehensive plan through an appropriate land development code; and (d) establish and maintain appropriate administrative procedures to carry out the plan and code; and

WHEREAS, the Fort Myers Beach Local Planning Agency has been established pursuant to Fort Myers Beach Ordinances 96-2 and 96-25; and

WHEREAS, public participation procedures for the new comprehensive plan were established by Fort Myers Beach Resolution 97-5; and

WHEREAS, the Fort Myers Beach Local Planning Agency, empowered by the above-cited laws and ordinances, prepared a new comprehensive plan for the Town of Fort Myers Beach to replace the transitional comprehensive plan adopted pursuant to the Town Charter to more adequately address the unique challenges presented by future growth in the town; and

WHEREAS, the Fort Myers Beach Local Planning Agency, in the preparation of the new comprehensive plan, has performed necessary research and studies; conducted three public workshops; participated in five joint workshops with the Town Council; held twice-monthly public meetings to review progress on the new plan; effectively provided for full public participation; provided notice to real property owners; broadly disseminated proposals and alternatives; provided opportunities for written and verbal comments, open discussion, and consideration and response to public and official comments; and prepared supporting data and analysis documentation as background and justification for the new comprehensive plan's goals, objectives, and policies; and

WHEREAS, pursuant to Section 163.3174, the Fort Myers Beach Local Planning Agency conducted a formal public hearing, with due notice having been provided, and having considered all comments received during the public hearing, recommended on April 21, 1998, that the Town Council adopt the new Fort Myers Beach Comprehensive Plan; and

WHEREAS, pursuant to Section 163.3184, the Fort Myers Beach Town Council conducted a formal public hearing beginning on May 18, 1998, and continuing on May 19 and 21, with due public notice having been provided, to obtain public comment; and having considered all written and oral comments received during this public hearing, and having provided for necessary revisions, on May 21, 1998, voted to transmit the proposed comprehensive plan in its entirety to the state land planning agency (the Department of Community Affairs) for review and comment; and

WHEREAS, the Department of Community Affairs, by letter dated August 14, 1998, forwarded its objections, recommendation, and comments on the proposed comprehensive plan; and

WHEREAS, pursuant to Section 163.3184, the proposed comprehensive plan was revised in view of comments from the Department of Community Affairs; and

WHEREAS, pursuant to Section 163.3184, the Town Council of the Town of Fort Myers Beach held a second public hearing on December 21, 1998, on the revised version of the comprehensive plan, with due public notice having been provided, and considered all oral and written comments, including those of the Local Planning Agency and the Department of Community Affairs; and

WHEREAS, in the exercise of its authority, the Town Council of the Town of Fort Myers Beach has determined it necessary and desirable to adopt in its entirety the new Fort Myers Beach Comprehensive Plan in order to preserve and enhance present advantages; encourage the most appropriate use of land, water, and natural resources; overcome present handicaps; and deal effectively with future problems that may result from the use and development land within the Town of Fort Myers Beach.

NOW THEREFORE BE IT ORDAINED BY THE TOWN COUNCIL OF FORT MYERS BEACH, FLORIDA, THAT:

SECTION ONE: PURPOSE AND INTENT

This ordinance is enacted to carry out the purpose and intent of, and exercise the authority set out in, the Local Government Comprehensive Planning and Land Development Regulation Act, Sections 163.3161 through 163.3217 and Chapter 166, *Florida Statutes*, as amended.

SECTION TWO: TITLE OF NEW COMPREHENSIVE PLAN

The new comprehensive plan shall be entitled the "Fort Myers Beach Comprehensive Plan."

SECTION THREE: CONTENTS OF THE FORT MYERS BEACH COMPREHENSIVE PLAN

(a) The Town of Fort Myers Beach shall publish a single-volume document that contains the adopted portions of the Fort Myers Beach Comprehensive Plan and much of the extensive research upon which this plan was based. This volume shall be organized into 15 chapters, as follows:

- Chapter 1, Introduction,*
- Chapter 2, "Envisioning Tomorrow's Fort Myers Beach"*
- Chapter 3, Community Design Element*
- Chapter 4, Future Land Use Element*
- Chapter 5, Coastal Management Element*
- Chapter 6, Conservation Element*
- Chapter 7, Transportation Element*
- Chapter 8, Utilities Element*
- Chapter 9, Stormwater Management Element*
- Chapter 10, Recreation Element*
- Chapter 11, Capital Improvements Element*
- Chapter 12, Housing Element*
- Chapter 13, Historic Preservation Element*
- Chapter 14, Intergovernmental Coordination Element*
- Chapter 15, Procedures and Monitoring*

(b) Only the following specific portions of this volume are being formally adopted through this ordinance as its new comprehensive plan under Sections 163.3161 through 163.3217, *Florida Statutes*, as amended:

- All of Chapters 1, 2, and 15.*
- All goals, objectives, and policies found in Chapters 3 through 14.*
- The "Future Land Use Map" (Figure 16 in the Future Land Use Element).*
- The "Future Transportation Map" (Figure 18 in the Transportation Element).*
- The five-year schedule of capital improvements (Table 11-7 in the Capital Improvements Element)*

(c) The published volume shall provide, in its opening chapter, this same description of which portions of the volume have been formally adopted by the town.

(d) The published volume is incorporated by this reference as an integral part of this ordinance and it shall be placed on file with the Town Clerk. It shall remain available for inspection by the public at Town Hall, and a copy shall be placed at the reference desk of the Fort Myers Beach Public Library. Additional copies shall also be sold at Town Hall for a reasonable publication charge.

SECTION FOUR: REPEAL OF TRANSITIONAL COMPREHENSIVE PLAN

(a) Section 15.07 of the Town Charter adopted, as a transitional comprehensive plan, the then-existing Lee County Comprehensive Plan. By virtue of this ordinance, the Town of Fort Myers will no longer recognize the Lee County Comprehensive Plan as its transitional comprehensive plan, and that plan shall be of no effect as to any actions occurring after the effective date of this ordinance.

(b) The Town Charter also adopted the then-existing Lee County land development regulations as its transitional land development regulations. This ordinance does not repeal or replace those transitional land development regulations, although such replacement will occur in the near future by separate ordinance. However, the explicit terms of the new comprehensive plan will supersede certain land development regulations by virtue of being more restrictive. Conflicts shall be resolved by through the procedures found in Chapter 15 of the new Fort Myers Beach Comprehensive Plan.

SECTION FIVE: APPLICABILITY AND EFFECT

The applicability and effect of the Fort Myers Beach Comprehensive plan shall be as provided by its specific terms, by the Local Government Comprehensive Planning and Land Development Regulation Act, Sections 163.3161 through 163.3217, *Florida Statutes*, and by this ordinance. No public or private development shall be permitted except in conformity with the Fort Myers Beach Comprehensive Plan, and all land development regulations and development orders shall be consistent with this plan.

SECTION SIX: CONFLICTS OF LAW

Whenever the requirements or provisions of this ordinance are in conflict with the requirements or provisions of any other lawfully adopted ordinance or statute, the most restrictive requirements will apply.

SECTION SEVEN: CODIFICATION AND SCRIVENER'S ERRORS

The Town Council anticipates that this comprehensive plan will be revised in the future through amendments adopted pursuant to state law. Sections of this comprehensive may be renumbered or relettered and typographical and grammatical errors can be corrected where authorized by the Town Manager without requiring a public hearing, provided the changes do not affect the intent or application of this comprehensive plan. Any such changes will be reflected in the town's next publication of this comprehensive plan or portion thereof.

SECTION EIGHT: SEVERABILITY

It is the legislative intent that if any section, subsection, sentence, clause, map, goal, objective, or policy of this ordinance is held to be invalid, unenforceable, or unconstitutional by any court of competent jurisdiction, such portion will be deemed a separate provision, and the remaining provisions of this ordinance will not be affected. It is the legislative intent of the Town Council that this ordinance would have been adopted had such unconstitutional provision not be included therein.

SECTION NINE: EFFECTIVE DATE

This ordinance shall become effective on January 1, 1999.

THE FOREGOING ORDINANCE was offered by Councilmember Cereceda who moved its adoption. The motion was seconded by Councilmember Murphy and, being put to a vote, the vote was as follows:

Anita Cereceda	<u>aye</u>
Daniel Hughes	<u>aye</u>
John Mulholland	<u>aye</u>
Garr Reynolds	<u>no</u>
Ray Murphy	<u>aye</u>

DULY PASSED AND ADOPTED THIS 21st DAY OF DECEMBER, 1998

ATTEST:

By: Maury Seal-George
Town Clerk

Town Council of Fort Myers Beach, Florida
By: [Signature]
Mayor

APPROVED AS TO FORM BY:
[Signature]
Town Attorney

ORDINANCE No. 03-03

AN ORDINANCE AMENDING THE ZONING CHAPTER (CHAPTER 34) OF THE TOWN OF FORT MYERS BEACH LAND DEVELOPMENT CODE AND ADOPTING AN INTERIM ZONING MAP THAT ASSIGNS A NEW ZONING DISTRICT TO ALL LAND IN THE TOWN; PROVIDING AUTHORITY; REPEALING CHAPTER 34 "ZONING" OF THE TRANSITIONAL LAND DEVELOPMENT REGULATIONS; REPEALING APPENDIX L OF THE TRANSITIONAL LAND DEVELOPMENT REGULATIONS; REPEALING ORDINANCES 96-02, 96-25, AND 00-03 "LOCAL PLANNING AGENCY"; ADOPTING AN INTERIM ZONING MAP THAT ASSIGNS A NEW ZONING DISTRICT TO ALL LAND IN THE TOWN; ADOPTING A NEW CHAPTER 34 OF THE LAND DEVELOPMENT CODE ENTITLED "ZONING DISTRICTS, DESIGN STANDARDS, AND NONCONFORMITIES" WHICH PROVIDES ARTICLE I IN GENERAL; ARTICLE II ZONING PROCEDURES, Division 1 Generally, Division 2 Town Council, Division 3 Local Planning Agency, Division 4 Applications and Procedures, Division 5 Public Hearings and Review, and Division 6 Interpretations, Enforcement, and Special Administrative Actions; ARTICLE III ZONING DISTRICT REGULATIONS, Division 1 Mapping of Zoning Districts, Division 2 Allowable Land Uses in Each Zoning District, Division 3 Explanation of Property Development Regulations, Division 4 Conventional Zoning Districts, Division 5 Redevelopment Zoning Districts, Division 6 Planned Development Zoning Districts, Division 7 Commercial Design Standards, and Division 8 Residential Design Standards; ARTICLE IV SUPPLEMENTAL REGULATIONS, Division 1 Generally, Division 2 Accessory Uses, Buildings, and Structures, Division 3 Sexually-oriented Businesses, Division 4 Aircraft, Division 5 Alcoholic Beverages, Division 6 Animals, Division 7 Animal Clinics and Kennels, Division 8 Automotive Businesses, Division 9 Bus Stations and Transit Terminals, Division 10 Care and Assisted Living Facilities, Division 11 Commercial Antennas and Communication Towers, Division 12 Drug Paraphernalia, Division 13 Environmentally Sensitive Areas, Division 14 Essential Services, Essential Service Equipment, and Essential Service Buildings, Division 15 Excavations, Division 16 Reserved, Division 17 Fences, Walls, and Entrance Gates, Division 18 Home Occupations; Live/Work and Work/Live Dwellings, Division 19 Hotels, Motels, and Bed-and-Breakfast Inns, Division 20 Reserved, Division 21 Marine Facilities and Live-Aboard Vessels, Division 22 Reserved, Division 23 Mobile Homes, Division 24 Moving of Buildings, Division 25 Off-Street Loading Areas, Division 26 Parking, Division 26-A Performance Standards, Division 27 Places of Worship and Religious Facilities, Division 28 Reserved, Division 29 Private Clubs and Membership Organizations, Division 30 Recreation Facilities, Division 31 Recreational Vehicles, Division 32 Schools, Division 32-A Short-Term Rentals, Division 33 Signs, Division 34 Special Events, Division 35 Reserved, Division 36 Storage Facilities and Outdoor Display of Merchandise, Division 37 Subordinate and Temporary Uses, Division 38 Tall Structures, Division 38-A Tattoo Studios and Body-Piercing Salons, Division 39 Use, Occupancy, Construction, and Moving Regulations, Division 40 Vehicle Visibility, and Division 41 Water-Oriented Rentals; ARTICLE V NONCONFORMITIES, Division 1 Generally, Division 2 Nonconforming Buildings, Division 3 Nonconforming Uses, and Division 4 Nonconforming Lots; PROVIDING SEVERABILITY; AND ESTABLISHING AN EFFECTIVE DATE.

IT IS HEREBY ORDAINED BY THE TOWN OF FORT MYERS BEACH AS FOLLOWS:

SECTION 1. AUTHORITY. This Ordinance is enacted pursuant to the provisions of Chapter 95-494, Laws of Florida, Chapters 163 and 166, Florida Statutes, and other applicable provisions of law.

SECTION 2. REPEAL OF CHAPTER 34 “ZONING” OF THE TRANSITIONAL LAND DEVELOPMENT REGULATIONS. By the authority of Section 15.08 (c) of the Town Charter, Chapters 34 of the transitional land development regulations are hereby repealed. Transitional Chapter 34 is entitled ZONING and contains the following articles: Article I In General, Article II Administration, Article III Reserved, Article IV Planned Developments, Article V Comprehensive Planning; The Lee Plan; Article VI District Regulations, Article VII Supplementary District Regulations; and Article VIII Nonconformities.

SECTION 3. REPEAL OF APPENDIX L OF THE TRANSITIONAL LAND DEVELOPMENT REGULATIONS. By the authority of Section 15.08 (c) of the Town Charter, APPENDIX L of the transitional land development regulations is hereby repealed. Transitional Appendix L was adopted by Fort Myers Beach Ordinance 96-20 as the Master Site Plan for the Fort Myers Beach Downtown District (also known as the core area overlay district).

SECTION 4. REPEAL OF ORDINANCES 96-02, 96-25, AND 00-03 “LOCAL PLANNING AGENCY.” By the authority of Article 10 of the Town Charter, Fort Myers Beach Ordinances No. 96-02, 96-25, and 00-03 which established and governed the Fort Myers Beach Local Planning Agency, are hereby repealed. Pursuant to Section 5 below, the terms of Ordinances 96-02, 96-25, and 00-03 are being incorporated, with modifications, into the land development code as §§ 34-111–34-120 and 34-123 of Chapter 34.

SECTION 5. ADOPTION OF INTERIM ZONING MAP. Exhibit A, a copy of which is attached to this ordinance, is hereby adopted as the interim zoning map for the Town of Fort Myers Beach. In accordance with Section 34-613 of the new land development code, the interim zoning map assigns all land in the Town of Fort Myers to one of the new zoning districts established by the new Chapter 34 of the land development code (see Exhibit B). The new zoning districts shall take effect immediately and shall replace the previous zoning districts that had been assigned to all land in the Town of Fort Myers Beach. Previous approvals of variances, special exceptions, special permits, and other zoning actions that did not change zoning district boundaries cannot be shown on the interim zoning map due to its scale but are not affected by the adoption of the interim zoning map.

SECTION 6. ADOPTION OF NEW CHAPTER 34 OF THE LAND DEVELOPMENT CODE. The new Chapter 34 of the Town of Fort Myers Beach land development code entitled “ZONING DISTRICTS, DESIGN STANDARDS, AND NONCONFORMITIES” shall be as contained in the attached Exhibit B. Entirely new language is indicated with underlining. Language being repealed from the transitional land development regulations is indicated with strike-throughs. Language being readopted by this ordinance is neither underlined nor struck through. The new Chapter 34 contains the following articles, divisions, and subdivisions:

ARTICLE I. IN GENERAL

ARTICLE II. ZONING PROCEDURES

Division 1. Generally

Division 2. Town Council

Division 3. Local Planning Agency

Division 4. Applications and Procedures

Subdivision I. General Procedures

Subdivision II. Additional Procedures for Planned Development Zoning Districts

Division 5. Public Hearings and Review

Division 6. Interpretations, Enforcement, and Special Administrative Actions

ARTICLE III. ZONING DISTRICT REGULATIONS

Division 1. Mapping of Zoning Districts

Division 2. Allowable Land Uses in Each Zoning District

Division 3. Explanation of Property Development Regulations

Division 4. Conventional Zoning Districts

Division 5. Redevelopment Zoning Districts

Subdivision I. Generally

Subdivision II. DOWNTOWN Zoning District

Subdivision III. SANTINI Zoning District

Subdivision IV. VILLAGE Zoning District

Subdivision V. CB Zoning District

Division 6. Planned Development Zoning Districts

Subdivision I. Generally

Subdivision II. RPD (Residential Planned Development) Zoning District

Subdivision III. CPD (Commercial Planned Development) Zoning District

Subdivision IV. Former Planned Development Zoning Districts

Division 7. Commercial Design Standards

Division 8. Residential Design Standards

ARTICLE IV. SUPPLEMENTAL REGULATIONS

Division 1. Generally

Division 2. Accessory Uses, Buildings, and Structures

Division 3. Sexually-oriented Businesses

Division 4. Aircraft

Division 5. Alcoholic Beverages

Division 6. Animals

Division 7. Animal Clinics and Kennels

Division 8. Automotive Businesses

Division 9. Bus Stations and Transit Terminals

Division 10. Care and Assisted Living Facilities

Division 11. Commercial Antennas and Communication Towers

Division 12. Drug Paraphernalia

Division 13. Environmentally Sensitive Areas

Division 14. Essential Services, Essential Service Equipment, and Essential Service Buildings

Division 15. Excavations

Division 16. Reserved.

Division 17. Fences, Walls, and Entrance Gates

Division 18. Home Occupations; Live/Work and Work/Live Dwellings

Division 19. Hotels, Motels, and Bed-and-Breakfast Inns

- Division 20. Reserved
- Division 21. Marine Facilities and Live-Aboard Vessels
- Division 22. Reserved
- Division 23. Mobile Homes
- Division 24. Moving of Buildings
- Division 25. Off-Street Loading Areas
- Division 26. Parking
- Division 26-A. Performance Standards
- Division 27. Places of Worship and Religious Facilities
- Division 28. Reserved
- Division 29. Private Clubs and Membership Organizations
- Division 30. Recreation Facilities
- Division 31. Recreational Vehicles
- Division 32. Schools
- Division 32-A. Short-Term Rentals
- Division 33. Signs
- Division 34. Special Events
- Division 35. Reserved
- Division 36. Storage Facilities and Outdoor Display of Merchandise
- Division 37. Subordinate and Temporary Uses
 - Subdivision I. In General
 - Subdivision II. Temporary Uses
 - Subdivision III. Special events.
- Division 38. Tall Structures
- Division 38-A. Tattoo Studios and Body-Piercing Salons
- Division 39. Use, Occupancy, Construction, and Moving Regulations
- Division 40. Vehicle Visibility
- Division 41. Water-Oriented Rentals

ARTICLE V. NONCONFORMITIES

- Division 1. Generally
- Division 2. Nonconforming Buildings
- Division 3. Nonconforming Uses
- Division 4. Nonconforming Lots

SECTION 7. SEVERABILITY. If any one of the provisions of this ordinance should be held contrary to any express provision of law, or contrary to the policy of express law although not expressly prohibited, or against public policy, or for any reason whatsoever be held invalid, then such provision shall be null and void and shall be deemed separate from the remaining provisions of this ordinance, and in no way shall affect the validity of all other provisions of this ordinance.

SECTION 8. EFFECTIVE DATE. This ordinance shall take effect immediately upon its adoption.

The foregoing ordinance was enacted by the Town Council upon a motion by Council Member Hughes and seconded by Council Member Rynearson; upon being put to a vote, the result was as follows:

Howard Rynearson	YES
Daniel Hughes	YES
Bill Thomas	YES
W. H. "Bill" Van Duzer	YES
Terry Cain	YES

DULY PASSED AND ENACTED this 3rd day of March, 2003.

ATTEST: TOWN OF FORT MYERS BEACH

By: _____
Marsha Segal-George, Town Clerk

By: _____
Daniel Hughes, Mayor

Approved as to form by:

Richard V.S. Roosa, Town Attorney

EXHIBIT B

FORT MYERS BEACH LAND DEVELOPMENT CODE

CHAPTER 34 ZONING DISTRICTS, DESIGN STANDARDS, AND NONCONFORMITIES

ARTICLE I. IN GENERAL

- Sec. 34-1. Purpose and intent of chapter.*
Sec. 34-2. Definitions.
Sec. 34-3. Rules of construction.
Sec. 34-4. Applicability of chapter; deed restrictions and vested rights.
Sec. 34-5. Interpretation of chapter.
Secs. 34-6--34-50. Reserved.

ARTICLE II. ZONING PROCEDURES ADMINISTRATION

Division 1. Generally

- Sec. 34-51. Notice of public hearings required.*
Sec. 34-52. ~~Unauthorized Communications with~~ public officials.
Sec. 34-53. Fees and charges.
Secs. 34-54--34-80. Reserved.

Division 2. Town Council

Board of County Commissioners

- Sec. 34-81. Appointment of local planning agency.*
Sec. 34-82. Initiation of zoning actions.
Sec. 34-83. Functions and authority. Land use ordinance amendments or adoption.
Sec. 34-84. General procedures for zoning actions on specific zoning applications.
Sec. 34-85. Rezoning.
Sec. 34-86. Appeals from administrative action.
Sec. 34-87. Variances.
Sec. 34-88. Special exceptions.
Sec. 34-89. Developments of regional impact.
Sec. 34-90. Land development code interpretations.
Sec. 34-91. Comprehensive plan interpretations.
Sec. 34-92. Comprehensive plan amendments.
Sec. 34-~~93~~ ~~84~~. Rehearing of decisions.
Sec. 34-94. Special master proceedings under the Florida land use and environmental dispute resolution act (F.S. § 70.51).

Sec. 34-95. Proceedings under the Bert J. Harris, Jr., private property rights protection act (F.S. § 70.001).

Sec. 34-~~96~~ ~~85~~. Final decision; judicial review.
Secs. 34-~~97~~ ~~86~~--34-110. Reserved.

Division 3. Local Planning Agency

- Sec. 34-111. Agency established.*
Sec. 34-112. Purpose and scope.
Sec. 34-113. Composition, appointment, and compensation of members.
Sec. 34-114. Members' terms and vacancies.
Sec. 34-115. Forfeiture of office.
Sec. 34-116. Election and duties of officers.
Sec. 34-117. Clerk.
Sec. 34-118. Rules and procedures.
Sec. 34-119. Employment of staff and experts.
Sec. 34-120. Specific functions, powers, and duties as to comprehensive planning and adoption of land development regulations.
Sec. 34-121. Functions, powers, and duties as to zoning matters.
Sec. 34-122. Functions, powers, and duties as to historic preservation.
Sec. 34-123. Cooperation with the local planning agency.
Sec. 34-124. Legal counsel to the local planning agency.
Secs. 34-~~125~~ ~~116~~--34-~~200~~ ~~140~~. Reserved.

Division 4. Hearing Examiner [deleted in its entirety]

Division 5. Department of Community Development [deleted in its entirety]

Division ~~4~~ ~~6~~. Applications and Procedures for Changes, Permits, Interpretations, and Approvals ***Subdivision I. General Procedures***

- Sec. 34-201. General procedure for applications requiring public hearing.*
Sec. 34-202. General submittal requirements for applications requiring public hearing.
Sec. 34-203. Additional requirements for certain owner-initiated applications requiring public hearing.
Secs. 34-204--34-210. Reserved.

~~Sec. 34-204. Applications for development approval.~~
~~Sec. 34-205. Applications for building permits.~~
~~Sec. 34-206. Grading permits.~~
~~Sec. 34-207. Excavation permit for stormwater retention facilities.~~
~~Sec. 34-208. Requests for interpretation of zoning regulations. [moved to 34-265]~~
~~Sec. 34-209. Building relocation permit. [moved to 34-1951]~~
~~Sec. 34-210. Temporary use permits. [moved to 34-3050]~~

~~Sec. 34-211. Denials and resubmission of applications. [modified and relocated to § 34-84(4)]~~

Subdivision II. Additional Procedures for Planned Development Zoning Districts

~~Secs. 34-342--34-370. Reserved.~~
~~Sec. 34-211 371. Generally.~~
~~Sec. 34-372. Preapplication conference.~~
~~Sec. 34-212 373. Application for a planned development.~~
~~Sec. 34-213. Sufficiency and completeness.~~
~~Sec. 34-214. Application for an amendment.~~
~~Sec. 34-215 374. Covenant Documentation of unified control.~~
~~Sec. 34-375. Prehearing conference.~~
~~Sec. 34-376. Prehearing stipulation.~~
~~Sec. 34-216 377. Public hearings.~~
~~Sec. 34-217 378. Effect of planned development zoning.~~
~~Sec. 34-218 379. Binding nature of approval of master concept plan.~~
~~Sec. 34-219 380. Administrative amendments to approved master concept plan.~~
~~Sec. 34-220 381. Duration of rights conferred by adopted master concept plan.~~
~~Sec. 34-382. Development permit.~~
~~Secs. 34-221 383--34-230 410. Reserved.~~

Division 5 7. Public Hearings and Review

~~Sec. 34-231. Definitions.~~
~~Sec. 34-232. Required hearings.~~
~~Sec. 34-233. Preliminary review and notice certification.~~
~~Sec. 34-234. Public participation.~~
~~Sec. 34-235. Deferral or continuance of public hearing.~~
~~Sec. 34-236. Notices.~~
~~Secs. 34-237--34-2640. Reserved.~~

Division 6 8. Interpretations, Enforcement, and Special Administrative Actions

~~Sec. 34-261. Generally.~~
~~Sec. 34-262. Complaints.~~
~~Sec. 34-263. Penalties.~~
~~Sec. 34-264. Persons who may be charged with violations.~~
~~Sec. 34-265. Additional remedies.~~
~~Sec. 34-265 208. Requests for interpretation of this code zoning regulations.~~
~~Sec. 34-266. Enforcement. Cease and desist orders.~~
~~Sec. 34-267. Forced relocation of businesses. Authority to permit uses pending a zoning action.~~
~~Sec. 34-268. Administrative setback variances.~~
~~Sec. 34-269. Compliance agreements.~~
~~Secs. 34-26970--34-610300. Reserved.~~

ARTICLE III. RESERVED

ARTICLE IV. PLANNED DEVELOPMENTS

ARTICLE V. COMPREHENSIVE PLANNING, THE LEE PLAN

~~Sec. 34-491. The Lee Plan. [moved to § 34-619]~~
~~Secs. 34-492--34-610. Reserved.~~

ARTICLE III VI. ZONING DISTRICT REGULATIONS

Division 1. Mapping of Zoning Districts

~~Generally~~
~~Sec. 34-611. Zoning districts established.~~
~~Sec. 34-612. Types and general purpose of districts.~~
~~Sec. 34-613. Designation of district boundaries.~~
~~Sec. 34-614. Existing Official zoning map.~~
~~Sec. 34-615. New official Current zoning maps.~~
~~Sec. 34-616. Records management for zoning maps.~~
~~Sec. 34-617. Unauthorized changes to zoning maps.~~
~~Sec. 34-6168. Rules for interpretation of district boundaries.~~
~~Sec. 34-619. District conversions.~~
~~Sec. 34-617-618. Reserved.~~

Division 2. Allowable Land Uses in Each Zoning District

~~Sec. 34-619. The Fort Myers Beach Comprehensive Plan.~~
~~Sec. 34-620. Allowable uses of land generally. Uses not specifically listed.~~

- ~~Sec. 34-621. Allowable uses of land described. Use and development regulations for conventional districts.~~
- ~~Sec. 34-622. Use activity groups. Use groups and sub-groups.~~
- ~~Sec. 34-623. Performance standards.~~
- ~~Secs. 34-623~~4~~--34-650. Reserved.~~

Division 3. Explanation of Property Development Regulations

- ~~Sec. 34-631. Building heights.~~
- ~~Sec. 34-632. Density.~~
- ~~Sec. 34-633. Intensity and floor area ratios.~~
- ~~Sec. 34-634. Intensity and building coverage.~~
- ~~Sec. 34-635. Commercial design standards.~~
- ~~Sec. 34-636. Reserved.~~
- ~~Sec. 34-637. Minimum lot sizes.~~
- ~~Sec. 34-638. Minimum setbacks.~~
- ~~Sec. 34-639--34-640. Reserved.~~

Division 4. Conventional Zoning Districts

- ~~Sec. 34-641. General purpose.~~
- ~~Sec. 34-642. RS (Residential Single-Family) zoning district.~~
- ~~Sec. 34-643. RC (Residential Conservation) zoning district.~~
- ~~Sec. 34-644. RM (Residential Multifamily) zoning district.~~
- ~~Sec. 34-645. CR (Commercial Resort) zoning district.~~
- ~~Sec. 34-646. CM (Commercial Marina) zoning district.~~
- ~~Sec. 34-647. CO (Commercial Office) zoning district.~~
- ~~Sec. 34-648. SANTOS zoning district.~~
- ~~Sec. 34-649. IN (Institutional) zoning district.~~
- ~~Sec. 34-650. CF (Community Facilities) zoning district.~~
- ~~Sec. 34-651. BB (Bay Beach) zoning district.~~
- ~~Sec. 34-652. EC (Environmentally Critical) zoning district.~~
- ~~Sec. 34-653--34-660. Reserved.~~

Division 5. Redevelopment Zoning Districts

Subdivision I. Generally

- ~~Sec. 34-661. General purpose.~~
- ~~Sec. 34-662. Build-to lines and setback lines.~~
- ~~Sec. 34-663. Building frontages and lot frontages.~~
- ~~Sec. 34-664. Commercial design standards.~~
- ~~Sec. 34-665. Reserved.~~
- ~~Sec. 34-666. Property development regulations.~~
- ~~Sec. 34-667--34-670. Reserved.~~

Subdivision II. DOWNTOWN Zoning District

- ~~Sec. 34-671. Purpose.~~

- ~~Sec. 34-672. District map and applicability.~~
- ~~Sec. 34-673. Allowable uses.~~
- ~~Sec. 34-674. Building placement.~~
- ~~Sec. 34-675. Building size.~~
- ~~Sec. 34-676. Circulation and parking.~~
- ~~Sec. 34-677. Additional requirements.~~
- ~~Sec. 34-678--34-680. Reserved.~~

Subdivision III. SANTINI Zoning District

- ~~Sec. 34-681. Purpose.~~
- ~~Sec. 34-682. District map and applicability.~~
- ~~Sec. 34-683. Creation of neighborhood center.~~
- ~~Sec. 34-684--34-690. Reserved.~~

Subdivision IV. VILLAGE Zoning District

- ~~Sec. 34-691. Purpose.~~
- ~~Sec. 34-692. District map and applicability.~~
- ~~Sec. 34-693. Regulations to obtain development order for pre-approved redevelopment option.~~
- ~~Sec. 34-694. Regulations for existing mobile homes and recreational vehicles.~~

- ~~Sec. 34-695--34-700. Reserved.~~

Subdivision V. CB Zoning District

- ~~Sec. 34-701. Purpose.~~
- ~~Sec. 34-702. Applicability.~~
- ~~Sec. 34-703. Allowable uses.~~
- ~~Sec. 34-704. Building placement.~~
- ~~Sec. 34-705. Building size.~~
- ~~Sec. 34-706. Circulation and parking.~~
- ~~Sec. 34-707. Commercial design standards.~~
- ~~Secs. 34-708--34-930. Reserved.~~

- ~~Division 2. Agricultural Districts~~
- ~~Division 3. Residential Districts~~
- ~~Division 4. Recreational Vehicle Park Districts~~
- ~~Division 5. Community Facilities Districts~~
- ~~Division 6. Commercial Districts~~
- ~~Division 7. Marine-Oriented Districts~~
- ~~Division 8. Industrial Districts~~

Division 6 9. Planned Development Zoning Districts

Subdivision I. Generally

- ~~Sec. 34-931. Purpose and effect. intent.~~
- ~~Sec. 34-932. Regulation of land use in planned developments.~~
- ~~Sec. 34-933. Allowable permitted uses of land.~~
- ~~Sec. 34-934. Use regulations table.~~
- ~~Sec. 34-935. General conditions for all land uses.~~
- ~~Sec. 34-937. Commercial uses in RPD and MHPD districts.~~
- ~~Sec. 34-938. Industrial uses in CPD district.~~
- ~~Sec. 34-939. Recreational vehicle planned developments.~~
- ~~Sec. 34-940. Mixed use planned developments.~~
- ~~Secs. 34-934~~4~~--34-9460. Reserved.~~

Subdivision II. RPD (Residential Planned Development) Zoning District

Sec. 34-941. Intent of RPD (Residential Planned Development) zoning district.
Sec. 34-942. Allowable uses of land.
Sec. 34-943. Building placement, size, design, and other property development regulations.

Secs. 34-944--34-950. Reserved.

Subdivision III. CPD (Commercial Planned Development) Zoning District

Sec. 34-951. Intent of CPD (Commercial Planned Development) zoning district.
Sec. 34-952. Allowable uses of land.
Sec. 34-953. Building placement, size, design, and other property development regulations.

Sec. 34-954. Commercial design standards.

Secs. 34-955--34-960. Reserved.

Subdivision IV. Former Planned Development Zoning Districts

Sec. 34-961. Former MPD zoning district.

Sec. 34-962. Former PUD zoning district.

Subdivision V. PUD (Planned Unit Development) Zoning District

Sec. 34-963--34-990. Reserved.

Division 7. Commercial Design Standards

Sec. 34-991. Purpose and intent.
Sec. 34-992. Applicability and compliance.
Sec. 34-993. Definitions.
Sec. 34-994. Exterior walls.
Sec. 34-995. Principal facade walls.
Sec. 34-996. Roofs.
Sec. 34-997. Plazas and courtyards.
Sec. 34-998. Signage.
Sec. 34-999--34-1168. Reserved.

~~Division 10. Special Purpose Districts [deleted in its entirety]~~

~~Division 11. Overlay Districts [deleted in its entirety]~~

ARTICLE IV. VII. SUPPLEMENTARY DISTRICT SUPPLEMENTAL REGULATIONS

Division 1. Generally

~~Sec. 34-1169-1171. Purpose and applicability of article.~~
~~Sec. 34-1170-1172. Purpose of supplemental regulations.~~
~~Secs. 34-1173--34-1170. Reserved.~~

Division 2. Accessory Uses, Buildings, and Structures

Sec. 34-1171. Applicability of division.
Sec. 34-1172. Definitions.
Sec. 34-1173. Development regulations.
Sec. 34-1174. Location and setbacks generally.
Sec. 34-1175. Satellite dishes and amateur radio antenna/towers.
Sec. 34-1176. Swimming pools, tennis courts, porches, decks, and similar recreational facilities.
Sec. 34-1177. Accessory apartments not requiring owner-occupancy.
Sec. 34-1178. Accessory apartments in owner-occupied homes.
Sec. 34-1179. Trucks and commercial vehicles in residentially zoned districts. Commercial fishing equipment storage as accessory use to residence in Greater Pine Island area.
~~Sec. 34-1180. Additional dwelling unit on lot in agricultural districts.~~
~~Secs. 34-1180-34-1200. Reserved.~~

Division 3. Adult Entertainment, Adult Bookstores and Massage Parlors Sexually-oriented Businesses

Sec. 34-1201. Applicability of division.
Sec. 34-1202. Definitions.
Sec. 34-1203. Purpose of division.
Sec. 34-1204. Prohibited locations.
~~Secs. 34-1205--34-1230. Reserved.~~

Division 4. Aircraft Landing Facilities, Private

~~Sec. 34-1231. Permit required.~~
~~Sec. 34-1232. State permit.~~
~~Sec. 34-1233. Land area and site.~~
~~Sec. 34-1234. Building setbacks.~~
~~Sec. 34-1235. Setbacks for approach zones.~~
~~Sec. 34-1236. Compliance with height restrictions.~~
~~Sec. 34-1237. Repair of aircraft and machinery.~~
~~Secs. 34-1238. Use of engine-propelled aircraft.~~
~~Secs. 34-1239--34-1260. Reserved.~~

Division 5. Alcoholic Beverages

Sec. 34-1261. Definitions.
Sec. 34-1262. Compliance with applicable regulations.
Sec. 34-1263. Sale for off-premises consumption.
Sec. 34-1264. Sale or service for on-premises consumption.
~~Secs. 34-1265--34-1290. Reserved.~~

Division 6. Animals

- Sec. 34-1291. Keeping of animals. Applicability of division.
Sec. 34-1292. ~~Horses and other equines.~~
Sec. 34-1293. ~~Goats, sheep and swine.~~
Sec. 34-1294. ~~Noncommercial poultry raising.~~
Sec. 34-1295. ~~Dairy barns, commercial poultry raising.~~
Sec. 34-1296. ~~Other setbacks, exceptions to setback requirements.~~
Sec. 34-1297. ~~Activities requiring special approval.~~
Secs. 34-12928--34-1320. Reserved.

**Division 7. Animal Clinics and Kennels
Facilities**

- Sec. 34-1321. Permitted activities.
Sec. 34-1322. Enclosure of facilities.
Secs. 34-1323--34-1350. Reserved.

**Division 8. Automotive Businesses, ~~Display,~~
~~Rental, Repair, or Storage of Vehicles or~~
Equipment**

- Sec. 34-1351. ~~Automobile~~ vehicle repair and service.
Sec. 34-1352. ~~Display, sale, rental, or storage~~
~~facilities for motor vehicles, boats,~~
~~recreational vehicles, trailers, mobile~~
~~homes, or equipment.~~
Sec. 34-1353. Automobile rental.
Secs. 34-13543--34-1380. Reserved.

**Division 9. Bus Depots, Stations and Transit
Terminals**

- Sec. 34-1381. Purpose of division.
Sec. 34-1382. Site plan.
Sec. 34-1383. Access.
Sec. 34-1384. Parking generally.
Sec. 34-1385. ~~Parking for bus terminals.~~
Sec. 34-1386. ~~Modification of parking~~
~~requirements.~~
Sec. 34-1387. ~~Expansion of existing bus~~
~~station/depot.~~
Secs. 34-13858--34-1410. Reserved.

**Division 10. Care and Assisted Living Facilities
and Centers**

- Sec. 34-1411. Assisted Adult ~~congregate~~ living
facilities.
Secs. 34-1412, 34-1413. Reserved.
Sec. 34-1414. Continuing care facilities.
Sec. 34-1415. Density equivalents.
Secs. 34-14165--34-1440. Reserved.

**Division 11. Commercial Antennas and
Communication Towers**

- ~~[existing text deleted in its entirety]~~
Sec. 34-1441. Purpose and intent.
Sec. 34-1442. Definitions.
Sec. 34-1443. Commercial antennas mounted on
alternative support structures.
Sec. 34-1444. Commercial antennas mounted on
communication towers.
Secs. 34-1445--34-1550. Reserved.

~~Division 12. Density [deleted in its entirety]~~

Division 12=A. Drug Paraphernalia

- Sec. 34-1551. Drug paraphernalia defined.
Sec. 34-1552. Determination of paraphernalia.
Sec. 34-1553. Manufacture and delivery of drug
paraphernalia.
Sec. 34-1554--34-1570. Reserved.

Division 13. Environmentally Sensitive Areas

- Sec. 34-1571. Purpose of division; areas of
concern.
Sec. 34-1572. Applicability of division.
Sec. 34-1573. Environmental assessment report.
Sec. 34-1574. Compliance with applicable
regulations; new roads, development,
or expansion of existing facilities.
Sec. 34-1575. Coastal zones.
Sec. 34-1576. ~~Islands.~~ Reserved.
Sec. 34-1577. Wetlands.
Sec. 34-1578. ~~Floodplains.~~
Secs. 34-15789--34-1610. Reserved.

**Division 14. Essential Services, Essential
Service Equipment, and Essential Service
Buildings and Facilities**

- Sec. 34-1611. Purpose of division.
Sec. 34-1612. Where permitted uses.
Sec. 34-1613. ~~Setbacks.~~ Reserved.
Sec. 34-1614. Height of structures in visibility
triangle.
Sec. 34-1615. Maximum number of structures per
residential block.
Sec. 34-1616. ~~Safety requirements.~~ Screening and
buffering.
Sec. 34-1617. Exemptions from property
development regulations.
Secs. 34-1618--34-1650. Reserved.

Division 15. Excavations Activities
Subdivision I. Generally
Sec. 34-1651. Required approvals.
Secs. 34-1652--34-1710 ~~1670~~: Reserved.
Subdivision H. Mining [deleted in its entirety]

Division 16. Reserved.
*Farm Produce Stands, U-Pick Operations,
Roadside Stands And Portable Kiosks
[deleted in its entirety]*

Division 17. Fences, Walls, and Entrance Gates and Gatehouses
Sec. 34-1741. Applicability of division.
Sec. 34-1742. Design and construction of fences and walls. Building permit.
Sec. 34-1743. Reserved. Construction of fences.
Sec. 34-1744. Location and height of fences and walls.
Sec. 34-1745. Buffer for commercial and industrial uses.
Sec. 34-1746. Reserved. Visibility at entrances and exits.
Sec. 34-1747. Construction in easements.
Sec. 34-1748. Enclosure of high-voltage transformers and other utility equipment.
Sec. 34-1749. Entrance gates and gatehouses.
Sec. ~~34-1750~~. Walls and fences along limited access or controlled access streets.
Secs. 34-1750~~1~~--34-1770. Reserved.

Division 18. Home Occupations; Live/Work and Work/Live Dwellings
Sec. 34-1771. Intent of division.
Sec. 34-1772. Home occupations. Permitted uses, operation.
Sec. 34-1773 Live/work dwelling units.
Sec. 34-1774 Work/live dwelling units.
Secs. 34-1775~~3~~--34-1800. Reserved.

Division 19. Hotels, and Motels, and Bed-and-Breakfast Inns
Sec. 34-1801. Definitions.
Sec. 34-1802. Size of guest units.
Sec. 34-1803~~2~~. Allowable intensity. Property development regulations.
Sec. 34-1804. Parking.
Sec. 34-1805. Additional regulations for bed-and-breakfast inns.
Sec. 34-1806. Replacing a nonconforming hotel/motel.
Sec. 34-1807~~3~~. Conversions.
Sec. ~~34-1804~~. Subordinate uses.

Sec. 34-1805. Density limitation for Captiva Island.
Secs. 34-1808~~6~~--34-1830. Reserved.

Division 20. Reserved Junk, Scrap or Salvage Yards, Dumps and Sanitary Landfills [deleted in its entirety]
Secs. 34-1831~~7~~--34-1860. Reserved.

Division 21. Marine Facilities, Structures and Equipment and Live-Aboard Vessels
Sec. 34-1861. Boats, floating structures, floating equipment and live-aboards.
Sec. 34-1862. Reserved. Marinas, fish houses and docking facilities.
Sec. 34-1863. Construction and maintenance of docks, seawalls and other structures designed for use on or adjacent to waterways.
Secs. 34-1864--34-1890. Reserved.

Division 22. Reserved Farm Labor Housing [deleted in its entirety]
Secs. 34-1891~~5~~--34-1920. Reserved.

Division 23. Mobile Homes
Sec. 34-1921. Mobile home subdivisions.
Sec. 34-1922. Mobile home parks.
Sec. 34-1923~~1~~. Move-on permit requirements.
Sec. ~~34-1922~~. Tiedowns.
Sec. ~~34-1923~~. Skirting.
Secs. 34-1924--34-1950. Reserved.

~~Division 24. Model Homes, Units and Display Centers [deleted in its entirety]~~

Division 24. Moving of Buildings
Sec. 34-1951~~209~~. Building relocation permits. [moved from § 34-209]
Secs. 34-1952--34-1980. Reserved.

Division 25. Off-Street Loading Areas
Sec. 34-1981. Applicability of division.
Sec. 34-1982. Access.
Sec. 34-1983. Lighting, maintenance, and drainage.
Sec. 34-1984. Other use of loading areas.
Sec. 34-1985. Screening.
Sec. 34-1986. Loading area required; loading plan; location of loading area.
Sec. 34-1987. Number of spaces.
Secs. 34-1988--34-2010. Reserved.

Division 26. Off-Street Parking

- Sec. 34-2011. Types of parking facilities.
Applicability of division.
- Sec. 34-2012. Definitions.
- Sec. 34-2013. Access.
- Sec. 34-2014. Parking plan.
- Sec. 34-2015. Location and design generally.
- Sec. 34-2016. Dimensional requirements;
delineation of parking spaces.
- Sec. 34-2017. Parking lot surfaces.
- Sec. 34-2018. Joint use of off-street parking lots.
- Sec. 34-2019. Other use of off-street parking lots.
- Sec. 34-2020. Required parking spaces.
- Sec. 34-2021. Reserved. Exception for fast order
food establishments located in
multiple use complex.
- Sec. 34-2022. Temporary Seasonal parking lots.
- Secs. 34-2023--34-2030 ~~2050~~. Reserved.

Division 26-A. Performance Standards

- Sec. 34-2031. Performance standards,
environmental quality.
- Sec. 34-2032. Performance standards, creation of
nuisance.
- Secs. 34-2033--34-2050. Reserved.

Division 27. Places of Worship and Religious Facilities

- Sec. 34-2051. Property development regulations.
- Sec. 34-2052. Parking.
- Sec. 34-2053. Expansion of existing place of
worship.
- Secs. 34-2054--34-2080. Reserved.

Division 28. Reserved Plant Nurseries

- Secs. 34-2081--34-2110. Reserved.

Division 29. Private Clubs, Fraternal Clubs and Membership Organizations Clubs

- Sec. 34-2111. Applicability of district use
regulations to membership
organizations.
- Secs. 34-2112--34-2140. Reserved.

Division 30. Property Development Regulations
[deleted in its entirety]

Division 30. Recreation Facilities

- Sec. 34-2141. ~~2471~~. Applicability of division.
- Sec. 34-2472. Required approvals.
- Sec. 34-2142. ~~2473~~. Minimum lot area and
setbacks.
- Sec. 34-2474. Setbacks.

- Sec. 34-2475. Access.
- Sec. 34-2143. ~~2476~~. Accessory uses.
- Sec. 34-2144. ~~2477~~. Lighting.
- Sec. 34-2478. Parking.
- Sec. 34-2145. ~~2479~~. Sound systems.
- Secs. 34-2146--34-2350. Reserved.

Division 31. Recreational Vehicles
as Permanent Residences

- Sec. 34-2351. Use as permanent residence.
Recreational vehicle subdivisions.
- Sec. 34-2352. Recreational vehicle parks.
- Secs. 34-2353--34-2380. Reserved.

Division 32. Schools

- Sec. 34-2381. All schools.
- Sec. 34-2382. Noncommercial schools.
- Sec. 34-2383. Schools operated as businesses.
- Secs. 34-2384--34-2390 ~~2410~~. Reserved.

Division 32-A. Short-Term Rentals

- Sec. 34-2391. Restrictions on weekly rentals in
certain zoning districts.
- Sec. 34-2392. Registry of certain pre-existing
weekly rentals.
- Sec. 34-2393. Code of conduct for short-term
rentals.
- Sec. 34-2394. Enforcement and penalties.
- Sec. 34-2395--34-2410. Reserved.

Division 33. Signs

- Sec. 34-2411. Location and construction.
- Secs. 34-2412--34-2440. Reserved.

Division 34. Special Events

- Special Setback Regulations for Specific Uses*
- Sec. 34-2441. Special events defined.
- Sec. 34-2442. Permits for special events.
- Secs. 34-2443--34-2470. Reserved.

Division 35. Reserved Sports/Amusement Parks
and Recreational Facilities [moved to division 30]

- Secs. 34-2471--34-3000. Reserved.

Division 36. Storage Facilities and Outdoor Display of Merchandise

- Sec. 34-3001. Applicability of division.
- Sec. 34-3002. Mobile vendors prohibited. General
setback requirements.
- Sec. 34-3003. Reserved. Lighting.
- Sec. 34-3004. Outdoor display of merchandise for
sale or rent.

Sec. 34-3005. Storage facilities.
Secs. 34-3006--34-3020. Reserved.

Division 37. Subordinate and Temporary Uses
Subdivision I. In General

Sec. 34-3021. Subordinate uses.
Secs. 34-3022--34-3040. Reserved.
Subdivision II. Temporary Uses
Sec. 34-3041. Generally.
Sec. 34-3042. Carnivals, fairs, circuses and amusement devices.
Sec. 34-3043. Christmas tree sales.
Sec. 34-3044. Temporary contractor's office and equipment storage shed.
Sec. 34-3045. Alcoholic beverages, horse shows and exhibitions.
Sec. 34-3046. Temporary use of mobile home.
Sec. 34-3047. Temporary telephone distribution equipment.
Sec. 34-3048. Ancillary temporary uses in parking lots.
Sec. 34-3049. Temporary Seasonal parking lots.
Sec. 34-~~3050~~ ~~210~~. Temporary use permits. [moved from § 34-210]
Secs. 34-3051~~0~~--34-3054~~70~~. Reserved.
Subdivision III. Special Events.
Sec. 34-3055. Special events.
Secs. 34-3056~~0~~--34-3060 ~~70~~. Reserved.

Division 38. Tall Structures

Sec. 34-~~3061~~ ~~1008~~. Permit for tall structures.
Secs. 34-3062--34-3065. Reserved.

Division 38-A. Tattoo Studios and Body-Piercing Salons

Sec. 34-3066. Purpose of division.
Sec. 34-3067. Definitions.
Sec. 34-3068. Minimum spacing required for new or relocated establishments.
Sec. 34-3069. Destruction by natural disaster.
Secs. 34-3070--34-3100. Reserved.

Division 38. Units of High Impact
[deleted in its entirety]

Division 39. Use, Occupancy, and Construction, and Moving Regulations

Sec. 34-3101. Compliance with applicable regulations.
Sec. 34-3102. Reserved. Number of principal buildings on lot.
Sec. 34-3103. Permit for moving building.
Sec. 34-~~3104~~. Clearing, grading or filling of land.
Secs. 34-3104~~5~~--34-3130. Reserved.

Division 40. Vehicle Visibility

Sec. 34-3131. Vehicle visibility at intersections.
Secs. 34-3132--34-3150. Reserved.

Division 41. Water-Oriented Rentals Activities

Sec. 34-3151. Water-oriented rental establishments, outdoors.
Secs. 34-3152--34-3200. Reserved.

ARTICLE V. ~~III~~ NONCONFORMITIES

Division 1. Generally

Sec. 34-3201. Purpose of article.
Sec. 34-3202. Three types of nonconformities nonconforming use defined.
Sec. 34-3203. Illegal buildings, uses, and lots. Enlargement or expansion of nonconforming structure.
Sec. 34-3204. Amortization. Mobile home and recreational vehicle unit replacements and roof repairs.
Sec. 34-3205. Reserved. Uses approved by special exception or permit.
Sec. 34-3206. Nonconformities created by public acquisition. eminent domain proceedings.
Secs. 34-3207--34-323~~20~~. Reserved.

Division 2. Nonconforming Use of Land
[deleted in its entirety]

Division 2, 3. Nonconforming Buildings and Use of Buildings

Sec. 34-323~~1~~. Nonconforming buildings defined. and structures.
Sec. 34-3232. Continued use of a nonconforming building.
Sec. 34-3233. Repairing a nonconforming building.
Sec. 34-3234. Enlarging a nonconforming building.
Sec. 34-3235. Moving a nonconforming building.
Sec. 34-3236. Replacing a nonconforming building.
Sec. 34-3237. Pre-disaster buildback.
Sec. 34-3238. Post-disaster buildback.
Secs. 34-3239--34-3240. Reserved.

Division 3. Nonconforming Uses

Sec. 34-3241~~2~~. Nonconforming uses generally. of buildings.
Sec. 34-3242. Enlarging a nonconforming use.
Sec. 34-3243. Replacing a nonconforming use.

Sec. 34-3244. Discontinuing a nonconforming use.
Sec. 34-3245. Repairing a building containing a nonconforming use.
Sec. 34-324605. Nonconforming uses approved by special exception or permit.
Secs. 34-32473--34-3270. Reserved.

Division 4. Nonconforming Lots

Sec. 34-3271. Definition of nonconforming lot defined.
Sec. 34-3272. Determining when a lot was created. Lot of record defined, general development standards.
Sec. 34-3273. General requirements for residential uses on nonconforming lots.
Sec. 34-32743. Minimum use determinations. Construction of single-family residence.
Sec. 34-3275. Combining nonconforming lots.
Sec. 34-32764. Placement of Replacing a mobile home or recreational vehicle on a nonconforming lot.
Sec. 34-32775. Commercial or industrial use on a nonconforming lot.

ARTICLE I. IN GENERAL

Sec. 34-1. Purpose and intent of chapter.

(a) The purpose of this chapter is to encourage and promote, in accordance with present and future needs, the safety, health, order, convenience, prosperity, and general welfare of the citizens of the Town of Fort Myers Beach county, to recognize and promote real property rights, and to provide:

- (1) for efficiency and economy in the process of development,
- (2) for the appropriate and best use of land,
- (3) for preservation, protection, development, and conservation of the historical and natural resources of land, water, and air,
- (4) for convenience of traffic and circulation of people and goods,
- (5) for the use and occupancy of buildings,
- (6) for healthful and convenient distribution of population,
- (7) for adequate public utilities and facilities,
- (8) for promotion of the amenities of beauty and visual interest,
- (9) for protection of the character and maintenance of the stability of residential; agricultural; and business and industrial areas, and
- (10) for development in accordance with the Fort Myers Beach Comprehensive Plan. Lee Plan adopted by the county,

(b) These purposes are furthered by establishing zoning districts and by regulating the location and use of buildings, signs, and other structures, water, and land for agriculture, trade, industry and residence, by regulating and limiting or determining the height, bulk, and access to light and air of buildings and structures, the area of yards and other open spaces, and the density of use. To accomplish these objectives, the regulations and districts and accompanying maps have been designed with reasonable consideration, among other things, to the character of the districts and their peculiar suitability for particular uses.

(c) No building or structure, or part thereof, shall hereafter be erected, constructed, reconstructed, altered, or maintained, and no existing use, new use, or change of use of any building, structure, or land, or part thereof, shall be made or continued except in conformity with the provisions of this code. Special regulations apply to certain nonconforming

buildings and uses as provided in article V of this chapter.

Sec. 34-2. Definitions.

The following words, terms, and phrases, when used in this chapter, shall have the following meanings, unless ascribed to them in this section, except where the context clearly indicates a different meaning:

Abutting property, unless specifically stated otherwise within this chapter, means properties having a boundary line, or point or portion thereof, in common, with no intervening street right-of-way or easement, or any other easement over 25 feet in width.

Access, vehicular means the principal means of vehicular ingress and egress to abutting property from a street right-of-way or easement.

Accessory apartment. See §§ 34-1177–1178.

Accessory building or structure. See *Building or structure, accessory.*

Accessory use. See *Use, accessory.*

Administrative office means an office which is customarily ancillary and subordinate to the permitted principal use of the property and which is used for clerical and administrative functions of the principal use. This term shall be interpreted to include managers or association offices for residential rental property, subdivisions, recreational vehicle parks and similar type activities.

Aggrieved person or party means anyone who has a legally recognizable interest which is or which may be adversely affected by an action of or an action requested of the town council Board of County Commissioners or any other person or board that has been delegated such authority by the town council. Board of County Commissioners. Property owners within 375 feet of the subject property are presumed to have a legally recognizable interest. A person or entity claiming to be aggrieved, and whose property lies outside of the 375-foot perimeter, will be required to offer proof that their interests are adversely affected. A person or entity pursuing an appeal solely out of spite shall not be presumed to have a legally recognizable interest.

Agricultural uses [deleted]

Aircraft landing facilities, private [deleted]

Airport operations facilities [deleted]

Alter and *alteration* mean any change in size, shape, character, or use of a building or structure.

Amateur radio antenna/tower means a structure erected and designed to receive or transmit radio waves by licensed amateur radio operators.

Amusement device means any mechanical device or combination of devices which carries or conveys passengers on, along, around, over, or through a fixed or restricted course or within a defined area for the purpose of giving its passengers amusement, pleasure, or excitement. This definition shall specifically include all amusement devices, amusement attractions, and temporary structures regulated by F.S. ch. 616 and the state department of agriculture and consumer services.

Amusement device, permanent means a device which is used, or intended to be used, as an amusement device or amusement attraction that is erected to remain a lasting part of the premises.

Amusement park [deleted]

Animal clinic or kennel means an establishment providing for the diagnosis and treatment of ailments of animals other than humans, or for the temporary care of more than four dogs or cats for others, and which may include facilities for overnight care. See division 7 of article IV of this chapter. *Animal kennel.*

Animal kennel means an establishment where more than four dogs or cats (except litters of animals of not more than six months of age) are kept, raised, bred, cared for, or boarded, for a fee.

Animals, Class I [deleted]

Animals, Class II [deleted]

Apparel, manufacturing. See § 34-622(c)(1).

Applicant means any individual, firm, association, syndicate, copartnership, corporation, trust, or other legal entity, or their duly authorized

representative, commencing proceedings under this chapter.

Application, ~~town- county initiated~~ means any application in which the town council Board of County Commissioners is designated as the applicant, regardless of whether the town Lee County is the owner of the subject parcel.

Application, owner-initiated means any application that is not town- county initiated.

Application or appeal means any matter lying within the jurisdiction of the town council, hearing examiner and any application for rezoning which will be or is scheduled to be heard by the Board of County Commissioners.

Approved discharge device ~~[deleted]~~

Architect means a professional architect duly registered and licensed by the state.

Adult congregate living facilities (ACLF) or Assisted living facility means a residential land use, licensed under ch. 58A-5 F.A.C. 10A-5, Florida Administrative Code, which may be a building, a section of a building, a section of a development, a private home, a special boarding home, a home for the aged, or similar place, whether operated for profit or not, which undertakes through its ownership or management to provide, for a period exceeding 24 hours, housing and food service plus one or more personal services for four or more adults not related to the owner or administrator by blood or marriage. A facility offering such services for fewer than four adults shall be ~~construed as being~~ within the context of this definition if it ~~formally or informally~~ advertises to or solicits the public for residents or referrals and holds itself out to the public ~~as to be~~ an establishment ~~which~~ providing such services. These facilities are not synonymous with the term “health care facility” or “nursing home.” For purposes of this definition only, the term “personal services” means services in addition to housing and food service, which include but are not limited to personal assistance with bathing, dressing, ambulation, housekeeping, supervision, emotional security, eating, supervision of self-administered medications, restoration therapy, and assistance with securing health care from appropriate sources.

ATM and automatic teller machine mean an unattended banking station located outside of or away from the principal bank building and in operation beyond normal lobby hours, operated by computerized equipment, and capable of carrying out specific banking transactions.

Authorized representative means any person who appears with the permission of and on behalf of another person and who provides legal argument or relevant competent evidence through testimony, submission of documents, or otherwise.

Auto parts store ~~means establishments primarily engaged in the retail sale of new or used automobile, truck, trailer, or motorcycle parts and accessories. The term does not include auto wrecking yards.~~

Auto wrecking yard ~~[deleted]~~

Automobile self-service fuel pumps means vehicle fuel dispensing ~~devices pumps~~ providing an accessory use to a permitted retail ~~trade~~ establishment, ~~but in which only self-service pumps are provided and No other vehicle service is permitted by approval of automobile fuel pumps. provided. For purposes of determining the number of “pumps,” a “pump” may serve only one vehicle at a time. If a pump island contains a pump which can be used simultaneously by two vehicles, then it is counted as two pumps.~~

Automobile rental means the use of any building, land area, or other premises or portion thereof primarily for the rental (not leasing) of automobiles and light trucks. Incidental servicing and maintenance of the rental vehicles, excluding body/frame repair and painting, is a normal ancillary function.

Automobile repair means establishments that primarily offer parts installation and general vehicle servicing including diagnostic centers and the servicing of brakes, electrical systems, engines, glass, mufflers, oil, radiators, tires, transmissions, upholstery, etc. Automobile repair establishments may also provide body/frame repair, painting, and similar services when ancillary to general vehicle servicing.

Automobile service station means an establishment primarily engaged in the retail sale of motor fuel or lubricants, but which may also include

facilities for washing, polishing, waxing, greasing, tire repair (with no recapping or vulcanizing) and other minor incidental repairs, and emergency road service, including towing and emergency repairs and services; provided, however, such establishment is not primarily engaged in work or services listed as "automotive repair and service" (see § 34-622(c)(2)). See *Self-service fuel pump station*.

Automotive repair and service. See § 34-622(c)(2).

Banks and financial establishments. See § 34-622(c)(3).

Bar or and cocktail lounge mean any establishment devoted primarily to the retailing and on-premises drinking of beer, wine, malt, vinous, or other alcoholic beverages.

Beach or bay access means a right-of-way or easement that provides at least pedestrian access to beaches, bays, canals, or wetlands.

Bed and breakfast establishment. For purposes of this chapter, bed and breakfast establishments shall be treated the same as a boarding house.

Bed-and-breakfast inn means a public lodging establishment with nine or fewer guest units that serves breakfast to overnight guests. A bed-and-breakfast inn may be located in a single building or in a cluster of separate buildings. See division 19 of article IV of this chapter.

Board means the Board of County Commissioners of Lee County, Florida.

Boarding house means an establishment with lodging facilities for more than four but less than ten persons, where meals are regularly prepared and served for compensation, and where food is placed upon the table family style, without service or ordering of individual portions from a menu. See *Rooming house*.

Boat means any vessel, watercraft, or other artificial contrivance used, or which is capable of being used, as a means of transportation, as a mode of habitation, or as a place of business, professional, or social association on waters of the town county, including:

- (1) Foreign and domestic watercraft engaged in commerce;
- (2) Passenger or other cargo-carrying watercraft;
- (3) Privately owned recreational watercraft;
- (4) Airboats and seaplanes; and
- (5) Houseboats or other floating homes.

Boat dealers are establishments primarily engaged in the display, sales, or leasing of new or used motorboats, yachts, and other watercraft, including boat trailers. Incidental servicing and repairs and the stocking of replacement parts is a normal ancillary function.

Boat parts store [deleted]

Boat repair and service means establishments primarily engaged in minor repair service to small watercraft, including the sale and installation of accessories. See *Marina*.

Boatyard means a boating or harbor facility located on or having direct access to navigable water for building, maintaining, and performing extensive repair on boats and small ships, marine engines, and equipment. A boatyard shall be distinguished from a marina by the larger scale and greater extent of work done in a boatyard and by the use of dry dock, marine railway, or large capacity lifts used to haul out boats for maintenance or repair. See *Marina*.

Bonita Beach [deleted]

Building means any structure, either temporary or permanent, having a roof intended to be impervious to weather, and used or built for the shelter or enclosure of persons, animals, chattels, or property of any kind. This definition shall include ~~tents, awnings, cabanas, or vehicles~~ situated on private property and serving in any way the function of a building, but does not include screened enclosures not having a roof impervious to weather.

Building or structure, accessory means a building or structure which is customarily incidental and subordinate to a principal building or to the principal use of the premises, and located on the same premises. See *Building, principal*.

Building, conventional means:

- (1) A building, built upon the site and upon its own permanent foundation, constructed of

basic materials such as wood, masonry, or metal or minimally prefabricated components such as roof trusses, wall panels, and bathroom/kitchen modules, and conformable to the locally adopted building, electrical, plumbing, and other related codes; or

- (2) A building manufactured off the site in conformance with F.S. ch. 553, pt. IV (or ch. 9B-1, F.A.C.), subsequently transported to its site complete or in modules and fixed to its own foundation with no intention to relocate.

Building coverage. See § 34-634.

Building heights. See § 34-631. ~~of means the vertical distance measured from grade to the highest point of the roof surface of a flat or Bermuda roof; to the deck line of a mansard roof; and to the mean height level between eaves and ridge of gable, hip, and gambrel roofs. Where minimum floor elevations in floodprone areas have been established by law, the building height shall be measured from such required minimum floor elevations (see article VII, division 30, subdivision H, of this chapter):~~

Building material sales. See § 34-622(c)(4). includes establishments selling new or used building materials such as lumber, roofing, siding, shingles, drywall, brick, tile, cement, sand, or gravel.

Building official means the director of the division of code enforcement or his designee.

Building, principal means a building in which is conducted the main or principal use of the premises on which the building is situated.

Bus station/depot [deleted]

Bus stop [deleted]

Bus terminal. See Transit terminal. ~~means any premises for the transient housing or parking of buses and where the loading and unloading of passengers, luggage or packages or the transfer of passengers, luggage or packages to other buses may occur.~~

Business office [deleted]

Business services. See § 34-622(c)(5).

Camera shop [deleted]

Car wash means establishments primarily engaged in washing cars or in furnishing facilities for the self-service washing of cars.

Carnival means an enterprise which travels from community to community, generally staying for ten days or less in any one location, and which offers one or more amusement devices or attractions.

Carport means a freestanding or attached structure, consisting of a roof and supporting members such as columns or beams, unenclosed from the ground to the roof on at least two sides, and designed or used for the storage of motor-driven vehicles owned and used by the occupants of the building to which it is accessory.

Cemetery [deleted]

Change of occupancy [deleted]

Chemicals and allied products. [deleted]

Cleaning and maintenance services. See § 34-622(c)(7).

Clothing stores, general. See § 34-622(c)(8).

Clubs. See Membership organization.

~~(1) Club, commercial [deleted]~~

~~(2) Club, country [deleted]~~

~~(3) Club, fraternal [deleted]~~

~~(4) Club, membership organization [deleted]~~

~~(5) Club, private [deleted]~~

Cluster development [deleted]

Commercial means an activity involving the sale of goods or services carried out for profit.

Commercial accessory use means the use of a structure or premises that is customarily incidental and subordinate to the principal use of a commercial structure or premises. See Use, principal. Typical commercial accessory uses are: Parking lots, accessory; Storage, indoor; and Telephone booth or pay telephone station. Various divisions of article IV of this chapter describe permitted commercial accessory uses. Uses that are listed separately on Table 34-1 of this code, such as drive-throughs and automobile fuel pumps, are not commercial accessory uses and are permitted only in zoning

districts where they are explicitly identified in Tables 34-1 and 34-2.

Commercial antenna (see definition in § 34-1442)

~~Commercial fishery~~ [deleted]

Communication tower (see definition in § 34-1442)

Community residential home means a dwelling unit licensed to serve clients of the state department of ~~children and family services health and rehabilitative services~~ which provides a living environment for one to six unrelated residents who operate as the functional equivalent of a family, including such supervision and care by a supportive staff as may be necessary to meet the physical, emotional, and social needs of the residents. Residents include only aged persons as defined in F.S. § 400.618(3), as amended; physically disabled or handicapped persons as defined in F.S. § 760.22(7), as amended; developmentally disabled persons as defined in F.S. § 393.063(11), as amended; nondangerous mentally ill persons as defined in F.S. § 394.455(3), as amended; or children as defined in F.S. § 39.01(8) and F.S. § 39.01(10), as amended.

Compatible means, in describing the relation between two land uses, buildings or structures, or zoning districts, the state wherein those two things exhibit either a positive relationship based on fit, similarity or reciprocity of characteristics, or a neutral relationship based on a relative lack of conflict (actual or potential) or on a failure to communicate negative or harmful influences one to another.

Comprehensive plan means the document, and its amendments, adopted by the ~~town council~~ Board of County Commissioners pursuant to F.S. ch. 163, for the orderly and balanced future economic, social, physical, environmental, and fiscal development of the town county. The terms “comprehensive plan” and “the Fort Myers Beach Comprehensive Lee Plan” are synonymous.

Condominium means that form of ownership of property under which units or improvements are subject to ownership by one or more owners, and

~~there is appurtenant to each unit or part thereof an undivided share in common elements.~~

~~Consultant~~ [deleted]

~~Contiguous lots~~ [deleted]

Continuance. See § 34-231.

Continuing care facility (CCF) means a facility, licensed under F.S. ch. 651, ~~which must be developed as a planned development (PD)~~, which undertakes through its ownership or management to provide housing and food service to adult residents. The facility must meet the criteria for exemption from the Fair Housing Act Amendments of 1988, title VII USC.

~~Contractors and builders.~~ See § 34-622(c)(9).

Contractor's shop means a room or group of rooms used by a contractor for the custom fabrication of building-related products such as, but not limited to, air conditioning duct work, pool screen enclosures, door trim, etc., and for the interior storage of materials, but which does not include any exterior fabricating or use any exterior storage area. Specifically prohibited is the storage or parking of heavy construction equipment such as cement trucks, cranes, bulldozers, well-drilling trucks and other similar heavy equipment, or wrecking or demolition debris.

Contractor's storage yard means a lot or parcel upon which a contractor maintains an area to store and maintain construction equipment and other materials customarily used in the trade carried on by the contractor. Storage of wrecking debris is prohibited.

Convenience food and beverage store means a store which specializes in convenience products and other commodities, which may have self-service fuel pumps and which normally is open to the public beyond the normal sales hours of other retail stores.

~~Conversion~~ [deleted]

Corner lot. See *Lot, corner.*

Correctional facility, county means a county-operated facility for incarceration of offenders, including detention centers and jails.

~~County Coastal construction control line or zones. See definition in § 6-333(a). The county coastal construction control line or zones landward of the mean high water along the Gulf of Mexico are identified on the county coastal construction setback map which is on file at the department of community development.~~

Cross-access agreement means an agreement between adjacent property owners in which internal connections are provided between adjoining parking areas in order to minimize the number of driveways from the parking areas to streets.

Cultural facility means facilities of historic, educational, or cultural interest, such as art galleries, aquariums, botanical gardens, concert halls, historical sites, and museums. ies. See § 34-622(c)(10).

~~Current assessed value [deleted]~~

Day care center, adult means a facility or establishment which undertakes through its ownership or management to provide basic services such as but not limited to a protective setting, social or leisure time activities, self-care training, or nutritional services to three or more adults not related by blood or marriage to the owner or operator, who require such services. This definition shall not be interpreted to include overnight care.

Day care center, child means a facility or establishment which provides care, protection, and supervision for six or more children unrelated to the operator and which receives a payment, fee, or grant for any of the children receiving care, whether or not operated for profit. This definition shall not include public or nonpublic schools which are in compliance with the Compulsory School Attendance Law, F.S. ch. 232. The term “child day care center” is synonymous with the terms “preschool” and “nursery school.”

Deferral. See § 34-231.

~~Denial with prejudice means an action taken by a hearing board indicating that the request being acted upon is formally denied and shall not be resubmitted, except as provided for in § 34-84(4)a, 34-211(a).~~

~~Denial without prejudice means an action taken by a hearing board indicating that the specific request being acted upon is formally denied but that the hearing board is willing to consider a modification of the request may be considered as set forth in § 34-84(4)b, 34-211(b).~~

Density means an existing or projected relationship between numbers of dwelling units and land area. See § 34-632 for methods of computing residential densities. Refer to article VII, division 12, subdivision II, of this chapter, and article VII, division 19, of this chapter.

~~Department [deleted]~~

~~Department store [deleted]~~

~~Detrimental uses [deleted]~~

Developer means any individual, firm, association, syndicate, copartnership, corporation, trust, or other legal entity commencing development.

Development and to develop. A development includes the construction of any new buildings or other structures on a lot, the relocation of any existing buildings, or the use of a tract of land for any new uses. To develop is to create a development.

~~Development of county impact (DCI) [deleted]~~

Development of regional impact (DRI) means any development which, because of its character, magnitude, or location, would have a substantial effect upon the health, safety, or welfare of citizens of more than one county.

~~Development parcel [deleted]~~

~~Development perimeter [deleted]~~

Deviation means a departure from a specific regulation of this code chapter, when requested and approved by the town council Board of County Commissioners as part of the application for a planned development (see § 34-932(b), or special permit). A deviation is not the same as a variance in that the criteria for granting a variance in § 34-87(3) need not be met.

Director means the person to whom the town manager has delegated the authority to administer this chapter, or that person's designee, administrative director of the department of community development or his designee. As used in this chapter, the terms "division director," "department director" and "director" are synonymous.

~~District [deleted]~~

Dock means a structure built across wetlands or open water used for the mooring of watercraft or for fishing, observation, or similar recreational activities.

Domestic tropical birds means birds not indigenous to the state or the United States that are commonly kept as pets in a home, including but not limited to canaries, finches, lovebirds, parrots, parakeets, cockatiels, and mynah birds.

~~Dormitory [deleted]~~

Double-frontage lot means any lot, not a corner or through lot, having two or more property lines abutting to a street right-of-way or easement.

~~Drive-in theater [deleted]~~

Drive-through facility means an establishment or portion thereof where a patron is provided products or services without departing from his automotive vehicle or in which the patron may temporarily depart from his vehicle in a nonparking space while servicing it, such as a do-it-yourself car wash or fuel pump. The terms "drive-through," "drive-in," and "drive-up" are synonymous. Drive-throughs are classified as Type 1 when they serve land uses with lower volumes and limited hours such as banks and pharmacies, and Type 2 when they serve land uses that typically have higher volumes and/or extended hours such as convenience stores, automobile fuel pumps, and car washes. See § 34-620(f) regarding the prohibition on drive-through lanes for restaurants and § 34-676(f) regarding drive-through lanes in the Downtown zoning district.

Drug paraphernalia. See § 34-1551.

~~Drugstore [deleted]~~

Duplex. See Dwelling unit, types.

Dwelling unit means a room or rooms connected together, which could constitute a separate, independent housekeeping establishment for a family, for owner occupancy, or for rental or lease on a weekly, monthly, or longer basis as specified in this code for various zoning districts, and physically separated from any other rooms or dwelling units which may be in the same structure, and containing sleeping and sanitary facilities and a ~~one~~ kitchen. The term "dwelling unit" shall not include rooms in ~~hotels, motels or institutional~~ certain assisted living or continuing care facilities (see § 34-1415) or in accessory apartments in owner-occupied homes (see § 34-1178(d)). See also Guest Housing unit and Living unit.

Dwelling unit, types.

~~(1) Duplex~~ means a single, freestanding, conventional building on a single lot, designed for two dwelling units under single ownership, or wherein each dwelling unit is separately owned or leased but the lot is held under common ownership.

~~(1)~~ ~~(2)~~ Single-family residence means a single, freestanding, conventional detached building designed for one dwelling unit and which could be used for occupancy by one family.

~~(2)~~ ~~(3)~~ Two-family attached means a single, freestanding, conventional detached building designed as two dwelling units attached by a common wall or roof, but wherein each unit is located on a separate lot under separate ownership.

~~(4)~~ Townhouse means a group of three or more dwelling units attached to each other by a common wall or roof wherein each unit has direct exterior access and no unit is located above another, and each unit is completely separated from any others by a rated firewall or a fire and sound resistant enclosed separation or space, and wherein each dwelling unit is on a separate lot under separate ownership.

~~(3)~~ Live/work unit means a single dwelling unit in a detached building, or in a multifamily or mixed-use building, that also accommodates limited commercial uses within the dwelling unit. The predominate use of a live/work unit is residential, and commercial activity is a secondary use. See § 34-1773.

~~(4)~~ Work/live unit means a single dwelling unit in a detached building, or in a multifamily, mixed-use, or commercial building, where

the predominate use of the unit is commercial. See § 34-1774.

- (5) *Mobile home* means a building, manufactured off the site in conformance with the Federal Mobile Home Construction and Safety Standards (24 CFR 3280 et seq.), subsequently transported to a site complete or in sections where it is emplaced and tied down in accordance with ch. 15C-1, F.A.C., with the distinct possibility of being relocated at a later date. See §§ 34-1921–1950.
- (6) *Multiple-family building* means a group of three or more dwelling units within a single conventional building, attached side by side, or one above another, or both, regardless of whether and wherein each dwelling unit may be individually owned or leased but the land on which the building is located is under common, or single, or individual ownership. Freestanding dwelling units with at least one wall on a side or rear property line are also considered to be part of multiple-family buildings. Dwelling units, other than caretaker's quarters, which are included in a building which also contains permitted commercial uses shall also be deemed to be multiple-family dwelling units.
- (7) *Caretaker* means a single dwelling unit, whether in a freestanding building or part of another structure, that is permitted in some zoning districts as an accessory use to house an on-site caretaker.
- (7) ~~*Zero lot line* means a dwelling unit with at least one wall of a building on a side or rear line of the lot on which it stands.~~

Easement means a grant of a right to use land for specified purposes. It is a nonpossessory interest in land granted for limited use purposes.

Electrical machinery and equipment, manufacturing. [deleted]

Engineer means a professional engineer duly registered and licensed by the state.

Enlargement and *to enlarge*. An enlargement is an addition to the floor area or volume of an existing building, or an increase in that portion of a tract of land occupied by an existing use.

Entrance gate means a mechanized control device which is located near the point of access to a

development which serves to regulate the ingress of vehicles to the interior of the development for the purpose of security and privacy.

Environmental quality [deleted]

Environmentally sensitive land means any lands or waters, the development or alteration of which creates or has the potential to create a harm to the public interest due to their value as sources of biological productivity, as indispensable components of various hydrologic regimes, as irreplaceable and critical habitat for native species of flora and fauna, or as objects of scenic splendor and natural beauty. Among these types of land are those designated wetlands, resource protection areas and transition zones.

Equivalent means the state of correspondence or virtual identity of two land uses or zoning districts that exhibit similar levels of effects on each other and the community at large as defined by such factors as their intensities and schedules of use and activity, their demands for services and infrastructure such as roads and water and sewer systems, their impacts on natural resources and other similar parameters. The term "equivalent" is not synonymous with the term "compatible."

Essential service facilities. See § 34-622(c)(13).

Essential service building means a free-standing building or structure exceeding 6 feet in height or 100 square feet in area that, except for its size would qualify as an "essential services." See division 14 of article IV of this chapter.

Essential service equipment means an above-ground structure that exceed 27 cubic feet, but less than 6 feet high and 100 square feet in area, and that except for its size would qualify as "essential services" See division 14 of article IV of this chapter.

Essential services means the erection, construction, alteration, or maintenance, by a public or private utility company for the purpose of furnishing adequate service by such company for the public health, safety, or general welfare, of electrical and communication cables, poles, and wires, and water and sewer collection, transmission or distribution mains, drains, and pipes, including fire hydrants. This definition includes necessary

transformers, switching equipment, meters, pumps, and similar equipment which is less than 27 cubic feet in size, but does not include communication towers which are regulated by division 11 of article IV of this chapter or telephone booths or pay telephone stations which are regulated by §§ 34-638(d)(2)e and 34-2019(b). This definition shall not be interpreted to include buildings, structures, or uses listed as “essential service equipment” or “essential service building” (as defined herein). See division 14 of article IV of this chapter. facilities” (see § 34-622(c)(13)).

Existing only. ~~When used following a listed permitted use, the term “existing only” shall mean a building, structure or use which lawfully existed on the effective date of the ordinance from which this chapter is derived (August 1, 1986). When this term (or its abbreviation EO) is used in Table 34-1, it describes a specific land use that is permitted only if that use lawfully existed on the same property on August 1, 1986. Such lawfully existing use shall have the same rights as a permitted use and may be expanded or reconstructed on the same parcel in accordance with all applicable regulations, on the parcel which existed on August 1, 1986. The use is permitted only if it lawfully existed on September 27, 1993, or was granted a special exception within the two years prior to that date and commenced the approved construction within two years after that date. Except for mobile home and recreational vehicle parks, a use that qualifies as “existing only” will not be classified as a nonconforming use; it will be afforded the same privileges as a permitted use and may be expanded or reconstructed, in accordance with all applicable current regulations, but only on the specific parcel on which it is located, as that parcel was legally described on September 27, 1993.~~

Exotic animals [deleted]

Fabricated metal products, manufacturing: [deleted]

Fair [deleted]

Family means one or more persons occupying a dwelling unit and living as a single, nonprofit housekeeping unit, provided that a group of five or more adults who are not related by blood, marriage, or adoption shall not be deemed to constitute a family. The term “family” shall not be construed to

mean a fraternity, sorority, club, monastery, convent, or institutional group.

Family day care home, as defined in F.S. § 403.302, means an occupied residence in which child care is regularly provided for children from at least two unrelated families and which receives a payment, fee, or grant for any of the children receiving care, whether or not operated for profit. A family day care home shall be allowed to provide care for one of the following groups of children, which shall include those children under 13 years of age who are related to the caregiver:

- (1) A maximum of four children from birth to 12 months of age.
- (2) A maximum of three children from birth to 12 months of age, and other children, for a maximum total of six children.
- (3) A maximum of six preschool children if all are older than 12 months of age.
- (4) A maximum of 10 children if no more than 5 are preschool age and, of those 5, no more than 2 are under 12 months of age.

Farm labor housing [deleted]

Flea market, indoor [deleted]

Floor area means the usable total area of every each story of a building, or portion thereof, within the surrounding exterior walls of the building or structure.

Floor area ratio. See § 34-633.

Florist shop [deleted]

Food and beverage service, limited means the provision of food or beverages for members and guests of a membership organization private club or recreational hall center but not available to the general public. See the provisions of article IV ~~VII~~, division 5, of this chapter relating to on-premises consumption of alcoholic beverages.

Food and kindred products, manufacturing: [deleted]

Food stores. See § 34-622(c)(16).

Foodcart [deleted]

Fraternity house [deleted]

~~Furniture and fixtures, manufacturing.~~ See § 34-622(c)(18).

~~Garage, private~~ [deleted]

~~Garage, public~~ [deleted]

Garage sale or yard sale mean an informal sale of used household or personal articles, such as furniture, tools, or clothing, held on the seller's own premises, or conducted by several people on one of the sellers' own premises. Garage and yard sales are limited to not more than one week in duration, with sales limited to two garage or yard sales per year. See Residential accessory use.

~~Gasoline dispensing system, special~~ means a gasoline dispensing system which is card-operated for governmental or commercial entities only in accordance with the provisions of ch. 4A-16, part VI, "Service Stations," of the Florida Administrative Code.

~~Gasparilla Island conservation district~~ [deleted]

~~Gatehouse~~ [deleted]

~~Gift, novelty, and souvenir shops~~ [deleted]

Glare means bright or brilliant light emitting from a point source of light, or reflected or refracted from a point source of light, with an intensity great enough to:

- (1) reduce an observer's ability to see;
- (2) cause an observer to experience momentary blindness or a temporary loss of visual performance or ability; or
- (3) cause an observer with normal sensory perception annoyance or discomfort to the degree which constitutes a nuisance.

Golf course means a tract of land laid out for at least nine holes for playing the game of golf and improved with tees, greens, fairways, and hazards. Miniature golf is classified as a Recreation facility, commercial and not as a golf course.

~~Government agency~~ [deleted]

~~Greater Pine Island~~ [deleted]

~~Grocery~~ [deleted]

Gross floor area includes the total floor area of a building within the surrounding exterior walls. See also § 34-633.

Group quarters means a building in which a number of unrelated individuals that do not constitute a family live and share various spaces and facilities for, for example, cooking, eating, sanitation, relaxation, study, and recreation. Examples of group quarters include fraternity houses, boarding houses, adult congregated assisted living facilities, dormitories, sororities, rooming houses, and other similar uses.

~~Guest house~~ [deleted]

Guest unit means a room or group of rooms in a hotel/motel or bed-and-breakfast inn that are designed to be used as temporary accommodations for one or more people traveling together. All guest units provide for sleeping and sanitation, although sanitation may be provided through shared bathrooms. See division 19 of article IV of this chapter.

Habitable means space in a structure available for living, sleeping, eating, cooking, or any commercial purposes. However, storage space is not considered to be habitable space.

Hardship means an unreasonable burden that is unique to a parcel of property, such as peculiar physical characteristics. Economic problems may be considered but may not be the sole basis for finding the existence of a hardship.

~~Hardware store~~ [deleted]

Health care facility. See § 34-622(c)(20). means an establishment such as a nursing home or hospice that is primarily engaged in furnishing medical, nursing, or other care to persons residing on the premises, but not including hospitals.

~~Hearing board~~ [deleted]

~~Hearing examiner~~ [deleted]

~~Heliport~~ [deleted]

Helistop means an area, either at ground level or elevated on a structure, licensed, or approved for the landing and takeoff of helicopters, heliport; but

without auxiliary facilities such as parking, waiting room, fueling, and maintenance equipment.

Hidden path means an interconnected system of pedestrian and bicycle pathways throughout the town that improves mobility and promotes community interaction (see Objective 2-A of the Fort Myers Beach Comprehensive Plan).

~~Hobby, toy, and game shops. See § 34-622(c)(21).~~

Home care facility means a conventional residence in which up to three unrelated individuals are cared for, but without provision for routine nursing or medical care.

Home occupation means an ~~business~~ occupation, or other activity undertaken for gain customarily carried on by an occupant of a dwelling unit as an accessory use which is clearly incidental to the use of the dwelling unit for residential purposes and which is operated in accordance with the application provisions of article IV ~~VH~~, division 18, of this chapter. See also Dwelling unit, live/work unit and Dwelling unit, work/live unit.

~~Hospice [deleted]~~

Hospital means a medical establishment that offers services more intensive than those required for room, board, personal services, and general nursing care, and offers facilities and beds for use beyond 24 hours by individuals requiring diagnosis, treatment, or care for injury or infirmity.

Hotel/motel means a building, or group of buildings on the same premises and under single control, which are kept, used, maintained or advertised as, or held out to the public to be, a place where sleeping accommodations are supplied for pay to transient guests for periods of one day or longer. See division 19 of article IV of this chapter.

~~Hotel/motel, business. See article VH, division 19, of this chapter.~~

~~Hotel/motel, efficiency. See article VH, division 19, of this chapter.~~

~~Household/office furnishings. See § 34-622(c)(22).~~

~~Housing unit means a house, apartment, mobile home or trailer, group of rooms or single room occupied or intended for occupancy as separate living quarters. Separate living quarters are those in which the occupants do not live and eat with any other person in the structure and which have direct access from the outside of the building or through a common hall. See Dwelling unit and Living unit.~~

~~Increase nonconformity [deleted]~~

Independent living unit means a unit which is authorized only as a part of a licensed continuing care facility (CCF), which may be equipped with a kitchen.

~~Insurance companies. See § 34-622(c)(23).~~

Intensity means a measurement of the degree of customarily nonresidential uses based on use, size, impact, bulk, shape, height, coverage, sewage generation, water demand, traffic generation, or floor area ratios. See also § 34-633.

~~Junkyard [deleted]~~

Land means earth, water, and air above, below, or on the surface, and includes any improvements or structures customarily regarded as land.

Land use means the development that has occurred on the land, the development that is proposed by a developer on the land, or the use that is permitted or permissible on the land under the Fort Myers Beach Comprehensive ~~Use~~ Plan or an element or portion thereof, land development regulations, or a land development code, as the context may indicate.

Landscape architect means a professional landscape architect duly registered and licensed by the state.

Laundromat means a business that provides washing, drying, dry cleaning, or ironing machines for hire for customers to use on the premises.

~~Laundry or dry cleaning. See § 34-622(c)(24).~~

Lawful or lawfully means a building, or use, or lot which was permitted by right, special exception, variance, special permit, or other action approving the use or placement of a structure by the Board of

~~County Commissioners or zoning board (such as by variance); at the time it was built, or occupied, or subdivided, and such building, or use, or lot was located in compliance with the comprehensive plan and zoning regulations for the district in which located, or in accordance with the terms of the variance.~~

~~Lawn and garden supply stores [deleted]~~

~~Leather products, manufacturing. [deleted]~~

~~Lee Plan [deleted]~~

Light trespass means light emitting from a point source of light that falls outside the boundaries of the property on which the point source of light is located and which constitutes a nuisance to a reasonable person of normal sensory perception.

Live-aboard means the use of a boat as a living unit.

Living unit means any temporary or permanent unit used for human habitation. See Dwelling unit and Guest Housing unit.

Loading space, off-street means a space logically and conveniently located for pickups or deliveries or for loading or unloading, scaled to delivery vehicles expected to be used and accessible to such vehicles when required off-street parking spaces are filled.

Local planning agency. See article II, division 3 of this chapter. means the county planning and zoning commission performing the functions set forth in § 163.3174, as well as the functions set forth in § 34-115.

Lock-off accommodations means a living unit which cannot be physically separated from another living unit but can be separated from it by locking a door, and which contains at least one bedroom and one bath and is accessible from a separate outside door.

Lock-off accommodations means a single guest unit or living unit designed in such a manner that at least one room and a bathroom can be physically locked off from the main unit and occupied as a separate unit. Each portion may have a separate outside entry, or share a common foyer with separate lockable interior doors, or share a lockable

door or doors separating the two units. See § 34-632 and division 19 of article IV of this chapter.

Lot means a parcel of land considered as a unit. See also Lot, corner.

Lot area means the total horizontal area within the lot lines.

Lot, corner means:

- (1) A lot located at the intersection of two or more streets where the corner interior angle formed by the intersection of the two streets is 135 degrees or less; or
- (2) A lot abutting a curved street if straight lines drawn between the intersections of the side lot lines and the street right-of-way or easement to the foremost point of the lot form an interior angle of less than 135 degrees.

~~Lot coverage means that portion of the lot area, expressed as a percentage, occupied by all buildings or structures.~~

Lot line means a line which delineates the boundary of a lot.

Lot line, front means the lot line which separates the lot from a street right-of-way or easement.

Lot line, rear means that lot line which is parallel to or concentric with and most distant from the front lot line of the lot. In the case of an irregular or triangular lot, a line 20 feet in length, entirely within the lot, parallel to or concentric with and at the maximum possible distance from the front lot line, shall be considered to be the rear lot line. In the case of a through lot, there shall be no rear lot line. In the case of a double-frontage lot, the line directly opposite from the front line shall be designated as either a rear line or a side line depending upon the designation of the adjacent property. In the case of corner lots, the rear lot line shall be the line most nearly parallel to or concentric with and most distant from the front lot line most prevalent along the block.

Lot line, side means any lot line which is not a front or rear lot line.

Lot measurement, depth.

- (1) For lots lawfully created prior to January 28, 1983, depth of a lot shall be considered the

distance between the midpoints of straight lines connecting the foremost points of the side lot lines in the front and the rearmost points of the side lot lines in the rear.

- (2) For lots lawfully created after January 28, 1983, depth of a lot shall be considered to be the distance between the front lot line and the rear lot line as measured at the midpoint of the front lot line to the midpoint of the rear lot line. To determine the midpoint of a curved line, a straight line is drawn connecting the points of intersection of the curved line with the side lot lines. A line drawn perpendicular to the midpoint of the straight line to the point it intersects the curved line shall determine the midpoint of the curved line for purposes of this chapter.

Lot measurement, width.

- (1) For lots lawfully created prior to January 28, 1983, width of a lot shall be considered to be the average distance between straight lines connecting front and rear lot lines at each side of the lot, measured as straight lines between the foremost points of the side lot lines in front (where they intersect with the street line) and the rearmost points of the side lot lines in the rear.
- (2) For lots lawfully created after January 28, 1983, width of a lot shall be considered to be the distance between the side lot lines (or a front and side lot line for corner lots) as measured along the minimum required street setback line. See § 34-637(c) for exceptions.

Lot of record means a lot which is part of a plat which has been lawfully recorded in the plat books in the office of the clerk of the circuit court of the county, and is in compliance with F.S. ch. 177, or a parcel of land, the deed of which was lawfully recorded in the office of the clerk of the circuit court of the county on or before January 28, 1983.

Lot, through means any lot having two opposite lot lines abutting a street right-of-way or easement.

Machinery, manufacturing. [deleted]

Manufactured housing. See *Building, conventional*.

Manufacturing means establishments which are primarily engaged in the mechanical or chemical

transformation of materials or substances into new products, as well as establishments primarily engaged in assembling component parts of manufactured products if the new product is not a permanent structure or other fixed improvement.

~~*Marina* means a boating facility, chiefly for recreational boating, located on navigable water frontage, which provides a boat ramp with parking for vehicles and trailers, boat slips, dockage, or dry boat storage (with a service to place boats in the water upon request), and one or more marina accessory uses (df), to patrons other than residents of the premises. The word "marine" will also apply to navigable fresh waters. This term may not be construed to apply to docks, davits, boathouses, and similar facilities appurtenant to a residential land use providing only dockage or mooring to the residents, or to any county-owned boatramp or docking facility.~~

Marina means a commercial water-dependent use located on property adjacent to water with direct access to a navigable channel. The primary function must be to provide commercial dockage, mooring, storage, and service facilities for watercraft and land-based facilities and activities necessary to support the water-dependent use. The term "marina" does not include boatyards, nor does it include cruise ships and similar uses that draw large amounts of vehicular traffic (see § 34-620(f)), nor does it apply to docks, davits, boathouses, and similar docking facilities that are accessory or ancillary and subordinate to:

- (1) residential buildings that are located on the same premises and under the same ownership or control as the docks, davits, boathouses, boat ramps, and similar docking facilities; and
- (2) commercial establishments that are not water-dependent uses.

Marina accessory uses means uses normally ancillary and subordinate to a marina, including but not limited to: boat dealers; sale of marine fuel and lubricants, marine supplies, boats, boat motors, and boat parts; restaurant or refreshment facility, boat rental, minor boat rigging, boat repair and service, and motor repair. However, no dredge, barge, or other work dockage or service is permitted and no boat construction or reconstruction is permitted. See *Boatyard*.

~~Massage establishment [deleted]~~

~~Measuring, analyzing, and controlling instruments, manufacturing. See § 34-622(c)(28).~~

~~Medical office [deleted]~~

Membership organization means an organization operating with formal membership requirements with the intent to pursue common goals or activities.

~~Mining [deleted]~~

Mini-warehouse means any building designed or used to provide separate individual storage units with separate exterior doors as the primary means of access rooms to individuals or businesses for a fee, or rental, with such rooms being intended. The storage units must be used solely as dead storage depositories for personal property, inventory, and equipment and not for any other commercial or industrial use. See Warehousing, public and Storage, dead.

Mixed-use building means a single building that contains two different land uses, such as commercial and residential uses, or commercial and civic uses.

Mobile home. See Dwelling unit, types.

~~Model [deleted]~~

~~Modular home. See Building, conventional.~~

Moor means to secure a vessel with lines.

Multiple-family building. See Dwelling unit, types.

Multiple-occupancy complex means a parcel of property under one ownership or singular control, or developed as a unified or coordinated project, with a building or buildings housing more than five occupants conducting a business operation of any kind.

~~Multi-slip docking facility [deleted]~~

~~Music store [deleted]~~

~~Newsstand [deleted]~~

~~Nightclub [deleted]~~

Nonconforming building, nonconforming structure, lot, or nonconforming use – see definitions in § 34-3202 of means an existing building or structure, lot, or use, lawful when established, which fails to comply with any provisions of this chapter, or which fails to comply as the result of subsequent amendments. See article VHH of this chapter.

~~Nonstore retailers. See § 34-622(c)(30).~~

~~Nontransient park [deleted]~~

Notary, notarize(d). Whenever the terms “notarize” or “notarized” appear, they expressly include and contemplate the use of the written declaration set forth under F.S. § 92.525, so long as the cited statutory requirements are met, except that written declarations may not include the words “to the best of my knowledge and belief” as this limitation is not permitted by the provisions of this code.

~~Novelties, jewelry, toys, and signs, manufacturing. See § 34-622(c)(29).~~

~~Nursery school. See Day care center, child.~~

Offices, general or medical mean a room or group of rooms where a business, government, profession, agency, or financial institution provides its services, but excluding uses listed as residential, lodging, retail, marine and civic in division 2 of article III of this chapter and otherwise classified by this code, and excluding uses that the director deems to have potential impacts that differ substantially from conventional office uses. Incidental retail sales and indoor storage may be provided in conjunction with these services. The following types of establishments are not considered to be offices for the purposes of this chapter: Automobile rental Drive-throughs (Type 1 or Type 2); and Wholesale establishments. See also Administrative office.

Opaque means the quality of blocking visibility through a material. For instance, concrete is 100% opaque; clear glass is 0% opaque; and a picket fence with 3-inch pickets separated by 3 inches of space is 50% opaque.

~~Outparcel [deleted]~~

~~Package store [deleted]~~

~~Paint ball range, outdoor [deleted]~~

~~Paint, glass, and wallpaper store [deleted]~~

~~Paper and allied products, manufacturing. [deleted]~~

Parasailing operations office means a land-based site that can qualify for a parasailing activity license in accordance with chapter 27 of this code. Parasailing operations offices are permitted as resort accessory uses and also by special exception in certain zoning districts.

Park, neighborhood means a recreational area open to the public and no larger than one acre that primarily serves the immediately surrounding neighborhood.

Park, community or regional means a recreational area open the public and larger than one acre that is designed to serve the entire community or larger areas.

~~Park-trailer. See Recreational vehicle.~~

Parking garage means a building or structure that allows the parking of motor vehicles on two or more levels, whether the garage is provided only for vehicles of occupants of the principal use or the garage is available for the use of the general public. However, for the purposes of this chapter, a building containing two or more levels of parking only for the vehicles of occupants of the principal use shall not be considered a parking garage if it is built below and fully within the perimeter of the remainder of the principal building.

Parking lot, accessory means an area of land set aside for the temporary parking of vehicles owned or leased by the owner of the premises, guests, employees, or customers of the principal use. See Commercial accessory use.

Parking lot, shared permanent commercial means a parking lot which constitutes the principal use of the property and which is available to the public for a fee, or which may be leased to individual persons or assigned to specific businesses or properties.

Parking lot, seasonal temporary means an area of land set aside temporarily to provide overflow

parking to meet (seasonal) demands, as set forth in § 34-2022.

~~Parks. See § 34-622(c)(32).~~

~~Party of record [deleted]~~

~~Permanent resident [deleted]~~

~~Permanent unit [deleted]~~

Personal services. See § 34-622(c)(33): means establishments primarily engaged in providing frequent or recurrent services involving the care of a person or his or her personal goods or apparel, such as beauty and barber shops, clothing alterations and repair, health clubs, and laundry drop-off points. The following types of establishments are not considered to be personal services for the purposes of this chapter: Automobile rentals, Car wash, Laundromat (whether self-service or operator-assisted); and Mini-warehouse. This chapter contains specific regulations for certain personal services (for example, see § 34-3066–3070 on tattoo studios and body piercing).

Personal watercraft operations office means a land-based site that can qualify for a personal watercraft vendor's license in accordance with chapter 27 of this code. Personal watercraft operations offices are permitted as resort accessory uses and also by special exception in certain zoning districts.

~~Pet services [deleted]~~

~~Pet shop [deleted]~~

~~Petroleum, manufacturing. [deleted]~~

~~Pharmacy [deleted]~~

~~Photofinishing laboratories [deleted]~~

Place of worship means a structure or structures designed primarily for accommodating an assembly of people for the purpose of religious worship, including related religious instruction, church, or synagogue ministries involving classes for 100 or less children during the week, and other church or synagogue sponsored functions which do not exceed the occupancy limits of the building.

Planned development. See article III, division 6 of this chapter. means a development that is designed and developed as a cohesive, integrated unit under single ownership or unified control which permits flexibility in building siting, mixture of housing types or land uses, clustering, common functional open space, the sharing of services, facilities, and utilities, and protection of environmental and natural resources.

Planned unit development (PUD). See article VI, division 10, subdivision IV, of this chapter.

Plant nursery [deleted]

Plat means a plat as defined by F.S. ch. 177.

Plaza means an unroofed public open space designed for pedestrians that is open to the sidewalk on at least one side.

Point source of light means a manmade source emanating light, including but not limited to: incandescent, tungsten-iodine (quartz), mercury vapor, fluorescent, metal halide, neon, halogen, high-pressure sodium, and low-pressure sodium light sources, as well as torches, campfires, and bonfires.

Portable kiosk. See § 34-1712.

Premises means any lot, area, or tract of land.

Premises, on the same means being on the same lot or building parcel or on an abutting lot or adjacent building in the same ownership.

Primary metal industries, manufacturing. See § 34-622(c)(35).

Principal building. See *Building, principal*.

Principal use. See *Use, principal*.

Printing and publishing. See § 34-622(c)(36).

Prison [deleted]

Private park [deleted]

Processing and warehousing means the storage of materials in a warehouse or terminal and where such materials may be combined, broken down or

aggregated for transshipment or storage purposes where the original material is not chemically or physically changed. The term “processing and warehousing” shall mean an establishment essentially for storage and shipment as opposed to a manufacturing establishment.

Produce stand. See article VII, division 16, of this chapter.

Property line. See *Lot line*.

Public park [deleted]

Quarter section line [deleted]

Racetracks. See § 34-622(c)(37).

Recreation hall means a building owned or operated by a condominium or homeowners’ association for a social or recreational purpose, but not for profit or to render a service which is customarily carried on as a business. This definition does not include fraternities or sororities.

Recreational facilities.

- (1) Commercial Recreation facilities, commercial means a recreation equipment or facilities not classified as a Park, neighborhood or Park, community or regional, or as personal, private-on-site, or private-off-site recreation facility, but instead operated as a business and open to the public for a fee. (Golf courses are defined separately in this section.) See § 34-622(c)(38).
- (2) Personal Recreation facilities, personal means a recreation equipment or facilities such as swimming pools, tennis, shuffleboard, handball or racquetball courts, swings, slides, and other playground equipment provided as an accessory use on the same premises and in the same zoning district as the principal permitted use and designed to be used primarily by the owners, tenants, or employees occupants of the principal use and their guests. See Residential accessory use.
- (3) Private Recreation facilities, private ON-SITE means a recreation hall, equipment, or facilities such as swimming pools, tennis, shuffleboard, handball, or racquetball courts, swings, slides, and other playground equipment which are located on the same

~~premises and in the same zoning district as the development or neighborhood it serves, owned, leased or, operated by a nonprofit organization, such as a homeowners', co-op, or condominium association and located in the development or neighborhood controlled by the association, and open only to bona fide members and guests of such nonprofit organization. This term shall not be interpreted to include fraternal or membership organization clubs.~~

- (4) Recreation facilities, private OFF-SITE means recreation hall, equipment, or facilities such as swimming pools, tennis, shuffleboard, handball, or racquetball courts, swings, slides, and other playground equipment which are owned, leased or operated by a homeowners', co-op, or condominium association for use by the association's members and guest, but which are not located in the development or neighborhood controlled by the association.
- (5) ~~(4)~~ Public Recreation facility, public means a recreation facility operated by a governmental agency and open to the general public.

Recreational vehicle means a recreational vehicle type unit which is so defined in F.S. § 320.01(b). It is primarily designed as temporary living quarters for recreational, camping or travel use, and has its own motive power or is mounted on or drawn by another vehicle. Because the statutory definition set forth in F.S. § 320.01(b) changes, the definition of the term "recreational vehicle," as used in this chapter, is intended to change with such statutory changes so as to be consistent with them. See also § 34-694.

[remainder of this definition has been deleted; it described six types of recreational vehicles]

Recreational vehicle park, developed means a parcel (or portion thereof) or ~~abutting contiguous~~ parcels of land designed, used or intended to be used to accommodate two or more occupied recreational vehicles. See § 34-694 and division 31 of article IV of this chapter, ~~and in which necessary utilities and streets and the final site grading or paving of concrete pads or vehicle stands was completed prior to September 16, 1985.~~

Recreational vehicle park, expanded expansion to an existing means the preparation of additional sites,

by the construction of facilities for servicing the sites on which the recreational vehicles are to be located (including the installation of utilities, final site grading, pouring of concrete pads or the construction of streets), ~~for which a preliminary development order was not issued by the county prior to September 16, 1985. This shall not be interpreted to include pads for utility rooms, enclosures or storage sheds where explicitly permitted. See division 31 of article IV of this chapter.~~

~~Recreational vehicle park, new [deleted]~~

~~Recreational vehicle park, phased [deleted]~~

~~Recreational vehicle park resident, permanent [deleted]~~

~~Recycling facility [deleted]~~

Religious facilities means religious-related facilities and activities, which may include but are not limited to places of worship, bus storage facilities or areas, convents, monasteries, retreats, church or synagogue ministries involving classes for more than 100 children during the week, and homes for the aged.

~~Rental establishments. See § 34-622(c)(39).~~

Rental of beach furniture means a business that provides beach chairs, umbrellas, and similar equipment for a fee. Rental of beach furniture is permitted as a resort accessory use and also by right in certain zoning districts. See divisions 1 and 2 of ch. 14 and § 34-3151.

~~Repair shops. See § 34-622(c)(40).~~

~~Research and development laboratories. See § 34-622(c)(41).~~

Residence. See Dwelling unit; and Living unit ~~and Housing unit.~~

~~Residential accessory uses. See § 34-622(c)(42).~~ means the use of a structure or premises that is customarily incidental and subordinate to the principal use of a residential structure. See Use, principal. Typical residential accessory uses are: carports and garages (§ 34-1013); decks, gazebos, patios, and screen enclosures; dock, personal

(§ 34-1863): fences and walls (division 17 in article IV); garage sales or yard sales (see definition in this section); recreation facilities, personal; seawalls (ch. 26); and storage sheds. Division 2 and other portions of article IV provide regulations for many residential accessory uses.

Resort means a mixed-use facility that accommodates transient guests or vacationers. Resorts contain at least 50 units, which may include a combination of dwelling units, guest units and timeshare units, and provide food service, outdoor recreational activities, and/or conference facilities for their guests, facility principally for the accommodation or short-term residence of transient guests or vacationers, but where the primary attraction is generally recreational features or activities:

Resort accessory use means the use of a structure or premises that is customarily incidental and subordinate to a resort. See Use, principal. Typical resort accessory uses are: Amusement devices (§§ 34-2141–2145 and 34-3042); Golf courses; Parasailing operations office (ch. 27); Personal watercraft operations office (ch. 27); and Rental of beach furniture (ch. 14).

Resource protection area [deleted]

Resource recovery [deleted]

Restaurant, fast food means an establishment whose principal business is the sale of food or beverages in a ready-to-consume state primarily for off-site consumption, and which may not contain drive-through facilities. [as amended by Fort Myers Beach Ordinance 00-13]

Restaurant, standard means an establishment whose principal business is the sale of food or beverages to customers in a ready-to-consume state. See § 34-620(f) regarding the prohibition on drive-through lanes for restaurants, and whose principal method of operation includes one or both of the following characteristics:

- (1) Customers, normally provided with an individual menu, are served their foods and beverages by a restaurant employee at the same table or counter at which food and beverages are consumed;

~~(2) A cafeteria-type operation is conducted where food and beverages generally are consumed within the restaurant building. See § 34-622(c)(43).~~

Retail store means an establishment operating within a fully enclosed building that provides goods and incidental services directly to consumers where such goods are available for immediate purchase or rental. Retail stores are classified as small (less than 5,000 square feet) or large (more than 5,000 square feet), based on gross floor area per establishment. The following types of establishments are not considered to be retail stores for the purposes of this chapter: Automobile fuel pumps, Automobile rentals, Marina, and Mini-warehouse.

Retaining wall [deleted]

Right-of-way line. See Street right-of-way line.

Roadside stand. See article VII, division 16, of this chapter:

Rooming house means a residential building used, or intended to be used, as a place where sleeping or housekeeping accommodations are furnished or provided for pay to transient or permanent guests or tenants on a weekly or longer basis in which less than ten and more than three rooms are used for the accommodation of such guests or tenants, but which does not maintain a public dining room in the same building or in any accessory building.

Rooming unit means a room or group of rooms used, or designed and intended to be used, as a living facility for a single family, and which contains provisions for living, sleeping and sanitation but does not provide cooking or eating facilities.

Rubber and plastics products, manufacturing: [deleted]

School, commercial. See § 34-622(c)(45). means an educational institution run by a public agency, a church or synagogue, or a not-for-profit organization. See division 32 of article IV of this chapter.

Vertical Seawall has the meaning provided in § 26-41. means a vertical bulkhead located at or

~~below mean high water, built to withstand wave force and erosion. See *Retaining wall*.~~

~~*Self-service fuel pump station* [deleted]~~

~~*Self-service fuel pumps* [renamed *Automobile fuel pumps*]~~

~~*Servants' quarters* [deleted]~~

Setback means the minimum horizontal distance required between a specified line and the nearest point of a building or structure. See also "build-to" lines in § 34-662 and setback exceptions in § 34-638(d).

- (1) *Street setback* means the setback extending across the front of a lot measured from the edge centerline of an existing or proposed street right-of-way or street easement. See § 34-638, 2192 for requirements. ~~Whenever this chapter refers to street setback it shall be interpreted to mean existing or proposed street right-of-way or street easement, whichever is greater.~~
- (2) *Side setback* means the setback, extending from the required street setback to the required rear lot line, or opposing street setback in the case of a double-frontage lot, measured from the side lot line. There are two types of side setbacks, those applying to waterfront lots and those applying to non-waterfront lots. See § 34-638.
- (3) *Rear setback* means the setback, extending across the rear of a lot, measured from the rear lot line. See § 34-638.
- (4) *Water body setback* means the setback measured from the mean high water ~~tide~~ line (MHWL), or the control elevation line if applicable, of a water body. See § 34-638, 2194 for requirements.
- (5) *Section line or quarter section line setback* means the setback measured from a section or quarter section line, as applicable.

Shield means to establish a visual and sound barrier by the use of a berm, wall, screening, or other methods that will not permit the sound or sight of the facility in question to be apparent from adjoining property.

~~*Shopping center* [deleted]~~

Shoreline means a straight or smoothly curved line which, on tidal waters, follows the general configuration of the mean high-water line, and which on nontidal waters is determined by the annual average waterline. Boat slips and other manmade or minor indentations shall be construed as lying landward of the shoreline and are considered upland when computing the lot area of waterfront property.

~~*SIC code* [deleted]~~

Single-family residence. See *Dwelling unit, types*.

~~*Social services.* See § 34-622(c)(46).~~

Special exception. See *Use, special exception*.

~~*Specialty retail shop.* See § 34-622(c)(47).~~

~~*Stable, boarding* [deleted]~~

~~*Stable, commercial* [deleted]~~

~~*Stable, private* [deleted]~~

~~*Stone, clay, glass and concrete products, manufacturing* [deleted]~~

Storage means the safekeeping of any goods, wares, products, or other commodities in any area for more than 48 hours for later use or disposal. The term "storage" includes the keeping of boats, cars, recreational vehicles, etc., for others, whether or not compensation is made to the property owner. The term shall not include animals, nor shall it apply to normally anticipated outdoor display of products for sale such as by boat, mobile home, construction equipment or vehicle dealers, or landscaping materials, or customary and usual activities accessory to agricultural or residential dwellings.

Storage, dead means the storage of goods, wares, products, or other commodities, with no sales, conferences, or other human activity other than the placement, removal, or sorting of stored items.

Storage, indoor means storage accessory to a permitted use and which is contained wholly within a building. When listed as a permitted or permissible use in the zoning district regulations, it shall not be construed to mean a warehouse or a mini-warehouse. See *Commercial accessory use*.

Storage, open means any storage not defined as indoor storage.

Story (floor) means that portion of a building included between the upper surface of a floor and upper surface of the floor or roof next above, including space at ground level as the first story provided it is six feet or more in height. Space within a roofline that is entirely non-habitable shall not be considered to be a story. See § 34-631.

STRAP number is a means of property identification which consists of seventeen digits including the section, township, range, area, and parcel numbers.

Street means a public or private thoroughfare which affords vehicle access to the principal means of ingress or egress to a lot. The term “street” is synonymous with the terms “avenue,” “boulevard,” “drive,” “lane,” “place,” “road,” and “way,” or similar terms.

Street right-of-way, existing is a general term denoting land, property, or interest therein, usually in a strip, acquired for or devoted to transportation purposes, which has been dedicated to the public and accepted by the town council or board of county commissioners.

~~*Street right-of-way or street easement line*~~ [deleted]

~~*Street right-of-way, proposed*~~ [deleted]

Structure means that which is built or constructed. The term “structure” shall be construed as if followed by the words “or part thereof.”

~~*Studios.*~~ See § 34-622(c)(49).

~~*Supermarket*~~ [deleted]

Surveyor or professional surveyor means a Professional Land Surveyor and Mapper (PSM) duly registered and licensed by the state.

Telephone booth or pay telephone station means a telephone installation made available for use by the general public for a fee, whether installed in an enclosed booth, attached to a pole, post, or pedestal, or attached to a building. A telephone booth or pay telephone station is not an “essential service” nor

“essential service equipment,” nor is it considered to be a “Residential Accessory Use.” See *Commercial accessory use.*

~~*Temporary use.*~~ See *Use, temporary.*

~~*Textile mill products.*~~ [deleted]

Theater means a building or part thereof that seats more than 200 people and is devoted to showing motion pictures, or for dramatic, musical, or live entertainment.

Through lot. See *Lot, through.*

Timeshare unit means any dwelling unit, guest unit, or living unit rooming unit for which a timesharing plan, as defined in F.S. ch. 721, has been established and documented. See § 34-632 for determining density of timeshare units that include “lock-off accommodations.”

~~*Tobacco manufacturing.*~~ [deleted]

~~*Tower*~~ [deleted]

~~*Townhouse.*~~ See *Dwelling unit, types.*

Transient guest means any guest registered as provided for in F.S. § 513.01(7), for six months or less.

~~*Transient park*~~ [definition moved to § 34-694]

~~*Transient unit*~~ [definition moved to § 34-694]

Transit terminal means a location where airport shuttles may stop to load or unload passengers and luggage and which allows convenient transfers to local trolleys and taxis.

~~*Transition zone*~~ [deleted]

~~*Transportation department*~~ [deleted]

~~*Transportation equipment, manufacturing.*~~ [deleted]

~~*Transportation services.*~~ See § 34-622(c)(53).

~~*Travel trailer.*~~ See *Recreational vehicle.*

~~*Truck stop*~~ [deleted]

~~Trucking terminal [deleted]~~

~~Two-family. See Dwelling unit, types.~~

~~Unauthorized communication [deleted]~~

~~Unified control means that a single property owner or entity has been authorized by all owners of the property to represent them and to encumber the parcel with covenants and restrictions applicable to development of the property as approved by the town. the unrestricted right of any owner or agent to enforce whatever conditions are set on the use and development of a parcel of land through the provisions of this chapter, by binding his heirs, assigns, or other successors in title with covenants or restrictions on the development and subsequent use of the property.~~

~~Unified control, covenant of means the demonstration and documentation that an owner or agent has unified control over a piece of property and is competent and willing to bind his heirs, assigns or other successors in title in the public interest to whatever conditions are placed on the development and subsequent use of the property through the provisions of this chapter.~~

~~Unit of high impact means any dwelling unit or rooming unit:~~

- ~~(1) Located in a hotel or motel and rented or leased to guests for terms of less than 30 consecutive days.~~
- ~~(2) That is being developed or converted to a timeshare unit as defined by the Florida Real Estate Time-Share Act, F.S. ch. 721, and being created and divided into ten or more periods.~~

~~Use means any purpose for which a building or other structure or a tract of land may be designed, arranged, intended, maintained, or occupied; or any activity, occupation, business, or operation carried on, or intended to be carried on, in a building or other structure or on a tract of land.~~

~~Use, accessory means a use of a structure or premises which is customarily incidental and subordinate to the principal use of the structure or premises. See Use, principal; Commercial accessory use; Residential accessory use; and Resort accessory use.~~

~~Use, mixed means the development of land or building or structure with two or more different but compatible uses, such as but not limited to residential, office, industrial and technological, retail, commercial, public, entertainment or recreation uses, in a compact urban form.~~

~~Use permitted by right means a use or uses which, by their very nature, are allowed within the specified zoning district provided all applicable regulations of the town county are met. Permitted use includes the principal use of the land or structure as well as accessory uses, unless specifically stated to the contrary.~~

~~Use, principal means the primary purpose for which land or a structure or building is used.~~

~~Use, public means the use of any land, water, or building by a public agency for a public service or purpose.~~

~~Use, special exception means a use or certain specified departures from the regulations of this chapter that may not be appropriate generally or without restriction throughout a zoning district, but which, when controlled as to number, area, location, or relation to the neighborhood, would promote the public health, safety, welfare, order, comfort, convenience, appearance, or prosperity, and may be permitted, in accordance with all applicable regulations.~~

~~Use, special permit [deleted]~~

~~Use, temporary means a use or activity which is permitted only for a limited time, and subject to specific regulations and permitting procedures. See article IV, division 37 of this chapter.~~

~~Use variance. See Variance, use.~~

~~Used merchandise stores. See § 34-622(c)(54).~~

~~Variance means a departure from the provisions of this chapter or from any town county ordinance (excluding building codes) relating to building and other structural setbacks, lot dimensions such as width, depth, or area, structure or building height, open space, buffers, off-street parking or loading requirements, floor area ratio, design, lot coverage, impervious areas, landscaping, and similar type regulations, but not involving A variance may not~~

involve the actual use of the property, building, or structures, procedural requirements, or definitions. This definition specifically excludes ~~section and quarter section line setbacks, street setbacks, modifications for solar or wind energy or other provisions specifically indicated as requiring a special exception permit, and variances from impact fees. However, in the case of planned development districts, the term “variance” means all of those requests to deviate from the provisions of this chapter, chapter 10 or other applicable regulations. A variance may be granted in accordance with the procedures set forth in § 34-87, when the enforcement of the ordinance, as it applies to a specific lot, would work an undue hardship. The applicant must demonstrate that the hardship is peculiar to his property and not to other properties in the zone. A finding must be made that the variance can be granted without any adverse impact on the public good. See *Variance, use* and *Variance, procedural*.~~

Variance, procedural means any departure from the procedural requirements of this chapter, chapter 10 or any other ordinance. Procedural variances are never permitted.

Variance, use means any departure from the provisions of this chapter and not specifically included in the definition set forth under *Variance* or *Variance, procedural*. The term “use variance” also means any attempt to vary any one or more of the definitions set forth in this chapter, either directly or indirectly. Use variances are never permitted.

~~*Variety store* [deleted]~~

~~*Vehicle and equipment dealers*. See section 34-622(c)(55): means the use of any building or land area for the display, sales, leasing, or storage of automobiles, trucks, trailers, recreational vehicles, construction equipment, and similar vehicles and equipment. See also *Automobile rental* and *Boat dealers*.~~

~~*Warehouse, private* [deleted]~~

~~*Warehouse, public* [deleted]~~

Water-dependent uses means land uses for which water access is essential and which could not exist without water access.

Water-related uses means land uses that might be enhanced by proximity to the water but for which water access is not essential.

Water, body of: means any artificial or natural depression in the surface of the earth that is inundated with daily tidal flows, and all adjacent wetlands as defined in § 14-293.

- (1) *Artificial bodies of water* means man-made canals and similar water bodies that extend a natural water body into uplands, a depression or concavity in the surface of the earth, other than a swimming pool, created by human artifice, or that portion of a natural body of water extended or expanded by human artifice, and in which water stands or flows for more than three months of the year.
- (2) *Natural bodies of water* include the Gulf of Mexico, Matanzas Pass, Estero Bay, Ostego Bay, Buccaneer Lagoon, and similar water bodies that were created by natural geophysical forces, means a depression or concavity in the part of the surface of the earth lying landward of the line of mean sea level (NGVD) which was created by natural geophysical forces and in which water stands or flows for more than three months of the year, also, the bays and estuaries lying between the county mainland and the barrier islands (Gasparilla Island, Cayo Costa, North Captiva Island, Captiva Island, Sanibel Island, Estero Island, Lovers Key, Big Hickory Island and Little Hickory Island and Bonita Beach) with the outermost boundary defined by a series of short straight lines that can be drawn connecting these islands.

~~*Waterway* [deleted]~~

Wetlands are defined in § 14-293. Wetlands in the Town of Fort Myers Beach are generally indicated on the future land use map of the Fort Myers Beach Comprehensive Plan, but the precise boundaries of wetlands shall be determined by this definition. means an area that is subject to permanent or prolonged periods of inundation or saturation (i.e., water is at the soil surface for at least two to seven months, seven out of ten years) and does or would support a prevalence of vegetative or aquatic life that requires saturated or seasonally saturated soil conditions for growth and reproduction. Wetlands generally include swamps

~~and marshes and may include similar areas such as sloughs, wet meadows and natural ponds.~~

~~Wholesale establishments. See § 34-622(c)(56). means a place of business primarily engaged in preparing and selling merchandise to retailers, other businesses, or other wholesale establishments, and operating completely within an enclosed building.~~

~~Zero-lot-line development [deleted]~~

~~Cross reference(s)--Definitions and rules of construction generally, § 1-2.~~

Sec. 34-3. Rules of construction.

The following rules of construction apply to the text of this chapter:

- (1) Where the term “ordinance,” “law,” “statute,” or “map” is referred to in the text, it is meant to include the phrase “as adopted and as amended from time to time” unless specifically stated to the contrary in the text.
- (2) In case of any difference of meaning or implication between the text of this chapter and any caption, illustration, summary table, or illustrative table, the text will control.
- (3) Where this chapter refers to a specific federal, state, ~~or county,~~ or town agency, department or division, it will be interpreted to mean “or any succeeding agency authorized to perform similar functions or duties.”

Sec. 34-4. Applicability of chapter; deed restrictions and vested rights.

(a) *Scope of chapter.* The provisions of this chapter shall apply uniformly to all land, water, buildings, and structures now or hereafter located in the Town of Fort Myers Beach ~~unincorporated areas of the county.~~

(b) *Deed restrictions.* The provisions of this chapter shall be held to be minimum requirements adopted for the promotion of the public health, safety, and welfare. It is not intended by this chapter to interfere with, abrogate, or annul any easements, covenants, or other agreement between the parties; provided, however, that, where this chapter imposes a greater restriction upon the uses of structures, land, and water, or requires more open space, than is required by other rules or regulations, or by easements, covenants, or agreements, by recorded

deed, plat, or otherwise, the provisions of this chapter shall govern. The ~~town county~~ shall not be responsible for the enforcement of private deed restrictions.

(c) *Vested rights.* Nothing in this chapter is to be interpreted or construed to give rise to any vested right in the continuation of any particular use, district or zoning classification or any permissible activities therein; and such use, district, zoning classification, and permissible activities are hereby declared to be subject to subsequent amendment, change, or modification as may be necessary to the protection of public health, safety, and welfare.

~~(d) Special regulations for Gasparilla Island conservation district. [deleted in its entirety]~~

Sec. 34-5. Interpretation of chapter.

(a) The interpretation and application of the provisions of this chapter shall be reasonably and uniformly applied to all property within the Town of Fort Myers Beach ~~unincorporated areas of the county.~~ The provisions of this chapter are regulatory.

(b) The provisions of this chapter shall be held to be the minimum requirements adopted for the protection and promotion of the public health, safety, comfort, convenience, order, appearance, prosperity, or general welfare, and for securing safety from fire and other dangers, providing adequate light and air, and preventing excessive concentration of population.

(c) Whenever the regulations and requirements of this chapter are at variance with the requirements of any other lawfully enacted and adopted rules, regulations, ordinances, or laws, the most restrictive shall apply.

Secs. 34-6--34-50. Reserved.

**ARTICLE II. ZONING PROCEDURES
ADMINISTRATION[†]**

DIVISION 1. GENERALLY

Sec. 34-51. Notice of public hearings required.

No public hearing required by this chapter shall be held by the hearing examiner, local planning agency or town council Board of County Commissioners until notice of the public hearing has been provided in accordance with the requirements set forth in this article.

Sec. 34-52. Communications with public officials.

~~Unauthorized communications: [existing § 34-52 deleted in its entirety]~~

(a) Definitions. The following terms and phrases, when used in this section, shall have these meanings:

Ex parte communication means any direct or indirect communication in any form, whether written, verbal or graphic, with the town council or local planning agency, by any person outside of a public hearing and not on the record, concerning substantive issues in any proposed or pending quasi-judicial action relating to appeals, variances, rezonings, special exceptions or any other quasi-judicial action assigned by statute, ordinance or administrative code.

Legislative action means the formulation of a general rule or policy, such as enacting a comprehensive plan or a comprehensive rezoning of multiple properties.

Public official means an elected or appointed member of a town board or commission that recommends or takes quasi-judicial actions, specifically including all members of the town council and the local planning agency. Members of the town staff are not public officials under this definition unless they also serve on a board or commission that recommends or takes quasi-judicial actions.

Quasi-judicial action means the application by the local planning agency or town council of a

previously adopted general rule or policy that will have an impact on a limited number of persons or property owners, such as individual appeals, variances, rezonings, and special exceptions.

Unrestricted communication means any communication by the public with public officials which are specifically allowed and encouraged, for instance, communications regarding the town budget or the general welfare of the community; or legislative actions such as proposed ordinances or general changes to the Fort Myers Beach Comprehensive Plan.

(b) Any person not otherwise prohibited by statute, charter provision, or ordinance may discuss with any local public official the merits of any matter on which action may be taken by any board or commission on which the public official is a member.

(1) Except for quasi-judicial actions (such as appeals, variances, rezonings, and special exceptions), the town encourages unrestricted communications between all public officials and town residents, visitors, businesspeople, and property owners.

(2) When discussions on pending quasi-judicial actions (such as administrative appeals, variances, rezonings, and special exceptions) take place prior to an advertised public hearing, the following procedures, which mirror those in F.S. § 286.0115(1), shall remove any presumption of prejudice arising from such ex parte communications with public officials:

a. The substance of any ex parte communication with a public official which relates to quasi-judicial action pending before the official is not presumed prejudicial to the action if the subject of the communication and the identity of the person, group, or entity with whom the communication took place is disclosed and made a part of the record before final action on the matter.

b. A public official may read a written communication from any person. However, a written communication that relates to quasi-judicial action pending before a public official shall not be presumed prejudicial to the action, and such written communication shall be made

[†]Cross reference(s)--Administration generally, ch. 2.

- a part of the record before final action on the matter.
- c. Public officials may conduct investigations and site visits and may receive expert opinions regarding quasi-judicial action pending before them. Such activities shall not be presumed prejudicial to the action if the existence of the investigation, site visit, or expert opinion is made a part of the record before final action on the matter.
- d. Disclosure made pursuant to subsections a., b. and c. must be made before or during the public meeting at which a vote is taken on such matters, so that persons who have opinions contrary to those expressed in the ex parte communication are given a reasonable opportunity to refute or respond to the communication. This subsection does not subject public officials to the Code of Ethics for Public Officers and Employees (part III of F.S. ch. 112) for not complying with this paragraph.

Sec. 34-53. Fees and charges.

(a) The schedule of fees and charges for matters pertaining to this chapter shall be posted in the office where permits applications are filed, of the department of community development. The charges listed may be changed by resolution of the town council, Board of County Commissioners. In the absence of a resolution by the town council, the director shall charge fees that are comparable to the fees charged by the board of county commissioners for similar applications.

(b) No permit shall be issued and no inspection, public notice, or other action relative to a zoning matter shall be instituted until after such fees and charges have been paid.

Secs. 34-54--34-80. Reserved.

**DIVISION 2. TOWN COUNCIL
BOARD OF COUNTY COMMISSIONERS**

Sec. 34-81. Appointment of local planning agency.

The town council Board of County Commissioners shall appoint the members of the local planning agency.

Sec. 34-82. Initiation of zoning actions.

The town council Board of County Commissioners or the town manager its designee may initiate rezonings, special exceptions, variances, special permits, developments of regional impact, and zoning ordinance land development code amendments, formal interpretations of this code and the Fort Myers Beach Comprehensive Plan, and other actions as may be specified in this code. See division 4 of this article for specific application requirements. See § 34-201.

Sec. 34-83. Functions and authority. (a) Land use ordinance amendments or adoption.

- (1) **Function.** The town council Board of County Commissioners shall hold public hearings on all proposed land use ordinance amendments or adoptions.
- (2) **Considerations.** When deciding whether to adopt a proposed land use ordinance or amendment, the town council Board of County Commissioners shall consider the Fort Myers Beach Comprehensive Plan and same criteria, recommendations and issues as set forth in § 34-115(b)(1), as well as the recommendation of the local planning agency.
- (3) **Decisions and authority.** The decision of the town council Board of County Commissioners on any proposed land use ordinance amendment or adoption is final.
- (4) **Appeals.** Appeals of any decision concerning land use ordinance amendments or adoption shall be taken in accordance with applicable state law.

Sec. 34-84. General procedures for (b) zoning actions on specific zoning applications.

- (1) **Function.** ~~a.~~ The town council Board of County Commissioners shall hold public hearings (see §§ 34-231 through 34-265 division 7 of this article) on the following applications: rezonings, appeals from administrative actions, variances, the special exceptions that meet the criteria for developments of county impact, and developments of regional impact, and any other action in conjunction with such applications.

b. All requests for variances, special exceptions and special permits which are part of an application for a rezoning shall be considered by the Board of County Commissioners with the application for rezoning and heard together with and at the same time as the rezoning.

(2) Prior hearings. Public hearings before the town council shall be held after the local planning agency has held its hearing on these applications and rendered its formal recommendation to the town council, except for appeals of administrative actions, applications for interpretations of this code, and certain interpretations of the comprehensive plan, which shall require only a single public hearing before the town council.

(2) Considerations. In rendering its decision, the Board of County Commissioners shall consider the following:

- a. The criteria set forth in § 34-145(c)(2).
- b. The substantive recommendation of the hearing examiner when applicable.

(3) Decisions and authority.

- a. In exercising its authority, the town council Board of County Commissioners shall consider the recommendation of the local planning agency where applicable hearing examiner, but may, in conformity with the provisions of this chapter, reverse, affirm, or modify the recommendation of the hearing examiner, or remand the recommendation to afford due process.
- b. The town council Board of County Commissioners shall not approve any rezoning action other than that the rezoning published in the newspaper unless such change is more restrictive than the proposed rezoning published.
- c. The town council Board of County Commissioners has the authority to attach conditions and requirements to any approval of a request for a special permit, special exception, development of regional impact, planned development rezoning, or variance within their purview, deemed necessary for the protection of the health, safety, comfort, convenience, or welfare of the general public. Such conditions or requirements must be reasonably related to the action requested.

d. The decision of the town council Board of County Commissioners on any matter listed in this subsection (b) is final. If a decision of approval is not obtained, or if a tie vote results from a motion to grant a request or from a motion to deny a request, then the matter being considered shall be deemed to have been denied, unless a majority of the members present and voting agree by motion, before the next agenda item is called, to take some other action in lieu of denial. Such other action may be moved or seconded by any member, regardless of his vote on any earlier motion.

(4) Denials. [relocated from § 34-211]

Any denial by the Board of County Commissioners is denial with prejudice unless otherwise specified by the Board of County Commissioners (see § 34-211):

a. Denial with prejudice.

1. Except when specifically stated otherwise, a denial by the town council hearing examiner or Board of County Commissioners is a denial with prejudice.
2. If an application is denied with prejudice, no similar application for rezoning, special exception, or variance or special permit covering the same property, or portion of the property, shall be resubmitted or initiated for a period of 12 months from the date of denial. However, this shall not preclude the application for a different rezoning, special exception, or variance or special permit which in the opinion of the director administrative official is substantially different from the request originally denied.

b. Denial without prejudice.

1. When the town council hearing examiner or Board of County Commissioners denies without prejudice any application, it is an indication that, although the specifically requested action is denied, the town council hearing examiner or board is willing to consider the same request after modifications have been made, or an application for other action, without the applicant having to wait 12 months

before applying for consideration of the modified request or other action.

2. Any resubmitted application shall clearly state the modifications which have been made to the original request or other changes made in the application.

(5) **Rehearings.** Any rehearings of decisions under this section shall be in accordance with § 34-93.

(6) **Special master.** Final decisions under this section may be the subject of a request for relief under F.S. § 70.51 or 70.001 (see §§ 34-94 and 34-95).

(7) (4) **Judicial review.** Judicial review of final decisions under this section shall be in accordance with section 34-85 96.

Sec. 34-85. Rezoning.

(1) **Function.** The town council shall hear and decide all applications for changes in zoning district boundaries.

(2) **Considerations.** In reaching its decision, the town council shall consider the following, whenever applicable:

- a. Whether there exists an error or ambiguity which must be corrected.
- b. Whether there exist changed or changing conditions which make approval of the request appropriate.
- c. The impact of a proposed change on the intent of this chapter.
- d. The testimony of any applicant.
- e. The recommendation of staff and of the local planning agency.
- f. The testimony of the public.
- g. Whether the request is consistent with the goals, objectives, policies, and intent, and with the densities, intensities, and general uses as set forth in the Fort Myers Beach Comprehensive Plan.
- h. Whether the request meets or exceeds all performance and locational standards set forth for the proposed use.
- i. Whether urban services are, or will be, available and adequate to serve a proposed land use change.
- j. Whether the request will protect, conserve, or preserve environmentally critical areas and natural resources.
- k. Whether the request will be compatible with existing or planned uses and not cause

damage, hazard, nuisance, or other detriment to persons or property.

l. Whether the location of the request places an undue burden upon existing transportation or other services and facilities and will be served by streets with the capacity to carry traffic generated by the development.

m. For planned development rezonings, see § 34-216 for additional considerations.

(3) **Findings.** Before granting any rezoning, the town council shall find that the requested zoning district complies with:

- a. The Fort Myers Beach Comprehensive Plan.
- b. This chapter.
- c. Any other applicable town ordinances or codes.
- d. For planned development rezonings, see § 34-216 for additional findings.

(4) **Authority.**

a. When rezoning land to conventional zoning districts or redevelopment districts (see §§ 34-612(1) and (2)), the town council shall not impose any special conditions or requirements beyond those contained in this code, except as authorized by subsections 34-87(4)b. related to variances and 34-88(4)b. related to special exceptions.

b. In reaching decisions on planned development rezonings (see § 34-612(3)), the town council shall proceed in accordance with § 34-216 and shall have the authority to adopt a master concept plan, establish permitted uses, attach special conditions, and grant deviations from this code in accordance with §§ 34-932–933.

Sec. 34-86. (a) Appeals from administrative action. [moved from § 34-145]

- (1) **Function.** The town council hearing examiner will hear and decide appeals where it is alleged there is an error in any order, requirement, decision, interpretation, determination, or action of any administrative official charged with the administration and enforcement of the provisions of this code, chapter or any other ordinance or portion of this code which provides for similar review; provided, however, that:

- a. No appeal to the town council hearing examiner shall lie from any act by such administrative official pursuant to:
 - 1. An order, resolution, or directive of the town council Board of County Commissioners directing him to perform such act; or
 - 2. Any ordinance ~~or other regulation or provision in this code~~ which provides a different appellate procedure.
 - b. The appeal to the town council hearing examiner shall be in writing on forms provided by the director hearing examiner, and shall be duly filed with the hearing examiner within 30 calendar days, but not thereafter, after such act or decision by the administrative official. The appeal shall specify the grounds for the appeal.
 - c. No appeal shall be considered by the town council hearing examiner where it appears to be a circumvention of an established or required procedure. Specifically, in no case may an appeal be heard when the town council hearing examiner determines that the case should more appropriately be heard on a request for a variance.
 - d. Appeals from administrative action do not require a public hearing before the local planning agency. Notices of hearings on appeals shall be provided in accordance with the provisions of an applicable administrative code which shall be adopted by the Board of County Commissioners.
 - e. No appeal will be considered by the hearing examiner for any challenge to a development order which is controlled by F.S. § 163.3215. In cases of challenges to development orders controlled by F.S. § 163.3215, no suit may be brought and no verified complaint, as explained in F.S. § 163.3215(4), may be filed or accepted for filing until the development order giving rise to the complaint has become final by virtue of its having been issued by the director, or by virtue of its having been ordered by the county hearing examiner on an appeal reversing the director's denial of the development permit, or by the Board of County Commissioners in cases where the Board of County Commissioners has granted planned development zoning or an extension of a development order. Once a development order has been granted, the provisions of F.S. § 163.3215 will be the sole means of challenging the approval or denial of a development order, as that term is defined in F.S. § 163.3164(6), when the approval of the development order is alleged to be inconsistent with the Lee Plan, in which case an action brought pursuant to F.S. § 163.3215 will be limited exclusively to the issue of comprehensive plan consistency.
 - f. Except as may be required by F.S. § 163.3215, and then only pursuant to that statute, a third party shall not have standing to appeal an administrative decision granting or denying any development permit. Only the applicant or his agent shall be permitted to appeal such administrative action as set forth in this subsection (a).
- (2) **Considerations.**
- a. In reaching its his decision, the town council hearing examiner shall consider the following criteria, as well as any other issues which are pertinent and reasonable:
 - 1. Whether ~~or not~~ the appeal is of a nature properly brought to him for decision, or whether ~~or not~~ there is an established procedure for handling the request other than through the appeal process (i.e., a variance or special exception, etc.).
 - 2. The intent of the ordinance which is being applied or interpreted.
 - 3. The effect the ruling will have when applied generally to this code the ordinance which will be affected by the hearing examiner's decision.
 - b. Staff recommendations, the testimony of the appellant, and testimony of the general public shall also be considered.
- (3) **Authority.**
- a. In exercising its his authority, the town council hearing examiner may reverse, affirm, or modify any decision or action of any administrative official charged with the administration or enforcement of this chapter.
 - b. Subject to the limitations set forth in subsection (a)(3)a of this section, the hearing examiner may make a decision to take the appropriate action which the hearing examiner finds the administrative official should have taken. To that end, he

shall have the powers of the administrative official from whom the appeal is taken.
(4) ~~Judicial review.~~ Judicial review of final decisions of the hearing examiner with respect to administrative actions are to the circuit court in accordance with § 34-146.

Sec. 34-87. (b) Variances. [moved from § 34-145]

- (1) **Function.** The town council hearing examiner shall hear and decide all requests for variances from the terms of the regulations or restrictions of this code (except for administrative setback variances as provided in § 34-268) chapter and such other ordinances which assign this responsibility to the town council as may be assigned to him by the Board of County Commissioners, except that no use variance as defined in this chapter shall be heard or considered.
- (2) **Considerations.** In reaching its his decision, the town council hearing examiner shall consider the following criteria, recommendations and testimony:
 - a. Whether the facts support the five required findings in subsection (3) below: That exceptional or extraordinary conditions or circumstances exist which are inherent in the land, structure, or building involved and such exceptional or extraordinary conditions or circumstances create a hardship on the property owner and are not generally applicable to other lands, structures or buildings;
 - b. That the exceptional or extraordinary conditions or circumstances do not result from the actions of the applicant;
 - c. That literal interpretation of the provisions of the section of this chapter would deprive the applicant of rights commonly enjoyed by properties in the same district under terms of this chapter;
 - d. That granting the variance will not be injurious to the neighborhood or otherwise detrimental to the public welfare;
 - b. e. Staff recommendations and local planning agency recommendations;
 - c. f. Testimony from the applicant; and
 - d. g. Testimony from the public.
- (3) **Findings.** Before granting any variance, the town council must hearing examiner shall find that all of the following exist:

- a. That there are exceptional or extraordinary conditions or circumstances that are inherent to the property in question and that do not apply generally to the other nearby properties in the same zoning district;
 - b. That the exceptional or extraordinary conditions or circumstances are not the result of actions of the applicant taken subsequent to after the adoption of the regulation in question; ordinance (any action taken by an applicant pursuant to lawfully adopted regulations preceding the adoption of the ordinance from which this chapter is derived will not be considered self-created);
 - c. That the variance granted is the minimum variance that will relieve the applicant of an unreasonable burden caused by the application of the regulation in question to his property;
 - d. That the granting of the variance will not be injurious to the neighborhood or otherwise detrimental to the public welfare; and
 - e. That the condition or situation of the specific piece of property, or the intended use of the property, for which the variance is sought is not of so general or recurrent a nature as to make it more reasonable and practical to amend the regulation in question. ordinance.
- (4) **Authority.**
- a. The town council has hearing examiner shall have the authority to grant or deny, or modify, any request for a variance from the regulations or restrictions of this code chapter; provided, however, that no use variance as defined in this chapter, or any variance from definitions or procedures set forth in any ordinance, shall be granted.
 - b. In reaching its his decision, the town council has hearing examiner shall have the authority to attach such conditions and requirements as are necessary for the protection of the health, safety, comfort, convenience and welfare of the general public. Such conditions or requirements shall be reasonably related to the variance requested.
 - c. Variances may be reviewed by themselves or as part of a rezoning.

d. All decisions of the hearing examiner concerning variances filed as part of a rezoning shall be in the form of a recommendation to the Board of County Commissioners. Only a party of record or his representative shall be afforded the right to address the Board of County Commissioners.

(5) ~~Judicial review.~~ Judicial review of final decisions of the hearing examiner with respect to variances are to the circuit court in accordance with § 34-146.

Sec. 34-88. (c) Special exceptions. [moved from § 34-145]

- (1) **Function.** The town council hearing examiner shall hear and decide all applications for special exceptions permitted by the district use regulations.
- (2) **Considerations.** In reaching its his decision, the town council hearing examiner shall consider the following, whenever applicable:
 - a. ~~Whether there exists an error or ambiguity which must be corrected.~~
 - a. b. Whether there exist changed or changing conditions which make approval of the request appropriate.
 - c. ~~The impact of a proposed change on the intent of this chapter.~~
 - b. d. The testimony of any applicant.
 - c. e. The recommendation of staff and of the local planning agency.
 - d. f. The testimony of the public.
 - e. g. Whether the request is consistent with the goals, objectives, policies and intent of the Fort Myers Beach Comprehensive Lee Plan.
 - f. h. Whether the request meets or exceeds all performance and locational standards set forth for the proposed use.
 - i. ~~Whether urban services, as defined in the Lee Plan, are, or will be, available and adequate to serve a proposed land use change, when proposing a change to a future urban area category.~~
 - j. Whether the request is consistent with the densities, intensities and general uses set forth in the Lee Plan.
 - g. k. Whether the request will protect, conserve, or preserve environmentally critical areas and natural resources.

h. f. Whether the request will be compatible with existing or planned uses and not cause damage, hazard, nuisance, or other detriment to persons or property.

m. ~~Whether the location of the request places an undue burden upon existing transportation or other services and facilities and will be served by streets with the capacity to carry traffic generated by the development.~~

i. n. Whether a requested use will be in compliance with all applicable general zoning provisions and supplemental regulations pertaining to the use, as set forth in this chapter.

o. ~~Whether a proposed change is to rectify errors on the official zoning map.~~

- (3) **Findings.** Before granting any special exceptions, the town council hearing examiner shall find that the applicant has proved entitlement to the special exception by demonstrating compliance with:
 - a. The Fort Myers Beach Comprehensive Lee Plan;
 - b. This chapter; and
 - c. Any other applicable town county ordinances or codes.

(4) **Authority.**

a. The town council hearing examiner shall grant the special exception unless it he finds that granting the special exception is contrary to the public interest and the public health, safety, comfort, convenience and welfare of the citizens of the town county, or that the request is in conflict with the criteria in subsection (c)(3) of this section.

b. In reaching its his decision, the town council has hearing examiner shall have the authority to attach such conditions and requirements as are necessary for the protection of the health, safety, comfort, convenience, or welfare of the general public. Such conditions or requirements shall be reasonably related to the special exception requested.

c. Special exceptions may be reviewed by themselves or as a part of a rezoning.

d. All decisions of the hearing examiner concerning special exceptions filed as part of a rezoning or that meet the criteria for a development of county impact shall be in the form of a recommendation to the Board

~~of County Commissioners. Only a party of record or his representative shall be afforded the right to address the Board of County Commissioners.~~

- ~~(5) *Judicial review.* Judicial review of final decisions of the hearing examiner with respect to special exceptions are to the circuit court in accordance with § 34-146.~~

Sec. 34-89. Developments of regional impact.

The town council shall hold public hearings on all applications for developments of regional impact, in accordance with the requirements of ch. 380, Florida Statutes. If a proposed development of regional impact also requires a rezoning and/or a comprehensive plan amendment, the public hearings shall be held simultaneously provided that all advertising requirements for the individual applications can be met.

Sec. 34-90. Land development code interpretations.

The town council may hear and decide applications for interpretations of this code as provided in § 34-222. Such applications shall not require a public hearing or recommendation from the local planning agency.

Sec. 34-91. Comprehensive plan interpretations.

The town council will hear and decide applications for interpretations of the Fort Myers Beach Comprehensive Plan as permitted by ch. 15 of that plan. The following types of applications will be accepted:

- (1) *Equitable estoppel.* In circumstances where development expectations conflict with the comprehensive plan but judicially defined principles of equitable estoppel may override the otherwise valid limitations imposed by the plan, such expectations may be recognized by the town through a resolution of the town council. Such applications shall not require a public hearing or recommendation from the local planning agency.
- (2) *Appeals of administrative interpretations.* Persons or entities whose interests are directly affected by the comprehensive plan have the right to certain administrative interpretations of the plan as described in

ch. 15 of the plan. That section specifies the following procedures for appealing an administrative interpretation:

- a. *An administrative interpretation may be appealed to the town council by filing a written request within fifteen days after the administrative interpretation has issued in writing. In reviewing such an appeal, the town council shall consider only information submitted in the administrative interpretation process and shall review only whether the proper standards set forth in the comprehensive plan have been applied to the facts presented. No additional evidence shall be considered by the town council.*
- b. *The town council shall conduct such appellate review at a public meeting to be held within thirty days after the date of the written request for appeal. The town council may adopt the administrative interpretation being appealed, or may overrule it, with a written decisions to be rendered by the town clerk in writing within thirty days after the date of the hearing.*

- (3) *Legislative interpretations.* In order to apply the plan consistently and fairly, it will be necessary from time to time to interpret provisions in the plan in a manner which insures that the legislative intent of the town council which adopted the plan be understood and applied by subsequent councils, town employees, private property owners, and all other persons whose rights or work are affected by the plan. When the plan is interpreted, it should be done in accordance with generally accepted rules of statutory construction, based upon sound legal advice, and compiled in writing in a document which can be a companion to the plan itself.

- a. *Requests.* Requests for legislative interpretations may be made by any town council member, the town manager, the local planning agency, or any applicant for a type of development regulated by the plan.
- b. *Local planning agency.* Upon receiving a request and written recommendations from the town manager, the local planning agency shall review the same and forward them to the town council with its comments and recommendations.

c. Town council. Upon receiving the recommendations of the local planning agency, the town council shall render a final decision as to the correct interpretation to be applied. This interpretation shall be that which is adopted by absolute majority of the town council, and, upon being reduced to a resolution drafted in response to the council majority, it shall be signed by the mayor and recorded in the town's official records. The town clerk shall be responsible for maintaining copies of all such resolutions in a single document which shall be appropriately indexed and provided to all persons upon request. The document shall be updated regularly and the latest version thereof furnished to all persons requesting copies of the plan itself.

d. Legal effect of legislative interpretations. Any provision of the plan specifically construed in accordance with the foregoing procedures may not be re-interpreted or modified except by a formal amendment of the plan itself. Once formally adopted in accordance with these procedures, the interpretation shall have the force of local law and all persons shall be placed on constructive notice of it. Any development orders issued in reliance on legislative interpretations of this plan are subject to challenge under the provisions of F.S. § 163.3215.

Sec. 34-92. Comprehensive plan amendments.

(a) Amendments to any part of the Fort Myers Beach Comprehensive Plan may be proposed by private parties. All amendments requested during a calendar year will be considered simultaneously with any public amendment proposals put forth by the town council or local planning agency.

(b) Private applications for amendments must be received at town hall by the last business day of the calendar year. Amendment proposals do not need to include all of the information required by § 34-201, but must be sufficient to identify the parties making the request and the exact nature of the request, and must provide adequate supporting material in support of the request.

(c) Proposals to amend the Future Land Use Map must meet Comprehensive Plan Policy 4-C-10.

Sec. 34-93 84. Rehearing of decisions.

(a) Timely filing. Any person who may be aggrieved by any decision of the town council Board of County Commissioners made pursuant to an application for rezoning, development of regional impact, administrative appeal, special exception that meets the criteria of a development of county impact, or special exceptions, or variances or special permits heard as part of a rezoning may, within 30 calendar days after such decision, but not thereafter, file a written request with the county administrator or his designee a request in writing for a public rehearing before by the town council to modify or rescind its decision. Board of County Commissioners for a modification or rescission thereof. The request must be filed with the director within 15 calendar days after the decision. For purposes of computing the 15- computation of this 30-day period, the date of the decision is shall be the date of the public hearing at which the town council Board of County Commissioners made such decision by oral motion.

(b) Written request and response. All requests for a public rehearing shall state with particularity the any new evidence or the points of law or fact which the aggrieved person argues the town council Board of County Commissioners has overlooked or misunderstood, and must include all documentation offered to support the request for a rehearing. In addition, if the request is filed made by one other than the original applicant, the director county shall notify the applicant of the filing of the request for a rehearing and the applicant shall be allowed 15 days to submit an his independent written analysis.

(c) No oral testimony. The town council Board of County Commissioners shall decide whether to grant or deny the request for a rehearing based exclusively upon the aggrieved person's written request, and supporting documentation, any response, and the director's and/or town manager's administrator's written analysis thereof. The deliberations of the town council Board of County Commissioners with respect to the question of whether to grant a rehearing do not constitute a public hearing, and no oral testimony shall be allowed or considered by the town council Board of

County Commissioners in the course of these deliberations.

(d) (c) *Judicial review.* An aggrieved person need not request a The pursuit of a request for rehearing is not required in order to exhaust his administrative remedies as a condition precedent to seeking judicial review in filing an appeal to the circuit court. The proper filing of a request petition for rehearing will not toll the 30-day time limit set forth for to file an action seeking judicial review of final decisions, in § 34-85. If a rehearing request is refused, or if the request is granted but modification or rescission of the original motion of the Board of County Commissioners is denied, any aggrieved person may, within 30 calendar days after such refusal or denial, apply for judicial review of the original motion in accordance with § 34-85. No judicial review is available to review the town council's Board of County Commissioners' decision to deny refuse a rehearing request.

(e) A request for rehearing is not an administrative appeal as that term is used in F.S. § 70.51. Filing a request for rehearing will not toll the time for filing a request for relief under F.S. § 70.51.

(f) Filing of a request for rehearing will not toll the time for seeking relief under F.S. § 163.3215.

(d) There shall be no right to apply to court for relief on account of any determination or recommendation of the hearing examiner in those actions listed in § 34-83(b)(1) which require public hearing before the Board of County Commissioners.

Sec. 34-94. Special master proceedings under the Florida land use and environmental dispute resolution act (F.S. § 70.51)

(a) *Special master proceedings.* Special master proceedings may be requested by landowners who believe that action on a development order or enforcement of this code is unreasonable or unfairly burdens the use of their property. Special master proceedings are a non-judicial approach to resolving land-use disputes and will be conducted in accordance with state law and any administrative codes designated for that purpose.

(b) *Implementation of special master recommendation.* If the town council elects to adopt

the recommendation of any duly-appointed special master, the landowner will not be required to duplicate processes in which the owner previously has participated in to effectuate the recommendation.

(c) *Modification of special master recommendation.* The town council may elect to modify a special master's recommendation and implement it by development agreement, where applicable, or by other method in the ordinary course and consistent with the town's rules and procedures, so long as it does not require the duplication of processes in which the owner has participated in to effectuate the council's will.

(d) *Waiver of procedural requirements.* In order to implement the recommendation of a special master, or a modification of that recommendation, the town council has the authority to waive any or all procedural requirements contained in town ordinances or administrative codes and to directly exercise all authority otherwise delegated to the local planning agency, the town manager or designees, or any other part of town government.

Sec. 34-95. Proceedings under the Bert J. Harris, Jr., private property rights protection act (F.S. § 70.001).

(a) *Offers of Settlement.* Within 180 days of the filing of a notice of intent to file a claim under this act, the town may offer to resolve the claim by way of a settlement offer that includes an adjustment of the initial government action. Settlement offers may entail:

- (1) an increase or modification to density, intensity, or use of the owner's property, so long as the density, intensity, and use remain consistent with Fort Myers Beach Comprehensive Plan.
- (2) the transfer of development rights;
- (3) land swaps or exchanges;
- (4) compensation and purchase of the property or property interest, or
- (5) issuance of a development permit or order.

(b) The parties to a dispute arising under the Bert J. Harris, Jr., private property rights protection act may craft settlements that exceed the town's statutory or ordinance authority provided the parties jointly file a judicial action for court approval of the settlement.

(c) In order to implement a settlement offer, the town council has the authority to waive any or all procedural requirements contained in town ordinances or administrative codes and to directly exercise all authority otherwise delegated to the local planning agency, the town manager or designees, or any other part of town government.

Sec. 34-96 85. Final decision; judicial review.

(a) Any final zoning decision of the town council on a specific application Board of County Commissioners may be reviewed by the circuit court unless otherwise provided in this article. Except for review of verified complaints filed pursuant to F.S. § 163.3215, jurisdiction for review of any final decision of the Board of County Commissioners lies exclusively in circuit court. This review may only be obtained through filing a petition for writ of certiorari pursuant to the Florida Rules of Appellate Procedure. Any such petition must be filed within 30 calendar days after the decision has been rendered. For the purposes of computing the 30-day period, the date that the decision has been rendered is the date of the public hearing at which the town council Board of County Commissioners made such decision by oral motion.

(b) The person making application to the town council Board of County Commissioners for any final decision that is entitled to judicial review is a necessary and indispensable party to any action seeking judicial review of that final decision.

(c) This section is not intended to preclude actions pursuant to F.S. § 70.51 (see § 34-94), or actions pursuant to § 163.3215 that challenge consistency of any final zoning decision on a specific application with the Fort Myers Beach Comprehensive Plan.

Secs. 34-97 86--34-110. Reserved.

DIVISION 3. LOCAL PLANNING AGENCY

NOTES:

— Previous §§ 34-111–34-115 regarding Lee County's local planning agency are repealed in their entirety.

— New §§ 34-111–34-120 and 34-123 below incorporate and will replace Fort Myers Beach

Ordinances No. 96-02, 96-25, and 00-03, which established the town's local planning agency.

Sec. 34-111. Agency established.

The Town of Fort Myers Beach local planning agency (LPA) is hereby established.

Sec. 34-112. Purpose and scope.

The broad objectives of town planning and the creation of the local planning agency are to further the welfare of the citizens of the town by helping to promote a better, more helpful, convenient, efficient, healthful, safe, and attractive community environment and to insure that the unique and natural characteristics of the island are preserved.

Sec. 34-113. Composition, appointment, and compensation of members.

(a) The local planning agency shall consist of not less than seven nor more than nine members appointed by the town council. No members of the local planning agency shall be salaried officials of the town.

(b) The members of the local planning agency shall serve without compensation but may be reimbursed for expenses as are necessary to conduct the work of the agency from funds appropriated by the town council.

(c) In addition to the seven to nine voting members, the local planning agency shall also include as a nonvoting member a representative of the Lee County School District, as designated by the Lee County School Board, to attend and participate in those meetings at which the local planning agency considers comprehensive plan amendments and rezonings that would, if approved, increase residential density on the property that is the subject of the application (see F.S. 163.3174(1), 2002).

Sec. 34-114. Members' terms and vacancies.

(a) The term of office of a member of the local planning agency shall be staggered three years or until a successor has been appointed and has qualified, except that the respective terms of the members first appointed shall be two for one year, three for two years, and two for three years.

(b) Appointments shall be made annually at the first meeting of the council in January. Vacancies in the local planning agency shall, within thirty days, be filled by the council for the remainder of the term created by such vacancy.

Sec. 34-115. Forfeiture of office.

A local planning agency member shall forfeit office if the member:

- (1) Lacks at any time during the term of office any qualification for the office prescribed by town ordinance or state law; or
- (2) Violates any standard of conduct or code of ethics established by law for public officials; or
- (3) Is absent from three consecutive regular local planning agency meetings without being excused by the local planning agency.

Sec. 34-116. Election and duties of officers.

(a) The local planning agency shall elect a chairperson and a vice-chairperson each year at the first meeting of the newly appointed members.

(b) It shall be the duty of the chairperson to preside over all meetings of the local planning agency. In the absence of the chairperson, the vice-chairperson may preside.

Sec. 34-117. Clerk.

The town manager or designee shall be the clerk of the local planning agency. It shall be the duty of the clerk to keep a record of all proceedings of the local planning agency, transmit its recommendations when directed by the chairperson, maintain an updated complete file of all its proceedings at town hall, and perform such other duties as are usually performed by the clerk of a deliberative body.

Sec. 34-118. Rules and procedures.

The local planning agency shall meet at least eight times per year and shall meet no less often than bimonthly or more frequently at regular intervals to be determined by it, and at such other times as the chairperson or as it may determine. It may adopt rules for the transaction of its business. The rules may be amended from time to time, but only upon notice to all members that said proposed amendments shall be acted upon at a specified

meeting. A majority vote of the local planning agency shall be required for the approval of the proposed amendment. It shall keep a properly indexed record of its resolutions, transactions, findings, and determinations, which record shall be a public record. All meetings of the local planning agency shall be public meetings.

Sec. 34-119. Employment of staff and experts.

The local planning agency may, subject to the approval of the town council and within the financial limitations set by appropriations made or other funds available, recommend the town manager employ such experts, consultants, technicians and staff as may be deemed necessary to carry out the functions of the local planning agency. Such technical assistance to the local planning agency shall be under the day-to-day supervision of the town manager.

Sec. 34-120. Specific functions, powers, and duties as to comprehensive planning and land development regulations.

The functions, powers, and duties of the local planning agency as to comprehensive planning and adoption of land development regulations shall be to:

- (1) Acquire and maintain such information and materials as are necessary to an understanding of past trends, present conditions, and forces at work to cause changes in these conditions, and provide data for estimates of future conditions. Such information and material may include maps and photographs of man-made and natural physical features, statistics on trends and present and future estimated conditions with respect to population, property values, economic base, land uses, municipal services, various parameters of environmental quality, and such other information as is important or likely to be important in determining the amount, direction and kind of development to be expected in the town and its various parts and the necessary regulation thereof to insure that the unique and natural characteristics of the island be preserved.
- (2) Prepare principles and policies for guiding land uses and development in the town in order to preserve the unique and natural characteristics of the island, to overcome the

- island's present handicaps, and to prevent or minimize future problems.
- (3) Make or cause to be made any necessary special studies on the location, condition, and adequacy of specific facilities in the town or portion thereof. These may include, but are not limited to, studies on housing, commercial facilities, utilities, traffic, transportation, parking, and emergency evacuation.
 - (4) Review proposed land development codes and amendments thereto, and make recommendations to the town council as to their consistency with the comprehensive plan.
 - (5) Recommend to the town council annually whether the proposed capital improvements program is consistent with the comprehensive plan.
 - (6) Make administrative interpretations of the comprehensive plan when such interpretations are referred to the local planning agency by its legal counsel, in accordance with the ch. 15 of the comprehensive plan and § 34-124(3).
 - (7) Request legislative interpretations of the comprehensive plan in accordance with ch. 15 of that plan, when deemed appropriate by the local planning agency.
 - (8) Make recommendations to the town council on legislative interpretations that have been requested in accordance with ch. 15 of the comprehensive plan.
 - (9) Recommend action to the town council on any amendments that are proposed to the comprehensive plan.
 - (10) Monitor and oversee the effectiveness and status of the comprehensive plan and recommend to the town council such changes in the comprehensive plan as may from time to time be required, including preparation of the periodic evaluation and appraisal reports required by F.S. § 163.3191.
 - (11) Conduct such public hearings as may be needed for updating the comprehensive plan and such additional public hearings as are specified by law.
 - (12) Aid town officials charged with the direction of projects or improvements embraced within the comprehensive plan and generally promote the realization of the comprehensive plan.

- (13) Cooperate with municipal, county and regional planning commissions and other agencies or groups to further the local planning program and to assure harmonious and integrated planning for the area.
- (14) Perform any other duties which lawfully may be assigned to it by the town council.

Sec. 34-121. Functions, powers, and duties as to zoning matters.

The functions, powers, and duties of the local planning agency as to zoning matters shall be to:
[following material moved from 34-145(d)]

(d) Zoning matters:

- ~~(1) Functions:~~ Regarding zoning matters, the hearing examiner has the following prescribed duties and responsibilities:
 - (1) a: Prepare recommendations for changes or amendments relating to the boundaries of the various zoning districts, or to the regulations applicable thereto, to the town council Board of County Commissioners.
 - (2) b: Make recommendations on the following to the town council Board of County Commissioners:
 - a. 1: Applications for rezonings; including developments of county impact; planned unit developments and planned developments.
 - b. 2: Applications for developments of regional impact and Florida Quality Developments approval, which may or may not include a request for rezoning.
 - c. 3: Special exceptions that meet the criteria for a development of county impact, as set forth in § 34-203(b).
 - d. 4: Other special exceptions and variances which are submitted simultaneously with and are heard in conjunction with a rezoning.
 - e. 5: Variances from this code and any town county ordinance which specifies that variances from such ordinance can only be granted by the town council Board of County Commissioners.
 - f. Any other applications that require action by the local planning agency pursuant to this code.
 - c. Certain amendments to development of regional impact development orders do not require a public hearing. After staff review and recommendation, proposed

amendments of this type will proceed directly to the Board of County Commissioners and will be scheduled on the administrative agenda of a regular weekly meeting. The board will vote on the following types of amendments based upon the recommendation of staff without review by the hearing examiner:

1. Amendments that incorporate the terms of a settlement agreement designed to resolve pending administrative litigation or judicial proceedings; or
2. Any amendment contemplated under F.S. § 380.06(19)(c)2.

(2) *Considerations.* In preparing his recommendation on any matter, the hearing examiner shall consider the criteria set forth in subsection (c)(2) of this section.

(3) *Authority.*

- a. The local planning agency hearing examiner shall serve in an advisory capacity to the town council Board of County Commissioners with respect to zoning matters as set forth in subsections (1) and (2) (d)(1) of this section, and in such capacity may not make final determinations.
- b. The local planning agency hearing examiner shall not recommend the approval of a rezoning, and the town council Board of County Commissioners shall not approve a rezoning, other than the change published in the newspaper pursuant to § 34-236(b), unless such change is more restrictive and permitted within the land use classification as set forth in the Fort Myers Beach Comprehensive Use Plan.
- c. In reaching its his recommendations, the local planning agency hearing examiner shall have the authority to recommend conditions and requirements to be attached to any request for a planned development, special exception, or variance included under subsection (d)(1)b.3, 4 or 5 of this section.

(4) *Decisions.* All decisions of the hearing examiner concerning zoning matters under this subsection (d) will be in the form of a recommendation to the Board of County Commissioners. Only a party of record or his representative will be afforded the right to address the Board of County Commissioners:

Sec. 34-122. Functions, powers, and duties as to historic preservation.

The powers, and duties of the local planning agency regarding historic preservation shall include performing all functions assigned to the historic preservation board as set forth in ch. 22, article II, division 2.

Sec. 34-123. Cooperation with the local planning agency.

Each officer and employee of the town is hereby directed to give all reasonable aid, cooperation, and information to the local planning agency or to the authorized assistants of such agency when so requested.

Sec. 34-124. Legal counsel to the local planning agency.

The local planning agency have its own legal counsel, whose duties shall include:

- (1) Advising the local planning agency as to its legal responsibilities and options during the conduct of its business.
- (2) Preparing resolutions reflecting actions of the local planning agency.
- (3) Issuing administrative interpretations of the Fort Myers Beach Comprehensive Plan or referring requests for such interpretations to the local planning agency (see § 34-120(6)) when applications are submitted to the town clerk in accordance with chapter 15 of the comprehensive plan.

Secs. 34-12516--34-200140. Reserved.

DIVISION 4. HEARING EXAMINER

Sec. 34-141. Office established: *[deleted in its entirety]*

Sec. 34-142. Appointment, qualifications: *[deleted in its entirety]*

Sec. 34-143. Funding: *[deleted in its entirety]*

Sec. 34-144. Conduct of meetings, reports and records: *[deleted in its entirety]*

Sec. 34-145. Functions and authority:

(a) *Appeals from administrative action: [moved to § 34-86]*

(b) *Variations: [moved to § 34-87]*

(c) *Special exceptions: [moved to § 34-88]*

~~(d) Zoning matters. [moved to §§ 34-85 and 34-121]~~

~~(e) Special permits. [deleted in its entirety]~~

~~(f) Notice of intent to deny based on insufficient information. [deleted in its entirety]~~

~~Sec. 34-146. Final decision, judicial review. [deleted in its entirety]~~

~~Secs. 34-147--34-170. Reserved.~~

~~DIVISION 5.
DEPARTMENT OF COMMUNITY
DEVELOPMENT~~

~~Sec. 34-171. Appointment of director. [deleted in its entirety]~~

~~Sec. 34-172. Powers and duties. [deleted in its entirety; relevant portions have been moved to §§ 1-6 and 34-6]~~

~~Secs. 34-173--34-200. Reserved.~~

**DIVISION 4 6. APPLICATIONS AND
PROCEDURES FOR CHANGES, PERMITS,
INTERPRETATIONS, AND APPROVALS**

Subdivision I. General Procedures

Sec. 34-201. General procedure for applications requiring public hearing.

(a) **Initiation of application.** An application for a rezoning, development of regional impact, special exception, appeal from administrative action, special permit or variance may be initiated by:

(1) A landowner, or his authorized representative agent, for his own property; provided, however, that:

a. Except as provided in subsections (a)(1)b. and c. of this section, where there is more than one owner, either legal or equitable, then all such owners must jointly initiate the application or petition.

1. This does not mean shall not be construed to require that both a husband and wife must initiate the application on private real property which is owned by them.

2. Where the property is subject to a land trust agreement, the trustee may initiate the application.
 3. Where the fee owner is a corporation, any duly authorized corporate official may initiate the application.
 4. Where the fee owner is a partnership, the general partner may initiate the application.
 5. Where the fee owner is an association, the association or its governing body may appoint an agent to initiate the application on behalf of the association.
- b. Where the property is a condominium or a timeshare condominium, as defined and regulated in F.S. chs. 718 and 721, respectively, an application or petition may be initiated by both the condominium association and no less than 75 percent of the total number of condominium unit owners, or by both the owners' association and no less than 75 percent of timeshare condominium unit owners.
1. For purposes of this subsection, each individually owned condominium unit within the condominium complex and each individually owned timeshare unit as defined by F.S. ch. 721 counts as one unit, regardless of the number of individuals who jointly own the unit.
 2. In order to verify ownership, the applicants shall furnish the town county, as part of their application, a complete list of all unit owners, identified by unit number and timeshare period, as applicable, along with proof that all unit owners who did not join in the application were given actual written notice thereof by the applicants, who shall verify the list and fact of notice by sworn affidavit.
 3. So as to protect the legal rights of nonparticipating unit owners, the application shall be accompanied by a letter of opinion from a licensed Florida attorney, who shall attest that he has examined the declaration of condominium, the bylaws of the condominium association, and all other relevant legal documents or timeshare documents, as applicable, and concluded that the act of applying or petitioning to the town county violates

none of the provisions therein, or any federal or state law regulating condominiums or timeshare plans, or the rights of any of the nonparticipating unit owners, as derived from such documents and laws, and that approval of the requested act by the town county would violate no such rights.

- c. Where the property is a subdivision, an application or petition may be initiated by no less than 75 percent of the total number of lot or parcel owners and the homeowners' association, if applicable.
1. For purposes of this subsection, a subdivision is an area of property defined by a specific boundary in which lot divisions have been established on a plat that has been recorded in either a plat book or official records book whereby legal descriptions are referred to by lot or parcel number. This term may include any unit or phase of the subdivision and not the entire subdivision.
 2. In order to verify ownership, the applicants shall furnish the town county, as part of their application, a complete list of all lot owners, identified by lot number, along with proof that all lot owners who did not join in the application were given actual written notice thereof by the applicants, who shall verify the list and fact of notice by sworn affidavit.

(2) The town county, which for purposes of this section shall mean: the town council or town manager.

- a. ~~The Board of County Commissioners.~~
- b. ~~The hearing examiner, subject to approval by the Board of County Commissioners.~~

(b) Application submittal and official receipt procedure. The application procedure and requirements in this section ~~shall~~ apply to all applications for rezoning, special exceptions, appeals from administrative action, special permits and variances.

- (1) All properties within a single application must be abutting contiguous. The director may, at his discretion, allow a single application to cover non-abutting noncontiguous properties where it is in the public interest due to the size or scope and

nature of the request, and there is a rational continuity to the properties in question.

(2) No application shall be accepted unless it is presented on the official forms provided by the director department, or on computer-generated forms containing the same information, ~~accompanied by a hold harmless agreement for the utilization of computer-generated forms.~~

- a. Forms shall include but not be limited to disclosure forms for corporations, trusts, and partnerships, and disclosure of information regarding contract purchases and their percentages of interest.
- b. Disclosure shall not be required of any entity whose interests are solely equity interests which are regularly traded on an established securities market in the United States or another country.
- c. Disclosure forms shall be provided by the director, ~~established by an administrative code to be approved by the Board of County Commissioners.~~ Such completed disclosure forms shall be included in the materials distributed to the local planning agency zoning hearing examiner and the town council Board of County Commissioners for all zoning cases in which the Board of County Commissioners has the final decision or for which jurisdiction has been taken.
- d. Subsections (b)(2)a. through c. of this section shall not apply to town- county-initiated rezonings.

(3) Before an application may be accepted, it must fully comply with all information requirements enumerated in § 34-202 and 34-203, as applicable, unless specifically stated otherwise in this chapter.

(4) The applicant shall ensure that an application is accurate and complete. Any additional expenses necessitated because of ~~any~~ inaccurate or incomplete information ~~submitted~~ shall be borne by the applicant.

~~(5) The department shall review all applications for completeness. All applications shall be deemed complete unless a letter advising the applicant of any deficiencies has been mailed within ten working days of the date of the original filing. All amended applications shall similarly be deemed complete unless a subsequent letter advising the applicant of~~

any deficiencies has been mailed within ten working days of the date of the resubmittal.

- (5) ~~(6)~~ Upon receipt of the completed application form, all required documents, and the filing fee, the director will begin reviewing the application for completeness, department will place the request on the appropriate agenda and inform the applicant of the hearing dates; or, in the case of planned development applications, begin reviewing the application for sufficiency pursuant to § 34-213 373(a)(3).

Sec. 34-202. General submittal requirements for applications requiring public hearing.

(a) ~~County-initiated~~ **All applications.** Every ~~county-initiated~~ request for actions requiring a public hearing under this chapter shall include the following. However, upon written request using a form prepared by the director, the director may modify the submittal requirements contained in this section where it can be clearly demonstrated that the submission will have no bearing on the review and processing of the application. The request for a waiver or modification must be submitted to the director prior to submitting the application. A copy of the request and the and the director's written response must accompany the application submitted and will become a part of the permanent file. [second and third sentences relocated from § 34-202(c)]

- (1) **Legal description.** The request shall include A legal description of the property upon which the action is to be initiated, sufficiently detailed so as to locate the property on county maps or aerial photographs. The legal description application shall include a copy of the plat or plats, if any, and the county correct STRAP number(s). If the application includes multiple abutting parcels or consists of other than one or more undivided platted lots, the legal description must specifically describe the perimeter boundary of the total property, by metes and bounds with accurate bearings and distances for every line, but need not describe each individual parcel. However, the application must provide the STRAP number for every parcel. The director has the right to reject any legal description which is not sufficiently detailed to locate the property on official maps.

- (2) **Boundary survey or certified sketch of description.** A certified sketch of description, unless the subject property consists of one or more undivided platted lots in a subdivision recorded in the official Lee County Plat Books. The director may require a boundary survey where there is a question regarding the accuracy of the legal description of the property or a question regarding the location of structure(s) or easement(s) that may be relevant to the review of the application. All certified sketches and boundary surveys must meet the minimum technical standards for land surveying in the state, as set out in ch. 61G 17-6, F.A.C. The perimeter boundary must be clearly marked with a heavy line and must include the entire area that is the subject of the application.
- (3) **Confirmation of ownership.** If at any time during the review process the director concludes there is a question regarding ownership of the property, the director may require submittal of a title insurance policy, attorney's opinion of title, or ownership and encumbrance report.
- (4) ~~(2)~~ **Area location map.** The request shall include A map, at a suitable scale, drawn on an 8½-inch by 11-inch sheet of paper, that depicts indicating the property described in the legal description in relation to the surrounding neighborhood. The map shall be sufficiently referenced to known major streets, waterways, and or other physical boundaries so as to be clearly identifiable to the general public.
- (5) ~~(3)~~ **Property owners list.** The request shall include A complete list of all property owners; of the property subject to this request and their mailing addresses; for all property within the area described. If multiple parcels are involved, a map showing the owners' interest must be provided. The applicant is responsible for the accuracy of the list and map. For town-initiated actions only, For the purpose of this subsection; names and addresses shall be deemed to be those appearing on the latest tax rolls of the county.
- (6) **Surrounding property owners list.** The application shall include A complete list, and two sets of mailing labels, of all property owners, and their mailing addresses, for all property within 500 375 feet of the perimeter of the subject parcel or the portion thereof

that is the subject of the request. This list shall also include the owners of all individual condominium units within the 500-foot 375-foot perimeter, plus the managing entity of any timeshare properties. For the purpose of this subsection, names and addresses of property owners, condominium owners, and timeshare managers will be deemed to be those appearing on the latest tax rolls of the county at the time of application. The applicant shall be responsible for the accuracy of such list. In the event that more than six months lapses between the time of application and the date of mailing courtesy notices for the scheduled public hearing, the director may require the applicant to submit a new list and mailing labels. This list is for the purpose of mailing notice to property owners within 375 feet of the property described. The notice is a courtesy only and is not jurisdictional. Accordingly, failure to mail or to timely mail such notice or failure of any affected property owner to receive mailed notice will not constitute a defect in notice or bar the public hearing as scheduled.

[relocated from § 34-202(b)(3)]

- (7) **Surrounding property owners map.** The application shall include a county zoning map or other similar map displaying all of the parcels of property within 500 375 feet of the perimeter of the subject parcel or the portion thereof that is subject of the request, referenced by number or other symbol to the names on the surrounding property owners list. The applicant shall be responsible for the accuracy of the map. *[relocated from § 34-202(b)(4)]*
- (4) **Land use classification.** The request shall include the Lee Plan land use classification for the property in question.
- (8) **Additional material.** Additional material, depending on the specific type of action requested, may be required as set forth in §§ 34-202(b) and 34-203.
- (9) **Filing fee.** All fees, in accordance with the fee schedule (see § 34-53), for county-initiated applications shall be paid at the time the application is submitted to the department in accordance with the duly adopted fee schedule (see section 34-53).

(b) **Additional submittal requirements for owner-initiated applications.** In addition to the submittal requirements set forth in subsection (a), every application initiated by a property owner involving a changes in the zoning district boundaries, or a request for special exception, appeal from administrative action, or variance or special permit, initiated by a landowner, or his authorized agent, for his own property, shall include the following:

(1) **Evidence of authority.**

a. **Ownership interests.** ~~The application shall include~~ The names of all persons or entities parties having an ownership interest in the subject property, ~~to include~~ing the names of all stockholders and ~~trust the names of~~ beneficiaries of trusts (see § 34-201(b)(2)a. through c.).

b. **Agent authorization.** If the owner authorizes an agent to represent the owner in all matters pertaining to the application applicant has an agent, the owner must provide the agent with agent shall provide a notarized statement evidencing the agent's authority to act on the owner's behalf and encumber the property with conditions applicable to the approval requested in the application. An agent may authorize additional agents to assist in the preparation and presentation of the application. However, an agent cannot transfer authority to bind the property with respect to conditions. This later authority will only be recognized by the town when it is provided directly to the agent by the owner. document establishing his authority to represent the applicant as part of the application.

c. **Contract purchaser/vendee authorization.** If a the property is subject to a contract for purchaser or and the vendee is the applicant, a notarized statement from the property owner must be submitted authorizing the contract purchaser/vendee to act as an agent of the property owner for purposes of application submittal and agreement to conditions applicable to approval of the request. authorization form from the landowner to the applicant shall also be required as part of the application.

(2) **Legal description.** *[subject matter relocated to § 34-202(a)(1) and (2) and (b)(4)]*

- (3) ~~Property owners list.~~ [relocated to § 34-202(a)(5)]
- (4) ~~Property owners map.~~ [relocated to § 34-202(a)(6)]
- (2) (5) **Property Deed restrictions.** The application shall include a copy of the deed restrictions or other types of covenants and restrictions on the subject parcel, if any, along with a statement as to how the deed restrictions may affect the requested action. If there are no restrictions on the property, the applicant must indicate so on the application form.
- (6) ~~Land use classification.~~ The application shall include the Lee Plan land use classification for the subject property:
- (7) ~~Affidavit regarding proposed use.~~ [deleted]
- (3) **Boundary sketch.** The boundary sketch shall include the location of existing structures on the property.
- (4) **Confirmation of ownership.** If at any time during the review process the director concludes there is a question regarding ownership of the property, the director may require submittal of a title insurance policy, attorney's opinion of title, or ownership and encumbrance report.
- (5) (8) **Sketch of proposed building.** ~~Additional material.~~ Additional material, depending on the specific type of action requested, shall be required as set forth in § 34-203(a) through (g). In addition, All applications for PD planned development zoning, variances, appeals from administrative action (where relevant), and special exceptions, and special permits must be accompanied by a sketch or sketches that indicate the physical character of the proposed building(s), and in the case of variances, the difference between the proposal and the configuration that would be allowed without the variance.

(c) ~~Modifications to submittal requirements.~~
[moved to § 34-202(a)]

Sec. 34-203. Additional requirements for certain owner-initiated applications requiring public hearing.

(a) **Developments of regional impact.** All Developments of regional impact shall comply with the information submittal and procedural requirements of F.S. ch. 380, as administered

through the Southwest Florida Regional Planning Council. If the development of regional impact requires specific zoning actions (i.e., rezoning), ~~the intent of the procedures and requirements of § 34-202; and this section and article IV of this chapter shall be met.~~ Additionally, even if the development of regional impact does not require any specific zoning action, the applicant must submit a traffic impact statement, as described in § 34-212(6) §§ 34-373(a)(2)c and detailed in § 10-286, shall be submitted. Thresholds for developments of regional impact can be found in F.A.C. ch. ~~28-24~~ 27F-2.

(b) **Planned developments.** Planned development rezonings must comply with the additional submittal requirements in § 34-212. Additional procedural requirements are set forth in §§ 34-211–220.

(b) ~~Determination of development of county impact status.~~ [deleted in its entirety]

(c) **Rezonings other than developments of regional impact or developments of county impact.**

(1) All Requests for rezonings, other than those determined to be a development of regional impact or a development of county impact, shall, in addition to the requirements of § 34-202, include a statement of the basis or reason for the rezoning. Such statement is to be directed, at a minimum, to the guidelines for decision-making embodied in § ~~34-85(2)~~ 34-145(d)(2). This statement may be utilized by the town council Board of County Commissioners, hearing examiner and staff in establishing a factual basis for the granting or denial of the rezoning.

(2) ~~Applications for rezonings are required to comply with § 34-202(b).~~

(d) **Special exceptions.** Except as preempted under subsection (b)(3) of this section, every owner-initiated Applications for a special exception shall, in addition to the requirements of § 34-202(b), include the following:

(1) A statement as to how the property qualifies for the special exception requested, and what impact granting the request would have on surrounding properties. Such statement shall be directed, at a minimum, to the guidelines for decision-making embodied in § ~~34-88~~ 34-145(d)(2). This statement may be utilized by the town council hearing examiner and staff

in establishing a factual basis for granting or denial of the special exception.

- (2) A site development plan detailing the proposed use, including, where applicable, the following:
- a. The location and current use of all existing structures on the site, as well as those on adjacent properties within 100 feet of the perimeter boundaries of the site.
 - b. All proposed structures and uses to be developed on the site.
 - c. ~~Any existing public streets, easements, or land reservations within the site, and the proposed means of vehicular access to and from the site.~~
 - d. ~~A traffic impact analysis of projected trip generation for the development.~~
 - e. Proposed fencing and screening, if any.
 - f. Any other reasonable information which may be required by the director which is commensurate with the intent and purpose of this chapter.

- (3) On-premises consumption of alcoholic beverages. If the request is for a consumption-on-premises permit:
- a. The site plan must include a detailed parking plan.
 - b. A written statement describing the type of state liquor license to be acquired, e.g., 2 COP, SRX, 11C, etc., and the anticipated hours of operation for the business, must be submitted.
[relocated from § 34-203(g)(3)]

(e) **Variances.** Every owner-initiated Applications for a variance from the terms of this chapter shall, in addition to the requirements of § 34-202(b), include the following:

- (1) A document describing:
- a. The section number and the particular regulation of this code chapter from which relief (variance) is requested;
 - b. The reason why the variance is needed;
 - c. What effect, if any, granting of the variance would have on adjacent properties; ~~and~~
 - d. The nature of the hardship which is used to justify the request for relief; ~~and~~
 - e. A statement as to how the property qualifies for the variance, directed, at a minimum, to the guidelines for decision-making embodied in § 34-87.

- (2) A site plan describing:
- a. ~~Existing public streets, easements, or other reservations of land within the site;~~
 - a. b. All existing and proposed structures on the site;
 - b. c. All existing structures within 100 feet of the perimeter boundary of the site; and
 - c. d. The proposed variance deviation from the adopted standards.
- (3) ~~All other information required by the official forms provided by the department, and Any other reasonable information which may be required by the director department which is commensurate with the intent and purpose of this code chapter.~~

(f) **Use or procedural variances.** It is hereby noted that Use and procedural variances are not legally permissible, and no application for a use variance nor a procedural variance will be processed. ~~The director~~ Department staff will notify the applicant when a more appropriate procedure, e.g., rezoning; ~~or special exception or special permit~~, is required.

(g) **Special permits.** *[deleted in its entirety; certain portions have been relocated to § 34-203(d)(4)]*

Secs. 34-204–34-210. Reserved.

Sec. 34-204. Applications for development approval. *[deleted in its entirety]*

Sec. 34-205. Applications for building permits. *[deleted in its entirety]*

Sec. 34-206. Grading permits. *[deleted in its entirety]*

Sec. 34-207. Excavation permit for stormwater retention facilities. *[deleted in its entirety]*

Sec. 34-208. Requests for interpretation of zoning regulations. *[moved to 34-265]*

Sec. 34-209. Building relocation permit. *[moved to 34-1951]*

Sec. 34-210. Temporary use permits. *[moved to 34-3050]*

~~Sec. 34-211. Denials and resubmission of applications. [modified and relocated to § 34-84(4)]~~

**ARTICLE IV:
PLANNED DEVELOPMENTS**
[moved from §§ 34-341-34-410]

DIVISION 1. GENERALLY
[deleted in its entirety]

**DIVISION 2. APPLICATION
AND PROCEDURE FOR APPROVAL**

~~Sec. 34-371. Generally. [deleted in its entirety]~~

**Subdivision II. Additional Procedures for
Planned Development Zoning Districts**

Sec. 34-211. Generally.

(a) Planned development zoning districts are described in §§ 34-612(3) and 34-931-990.

(b) The application and procedure requirements described in this division are a supplement to the general requirements for rezoning applications found in this article.

Sec. 34-372. Preapplication conference:

(c) The applicant may initiate the planned development process by requesting an optional preapplication conference with the department staff. In this request, the applicant shall provide a description of the property in question, the location of the property, the existing use, special features, and the use proposed. Through this meeting, the applicant may avail himself of staff in order to be oriented to the planned development process, to determine what application materials are required (if a minor planned development), and to be advised of the impacts of the Fort Myers Beach Comprehensive Lee Plan, surrounding development and zoning, and other public policy on the development proposal.

Sec. 34-212 373. Application for a planned development.

(a) Required information. Except as specifically provided in subsection (b) of this section, An applicant for a planned development proposal shall

provide the following information, supplemented, where necessary, with written material, maps, plans, or diagrams, and conforming to the best engineering graphic and cartographic standards, in addition to the information regularly required in an application for a rezoning, etc. (see §§ 34-201, 34-202, 34-203, and 34-53): Wherever this section calls for the exact or specific location of anything on a map or plan, its the location of that thing shall be indicated by dimensions from an acceptable reference point, survey marker, or monument.

~~(1) Description of existing conditions. [deleted in its entirety]~~

~~(2) Description of proposed development. The application shall be accompanied by a description of the proposed development, consisting of, as a minimum, the following:~~

(1) **General application.** A general application for public hearing in accordance with the requirements set forth in §§ 34-201, 34-202, and 34-203.

(2) **Filing fee.** The filing fee (see § 34-53).

(3) **Evidence of unified control.** The same documentation evidencing unified control as is required by ch. 10 for development orders. A covenant and documentation of unified controls (see § 34-374).

(4) **Master concept plan.** ~~α~~ A clearly legible master concept plan, to be no less than 24 inches by 36 inches in size and at an appropriate scale to adequately show the proposed development in detail, meeting the standards set forth in either subsection (a)(2)a.1 or subsection (a)(2)a.2 of this section, and including the following information: required in subsections (a)(2)a.3, 4 and 5 of this section.

i. The subject parcel may be divided into development areas. For each development area, the following shall be shown, either within the areas or on schedules keyed to the areas:

a. i. The general size, configuration, and location of each development area; phase, and a description of the phasing of construction, unless the development is to be constructed in a single phase;

b. ii. The maximum height of any proposed buildings or structures, using this code's means of measuring height (see § 34-631);

c. Proposed principal and accessory land uses, identifying such uses by citing the same uses allowed by a specific zoning

- district, or by citing the enumerated uses of one or more use groups or sub-groups as found in Tables 34-1 and 34-2 of this article.
- d. iii. ~~The kinds of uses and the number of units proposed for each use, in terms of dwelling units by type, hotel or motel guest units, gross square feet of types of commercial or industrial uses, and maximum floor area ratios (see § 34-633); or other appropriate measures of intensity;~~
 - e. ~~iv.~~ The minimum width and composition of any ~~all~~ proposed buffers along the perimeter of the subject property, ~~as well as between the individual development areas.~~ References to types of buffers as described in ch. 10 are acceptable;
 - f. ~~v.~~ The location of any environmentally sensitive land and water, based upon standard environmental data and verified by a field inspection by town ~~the county~~ staff. An engineering ~~survey~~ is not required until the plan has been incorporated into an application for a development order;
 - g. ~~vi.~~ The exact location of all points of vehicular ingress and egress from existing easements or rights-of-way into the development, and the general location of all points of vehicular ingress and egress from proposed internal rights-of-way or easements into each development area;
 - h. ~~vii.~~ Access and facilities for public transit, where applicable;
 - ~~viii.~~ The percentage of open space, unless the proposed development is in a development area consisting solely of conventional single-family dwelling units on lots of no less than 6,500 square feet. For commercial and industrial developments, the percentage of open space within each lot or outparcel shall be as set forth in § 34-414(c);
 - i. ~~ix.~~ The general location of stormwater management areas; ~~excavations for on-site fill and wet retention;~~
 - j. ~~x.~~ The specific location of any requested deviations, including sample detail drawings that illustrate the effect of the proposed deviation, keyed to the schedule of deviations; and
 - k. ~~The exact location of existing rights-of-way and easements, whether or not those easements are recorded; and~~
1. Proposed dedications, if any, including public beach access, boat ramps, park or recreation areas, open space, or other easements.
 - ~~xi.~~ Where the subdivision or resubdivision of land is a feature of the proposed development, indication on the plan of the minimum size and dimensions of all of the lots, as well as all of the minimum proposed setbacks for principal structures. ~~If conventional zoning district property development regulations, such as lot coverage regulations, will be used, reference to the specific district shall be sufficient.~~
 - ~~2.~~ ~~If the plan does not divide the subject parcel into development areas, it shall indicate the general location of all proposed land uses, the general location and configuration and approximate dimensions of all proposed lots, parcels or outparcels, and the general location and pattern of vehicular and pedestrian circulation and movement within the site; in addition to the items listed in subsections (a)(2)a.1.ii through x of this section, for the entire site.~~
 - ~~3.~~ ~~The master concept plan shall also include a schedule of uses, containing the following information:~~
 - ~~i.~~ A summary of the kinds of uses proposed for the entire site. For projects containing residential uses, this shall include the types of proposed dwelling units;
 - ~~ii.~~ The units (gross square feet for commercial/industrial uses, number of units for residential or motel/hotel uses, beds for institutional types of uses, etc.) of each kind of use, for the entire site;
 - ~~iii.~~ For developments containing uses for which the parking requirements are to be determined by the director, the number of parking spaces proposed for those uses;
 - ~~iv.~~ The proposed percentage of open space for the entire site.
 - ~~4.~~ ~~The master concept plan shall also include the exact location of existing easements and rights-of-way.~~
 - ~~5.~~ ~~The master concept plan shall also include a schedule of deviations, including sample detail drawings, unless such drawings would merely duplicate the information~~

~~shown pursuant to subsection (a)(2)a.1.x of this section:~~

~~b. A completed questionnaire, on a form furnished by the department, detailing the conceptual surface water management program and the public infrastructure and service and facility demands anticipated from the proposed development, including impacts expected to fall on private for-profit utilities and special use districts.~~

~~(5) **Architectural elevations.** The master concept plan shall be accompanied by architectural elevations or a three-dimensional rendering that show, at a minimum, all building facades adjoining public streets. These drawings may substitute for the sketches required by § 34-202(b)(5) If any aspects of a proposed commercial or mixed-use building do not comply with the commercial design standards in §§ 34-991–34-1010, the applicant may request one or more deviations from those standards in accordance with § 34-932(b).~~

~~(6) **Traffic impact statement.** c. A traffic impact statement in the same a format and to the same degree of detail required for development orders (see § 10-286), unless waived by the director in accordance with § 34-202(a), by a form furnished by the county and in conformance with the adopted county administrative code:~~

~~d. A management plan as required by ch. 10, article III, division 8, pertaining to protected species requirements.~~

~~e. The text of the private covenants or restrictions, if any, proposed to ensure the enforcement of the limitations on permitted uses, the enforcement of the limitations on building, the integrity of open space and common facilities and the perpetual maintenance of the open space and common facilities, keeping always aware that the county shall not be party to those covenants except as they are incorporated into the planned development documents as special conditions:~~

~~f. A description of all proposed dedications, if any, including public beach access, boat ramps, park and recreation areas, open space or other types of easements:~~

~~g. A description of the program of phased construction, if the development is to be so constructed:~~

~~h. For developments of regional impact, the following: *[deleted in its entirety]*~~

Sec. 34-213. (3) Sufficiency and completeness.

a. No hearing will be scheduled for any application for a planned development until the application has been found sufficient.

(1) All applications for planned developments will be deemed sufficient unless a letter advising the applicant of insufficiencies has been mailed within 15 working days of the payment of the application fee. All amended applications will be deemed sufficient unless a subsequent letter advising the applicant of any insufficiencies has been mailed within 15 working days of the resubmittal. The contents of insufficiency letters will be limited to brief explanations of the manner in which insufficient applications do not comply with the formal requirements in this section.

(2) Subsequent to notification that the application has been found to be insufficient, the applicant has 60 days to submit supplemental or corrected documents, unless a longer time is agreed to in writing by the director and the applicant prior to the expiration of the 60 days. If the supplement or corrections are not submitted within the 60 days (or other time period agreed to) the application will be deemed withdrawn.

(3) Once an application has been found sufficient, any new information submitted by the applicant, or any changes made to information submitted by the applicant, may, at the discretion of the director, be grounds for a deferral or continuance of the public hearing, depending on the advertised status of the hearing.

(4) b. In those instances where a proposed planned development is identified by the director local staff as a possible development of regional impact, the applicant shall be notified that the application will be deemed sufficient only when accompanied by either a binding letter of interpretation from the state department of community affairs or a complete and sufficient ADA. Failure by the county to notify the applicant in a timely manner (within 30 days of the application) shall nullify any finding of insufficiency based on this requirement.

Sec. 34-214. Application for an amendment.

~~(b) *Exceptions.* (1) Amendments to application: Applications for amendments to an approved master concept plan or its attendant documentation, or for the reaffirmation of a previously vacated master concept plan (for plans approved prior to December 2, 1991), shall be treated procedurally as minor planned developments, but will require only as much information as is needed to describe the changes requested, to specify the incremental change in impacts expected from the amendment, and to detail the changes in development, environment, and background (surrounding land uses, traffic volumes, water, wastewater, and other service availability, etc.); if any, that have occurred since the original application was made. Some amendments can be approved administratively as provided in § 34-219; the remainder shall proceed through the public hearing process described in § 34-216.~~

~~(2) *Minor planned developments.* [deleted in its entirety]~~

~~(3) *Existing developments seeking planned development classification.* [deleted in its entirety]~~

~~(4) *Amendments to built planned developments (PD).* [deleted in its entirety]~~

Sec. 34-215. 374. Covenant Documentation of unified control.

(a) Any applicant for a rezoning or master concept plan confirmation under the planned development regulations as provided in this article shall submit documentation demonstrating corroborating unified control over the subject property. In addition, the applicant shall submit, on a standard form, a covenant with the county setting forth and agreeing to the obligation to control the development and subsequent use of the property in accordance with this article and any special condition attached to the master concept plan in accordance with this article. This shall include the obligation to impose these restrictions and limitations on any subsequent owner of all or any part of the subject property, including lots, development parcels and outparcels:

~~(b) [subject matter moved to § 34-217(c)]~~

~~(b) (c) In such instance as If the initial applicant conveys all or part of the subject property to a~~

subsequent purchaser, the conveyance shall be is subject to the original documentation demonstrating covenant of unified control and the subsequent owner shall file a document unless amended documentation is filed with the department director, accepting the obligation to enforce all conditions and restrictions attached to the master concept plan as if the original applicant. This amended documentation must shall be filed within 60 days of closing in a form acceptable to the town attorney. ; and shall be recorded with other notices related to the subject planned development. This requirement shall not apply to individual homesites or units (apartments) of a residential development or to any development wherein the obligation to enforce the regulations and conditions or covenants and restrictions is delegated to property owners or a condominium association or cooperative

~~(d) [subject matter moved to § 34-217(d)]~~

~~Sec. 34-375. Prehearing conference. [deleted in its entirety]~~

~~Sec. 34-376. Prehearing stipulation. [deleted in its entirety]~~

Sec. 34-216 377. Public hearings.

(a) Hearing before the local planning agency hearing examiner. After an application is complete, the staff prehearing conference required by this division; the application will be scheduled for a public hearing before the local planning agency hearing examiner.

(1) At the public hearing the local planning agency hearing examiner will consider the application in accordance with article II of this chapter.

(2) The recommendation made to the town council Board of County Commissioners must be supported by formal findings that address the guidelines set forth in § 34-85 145(c)(2) of this chapter. In addition, the findings must address whether the following criteria can be satisfied:

- a. The proposed use or mix of uses is appropriate at the subject location;
- b. Sufficient safeguards to the public interest are provided by the recommended conditions to the concept plan or by other applicable regulations; and

- c. All recommended conditions are reasonably related to the impacts on the public's interest created by or expected from the proposed development.
- d. The proposed use meets all specific requirements of the comprehensive plan that are relevant to the requested planned development, such as the following:
 - 1. Policies 4-B-4 and 4-C-3 on commercial uses in the "Mixed Residential" category.
 - 2. Policies 4-B-5 and 4-C-3 on commercial rezonings in the "Boulevard" category.
 - 3. Policy 4-C-4 on building heights taller than the standard height limit.
 - 4. Policy 4-C-8 on density transfers.
 - 5. Policy 4-E-1 on pre-disaster buildback.
 - 6. Policy 7-J-2 on traffic impact analyses and potential design improvements that could offset traffic impacts.
- (3) If the local planning agency hearing examiner determines that a proposed recommended condition is insufficient, ~~he~~ it may recommend an alternate condition for consideration by the town council Board of County Commissioners.
- (4) If the application includes a schedule of deviations pursuant to §§ 34-212(3) and 34-932(b) § 34-412, the local planning agency's hearing examiner's recommendation must approve, approve with modification, or reject each requested deviation based upon a finding that:
 - a. Each item enhances the achievement of the objectives of the planned development; and
 - b. The general intent of this chapter to protect the public health, safety, and welfare will be preserved and promoted; and
 - c. Each deviation operates to the benefit, or at least not to the detriment, of the public interest; and
 - d. Each deviation is consistent with the Fort Myers Beach Comprehensive Plan.
 If the local planning agency hearing examiner concludes that the application omits necessary deviations, ~~he~~ it may include the necessary deviations in ~~his~~ its recommendation without an additional hearing.
- (5) As a condition of approval of a deviation, the hearing examiner may recommend that the applicant receive administrative approval of a

more detailed development plan for each affected development area. Applications for administrative approval will be processed as administrative amendments in accordance with § 34-380 of this chapter and may be granted by the director upon a finding that public health, safety, and welfare will not be adversely affected thereby.

(b) Hearing before the town council. Board of County Commissioners.

- (1) Subsequent to ~~After~~ the local planning agency's hearing examiner's hearing, an application for a planned development, together with all attendant information, staff reports, and the local planning agency's hearing examiner minutes and resolution of recommendation, shall be forwarded to the town council Board of County Commissioners, which shall consider the application in public hearing per article II of this chapter. After reviewing all information, including staff reports review and local planning agency hearing examiner recommendations, the town council Board of County Commissioners may either:
 - a. Continue further consideration until additional information is provided by applicant or ~~the director~~ staff or until the applicant makes changes in the application, subject to re-review by ~~the director~~ staff and the local planning agency hearing examiner as required; or
 - b. Formally approve, approve with modification, or deny the application. Should the town council Board of County Commissioners deny without prejudice, it may remand the proposal to ~~the director~~ staff with directions to bring the application back to the local planning agency hearing examiner once the application is amended. If new or additional information, not previously provided to either ~~the director~~ staff or the local planning agency hearing examiner, is supplied by the applicant subsequent to after the local planning agency hearing examiner hearing, the town council Board of County Commissioners may remand the application to the local planning agency hearing examiner for rehearing.
- (2) Any decision made by the Board of County Commissioners ~~The decision of the town council~~ shall be supported by a formal

finding, that, in addition to the appropriate guidelines set forth in article II of this chapter, the criteria set forth in subsection (a)(2) of this section have or have not been satisfied, are or are not met.

- (3) In addition to adopting a master concept plan for the planned development, the town council Board of County Commissioners may adopt such special conditions as are necessary to address unique aspects of the subject property in the interest of protecting the public health, safety, and welfare. Should any recommended special condition be found to be insufficient, the town council Board of County Commissioners may substitute its own language for such special condition in the final resolution.
- (4) Should a schedule of deviations from other provisions of this chapter (see §§ 34-212(6) and 34-932(b) § 34-412) be a part of the planned development application, the town council Board of County Commissioners may approve, approve with modification, or reject the entire schedule or specific items based upon their finding that for each item:
- Each item enhances the achievement of the objectives of the planned development; and
 - The general intent of this chapter to protect the public health, safety, and welfare will be preserved and promoted;:
 - Each deviation operates to the benefit, or at least not to the detriment, of the public interest; and
 - Each deviation is consistent with the Fort Myers Beach Comprehensive Plan.
- (5) ~~The Board of County Commissioners may require, as a condition of approval of the deviation, that the applicant receive administrative approval of a more specific development plan for each affected development area or parcel. Applications for administrative approval will be processed as administrative amendments in accordance with § 34-380 of this chapter and may be granted by the director only upon a finding that public health, safety, and welfare will not be adversely affected thereby.~~
- (5) If the town council denies or modifies any requested use(s), deviations(s), or other information shown on the master concept plan, a revised master concept plan must be submitted to the director reflecting the substance of the approved resolution prior to

execution of the resolution. Legible copies of the revised master concept plan must be provided in two sizes, 24 inches by 36 inches and 11 inches by 17 inches in size.

- (6) No development orders may be issued until the approved resolution has been signed by proper town officials.

Sec. 34-~~217~~ 378. Effect of planned development zoning.

(a) *Compliance with applicable regulations.*

~~After~~ Subsequent to the adoption of the master concept plan and the conditions and auxiliary documentation that govern it, any and all development and subsequent use of land, water, and structures within any planned development shall be in compliance with the following, in order of precedence:

- (1) ~~The Fort Myers Beach Comprehensive Fee Plan.~~
- (2) This subdivision of the land development code. Divisions 1, 2, and 3 of this article.
- (3) The master concept plan and attendant conditions and auxiliary documentation.
- (4) Any applicable town county development regulations in force at the time of ~~final plan~~ submission of the application for a development order.
- (5) The general provisions of this chapter, unless otherwise excepted by an approved schedule of deviations.

(b) ***Applicability of development regulations.*** ~~At~~ approvals of general aspects of The master concept plan (see § 34-~~212(4)~~ 373(a)(2)) is ~~are~~ conceptual only, and are development pursuant to the master concept plan is subject to all development regulations established to protect health, safety, and welfare in force at the time of ~~final plan review~~ submission of the application for a development order, except where deviations have been formally granted in accordance with § 34-932(b). Any reliance in detail on the approval of a general aspect of the master concept plan is not justified and is not in good faith.

(c) ***Recording of notice.*** Upon approval of a master concept plan and the conditions and auxiliary documentation that govern it, a notice of such approval and its encumbrance of the real estate involved, all in proper form, shall be recorded by department on the official records of the county.

~~(d) Prohibitions: [deleted in its entirety]~~

(c) The obligation to enforce the conditions attached to the master concept plan remains with the original applicant until all of the subject property is developed and certified for use and occupancy, or until a subsequent owner assumes that obligation for all or part of the subject property. Completion or vacation of a phase of the development, or conveyance of a lot, development parcel, or outparcel, will relieve the original applicant only as to that phase, lot, development parcel, or outparcel, and then only when notice is filed in accordance with § 34-215. The obligation to enforce the conditions attached to a reaffirmed master concept plan will lie with whomever files the unified control documentation for that reaffirmation.

(d) If the town discovers noncompliance with the regulations or the master concept plan and its attachments, the town may withhold any permit, certificate, or license to construct, occupy, or use any part of the planned development. This will not be construed to injure the rights of tenants of previously completed and properly occupied phases.

Sec. 34-218 379. Binding nature of approval of master concept plan.

All terms, conditions, safeguards, and stipulations made at the time of the approval of a master concept plan shall be binding upon the applicant or any successor in title or interest to all or part of the planned development. Departure from the approved plans or failure to comply with any requirement, condition, or safeguard shall constitute a violation of this chapter.

Sec. 34-219 380. Administrative amendments to approved master concept plan.

(a) Amendments to an approved master concept plan or its attendant documentation may be requested at any time during the development or of useful life of a planned development.

(b) Amendments that may be approved by the department director include, in general, any change to the interior of the development which does not increase height, density, or intensity (i.e., number of dwelling units, hotel units, or quantity of commercial floor area), or a decrease in buffers or open space, or add additional land uses. The director

shall not approve any change which results in a substantial underutilization of public resources and public infrastructure committed to the support of the development, nor shall the director approve any change which results in a reduction of total open space, buffering, landscaping, and preservation areas or which adversely impacts on surrounding land uses.

(1) This authority is granted to the director to eliminate unnecessary processing delays for proposed changes that are:
a. substantially similar to the prior approval;
b. likely to be noncontroversial; and
c. in conformance with all town regulations and plans.

(2) Decisions by the director pursuant to this subsection may be appealed only as follows:
a. Appeals will not be considered for any of the following requests:

1. an increase in height, density, or intensity (i.e., number of dwelling units, guest units, or floor area), or
2. an additional land use, or
3. a variance or deviation from this code, or
4. a substantial change from previously approved architectural drawings or master concept plan.

b. The appeal must be filed and processed in accordance with § 34-86. In addition, the appellant must provide a list and map of surrounding property owners and one set of mailing labels in accordance with § 34-202(6) and (7), and shall pay a fee established by the director.

c. The director shall provide notice of the public hearing where this appeal will be considered using the procedures in § 34-236.

d. Upon considering an appeal, the town council may uphold or repeal the director's decision, or may modify that decision by removing, adding, or modifying any conditions of approval.

(c) All other requests for amendments to a master concept plan or its auxiliary documentation shall be treated procedurally as an amendment to the minor planned developments, but with application information and materials specified by § 34-214 373(b)(2); and public hearings in accordance with § 34-216.

(d) Any application for amendment that proposes a development which, taken by itself, would constitute a development of county impact (see §§ 34-203(b) and 34-341(b)) shall not be treated as a minor planned development unless it clearly meets the criteria set forth in § 34-341(c). Otherwise, it shall proceed as a new and separate planned development.

(e) Notice of any plan amendment shall be recorded in the same manner as the approved master concept plan itself.

Sec. 34-220 381. Duration of rights conferred by adopted master concept plan.

~~(a) Master concept plans approved prior to December 2, 1991, are subject to the following:~~

~~(1) through (4) [deleted in their entirety]~~

~~(b) Master concept plans approved after December 2, 1991, are subject to the following:~~

~~(1) An approved master concept plan and its attendant documentation shall be deemed to be vacated unless the property owner obtains applies for a development order for the first phase a substantial portion of the project within three five years of the date of the original approval by the town council, Board of County Commissioners. A substantial portion of the project shall consist of no less than 20 percent of the lots, dwelling units, square footage, or other applicable measurements of intensity for the development in question unless a lesser percentage is approved by the town council Board of County Commissioners.~~

~~(2) Timeframes for approval of subsequent portions of the development may shall be governed by a phasing plan, which shall be included in the resolution rezoning the subject parcel. Phases may be defined by geographical areas, units of intensity, traffic impacts, or any other units of measurement deemed appropriate by the town council, Board of County Commissioners. In the absence of a specific phasing plan in the resolution, subsequent phases must proceed as follows:~~

~~a. Within five years of the date of approval by the town council, the first phase must have been completed and a development order must have been obtained for the~~

second phase, consisting of 50% of the project.

~~b. Within eight years of the date of approval by the town council, the second phase must have been completed and a development order must have been obtained for the entire project.~~

~~(3) Any phase for which a development order has not been obtained or for which development has not been completed requested by the time specified in the resolution and all subsequent phases shall be deemed vacated, along with all subsequent phases.~~

~~(4) Any failure to complete development within a phase or the entire project, whichever is applicable, prior to the expiration of rights established by the development order for the phase or project shall result in the vacation of the applicable phase (and all subsequent phases) of the project.~~

~~(5) If all or part of a master concept plan is vacated, a notice of vacation shall be sent to the owner of record of the affected property via certified mail, and the notice, accompanied by all necessary maps and documents, shall be recorded by the department on the official records of the county in order to provide notice to subsequent purchasers and others having or seeking an interest in the property. Failure to provide direct notice of a vacation or to record the notice shall not vest or extend the validity of the vacated concept plan.~~

~~(4) Extensions of master concept plans may be granted as follows: by the Board of County Commissioners in accordance with subsection (a)(4)a. of this section. [relocated from § 34-381(a)(4)]~~

~~(4) An approved master concept plan may be extended as follows:~~

~~a. An approved master concept plan for a phase of or an entire planned development which has been vacated due to a failure to proceed on the applicant's part may be extended by the town council Board of County Commissioners for a period of no more than two years from the date of the extension based on the following findings of fact:~~

~~1. The master concept plan is consistent with this code and the current Fort Myers Beach Comprehensive Use Plan,~~

- including, but not limited to, density, intensity, and concurrency requirements;
2. The development shown by the master concept plan has not become incompatible with existing and proposed uses in the surrounding area as the result of development approvals issued subsequent to after the original approval of the master concept plan; and
 3. The development shown by the master concept plan will not, by itself or in conjunction with other development, place an unreasonable burden on essential public facilities.
- b. An application for an extension may be filed at any time after the vacation of the master concept plan and must consist of the following:
1. A completed application form provided by the ~~director department of community development~~;
 2. The approved master concept plan;
 3. The applicable zoning resolution;
 4. A written statement describing how the criteria listed in subsection ~~(4)a. (a)(4)a.~~ above have been met; and
 5. A fee, in accordance with an adopted administrative code.
- c. No more than two extensions may be granted for any development or phase thereof.
- ~~(6) Master concept plans for planned developments which do not require development orders are not subject to the timeframes for vacation in this section.~~
- (7) Phasing plans may be amended in accordance with § 34-214, 373(b)(1):

~~Sec. 34-382. Development permit. [deleted in its entirety]~~

~~Secs. 34-221383--34-230410. Reserved.~~

DIVISION 5 7. PUBLIC HEARINGS AND REVIEW

Sec. 34-231. Definitions.

For purposes of this division only, certain terms are defined as follows:

Continuance means an action initiated by the applicant, staff, local planning agency, or the town council ~~or a hearing examiner or the Board of County Commissioners~~ to postpone, to a later time or date, a public hearing after the notice of the public hearing has been submitted to the newspaper for publication as required in § 34-236.

Deferral means an action initiated by the applicant or staff to postpone, to a later time or date, a public hearing prior to the notice of the public hearing being submitted to the newspaper for publication.

Sec. 34-232. Required hearings.

(a) *Amendment or adoption of land use ordinances.*

- (1) Any proposed amendment to this chapter or to any land use ordinance, or adoption of any new land use ordinance, shall be enacted pursuant to the requirements set forth in F.S. § ~~166.041~~ ~~125-66(5)~~.
- (2) Prior to a final required hearing by the town council ~~Board of County Commissioners~~, the local planning agency shall review the amendment at a public hearing.

(b) *Owner-initiated requests.* Owner-initiated requests for rezonings, variances, special exceptions, and developments of regional impact require one public hearing before the local planning agency and one public hearing before the town council.

(c) *Town-initiated requests.* Town-initiated requests for rezonings, variances, special exceptions, and developments of regional impact require one public hearing before the local planning agency and:

- (1) Applications covering less than 10 abutting acres of land will require a single public hearing before the town council.
- (2) Applications covering more than 10 abutting acres of land will require two public hearings before the town council in accordance with F.S. § 166.041.

~~(b) *Rezoning, developments of regional impact, and special exceptions, special permits and variances submitted for simultaneous review.*~~
~~[deleted in its entirety]~~

~~(c) Other special exceptions, special permits and variances, administrative appeals. [deleted in its entirety]~~

Sec. 34-233. Preliminary review and notice certification.

(a) Staff review. The director will produce a written (staff) report summarizing each application and making a formal recommendation to the local planning agency and town council to be available about 7 days before the public hearing.

- (1) ~~No application for a land use ordinance amendment, rezoning, special exception, development of regional impact, special permit or variance, appeal or any other action required by this chapter to proceed through the public hearing process shall be heard by the hearing examiner or Board of County Commissioners, as applicable, until after the department staff has reviewed and prepared written comments on the requested action.~~
- (2) ~~All staff comments shall be forwarded to the hearing examiner or Board of County Commissioners, as applicable, prior to the scheduled public hearing.~~

(b) Other LPA reviews. No application or proposed land use ordinance amendment required under the provisions of this chapter to be reviewed by the local planning agency prior to review by the town council Board of County Commissioners shall be heard for final consideration by the town council Board of County Commissioners prior to receiving a substantive recommendation of the local planning agency. As used in this subsection, a motion to continue a matter by the local planning agency shall not be considered a substantive recommendation.

~~(c) Notice certification and affidavits.~~ No public hearing shall be commenced by the hearing examiner, local planning agency or Board of County Commissioners unless affidavit proof of required notice publication, posting and mailing, if applicable, is presented to the hearing examiner, local planning agency or Board of County Commissioners for review and submitted to the records keeper for filing with the minutes of the meeting.

Sec. 34-234. Public participation.

(a) Participation at public hearings. ~~before hearing examiner or local planning agency.~~ At a public hearing before the ~~hearing examiner or local planning commission~~ agency or town council, all persons shall be heard. However, the ~~hearing examiner or local planning agency~~ and town council shall have the right to refuse to hear testimony which is irrelevant, repetitive, defamatory, or spurious, and may establish reasonable time limits on testimony.

~~(b) Participation before Board of County Commissioners. [deleted in its entirety]~~

(b) Participation prior to public hearings. When any person discusses a matter that is the subject of a pending quasi-judicial hearing with a member of the local planning agency or the town council, such member shall disclose the discussion at the public hearing in accordance with § 34-52(b)(2).

Sec. 34-235. Deferral or continuance of public hearing.

The following procedures and regulations for deferring or continuing a public hearing shall apply for the ~~hearing examiner, local planning agency and town council~~ Board of County Commissioners:

- (1) Deferral. A scheduled but not yet advertised public hearing may be deferred by the ~~director~~ department staff or by the applicant as follows:
 - a. Town-County-initiated deferral. ~~The director may defer~~ Department staff or the hearing examiner may initiate a deferral of a scheduled public hearing prior to advertising, if additional or corrected information is required to permit staff to properly or adequately review a requested application, provided that notice is mailed to the applicant, or his authorized representative agent, stating the reason for the deferral and what additional information is required to complete staff review.
 - b. Applicant-initiated deferral. An applicant, or his duly authorized agent, may request a deferral of the public hearing if provided that:
 - † the request is in writing and received by the director ~~appropriate department~~ prior to ~~that department's~~ submitting

- notice of the hearing to the newspaper for publication; and
2. ~~The applicant agrees to have his application rescheduled in accordance with the scheduling procedures in effect at that time.~~
 - c. *Fee.* There shall be no additional fee for either a town- staff-initiated or applicant-initiated deferral. However, the applicant must obtain corrected zoning notice posters and post the signs on-site.
 - d. *Staff authority.* ~~Applicant-initiated deferral requests which meet the requirements of subsection (1)b of this section may be deferred by the director without any further action by the Board of County Commissioners.~~
- (2) *Continuance.* A scheduled, advertised public hearing may be continued by the town county or by the applicant as follows:
- a. *Town- County-initiated continuance.*
 1. The ~~hearing examiner, local planning agency or town council Board of County Commissioners,~~ upon staff request or upon its own initiative, may continue a public hearing when it is ~~deemed~~ necessary to require additional information, public testimony, or time ~~in order~~ to render an appropriate recommendation.
 2. The ~~county-initiated~~ hearing shall be continued to a date certain, and the ~~hearing examiner, local planning agency or town council Board of County Commissioners~~ shall continue its consideration on the hearing matter on that date certain. Any hearing not continued to a date certain is deemed to be denied without prejudice.
 3. There shall be no limitations on the number of ~~town- county-~~initiated continuances.
 4. The town county shall bear all renotification costs of any ~~town- county-~~initiated continuance.
 - b. *Applicant-initiated continuance.*
 1. The applicant, or his duly authorized agent, shall submit the request in writing to, and the request shall be received by, the appropriate department town manager at least one day prior to the advertised hearing date, or the applicant or his duly authorized agent

- shall appear before the ~~hearing examiner, local planning agency or town council Board of County Commissioners~~ at the beginning of its scheduled agenda and orally request the continuance.
2. The ~~hearing examiner, local planning agency or town council Board of County Commissioners~~ may either deny or grant the request for continuance.
 - i. If the request for continuance is denied, the hearing shall proceed in accordance with the published agenda.
 - ii. If the request for continuance is approved, the ~~hearing examiner, local planning agency or town council Board of County Commissioners~~ may set a date certain for hearing the application. Any hearing not continued to a date certain is deemed to be denied without prejudice.
 3. The applicant shall be entitled to one continuance before the local planning agency and one continuance before the town council each decision-making body as a matter of right. Each decision-making body shall have the authority to grant additional continuances upon a showing of good cause.
 4. A fee, in accordance with a ~~duly adopted~~ fee schedule, shall be charged for any applicant-initiated continuance to cover the costs of renotification. The applicant must bear all renotification costs of an applicant-initiated continuance.
- c. *Unknown hearing dates.* Continuances may also be granted to unknown dates at the discretion of the local planning agency or town council. Such continuances shall be rescheduled by the director and shall be readvertised in the same manner as the originally scheduled hearing. If such a continuance was requested by an applicant, the director may charge the applicant for additional costs of renotification.

Sec. 34-236. Notices.

(a) **Minimum required information.** A notice of public hearing under this chapter shall contain the following minimum required information:

(1) *Action proposed.*

a. ~~Land use ordinance amendments or adoption.~~ The notice shall describe the chapter or section of the land use ordinance to be amended, or the subject of a new ordinance, with sufficient clarity so as to advise the public of the subject to be amended or adopted, but need not describe the exact wording or change.

a. b. *Rezoning and developments of regional impact.* All required notices shall indicate the existing zoning of the property, the proposed zoning, and the general location of the property; by reference to common street names and addresses, ~~covered by the application;~~ with sufficient clarity certainty so as to advise the public, but need not describe the proposed plans or details thereof, or the specific legal description of the property.

b. c. ~~Special exceptions, special permits and variances.~~ All required notices shall indicate the existing zoning of the property; the proposed use by special exception ~~or special permit,~~ or the requirement from which the variance is being requested and the actual degree of variance being requested; and the location of the property; by reference to common street names and addresses, with sufficient clarity certainty so as to advise the public, but need not describe the proposed plans or details thereof or the specific legal description of the property.

c. d. *Appeals.* The notice shall summarize the decision or action upon which the appeal is based with sufficient clarity so as to advise the public of the subject matter.

(2) *Time and place of hearing.* The notice shall specify the date, time and place that the public hearing will be held by ~~the hearing examiner;~~ the local planning agency or the town council. ~~Board of County Commissioners,~~ as applicable.

(3) *Public availability of information.* The notice shall indicate where copies of the proposed amendment may be obtained or reviewed, or where the application for public hearing may be reviewed.

(4) *Location of record of notice.* A copy of such notice shall be kept available for public inspection during the regular business hours at town hall and at the director's office, ~~the office of the department of community development or hearing examiner,~~ as appropriate, and indicated in the notice.

(b) *Method of providing notice.* Notices of hearings before the ~~Board of County Commissioners,~~ the hearing examiner and the local planning agency and the town council shall be provided in accordance with applicable statutes and ~~as may be set forth in the county's administrative code,~~ subject to the requirements of subsection (a) of this section.

(c) *Mailed notices.* The list and map of surrounding property owners required by § 34-202(a)(6) is for the purpose of mailing notice to property owners within 500 feet of the property described. The notice is a courtesy only and is not jurisdictional. Accordingly, the failure to mail or to timely mail such notice, or failure of any affected property owners to receive mailed notice, will not constitute a defect in notice or bar the public hearing as scheduled.

Secs. 34-237--34-2640: Reserved.

DIVISION 6 8. INTERPRETATIONS, ENFORCEMENT, AND SPECIAL ADMINISTRATIVE ACTIONS

Sec. 34-261. Generally: *[deleted in its entirety]*

Sec. 34-262. Complaints: *[deleted in its entirety]*

Sec. 34-263. Penalties: *[subject moved to § 1-5]*

Sec. 34-264. Persons who may be charged with violations: *[moved to § 1-5(f)]*

Sec. 34-265. Additional remedies: *[moved to § 1-5(d)]*

Sec. 34-266. Cease and desist orders: *[subject moved to § 1-5]*

Sec. 34-265 208. Requests for interpretation of this code zoning regulations. *[moved from § 34-208]*

Where a question arises as to the meaning or intent of a section or subsection of this code chapter, a written request stating the area of concern and the explicit interpretation requested shall be submitted ~~to the director~~; on forms provided by the director department.

- (1) The director may render decisions of an administrative nature, such as but not limited to:
 - a. Proper zoning classification for a use not specifically addressed; and
 - b. Procedures to follow in unusual circumstances.
- (2) Interpretations which, in the opinion of the director, involve policy or legislative intent issues shall be placed on the agenda of the town council ~~a regularly scheduled meeting of the Board of County Commissioners for its consideration.~~
 - a. ~~If the question involves clarification of the legislative intent of this chapter, the Board of County Commissioners may render a decision as an administrative action item.~~
 - b. ~~Decisions involving policy issues or potential conflicts with the Lee Plan shall be scheduled for a public hearing in accordance with division 7 of this article.~~
- (3) ~~Annotations of all decisions of the director or Board of County Commissioners which may have an impact on future decisions shall be periodically printed and made available to the general public.~~

Sec. 34-266. Enforcement.

The director is authorized to pursue any one or combination of the enforcement mechanisms provided in this code (for example, § 1-5, or article V of ch. 2) for any violation of this article.

Sec. 34-267. Forced relocation of businesses. Authority to permit uses pending a zoning action:

(a) The director is authorized to permit proposed uses that are not permitted on a subject parcel for a period of not more than 180 days under the following circumstances:

- (1) The property owner, contract purchaser, or other authorized person has filed an application for a rezoning or a special exception for the subject parcel that would, if approved, make the requested use a permitted use;
- (2) The requested rezoning or special exception, in the opinion of the director, is clearly compatible with the neighboring uses and zoning and is consistent with the Fort Myers Beach Comprehensive Lee Plan;
- (3) The proposed use of the property is a business that is being relocated due to the town's county's economic development or redevelopment efforts or as the result of threatened or ongoing condemnation proceedings;
- (4) No new principal structures are to be constructed on the subject property; and
- (5) The applicant agrees in writing that the proposed use will cease within 180 days of the date of the administrative approval unless the town council Board of County Commissioners or hearing examiner, whichever is applicable, has rendered a final decision approving the requested rezoning or special exception. Upon execution, the agreement shall be recorded in the public records of the county.

(b) Decisions by the director pursuant to this section are discretionary and may not be appealed pursuant to § 34-86, subsection 34-145(a).

(c) The director may extend the effective date of the approval up to an additional 90 days upon good cause shown.

(d) No approval issued pursuant to this section shall excuse any property owner from compliance with any town county regulation except the list of permitted uses in the zoning district in question.

Sec. 34-268. Administrative setback variances.

(a) Upon written request using a form prepared by the director, the director is authorized to modify the setbacks in §§ 34-638, 34-1174-34-1176, and 34-1744 34-651 through 34-1041 and 34-1744 (residential fences only) of this chapter under the following circumstances:

- (1) Street, rear, side, or waterbody setbacks may be modified to permit the remodeling of or

additions to existing structures that are nonconforming with regard to a specific setback so long as the remodeling or addition will not result in:

- a. ~~The remodeling or addition will not result in~~ An increase in the height of the structure; ~~and or~~
 - b. ~~The remodeling or addition will not result in~~ A further diminution of the setback. The director may approve bay windows, chimneys, and similar architectural features that may encroach further into the setback provided the encroachment does not protrude beyond the existing overhang of the building.
- (2) Street, rear, side, or waterbody setbacks may be modified to permit the construction of a handicapped access appurtenant to any existing structure.
 - (3) Street, rear, side, or waterbody setbacks may be modified to allow the replacement of stairs or decking that provides access into an existing dwelling unit.
 - (4) Street, rear, side, or waterbody setbacks may be modified to legitimize minor errors in setbacks at the time of construction.
 - (5) Street, rear, or side setbacks may be modified for a residential lot with an unusual shape or orientation where, for instance, side and rear setbacks should be reversed. ~~Rear or side setbacks for lots that qualify for a single family determination, pursuant to the Lee Plan, may be modified to permit the construction of a single-family dwelling unit so long as the proposed lot coverage does not exceed 45 percent.~~
 - (6) Buildings or structures that are not in compliance with current setback regulations and which can be proven to have been permitted may also be reviewed by the director for consideration under this section.
- (b) The director, prior to approving the modifications, must make the following findings of fact:
- (1) There are no apparent deleterious effects upon the adjoining property owners;
 - (2) The modifications will not have an adverse impact on the public health, safety, and welfare; and
 - (3) The modifications will be the minimum required.

(c) Decisions by the director pursuant to this section are discretionary and may not be appealed in accordance with § 34-86. ~~145(a) of this chapter.~~

~~Sec. 34-269. Compliance agreements. [deleted in its entirety]~~

~~Secs. 34-26970--34-610 300. Reserved.~~

~~ARTICLE III. RESERVED~~

~~Secs. 34-301--34-340. Reserved.~~

~~ARTICLE IV. PLANNED DEVELOPMENTS [divisions 1 & 2 moved to §§ 34-211--34-220]~~

~~DIVISION 3. DESIGN STANDARDS~~

~~Sec. 34-411. General standards. [deleted in its entirety]~~

~~Sec. 34-412. Deviations from general zoning regulations. [moved to § 34-932(b)]~~

~~Sec. 34-413. Density or intensity of use. [moved to § 34-932(c)]~~

~~Sec. 34-414. Open space. [deleted in its entirety]~~

~~Sec. 34-415. Provision of public facilities and services. [deleted in its entirety]~~

~~Secs. 34-416--34-440. Reserved.~~

~~DIVISION 4. RESIDENTIAL PLANNED DEVELOPMENTS IN RURAL OR OUTER ISLANDS [deleted in its entirety]~~

~~ARTICLE V. COMPREHENSIVE PLANNING; THE LEE PLAN*~~

~~Sec. 34-491. The Lee Plan. [moved to § 34-619]~~

~~Secs. 34-492--34-610. Reserved.~~

Mapping of Zoning Districts

ARTICLE III. VI. ZONING DISTRICT REGULATIONS

DIVISION 1. MAPPING OF ZONING DISTRICTS GENERALLY

Sec. 34-611. Zoning districts established.

Land and water within Town of Fort Myers Beach is divided into zoning districts as set forth in this article in order to classify, regulate, and restrict the location of buildings erected or structurally altered for specific uses, to regulate the use of land, to regulate and limit the height and bulk of buildings hereafter erected or structurally altered, to regulate and determine the area of yards and other open space about buildings, to regulate the intensity of land use, and to promote the orderly growth of the town county, in compliance with the goals, objectives and policies set forth in the Fort Myers Beach Comprehensive Lee Plan, the unincorporated area is divided into zoning districts as set forth in this article.

Sec. 34-612. Types and general purpose of districts.

There are ~~three~~ two basic types of zoning districts provided for in this article: conventional zoning districts, ~~redevelopment districts~~, and planned development (PD) districts. The general purpose of each ~~both~~ types of zoning districts is to implement the goals, objectives, and policies of the Fort Myers Beach Comprehensive Lee Plan, as well as to provide protection to the public health, safety, and welfare through the regulation of land use.

- (1) *Conventional districts.* Conventional zoning districts are districts ~~within the unincorporated areas of the county within which land use is controlled primarily~~ through the regulation of the height and bulk of buildings and structures, the minimum area and dimensions of lots, ~~the percentage of lot coverage, minimum open space and yard areas, through the use of and setback requirements, the density of population, and the type and intensity of use of the land and buildings.~~ Use and development regulations for the conventional districts are provided in

~~divisions 2 through 8 Table 34-2 and other regulations are provided in Table 34-3 and division 4 of this article.~~

- (2) *Redevelopment districts.* Redevelopment districts differ from conventional zoning districts in that they implement specific redevelopment concepts established in the Fort Myers Beach Comprehensive Plan. For each of the five redevelopment districts, use regulations are provided in Table 34-2 and the more specific property development regulations are provided in division 5 of this article.

- (3) *PD, planned development districts.* In certain circumstances, landowners may choose or be required to rezone their land to a planned development (PD) district. The purpose and intent of the two various planned development districts is to further implement the goals, objectives and policies of the Lee Plan while providing provide a some degree of flexibility for a landowner to propose the development of land in a manner that differs from the specific provisions of this code. A planned development, once approved through the rezoning process, can only be developed in accordance with the master concept plan and special conditions that are contained in the resolution approving the planned development, in planning and designing developments by: [remainder of existing subsection (2) deleted in its entirety] Use and property development regulations for planned development districts are provided in division ~~6~~ 9 of this article.

Sec. 34-613. Designation of district boundaries.

(a) Major revisions to this chapter were approved by the Town of Fort Myers Beach in 2003, including the establishment of new zoning districts and the assignment of all land in the town to one of these zoning districts.

- (1) The new zoning district assignments are shown on the interim zoning map contained in Exhibit A of the amending ordinance. The new zoning district assignments took effect on March 3, 2003, the date that ordinance was adopted. Previous approvals of variances, special exceptions, special permits,

Mapping of Zoning Districts

and other zoning actions that did not change zoning district boundaries were not shown on the interim zoning map due to its scale but were not affected by the adoption of the interim zoning map. These approvals are indicated on the current zoning maps maintained for the town by Lee County.

- (2) Within one year after approval of the amending ordinance, the town shall approve by resolution a new official zoning map of the town as described in § 34-614 that reflects these new zoning districts and other zoning approvals that remain in effect, such as variances, special exceptions, and special permits.

(b) The boundaries of each zoning district are designated and established as shown on the interim zoning map, the official zoning map of the county. The official zoning map as described in § 34-614, and the current zoning map as described in § 34-615 shall be as much a part of this chapter as if fully described in this chapter.

(c) There is no right to rely solely on the interim, official, or current zoning maps to vest development or private rights. In addition to the zoning districts shown on these maps, development rights may be limited by other factors such as the Fort Myers Beach Comprehensive Plan; conditions on zoning resolutions for planned development districts, special exceptions, special permits, or variances; and the precise terms of prior administrative approvals.

Sec. 34-614. Existing Official zoning map.

(a) Generally. (1) Description. The existing official zoning map of the town county consists of computer-generated section maps a series of aerial photographs depicting zoning information which shall be were adopted by the town council by resolution, board of county commissioners in 1978, as further amended by various zoning resolutions and ordinances.

- (1) The official zoning map shall reflect the new zoning district boundaries adopted in 2003 through the interim zoning map (see § 34-613).

(2) The official zoning map shall also reflect past approvals of variances, special exceptions, special permits, and similar approvals from the previous zoning map, which had been approved by Lee County Resolution 94-03-27 on March 16, 1994 and subsequently amended by incremental decisions by officials of Lee County and the Town of Fort Myers Beach.

(3) When adopting its new official zoning map, the town council may delete from the previous maps references to past approvals that are believed to have expired or which have become obsolete due to changed regulations or conditions. However, the deletion of such approvals shall not affect any rights that landowners may have under explicit terms of this code.

(b) Amendments. [deleted in its entirety]

(c) Replacement. [deleted in its entirety]

(b) District boundaries. The boundaries of each district shall be shown on the official zoning map, and the district symbols shall be used to designate each district. [moved from § 34-615(a)(1)e.]

(c) Other boundaries. The perimeter of legal descriptions affected by variances, special exceptions, and similar approvals shall be noted with a symbol referencing additional zoning information, which may include the nature of the action, the hearing date, and any special conditions that were imposed.

(d) Mapping conventions. For mapping purposes only, a zoning district boundary line may be drawn to the centerline of a street, stream or river, or to the shoreline of a stream, river or other body of water; and all existing streets or bodies of water within such district may be included within such district without delineation of the streets or bodies of water. [moved from § 34-615(a)(1)f.]

(e) Errors. If it is determined that an error exists in the official zoning map, the town council may adopt a correction to the error by resolution at an advertised public hearing.

Mapping of Zoning Districts

~~(f) (2) Public availability.~~ The existing official zoning map shall be part of the public records of the town, county, and copies of the zoning map shall be made available for public inspection at reasonable hours.

~~(3) Vested rights.~~ There shall be no right to rely on the existing zoning maps to vest rights. It shall be the responsibility of all staff members and members of the public to consult the resolution or ordinance which amended the zoning of the subject property in order to determine the parameters and conditions on the subject zoning.

~~(b) Amendments.~~ [moved to § 34-615(d)(1)]

~~(c) Replacement.~~ [deleted in its entirety]

~~(g) Sec. 34-616. Records management for zoning maps.~~ The director department of community development shall retain a copy of the official zoning original maps adopted under the provisions of § 34-614 consistent with statutory record-keeping requirements, 34-615, as well as a copy of any map reflecting the latest revisions to the zoning maps. The county administrator or his designee shall retain, for historical purposes, all zoning maps, or microfilmed copies, utilized prior to the adoption of new maps under § 34-615.

~~Sec. 34-617. Unauthorized changes to zoning maps.~~ [deleted in its entirety]

Sec. 34-615. New official Current zoning maps.

(a) Description. The current zoning map of the town consists of scaled computer-generated section maps depicting the same information on the official zoning map as it has been subsequently modified by rezonings, zoning amendments, special exceptions, variances, administrative decisions, mapping corrections, etc. that have been entered into the computer data base since the most recent adoption of the official zoning maps. For purposes of this section, the term "mapping corrections" means corrections applied to the current zoning map to provide an accurate reflection of the legal description affected by a duly adopted zoning resolution.

(b) Printed copies. Printed copies of the current zoning map should contain the following statement: "This current zoning map represents the official zoning map plus all rezonings, special exceptions, variances, and administrative amendments approved as of (date)."

(c) Public availability. The current zoning map shall be part of the public records of the town and may be inspected at town hall or purchased from the Lee County Property Appraiser in downtown Fort Myers.

~~(a) Preparation and adoption.~~ [existing text of this subsection deleted in its entirety, except as indicated below]

~~(1) e.~~ [moved to § 34-614(b)]

~~(1) f.~~ [moved to § 34-614(d)]

(d) Changes.

(1) (b) Amendments. [moved from § 34-614(b)] No changes or amendments to the existing official zoning map shall be made except in compliance and conformity with all the procedures of this chapter, including the correction of errors resulting from clerical or drafting mistakes. Changes in district boundaries or other subject matter portrayed on the official zoning map shall be made promptly on copies of the current official zoning map after official adoption of the amendment. All amendments and changes approved by the town council or other authorized bodies Board of County Commissioners or the board of zoning adjustments shall become effective at the end of the appeal period specified in article II of this chapter. The filing of an appeal stays the effectiveness of the change. If no appeal is filed the director shall forthwith authorize the approved changes to be made on copies of the current official zoning map.

(2) (1) Changes to the current zoning map authorized by the town will be entered into the computer data base and then reflected on the current zoning map If a rezoning occurs on a parcel of property after public notice and hearings in accordance with the current county zoning ordinance and the enabling legislation, the changes shall be noted on

Mapping of Zoning Districts

copies of the official zoning map in the following manner:

- a. The property affected by a zoning district boundary change, special exception, variance, or other approval shall be drawn on the map indicating the new district designation or noted with a symbol, as well as a referencing additional zoning information, notation which will reference the reader to a margin notation.
 - b. The additional zoning information may include margin notation shall indicate, at a minimum, the resolution number, the hearing number, what the any change of zoning district, the nature of any other action, the hearing date, was and whether or not there were any special conditions that were imposed.
- (2) All special permits, special exceptions or variances approved by the Board of County Commissioners or board of zoning adjustments, as applicable, after public hearings and notice in accordance with article H of this chapter, shall be noted in the margin as follows:
- a. The property in question shall be marked with a reference number directing the reader to the margin notes; and
 - b. The margin note shall indicate, at a minimum, the resolution number, hearing number, type of action taken (i.e., special exception, permit or variance) and whether or not there were conditions.
- (3) If a page becomes difficult to interpret due to numerous revisions or for any other reason, the Board of County Commissioners may adopt a new page reflecting all changes approved in accordance with this chapter, which will supersede the original page.
- Sec. 34-6168. Rules for interpretation of district boundaries.**
- (a) When uncertainty exists as to the boundaries of districts of the official or current zoning map, the following rules shall apply:
- (1) Boundaries following centerlines. Boundaries indicated as approximately following the centerlines of streets, highways, or alleys or bodies of water shall be construed to follow such centerlines.
 - (2) Boundaries following lot, section, or tract lines. Boundaries indicated as approximately following lot lines, section lines, or tract lines shall be construed as following such lot lines.
 - (3) Boundaries following municipal boundaries. Boundaries indicated as approximately following municipal boundaries shall be construed as following such municipal boundaries.
 - (4) Boundaries following railroad lines. Boundaries indicated as approximately following railroad lines shall be construed to be the centerline of the railroad right-of-way.
 - (3) (5) Boundaries following shorelines. Boundaries indicated as approximately following the centerlines of water bodies streams, rivers or canals shall be construed to follow such centerlines. Boundaries indicated as following shorelines shall be construed to follow such shorelines as indicated on the aerial photography flown for the county in 1984. In the event of change in the shoreline due to natural causes, land created through accretion shall automatically be classified as EC until and unless a zoning district change is applied for and approved in accordance with procedures set forth in this chapter; provided, however, that the burden of proving the extent of any accreted property shall rest with the county, not the landowner.
 - (6) Parallel lines. ~~[deleted in its entirety]~~
 - (4) (7) Vacated lands. Street abandonments. Where a public road, street, or alley, or other form of right-of-way is officially vacated or abandoned, the regulations applicable to the property to which the vacated lands attach it is reverted shall also apply to such vacated lands or abandoned road, street or alley.
 - (8) Excluded areas.
 - a. Where parcels of land and water areas have been excluded or deannexed from incorporated areas or revert to the county in any manner, such parcels shall be classified as AG-2 until changed by public hearing.
 - (5) b. Accreted lands. Where land accretes through natural or artificial processes, except for incidental fill behind a seawall authorized

Mapping of Zoning Districts

by ch. 26 of this code, the accreted land shall be classified as EC unless reclassified until changed by public hearing in accordance with this chapter.

- (6) ~~(9)~~ *Uncertainties*. Where physical or cultural features existing on the ground are at variance with those shown on the official or current zoning map, or in case any other uncertainty exists as to the proper location of district boundaries, the director shall interpret the intent of the official or current zoning map as to the proper location of the district boundaries.

(b) When a parcel is split by two or more zoning districts, the property development regulations for the largest proportional district prevail. However, permitted uses and accessory uses are restricted to the uses permitted in the respective districts. See also § 34-1174.

Sec. 34-619. District conversions: *[existing section deleted in its entirety]*

Secs. 34-617–34-618. Reserved.

Allowable Land Uses In Each Zoning District

DIVISION 2. ALLOWABLE LAND USES IN EACH ZONING DISTRICT

Sec. 34-619. 49†. The Fort Myers Beach Comprehensive Lee Plan.

(a) The Fort Myers Beach Comprehensive Lee Plan is the document adopted by the town council Lee County Board of County Commissioners in accordance with F.S. ch. 163 to guide and regulate all land development activities within the town (see § 1-11) Lee County. All development orders (including rezonings), as defined in F.S. § 163.3164(7) shall be consistent with the goals, objectives, polices, and standards in this plan the Lee Plan. Where there are apparent conflicts between this plan the Lee Plan and any regulations in this code, this plan the chapter, the Lee Plan will prevail.

(b) The Fort Myers Beach Comprehensive Lee Plan contains a future land use map which divides the town into eight distinct categories:

- (1) Low Density
- (2) Mixed Residential
- (3) Boulevard
- (4) Pedestrian Commercial
- (5) Marina
- (6) Recreation
- (7) Wetlands
- (8) Tidal Water

The future land use map also contains a Platted Overlay which is applied in certain locations in addition to one of these eight categories, county into future urban, nonurban, and environmentally sensitive areas. All development must be consistent with the future land use map, the definitions of the land use categories in the text of the plan, and the remainder of the text of the Fort Myers Beach Comprehensive Lee Plan.

(c) This chapter includes a list of zoning districts. Some of these zoning districts in this article may describe permit uses, densities, or intensities that are not permitted in particular future land use map categories. Property may not be rezoned to a district that is inconsistent with the applicable future land use map category or with the remainder of the text of the Fort Myers Beach Comprehensive Lee Plan.

Sec. 34-620. Allowable uses of land generally. Uses not specifically listed:

(a) This division describes allowable land uses in the Town of Fort Myers Beach, most of which are defined in § 34-2, and then groups these uses with compatible uses having similar impacts. These “use groups and sub-groups” (see Table 34-1) are the basis for defining the allowable uses in the various zoning districts (see Table 34-2). Other regulations for individual zoning districts are contained in divisions 4, 5, and 6 of this article.

(b) The director is authorized to determine that some land uses that are not specifically described in this division listed in the use activity groups or in any of the use regulation tables are permitted by right, by special exception or by special permit in a particular zoning district based upon the expected impacts placement of the most similar listed uses described in this division and their assignment to in the various districts.

(c) The director may determine that the expected impacts of a land use that is not specifically described in this division cannot safely be assumed to match another use described in this division. In such a case, the director shall require that a property be rezoned into a planned development zoning district (see division 6 of this article) before that land use may be permitted.

(d) In every case, the following land uses can only be permitted through approval of a suitable planned development zoning district:

- (1) Boat dealers (except as a marina accessory use)
- (2) Building material sales
- (3) Continuing care facility (see § 34-1414)
- (4) Contractor’s shop
- (5) Contractor’s storage yard
- (6) Hospital
- (7) Parking garage (see § 34-2015(2)c.)
- (8) Storage, open (except as a marina accessory use)
- (9) Vehicle and equipment dealers

(e) Planning development zoning districts are also required by the Fort Myers Beach Comprehensive Plan in the following situations:

Allowable Land Uses In Each Zoning District

- (1) For new or expanded commercial activities other than those permitted by the current zoning district for land in the Mixed Residential category on the future land use map (see Policies 4-B-4 and 4-C-3).
- (2) For new or expanded commercial activities other than those permitted by the current zoning district for land in the Boulevard category on the future land use map (see Policies 4-B-5 and 4-C-3 and §§ 34-701–34-930).
- (3) For consideration of extra building height in certain circumstances (see Policy 4-C-4 and § 34-631(b)(5)).
- (4) For the transfer of residential and hotel/motel development rights from one parcel to another (see Policy 4-C-8 and § 34-632(6)).
- (5) For guest units that exceed the thresholds established in § 34-1803(a).
- (6) For pre-disaster buildback of buildings that exceed the current density or height limits (see Policy 4-E-1 and § 34-3237).

(f) In no case may a land use that is not permitted by the Fort Myers Beach Comprehensive Plan be approved within the town, even if requested through the planned development process. Examples of prohibited uses are:

- (1) New or expanded cruise ships and similar uses that draw large amounts of vehicular traffic (see Policy 4-B-7).
- (2) New or expanded industrial uses (see Policy 4-B-12.iv.), which includes boatyards, manufacturing, and processing and warehousing.
- (3) Development seaward of the 1978 coastal construction control line (see Policy 5-D-1.v.), except for minor structures as provided in § 34-1575.

(g) Other uses prohibited within the town are as follows:

- (1) New or expanded drive-through lanes for restaurants (as a result of town ordinance 00-13).
- (2) New or expanded mobile home subdivisions and parks (see §§ 34-1921–34-1922).
- (3) New or expanded recreational vehicle subdivisions and parks (see §§ 34-2351–34-2352).

Sec. 34-621. Allowable uses of land described.

Use and development regulations for conventional districts:

(a) *Applicability.* No land, body of water, or structure shall be used or permitted to be used and no structure shall hereafter be erected, constructed, moved, altered, or maintained in any conventional or redevelopment zoning district for any purpose other than as provided in ~~the use regulation~~ Tables 34-1 and 34-2 and in accordance with the property development regulations tables set forth in this article for the zoning district in which the property is located, except as may be specifically provided for in article VIII of this chapter pertaining to nonconforming uses, or in § 34-620 pertaining to uses not specifically listed in Table 34-1.

- (1) All uses of land, water, and structures ~~in the conventional zoning districts~~ are subject to the ~~county comprehensive plan (the Fort Myers Beach Comprehensive Plan)~~ and ~~its the county~~ future land use ~~plan~~ map, and therefore may not be permitted in all land use categories.
- (2) All uses of land, water, and structures ~~in the conventional zoning districts~~ are subject to the specific use and property development regulations set forth for the district in which located, as well as all general provisions and all applicable supplemental regulations set forth in this chapter. Except as may be specifically provided for elsewhere in this chapter, deviations from the property development regulations may only be granted in accordance with the procedures established in §§ 34-203(c) and (f) § 34-932(b) for deviations in planned development zoning districts and in § 34-87 34-145(b) for variances in conventional and redevelopment zoning districts.
- (3) Allowable uses in planned development zoning districts shall be determined at the time of each rezoning in accordance with § 34-933.

Allowable Land Uses In Each Zoning District

(b) ~~Use regulations tables. Divisions 2 through 9 Table 34-1 of this article contain use regulations tables which lists specific uses or use activity groups followed by a symbol indicating whether the use is permitted by right (P), special exception (SE), or special permit (SP), or by administrative approval (AA), existing only (EO), or temporary permit (TP), or not permitted at all. In all instances, unless specifically noted to the contrary, the symbols used in the use regulations tables shall have the following meaning:~~

AA *Administrative approval required.* The director has the authority to approve the use when in compliance with the referenced sections of this code chapter.

EO *Existing only.* The use is permitted only if it that use lawfully existed on the same property on August 1, 1986, September 27, 1993, or was granted a special exception within the two years prior to such date, and commenced the approved construction within two years after such date. A use which qualifies as existing only shall not be classified as a nonconforming use and shall be afforded the same privileges as a permitted use. Such lawfully existing use shall have the same rights as a permitted use and may be expanded or reconstructed on the same parcel in accordance with all applicable regulations.

P *Permitted.* The use is permitted by right when in compliance with all applicable regulations.

SE *Special exception required.* The town council hearing examiner may approve the use after public hearing upon a finding that the use is consistent with the standards set forth in § 34-88 145(c), as well as all other applicable regulations. The town council hearing examiner may place restrictions on the use as a condition of approval.

SP *Special permit required.* The hearing examiner may approve the use after public hearing upon a finding that the use is consistent with the standards set forth in §§ 34-203(g) and 34-145(e), as well as all other applicable regulations. The hearing examiner may place restrictions on the use as a condition of approval.

TP *Temporary permit.* The use may be granted a temporary permit in accordance with §§ 34-3041 and 34-3050.

= ~~Not permitted.~~ The use is not permitted or permissible in the zoning district.

AA/ The use is permissible either through SP administrative approval or special exception SE permit, subject to the regulations set forth in the specified section (for example, in § 34-1264(a)).

EO/ Lawfully existing uses are permitted, but new SE uses are permissible only by special exception.

(1) Parenthesized number. The use is limited as set forth in the referenced footnote.

Note (1) The use is limited as set forth in the referenced footnote.

~~(c) Property development regulations. Divisions 2 through 9 of this article contain property development regulations tables which set forth the minimum lot size and dimensions, setbacks, lot coverage, maximum building height and similar regulations for development of land within the specified districts.~~

~~Sec. 34-622. Use activity groups. [deleted in its entirety]~~

Sec. 34-622. Uses groups and sub-groups.

(a) Allowable land uses are assigned by Table 34-1 to one of six use groups:

- (1) Residential
- (2) Lodging
- (3) Office
- (4) Retail
- (5) Marine
- (6) Civic

(b) Within each use group, Table 34-1 also assigns each allowable land use to one of three sub-groups:

- (1) R - Restricted
- (2) L - Limited (which includes all R uses)
- (3) O - Open (which includes all R and L uses)

(c) Within each use sub-group, uses are divided into two categories:

Allowable Land Uses In Each Zoning District

- (1) Principal uses are the primary purposes for which land is being used. Allowable principal uses are listed first.
- (2) Accessory uses are allowable only in conjunction with an allowable principal use, and only when the accessory use is incidental and subordinate to the principal use.

(d) Table 34-2 assigns these use sub-groups to the zoning districts provided by this code. However, uses in planned development zoning districts are further restricted in accordance with § 34-933.

(e) To determine the allowable land uses on a particular lot:

- (1) First, consult the zoning map to determine the lot's current zoning district (see division 1 of this article).
- (2) Consult Table 34-2 to determine which use sub-groups are allowable in that zoning district.
- (3) Consult Table 34-1 to determine which individual land uses can be placed in each allowable sub-group. Note that the sub-groups are cumulative, with all Restricted uses incorporated into Limited, and all Restricted and Limited uses incorporated into Open.
- (4) See § 34-2 for definitions of the individual land uses.

(f) To determine which zoning districts will permit a specific land use:

- (1) First, consult the definitions in § 34-2 to determine the appropriate terminology to describe the specific land use.
- (2) Consult Table 34-1 to determine which use sub-group (or sub-groups) include the desired land use.
- (3) Consult Table 34-2 to determine which zoning districts allow that use sub-group.
- (4) Consult the zoning map to determine which land has been assigned to those zoning districts.

Sec. 34-623. Performance standards:
[moved to § 34-2031]

Sec. 34-623~~4~~-34-650. Reserved.

Table 34-1, Land Uses Assigned to Use Groups and Sub-Groups (p.1 of 2)

	<i><u>Residential</u></i>	<i><u>Lodging</u></i>	<i><u>Office</u></i>	
<i>Restricted</i> (R)	<u>Community residential home</u> P	<u>Rental of any permitted dwelling unit to a single family during any one-month period, with a minimum stay of one week (see §§ 34-2391-2410 for rules and exceptions)</u> P		<i>Restricted</i> (R)
	<u>Dwelling unit, single-family</u> P			
	<u>Home care facility</u> P			
	AS ACCESSORY USES:	AS ACCESSORY USES:	AS ACCESSORY USES:	
	<u>Accessory apartment (1) (see § 34-1177)</u> SE		<u>Home occupation (no outside help)</u> P	
	<u>Accessory apartment (see § 34-1178)</u> EO		<u>Home occupation (with outside help)</u> AA	
	<u>Residential accessory uses</u> P			
<u>Temporary mobile home (§ 34-3046)</u> TP				
<i>Limited</i> <i>(plus R uses)</i> (L)	<u>Dwelling unit: two-family (1) live/work (see § 34-1773)</u> P SE	<u>Rental of any permitted dwelling unit to a single family for periods of one week or longer (see §§ 34-2391-2410 for rules)</u> P SE		<i>Limited</i> <i>(plus R uses)</i> (L)
	<u>Mobile home or RV park (VILLAGE district only, as restricted in § 34-694)</u> EO	<u>Bed & breakfast inn (see § 34-1801)</u> SE		
	AS ACCESSORY USES:	AS ACCESSORY USES:	AS ACCESSORY USES:	
	<u>Accessory apartment (1) (see § 34-1177)</u> P	<u>On-premises consumption of alcoholic beverages (see division 5 of article IV)</u> AA/SE	<u>Administrative office</u> P	
<i>Open</i> <i>(plus R & L uses)</i> (O)	<u>Assisted living facility (see § 34-1411)</u> P	<u>Bed & breakfast inn (see § 34-1801)</u> P	<u>Automobile rental</u> SE	<i>Open</i> <i>(plus R & L uses)</i> (O)
	<u>Dwelling unit: multiple-family live/work (see § 34-1773)</u> P P	<u>Hotel/motel (see § 34-1801)</u> P	<u>Health care facility</u> P	
	<u>Rooming house</u> P	<u>Rental of any permitted dwelling unit or guest unit for periods of one day or longer</u> P	<u>Offices, general or medical</u> P	
	<u>Timeshare units</u> P	<u>Resorts</u> P	<u>Personal services</u> P	
	AS ACCESSORY USES:	AS ACCESSORY USES:	AS ACCESSORY USES:	
	<u>Golf course</u> EO	<u>Resort accessory uses</u> P	<u>Wholesale establishment</u> SE	
	<u>Recreation facility: private on-site private off-site</u> P SE	<u>Personal services</u> P	<u>Commercial accessory uses</u> P	
	<u>Subordinate commercial uses (see § 34-3021)</u> P	<u>Subordinate commercial uses (see § 34-3021)</u> P	<u>Drive-through, Type 1 (2)</u> P	
			<u>Subordinate commercial uses (see § 34-3021)</u> P	

(1) Provided density complies with the Fort Myers Beach Comprehensive Plan (see § 34-632).

(2) Automobile fuel pumps and all drive-throughs (whether Type 1 or Type 2) cannot be constructed within the outer perimeter of the Downtown zoning district except as provided in § 34-676(f), whether the subject property is classified in the Downtown zone or in a Commercial Planned Development zone. See also § 34-620(f)(4) regarding the prohibition on restaurant drive-throughs.

Table 34-1, Land Uses Assigned to Use Groups and Sub-Groups (p. 2 of 2)

	<u><i>Retail</i></u>	<u><i>Marine</i></u>	<u><i>Civic</i></u>	
Restricted Ⓜ			<u>Beach or bay access</u> P <u>Essential services</u> (see § 34-1612(a)) P <u>Hidden path</u> P <u>Park, neighborhood</u> P AS ACCESSORY USES: <u>ATM</u> P	Restricted Ⓜ
Limited (plus R uses) Ⓟ	<u>Dwelling unit:</u> <u>work/live (see § 34-1774)</u> SE <u>Membership organization</u> SE <u>Recreation facilities,</u> <u>commercial</u> SE <u>Parking lot, seasonal</u> (see § 34-2022) TP <u>Temporary uses</u> (see §§ 34-3041–3050) SE AS ACCESSORY USES: <u>On-premises consumption of</u> <u>alcoholic beverages (see</u> <u>§§ 34-1261–1290)</u> AA/SE	<u>Dock (for use by water taxi or</u> <u>water shuttle)</u> P <u>Marina</u> EO/SE <u>Parasailing operations office</u> SE <u>Personal watercraft operations</u> <u>office</u> SE <u>Rental of beach furniture</u> P AS ACCESSORY USES: <u>Dwelling unit, caretaker</u> <u>Dock (may be leased to non-</u> <u>occupants of principal use)</u> P	<u>Communication tower</u> (see § 34-1441–1550) SE <u>Day care center, adult or child</u> SE <u>Essential service building</u> (see § 34-1612(b)) SE <u>Essential service equipment</u> P <u>Recreation facility:</u> <u>private off-site</u> SE <u>public</u> P <u>Transit terminal</u> SE AS ACCESSORY USES: <u>Dwelling unit, caretaker</u> P <u>Restaurant, accessory to</u> <u>private rec. facilities only</u> SE	Limited (plus R uses) Ⓟ
Open (plus R & L uses) Ⓞ	<u>Automobile repair</u> SE <u>Bar or cocktail lounge</u> AA/SE <u>Car wash</u> SE <u>Dwelling unit:</u> <u>work/live (see § 34-1774)</u> P <u>Laundromat</u> P <u>Mini-warehouse</u> SE <u>Parking lot, shared</u> <u>permanent (34-2015(2)b.)</u> SE <u>Personal services</u> P <u>Restaurant (2)</u> P <u>Retail store, small</u> P <u>Retail store, large</u> SE AS ACCESSORY USES: <u>Commercial accessory uses</u> P <u>Drive-through: (2)</u> <u>Type 1</u> P <u>Type 2</u> SE <u>Automobile fuel pumps (2)</u> SE	<u>Boat dealer</u> P <u>Marina</u> P AS ACCESSORY USES: <u>Marina accessory uses</u> P	<u>Cultural facility</u> SE <u>Day care center, adult or child</u> P <u>Park, community or regional</u> P <u>Parking lot, shared permanent</u> SE <u>Place of worship</u> P <u>Religious facility</u> SE <u>School (see § 34-2381–2383)</u> P <u>Theater</u> SE AS ACCESSORY USES: <u>Helistop</u> SE <u>Restaurant, accessory only to</u> <u>public recreation facilities</u> P <u>Subordinate commercial uses</u> (see § 34-3021) P	Open (plus R & L uses) Ⓞ

(2) Automobile fuel pumps and all drive-throughs (whether Type 1 or Type 2) cannot be constructed within the outer perimeter of the Downtown zoning district except as provided in § 34-676(f), whether the subject property is classified in the Downtown zone or in a Commercial Planned Development zone. See also § 34-620(f)(4) regarding the prohibition on restaurant drive-throughs.

Table 34-2 — Use Sub-Groups Permitted in Each Zoning District ¹

	<u>Residential</u>	<u>Lodging</u>	<u>Office</u>	<u>Retail</u>	<u>Marine</u>	<u>Civic</u>
	Use Groups and Sub-Groups (Restricted, Limited, Open)					
RS <u>Residential Single-family</u>	(R)	(R)	(R)	=	(R)	(R)
RC <u>Residential Conservation</u>	(L)	(L)	(R)	=	(R)	(R)
RM <u>Residential Multifamily</u>	(O)	(L)	(L)	(R)	(R)	(L)
CR <u>Commercial Resort</u>	(O)	(O)	(O)	(L)	(L)	(L)
CM <u>Commercial Marina</u>	(R)	(R)	(L)	(L)	(O)	(L)
CO <u>Commercial Office</u>	(O)	(L)	(O)	(L)	(L)	(O)
SANTOS	(L)	(L)	(O)	(L)	(L)	(L)
IN <u>Institutional</u>	(L)	(L)	(L)	(R)	(L)	(O)
CF <u>Community Facilities</u>	(R)	(R)	(L)	(R)	(L)	(O)
BB <u>Bay Beach</u>	— see § 34-651(b) —					
EC <u>Environmentally Critical</u>	— see § 34-652(d) & (e) —					
DOWNTOWN	(O)	(O)	(O)	(O)	(L)	(O)
SANTINI	(O)	(O)	(O)	(O)	(O)	(O)
VILLAGE	(L) ²	(L) ²	(L) ²	(L) ²	=	(L)
CB <u>Commercial Boulevard</u>	(O)	(L)	(L) ³	(L) ³	(L)	(O)
RPD <u>Residential Planned Dev.</u> ⁴	(R)(L)(O)	(R)(L)	(R)(L)	(R)(L)	(R)(L)	(R)(L)
CPD <u>Commercial Planned Dev.</u> ⁴	(R)(L)(O)	(R)(L)(O)	(R)(L)(O)	(R)(L)(O)	(R)(L)(O)	(R)(L)(O)

Note 1: See Table 34-1 for a specific list of Use Groups (Residential, Lodging Office, Retail, Marine, and Civic) and Sub-Groups of each (Restricted, Limited, and Open).

Note 2: See § 34-692(3) which provides a pre-approved redevelopment option for the VILLAGE district that can also permit residential, lodging, office and retail uses in the Open Sub-Group under specified conditions.

Note 3: See § 34-702–703 for exceptions and limitations on new and expanded commercial uses.

Note 4: See § 34-933. The resolution approving a planned development zoning district (RPD or CPD) will specify which of the use groups or sub-groups enumerated in Table 34-1 will be permitted on that parcel.

Note that some potential use sub-groups are not listed above for the RPD zoning district because they may not be approved in any RPD zoning resolution.

Property Development Regulations For All Zoning Districts

DIVISION 3. EXPLANATION OF PROPERTY DEVELOPMENT REGULATIONS FOR ALL ZONING DISTRICTS

Sec. 34-631. Building heights.

(a) Methods of measurement. Maximum building heights specified in this code are measured in two ways, as shown in Figure 34-1.

- (1) Measured in stories, the height includes space at ground level as the first story, provided it is six feet or more in height.
 - a. Space within a roofline that is entirely non-habitable shall not be considered to be a story.
 - b. Any single story cannot exceed 16 feet in height, including structural members.
- (2) Measured in feet, the height is the vertical distance between the base flood elevation (BFE), as established by the maps described in § 6-408, and the top of the structural members that serve as the ceiling for the highest habitable story of the building. For parking garages, height is measured to the top of the structural members of the highest ceiling, or if parking is allowed on the roof level, to the highest point on the rooftop parking level.
- (3) Specific height regulations are provided for each zoning district.
 - a. For conventional zoning districts, see Table 34-3 in division 4 of this chapter.
 - b. For redevelopment zoning districts, see individual districts in division 5 of this chapter.
 - c. For planned development zoning districts, see division 6 of this chapter.

(b) Exceptions to height regulations.

- (1) Roof structures and parapet walls may exceed the height limit defined in any zoning district provided there is no habitable space inside the roof structure.
- (2) Architectural appurtenances such as cupolas, clerestories, towers, flagpoles, and steeples may also extend above the height limit if they do not exceed an area of 250 square feet. Any proposed appurtenance taller than an additional 15 feet or larger than 250 square feet would require a variance from this code.
- (3) Mechanical or structural appurtenances such as elevator and stairwell enclosures, air-conditioning equipment, and antennas may also extend above the height limit provided these appurtenances:
 - a. do not exceed 250 square feet per type; and
 - b. screening is provided as required by this code (see, for example, § 6-2(f) for rooftop mechanical equipment).
- (4) When properties are being rebuilt pursuant to the buildback regulations in § 34-3237 and 34-3238, specific height regulations in those sections may supersede the height regulations established for that property's zoning district.
- (5) In those few cases where individual parcels of land are so surrounded by tall buildings on lots that are contiguous (or directly across a street) that the height regulations in this chapter would be unreasonable, landowners may seek relief through the planned development rezoning process, which requires a public hearing and notification of adjacent property owners. The town will approve, modify, or deny such requests after evaluating the level of unfairness that would




Figure 34-1

Property Development Regulations For All Zoning Districts

result from the specific circumstances and the degree the specific proposal conforms with all aspects of this comprehensive plan, including its land-use and design policies, pedestrian orientation, and natural resource criteria. Particular attention would be paid to any permanent view corridors to Gulf or Bay waters that could be provided in exchange for allowing a building to be taller than the height limits in this chapter. In each case, the town shall balance the public benefits of the standard height limit against other public benefits that would result from the specific proposal.

- (6) For amateur radio antennas/towers, see § 34-1175. For communication towers and commercial antennas, see § 34-1441-1550).
- (c) **Space at ground level.**
- (1) Commercial space below the base flood elevation (at ground level) requires dry-floodproofing of the building (see §§ 6-401-474).
- (2) Space below the base flood elevation in new residential buildings may be used only for parking and limited storage (see §§ 6-401-474).

Sec. 34-632. Density.

Residential density cannot exceed the maximum levels established in the Fort Myers Beach Comprehensive Plan.

- (1) **Formula for computing density.** The maximum number of dwelling units allowed on a parcel of land is computed by taking the maximum number of dwelling units per acre the comprehensive plan allows on that parcel and multiplying it by the site's lot area in acres, with the result rounded down to the nearest whole number (except as provided in subsection (3) below).
- (2) **Determining lot area.** For purposes of this section, a site's lot area includes the gross acreage within the site's private property line, minus wetlands, canals or other water bodies that extend beyond the site, commercial and other non-residential land, and any land designated "Recreation" on the Comprehensive Plan's future land use map.

For any site with wetlands or land designated "Recreation," the maximum number of dwelling units shall be increased by one unit per 20 acres of such land.

- (3) **Existing subdivisions.** In existing subdivisions where lots are smaller than 15,000 square feet each:
- a. Residential densities may be computed based on the actual lot size plus one-half the width of adjoining streets and canals.
- b. Computed densities greater than 1.5 DU/acre may be rounded up to two dwelling units where two-family and multifamily dwelling units are permitted.
- c. This method for determining densities cannot be used for three or more lots that are being combined into a development project.
- (4) **Mixed-use buildings.** Residential densities may be computed without deleting any acreage for commercial uses that are located on other floors of mixed-use buildings. However, any acreage used primarily for commercial purposes cannot be included in computations of residential density.
- (5) **Adjustments to density computations.** The following rules shall apply when measuring density for living units or guest units that may not also qualify as dwelling units:
- a. When permitted on a property, certain other land uses such as assisted living facilities and hotels/motels are limited by using equivalency factors between those uses and dwelling units, such as provided in §§ 34-1415 and 34-1803.
- b. For density purposes, each living unit shall count as one dwelling unit except where this code explicitly provides a different measure for measuring density (see, for example, § 34-1178(d) regarding accessory apartments in owner-occupied homes).
- c. Lock-off accommodations in multiple-family buildings and timeshare units are living units and thus are calculated as separate dwelling units for density purposes.
- (6) **Density transfers.** The Town Council may, at its discretion, permit the transfer of residential and hotel/motel development

Property Development Regulations For All Zoning Districts

rights from one parcel to another if the following conditions established by Policy 4-C-8 of the comprehensive plan are met:

- a. the transfer is clearly in the public interest, as determined by the Town Council;
- b. the parcels affected by the transfer are in close proximity to each other;
- c. the density of residential or hotel/motel units being transferred is based upon allowable density levels in the comprehensive plan category from which the density is being transferred;
- d. the transfer is approved through the planned development rezoning process; and
- e. binding permanent restrictions are placed on the property from which development rights have been transferred to guarantee the permanence of the transfer.

Sec. 34-633. Intensity and floor area ratios.

Another measure of building intensity used in this code is the floor area ratio (FAR), which means the gross floor area of all buildings on a site divided by the site's lot area.

- (1) For purposes of this section, gross floor area includes the total floor area of all stories of a building within the surrounding exterior walls (whether the walls are solid or screened), plus all area below an elevated building that is 6 feet or more in height, plus all stories of covered parking, but not including any area whose roof is screened rather than solid (such as swimming pool enclosures).
- (2) For purposes of this section, a site's lot area includes the gross square footage within the site's private property line, minus wetlands, canals or other water bodies, and minus any land designated "Recreation" on the Comprehensive Plan's future land use map.

Sec. 34-634. Intensity and building coverage.

Another measure of building intensity used in this code is building coverage, which means the horizontal area of all principal and accessory buildings on a site divided by the site's lot area.

- (1) For purposes of this section, horizontal area means the area within the surrounding exterior walls (whether the walls are solid or screened). The term "horizontal area" does not include any area occupied by unroofed structures such as driveways, sidewalks, patios, outside stairways, or open swimming pools, and does not include any area whose roof is screened rather than solid such as swimming pool enclosures.
- (2) For purposes of this section, a site's lot area includes the gross square footage within the site's private property line, minus wetlands, canals, or other water bodies, and minus any land designated "Recreation" on the Comprehensive Plan's future land use map.

Sec. 34-635. Commercial design standards.

Except where this code specifically provides otherwise, the commercial design standards (see § 34-991-1010) apply to all commercial and mixed-use buildings or portions thereof that are being newly built, and to "substantial improvements" to such buildings as defined in § 6-405, on properties that are zoned in any of the following zoning districts:

- (1) SANTOS (§ 34-648);
- (2) DOWNTOWN (§ 34-671-680);
- (3) SANTINI (§ 34-681-690);
- (4) VILLAGE (§ 34-691-700);
- (5) CB (§ 34-701-710); and
- (6) CPD (commercial planned development) (§ 34-951-960).

Sec. 34-636. Reserved.

Sec. 34-637. Minimum lot sizes.

(a) All lot area, width, and depth dimensions in this code are mandatory minimums for newly created lots.

- (1) Minimum lot areas, width, and depths are specified for various zoning districts.
 - a. For all conventional zoning districts, see Table 34-3.
 - b. For redevelopment zoning districts, as described for the individual districts in division 5 of this chapter.

Property Development Regulations For All Zoning Districts

c. For PD districts, see §§ 34-943 and 34-953.

(2) Definitions and methods of measuring lot widths and depths are provided in § 34-2.

(b) Where two or more dwelling units or guest units are proposed for a single lot or combination of lots, the lot(s) must also be large enough to comply with the density limitations of the Fort Myers Beach Comprehensive Plan, as computed in accordance with § 34-632.

(c) Division 4 of article V of this chapter defines nonconforming lots, which may be smaller than the minimum lot areas, widths, and/or depths specified in this code.

(1) Certain nonconforming residential lots are subject to the smaller minimum lot areas, widths, and depths that are found in § 34-3274.

(2) Certain nonconforming commercial lots are subject to the smaller minimum lot areas, widths, and depths that are found in § 34-3277.

(d) Sec. 34-2142. Exception for essential service facilities group F: Essential services and essential service equipment facilities group F shall not be required to meet the minimum required lot area and dimensions for the district wherein located (see § 34-1617), provided that access, buffering, drainage, retention, parking, and other provisions of this chapter and chapter 10 are satisfied.

Sec. 34-638. Minimum setbacks.

(a) Generally. Most zoning districts require minimum setbacks between all buildings and structures and the street, the side lot line, the rear lot line, and any water body.

(1) Setbacks are minimum horizontal distances between a property line and the nearest point of all structures that ensure a minimum area without buildings. Detailed definitions are provided under “setback” in § 34-2.

(2) There are two types of side setbacks:

a. Side setbacks – waterfront lots. Larger side setbacks are required for waterfront lots, defined as lots that immediately adjoin a tidally influenced body of water,

whether artificial or natural (see definitions in § 34-2).

b. Side setbacks – non-waterfront lots. Smaller side setbacks are required for all other lots.

(3) The distinction between street setback lines and build-to lines is explained in § 34-662.

(4) Certain exceptions to minimum setbacks are provided in subsection (d) below.

(b) Where to find minimum setback dimensions. Minimum setback dimensions are specified as follows:

(1) For principal buildings:

a. For all conventional zoning districts, see Table 34-3.

b. For redevelopment zoning districts, as described for the individual districts in division 5 of this chapter.

c. For RPD districts, see § 34-943.

d. For CPD districts, see § 34-953.

(2) For accessory buildings, see §§ 34-1174–1176.

(c) Additional wetlands buffers. New development must maintain a 75-foot separation between wetlands and buildings or other impervious surfaces, in accordance with Policy 4-C-12 of the Fort Myers Beach Comprehensive Plan.

(1) This requirement does not apply to previously platted lots

(2) This requirement also does not apply to a previously approved development order to the extent it cannot reasonably be modified to comply with this requirement (see ch. 15 of the Fort Myers Beach Comprehensive Plan for details).

(d) Exceptions to setback dimensions. Sec. 34-2191. Measurement; permitted encroachments. All setbacks shall be measured to the nearest point of a building or structure. Encroachment into the setback shall be permitted as follows. In addition to the following general exceptions to minimum setbacks, commercial buildings that are subject to the commercial design standards may encroach into certain setbacks as provided in § 34-991–1010.

(1) Wing walls. [deleted in its entirety]

Property Development Regulations For All Zoning Districts

(1) Exceptions to all setbacks.

- a. Administrative setback variances. Under certain limited circumstances, administrative variances can be granted to minimum setbacks as provided in § 34-268.
- b. **(2) Overhangs.** An overhang which is part of a building may be permitted to encroach into any setback as long as the overhang does not extend more than three feet into the setback and does not permit any balcony, porch, or living space located above the overhang to extend into the setback.
- c. **(3) Shutters.** A shutter which is attached to a building may be permitted to encroach one foot into the setbacks.
- d. **(4) Awnings and canopies.**
 - 1. **a.** Awnings and canopies which are attached to a building may be permitted to encroach three feet into the setbacks, as long as their location does not interfere with traffic, ingress and egress, or life safety equipment.
 - 2. **b.** For purposes of this section, awnings and canopies may be attached to a nonconforming building and shall not be considered an extension or enlargement of a nonconformity, as long as the building is properly zoned for its use and the conditions as set forth in this section are met.
- e. Essential services. Essential services and essential service equipment shall not be required to meet the minimum setbacks for the district wherein located (see § 34-1617).

(2) Exceptions to street setbacks. Sec. 34-2192.

Street setbacks. (a) Required setback. Except as provided for in subsection (b) of this section, or unless a modification is granted as a special permit, variance or deviation, all buildings and structures must be set back from the adjacent street easement or right-of-way, according to the functional classification of the adjoining street as set forth on the official trafficways map. Any street not shown on the trafficways map as a collector or arterial street will be presumed to

be a local street or a private street for the purposes of this section:

SETBACKS FROM STREETS	
Street Classification	Setback from Edge of Right-of-Way or Street Easement Line (feet)
Arterial or collector street:	
With frontage street*	65
Without frontage street	25
Local	25
Private	20

* *Applies only where the frontage street is located within 40 feet of the right-of-way; does not apply where the frontage street is or will be located within the right-of-way.*

(b) Exceptions. (1) Exception for certain structures. Certain structures are exempt from the street setback requirements as follows:

- a. **Build-to lines.** Some zoning districts do not have any street setback requirements but instead have build-to lines, as described in § 34-662. Awnings, canopies, balconies, bay windows, porches, stoops, arcades, and colonnades may extend forward of the build-to line provided that they comply with the commercial design standards (see § 34-995(e)).
- b. **Porches, balconies, and stoops.** Porches, balconies, and stoops may extend up to 10 feet into the street setback zone of residential buildings, provided that:
 - 1. Any walls, screened areas, or railings in the setback zone extend no higher than 42 inches above the floor of the porch, balcony, or stoop; and
 - 2. No portion of a porch or balcony and no walls or screened areas may be closer than 10 feet to the edge of any street right-of-way or street easement.
- c. **a. Mail and newspaper delivery boxes.** Mail and newspaper delivery boxes may be placed in accordance with U.S. Postal Service regulations; however, the support for a mail or newspaper delivery box must be of a suitable breakaway or yielding design, and any mail or newspaper delivery box placed in an unsafe or hazardous location can be removed by the government agency with jurisdiction over the right-of-way at the property owner's expense.

Property Development Regulations For All Zoning Districts

d. ~~b. *Bus shelters, bus stop benches, and bicycle racks.* Bus shelters, bus stop benches, and bicycle racks may be located in any district without regard for minimum setbacks, provided the location of the structure is approved by the county department of transportation. town manager. No advertising is permitted on bus stop benches.~~

e. ~~c. *Telephone booths.* Telephone booths and pay telephone stations may be located in any zoning district that permits multifamily or commercial uses without regard for minimum setbacks, provided that the location shall be approved by the director, county department of transportation and engineering services.~~

d. ~~*Utility equipment.* Accessory utility equipment such as pad-mounted transformers, service pedestals, and telephone terminal or switching devices are exempt from certain setback requirements, provided that they comply with the provisions set forth in division 14 of this article.~~

(2) ~~*Exception for certain existing lots and structures.*~~

a. ~~The setbacks set forth in subsection (a) of this section shall not apply to residential structures or public schools erected prior to August 1, 1986, or which received a development order or building permit which is still valid on August 1, 1986.~~

b. ~~Street setbacks for corner lots recorded prior to January 28, 1983, which have a lot width of less than 100 feet shall be modified as follows:~~

1. ~~If the corner lot abuts two local streets, the setback for the street opposite the interior side yard may be reduced to 15 feet.~~

2. ~~If the corner lot abuts a local street and a street of higher classification, the street setback for the local street may be reduced to 15 feet.~~

(3) ~~*Structures along Colonial Boulevard.* [deleted in its entirety]~~

(4) ~~*Structures along Daniels Road.* [deleted in its entirety]~~

(c) ~~*Modifications.* [deleted in its entirety]~~

Sec. 34-2193. Reserved.

(3) ~~*Water body setbacks.* Sec. 34-2194. Setbacks from bodies of water:~~

a. ~~(a) *Gulf of Mexico.* Except as provided in this section or elsewhere in this code chapter, no building or structure shall be placed closer to the Gulf of Mexico than set forth in ch. 6, articles III and IV, pertaining to coastal zone protection, or 50 feet from mean high water, whichever is the most restrictive. See also special regulations for the EC zoning district in § 34-652 and the coastal zone restrictions in § 34-1575.~~

b. ~~(b) *Other bodies of water.* Except as provided in this section or elsewhere in this chapter, no building or structure shall be placed closer than 25 feet to a canal or to a bay or other water body. For purposes of measuring setbacks from a canal, bay, or other body of water, the following will be used:~~

1. ~~If the body of water is subject to tidal changes and the property does not have a seawall, the setback will be measured from the mean high water line.~~

2. ~~If the body of water is not subject to tidal changes and the property does not have a seawall, the setback will be measured from the control elevation of the body of water if known, or from the ordinary high water line if unknown.~~

3. ~~If the property has a seawall, the setback will be measured from the seaward side of the seawall, not including the seawall cap.~~

c. ~~(c) *Exceptions for certain accessory structures.*~~

(1) ~~*Planned developments.* [deleted in its entirety]~~

(2) ~~*Docks, seawalls and other watercraft landing facilities.* See § 34-1863.~~

(3) ~~*Other accessory structures.* Certain accessory buildings and structures may be permitted closer to a body of water as follows:~~

1. ~~*a. Fences and walls.* See division 17 of this article.~~

2. ~~*Shoreline structures.* See § 34-1863 and ch. 26.~~

Property Development Regulations For All Zoning Districts

3. ~~b.~~ *Nonroofed structures.* Swimming pools, tennis courts, patios, decks, and other nonroofed accessory structures or facilities which are not enclosed, except by fence, or which are enclosed on at least three sides with open-mesh screening from a height of 3 1/2 feet above grade to the top of the enclosure, shall be permitted up to but not closer than:

- ~~a-1.~~ Five feet from a seawalled canal or seawalled natural body of water;
- ~~b-2.~~ Ten feet from a nonseawalled artificial body of water; or
- ~~c-3.~~ Twenty-five feet from a nonseawalled natural body of water; whichever is greater. Enclosures with any two or more sides enclosed by opaque material shall be required to comply with the setbacks set forth in subsections (d)(3)a. and (d)(3)b. (a) and (b) of this section.

4. ~~c.~~ *Roofed structures.*

- ~~a.~~ ~~1.~~ Accessory structures with roofs intended to be impervious to weather and which are structurally built as part of the principal structure shall be required to comply with the setbacks set forth in subsections (a) and (b) of this section.
- ~~b.~~ ~~2.~~ Accessory structures with roofs intended to be impervious to weather and which are not structurally built as part of the principal structure may be permitted up to but not closer than 25 feet to a natural body of water, and ten feet to an artificial body of water.

(4) *Exceptions for certain nonconforming lots.*

- a. Certain nonconforming residential lots are subject to the modified side and rear setback requirements that are found in § 34-3273.
- b. Certain nonconforming mobile home lots in the VILLAGE zoning district are subject to the modified side and rear setback requirements that are found in § 34-694.
- c. Certain nonconforming commercial lots are subject to the modified side and rear

setback requirements that are found in § 34-3277.

~~Sec. 34-2195. Setbacks from lot lines abutting railroad right-of-way. [deleted in its entirety]~~

~~Sec. 34-2196. Uses employing solar energy or wind-driven electrical generators. [deleted in its entirety]~~

Secs. 34-638--34-640. Reserved.

Conventional Zoning Districts

DIVISION 4. CONVENTIONAL ZONING DISTRICTS

Sec. 34-641. General purpose.

The purpose of conventional zoning districts is to control land use in a uniform way throughout each zoning district, with similar use and dimensional regulations applying to all parcels within that district. Article IV of this chapter also contains supplemental regulations that apply to multiple zoning districts.

Sec. 34-642. RS (Residential Single-family) zoning district.

(a) The purpose of the RS zoning district is to provide stable neighborhoods where single-family detached homes are the predominant land use.

(b) In the RS zoning district, allowable uses are defined in Table 34-2 and property development regulations are contained in Table 34-3.

Sec. 34-643. RC (Residential Conservation) zoning district.

(a) The purpose of the RC zoning district is to recognize certain older neighborhoods that had been zoned for duplex, multifamily, or mobile homes purposes prior to incorporation of the town. Some lots in this district are large enough to accommodate a second dwelling unit (see Table 34-3 and §§ 34-632, 34-1177, and 34-1178).

(b) In the RC zoning district, allowable uses are defined in Table 34-2 and property development regulations are contained in Table 34-3.

Sec. 34-644. RM (Residential Multifamily) zoning district.

(a) The purpose of the RM zoning district is to designate suitable locations for a wide variety of multifamily residences.

(b) In the RM zoning district, allowable uses are defined in Table 34-2 and property development regulations are contained in Table 34-3.

Sec. 34-645. CR (Commercial Resort) zoning district.

(a) The purpose of the CR zoning district is to designate suitable locations for motels, resorts, and related services.

(b) In the CR zoning district, allowable uses are defined in Table 34-2 and property development regulations are contained in Table 34-3.

Sec. 34-646. CM (Commercial Marina) zoning district.

(a) The purpose of the CM zoning district is to allow commercial marinas in suitable waterfront locations to provide boaters with access to the water and related services.

(b) In the CM zoning district, allowable uses are defined in Table 34-2 and property development regulations are contained in Table 34-3.

Sec. 34-647. CO (Commercial Office) zoning district.

(a) The purpose of the CO zoning district is to allow office uses on land that is visible to the traveling public or on land that can serve as a transition between commercial and residential uses.

(b) In the CO zoning district, allowable uses are defined in Table 34-2 and property development regulations are contained in Table 34-3.

Sec. 34-648. SANTOS zoning district.

(a) The purpose of the SANTOS zoning district is allow a mixture of residential and low-intensity commercial uses that will separate the intense commercial uses along Estero Boulevard from the residential portions of the Venetian Gardens subdivision. This zoning district implements the recommendations of the Santos/Palermo Circle Planning Study (February, 1999) and Policy 4-C-11 of the Fort Myers Beach Comprehensive Plan.

(b) In the SANTOS zoning district, allowable uses are defined in Table 34-2 and property

Conventional Zoning Districts

development regulations are contained in Table 34-3.

(c) In addition to these restrictions on allowable uses and dimensional requirements, the commercial design standards found in § 34-991–1010 apply to all commercial and mixed-use buildings or portions thereof that are being newly built and to “substantial improvements” to such buildings as defined in § 6-405.

Sec. 34-649. IN (Institutional) zoning district.

(a) The purpose of the IN zoning district is to provide suitable regulations for churches, civic buildings, schools, and government buildings.

(b) In the IN zoning district, allowable uses are defined in Table 34-2 and property development regulations are contained in Table 34-3.

Sec. 34-650. CF (Community Facilities) zoning district.

(a) The purpose of the CF zoning district is to provide suitable regulations for parks and nature preserves.

(b) In the CF zoning district, allowable uses are defined in Table 34-2 and property development regulations are contained in Table 34-3.

Sec. 34-651. BB (Bay Beach) zoning district.

(a) The purpose of the BB zoning district is to implement the binding agreement that settled litigation over development rights in Bay Beach.

(b) Land uses in the BB zoning district shall conform to all requirements of the stipulated settlement agreement between Stardial Investments Company and the Town of Fort Myers Beach dated February 23, 2001, a copy of which is recorded in O.R. Book 3414, Pages 4775–4786, as amended in O.R. Book 3414, Pages 4787–4789, and including any future amendments to this agreement.

(1) Allowable land uses include those uses in lawful existence as of February 23, 2001, and those additional uses as defined in the settlement agreement.

- (2) Building size and placement shall be governed by the regulations in this code, including the property development regulations in the RM district, except where specifically superseded by terms of the settlement agreement.
- (3) Replacement buildings cannot exceed the height, square footage of floor and parking areas, and all other measurable parameters of the original buildings. See buildback regulations in § 34-3237–3238.

Sec. 34-652. EC (Environmentally Critical) zoning district.

(a) Purpose. The purpose of the EC zoning district is to designate beaches and significant wetlands whose preservation is deemed critical to the Town of Fort Myers Beach through its comprehensive plan, including:

- (1) Beaches that have been designated in the “Recreation” category on the future land use map, and.
- (2) Wetlands that have been correctly designated in the “Wetlands” category on the future land use map.

Subdivision H. Environmentally Critical District [moved from § 34-980–34-1000]

Sec. 34-981. Purpose and intent. (a) The purpose and intent of the EC environmentally critical district is to preserve and protect certain land and water areas in the unincorporated area of the county which have overriding ecological, hydrological or physiographic importance to the public at large.

(b) Intent. The application of the EC district is intended to prevent a public harm by precluding the use of land for purposes for which it is unsuited in its natural state and which injures the rights of others or otherwise adversely affects a defined public interest. The EC district shall be applied to an area of land or water only upon a recommendation by the hearing examiner and a finding by the Board of County Commissioners in their respective public hearings that the use or conversion of the property may create a public harm or a public need.

(c) Lands or waters to which this district shall be applied include those areas that would fit the criteria

Conventional Zoning Districts

of or that have been designated on the Lee Plan land use map as a resource protection area or transition zone.

(c) Accretion. Accretions of beaches or wetlands, whether by natural causes or through beach renourishment or artificial filling, will automatically be assigned to the EC zoning district.

Sec. 34-982. Standards for application of EC district.

[deleted in its entirety]

Sec. 34-983. Use regulations.

No land, body of water or structure shall be used or permitted to be used and no structure shall be hereafter erected, constructed, moved, altered or maintained in the EC district for any purpose other than as provided in this section.

(d) (1) Permitted uses. In the EC district, no land or water use shall be permitted by right except for those uses and developments permitted by the Fort Myers Beach Comprehensive Lee Plan in wetlands, beaches, or critical wildlife habitats, as applicable RPA and TZ zones and as may be set forth in § 14-298, including:

- (1) a. Boating and canoeing, with no motors permitted except electric trolling motors
 - b. Entrance gates and gatehouses (see article VII, division 17, of this chapter).
- (2) c. Fishing, limited to sport or recreational fishing only.
- (3) d. Forest management activities, limited to Removal of intrusive exotic species or diseased or dead trees, and pest control.
- (4) e. Hiking and nature study, including pedestrian boardwalks and dune crossovers where the activity does not require new access or clearing.
- (5) f. Outdoor education, in keeping with the intent of the district.
- (6) g. Recreation activities, residential accessory uses, and resort accessory uses that are performed outdoors. These activities and uses only, to include passive recreation and that active recreation requiring no permanent structures little or no facilities, capital investment or alteration of the natural

landscape. Any temporary structure used in conjunction with such uses must comply with all provisions of this code (for instance, see chapters 14 and 27).

~~h. Single-family dwellings and their customary accessory uses, when in compliance with the requirements of chapter 14, article IV, pertaining to wetlands protection.~~

- (7) i. Wildlife management, as wildlife or game preserves.

(e) (2) Special exceptions uses. Upon a finding that the proposed use is consistent with the standards set forth in § 34-88 ~~145(c)(2)~~, as well as all other applicable town county regulations, the town council hearing examiner may permit any specific use from the following list as a special exception, subject to conditions set forth in this chapter and in ~~0.~~ the resolution of approval:

- (1) a. Accessory structures, to include any building, structure, (including sea walls) or impervious surface area including bikeways which is accessory to a use permitted by right or by special exception in the EC district.
 - b. Boating, without restriction, except that it shall be limited to natural or existing manmade channels.
- (2) c. Nature study center, noncommercial, and its customary accessory uses.
- (3) Single-family residence and its customary accessory uses at a maximum density of one dwelling unit per twenty acres.

Sec. 34-984. Property development regulations.

(a) Residential density. Residential density in the EC district shall be subject to the land use category wherein located, as well as chapter 14, article IV, pertaining to wetlands protection.

(b) Setbacks. See article VII, division 30, subdivision III, of this chapter. In order to maximize flexibility in siting any structure permitted in the EC district, the minimum setbacks shall be as follows:

- (1) Street or accessway: Variable according to the functional classification of the street or road (see § 34-2192).
- (2) Side or rear lot lines or parcel boundaries: 15 feet.

Conventional Zoning Districts

- ~~(3) Gulf of Mexico: 50 feet from mean high water or as required by chapter 6, article III, whichever is the most restrictive.~~
- ~~(4) Other water body: 25 feet.~~

~~(f) (c) Additional regulations. See article VII, division 30, of this chapter for additional regulations pertaining to property development. See additional requirements in:~~

- ~~(1) Article I of ch. 14 pertaining to beach and dune management;~~
- ~~(2) Article IV of ch. 14 pertaining to wetlands protection); and~~
- ~~(3) Coastal zone regulations in § 34-1575.~~

Secs. 34-653 985--34-660 1000. Reserved.

Table 34-3 — Dimensional Regulations in Conventional Zoning Districts

ZONING DISTRICT	Setbacks <i>(see § 34-638 for explanation and exceptions)</i>						Lot size <i>(see § 34-637 for explanations and exceptions)</i>			F.A.R. <i>§ 34-633</i>	Building Coverage <i>§ 34-634</i>	Density <i>§ 34-632</i>	Height <i>(see § 34-631)</i>	
	<i>street</i>	<i>side - waterfront lot</i>	<i>side - non-waterfront</i>	<i>rear</i>	<i>water body (1)</i>	<i>Gulf of Mexico (2)</i>	<i>area</i>	<i>width</i>	<i>depth</i>	<i>ratio</i>	<i>percentage</i>	<i>feet</i>	<i>stories</i>	
RS Residential Single-family	20	10	7	20	25	50	7,500	75	100	=	40%	(3), (4)	25	3
RC Residential Conservation	10	7	5	20	25	50	4,000	45	80	=	40%	(3), (4), (5)	25	3
RM Residential Multifamily	20	20 (6)	7	20	25	50	7,500	75	100	1.2	=	(3), (4), (5)	30	3
CR Commercial Resort	10	20	15	20	25	50	20,000	100	100	1.2	=	(3)	30	3
CM Commercial Marina	20	20	20	20	0	50	20,000	100	100	1.0	=	(3)	35	3
CO Commercial Office	10	10	7	20	25	50	7,500	75	100	1.2	=	(3)	30	3
SANTOS	10	7	5	20	25	50	5,000	50	100	0.5	=	(1), (2), (3)	25	3
IN Institutional	20	10	7	20	25	50	7,500	75	100	0.8	=	(3)	35	3
CF Community Facilities	20	15	10	20	25	50	N/A	N/A	N/A	0.1	=	(3)	35	3
BB Bay Beach	— see § 34-651(b) —													
EC Environmentally Critical	20	25		25	20	50	(7)	N/A	N/A	.01	=	(7)	25	2

Note 1: An additional wetland buffer is required for new development; see § 34-638(c).
Note 2: See § 34-638(d)(3)a.
Note 3: Maximum densities are established by the Fort Myers Beach Comprehensive Plan; see § 34-632.
Note 4: Accessory apartments are allowed in owner-occupied homes under certain conditions; see § 34-1178.
Note 5: A second dwelling unit or accessory apartment may be allowed on larger lots; for details, see §§ 34-632, 34-1177, and 34-1178.
Note 6: Single-family and two-family homes on waterfront lots in the RM zoning district must maintain only a 10-foot side setback.
Note 7: See § 34-652(e)(3).

Redevelopment Zoning Districts

DIVISION 5. REDEVELOPMENT ZONING DISTRICTS

Subdivision I. Generally

Sec. 34-661. General purpose.

The purpose of the redevelopment zoning districts is to implement specific redevelopment concepts established in the Fort Myers Beach Comprehensive Plan and for other situations where conventional or planned development zoning districts are inappropriate. These districts require more detailed regulations than provided by conventional zoning districts, and use special terms as described in the following sections. Article IV of this chapter also contains supplemental regulations that apply to multiple zoning districts.

Sec. 34-662. Build-to lines and setback lines.

(a) Build-to and setback lines distinguished.

Most redevelopment districts specify build-to lines for street frontages and setback lines for side and rear property lines.

- (1) A build-to line identifies the *precise* horizontal distance (or range of distances) from a street that the front of all primary structures must be built to, in order to create a fairly uniform line of buildings along streets.
- (2) A setback line identifies the *minimum* horizontal distance between a property line and the nearest point of all structures, in order to ensure a minimum area *without* buildings.




Figure 34-2

(b) General requirements for build-to lines.

- (1) Build-to lines are illustrated conceptually on Figure 34-2.
- (2) Where a build-to line is specified as a range (for instance, 5 to 10 feet), this means that building fronts must fall within that range of distances from the front property line. Where there is a range, the front facade does not have to be parallel to the street or in a single plane, as long as the front facade remains within the range.
- (3) At least 75% of the building frontage is required to align with the build-to line. The remaining 25% may be recessed up to 10 feet behind the build-to line, for instance to provide recessed pedestrian entrances or simply for architectural diversity. (See also § 34-997 regarding plazas.)
- (4) Build-to lines are subject to adjustment to maintain visibility for vehicles exiting onto primary streets.

- a. Visibility triangles must be maintained on both sides of intersecting streets and exiting driveways as shown in Figures 34-3 and 34-4, or to provide equivalent visibility.




Figure 34-3




Figure 34-4

Redevelopment Zoning Districts

b. Within these triangles, no buildings, shrubs, or low-hanging tree limbs may obstruct visibility between the height of 2 feet and 6 feet above ground. However, visibility triangles are not required at intersections with roundabouts or all-way stop signs.

- (5) Build-to line requirements may be adjusted by the director to avoid trees larger than 8 inches in diameter (measured 54 inches above grade).
- (6) Upper stories are encouraged to remain in the same vertical plane as the first floor. Awnings, canopies, balconies, bay windows, porches, stoops, arcades, and colonnades are allowed on building exteriors provided that they comply with the commercial design standards (see § 34-995(e)).
- (7) Build-to line requirements shall take precedence over any buffer or setback requirements imposed by other portions of this code.

(c) General requirements for setback lines.

- (1) Setbacks from property lines. Minimum setbacks from property lines are defined for each zoning district.
- (2) Setbacks from water bodies. Minimum setbacks from water bodies including the Gulf of Mexico are provided in § 34-638(d)(3).

Sec. 34-663. Building frontages and lot frontages.

Building frontage is the length of a building facade that faces a street. Building frontages and lot frontages are illustrated on Figure 34-5.

Sec. 34-664. Commercial design standards.

Except where this code specifically provides otherwise, the commercial design standards (see § 34-991–1010) apply in all redevelopment zoning districts to all commercial and mixed-use buildings or portions thereof that are being newly built, and to “substantial improvements” to such buildings as defined in § 6-405.

Sec. 34-665. Reserved.




Figure 34-5

Sec. 34-666. Property development regulations.

In all redevelopment zoning districts, land use is controlled through the more specific property development regulations that are provided in the remainder of this division.

Secs. 34-667--34-670. Reserved.

DOWNTOWN

Subdivision II. DOWNTOWN Zoning District

Sec. 34-671. Purpose.

The purpose of the DOWNTOWN district is create the desired quality and character for the center of pedestrian-oriented commercial activities within the town. New commercial buildings are expected to accommodate pedestrians by providing storefronts near sidewalks and by offering shade and shelter along major streets. Old San Carlos Boulevard will serve as the town's "Main Street" and will be anchored by pedestrian plazas at each end.

Properties that have been zoned into a planned development (PD) district are governed by the terms of the PD zoning resolution rather than the requirements of the DOWNTOWN district, even if the property is shown on Figure 34-6.

(b) Streets have been categorized into primary streets, secondary streets, and pedestrian plazas to guide the regulations for properties fronting each type of street.

Sec. 34-672. District map and applicability.

(a) The area indicated on Figure 34-6 is the outer perimeter of the DOWNTOWN district.

Sec. 34-673. Allowable uses.

In the DOWNTOWN district, allowable uses are defined in Table 34-2.




Figure 34-6

DOWNTOWN

Sec. 34-674. Building placement.

(a) **Build-to lines established.** Build-to lines (see § 34-662) vary according to the streets and street types designated on Figure 34-6.

- (1) Build-to lines for all streets are 5 feet to 10 feet from front property lines, except:
 - a. Build-to lines are 0 feet for Old San Carlos Boulevard, all properties facing the Times Square and Bayfront pedestrian plazas, and Estero Boulevard west of the Sky Bridge.
 - b. Built-to lines are 0 to 5 feet for all of First, Second, Third, and Fifth, and the south side of Estero Boulevard from the Sky Bridge to Miramar Street.
- (2) The adjustments to build-to lines to maintain visibility that are required by § 34-662(b)(4) do not apply:
 - a. to building fronts facing the Times Square or Bayfront pedestrian plazas, or
 - b. to building fronts along Old San Carlos Boulevard, where wide sidewalks and on-street parking lanes will allow the necessary visibility.
- (3) Awnings, canopies, and marquees over sidewalks and pedestrian walkways are encouraged by the commercial design standards (§§ 34-991–1010) and are required along Old San Carlos Boulevard.
- (4) Enclosed habitable space may also be allowed over a public right-of-way if located over an arcade or colonnade that shades a public sidewalk (see § 34-995(e)(6)), provided that specific permission is granted by the Town of Fort Myers Beach.

(b) **Setback lines established.** Setback lines (see § 34-662) are established as follows:

- (1) For principal buildings:
 - a. Minimum rear setbacks are 25 feet from rear property lines, except as follows:
 1. In Times Square, as defined on Figure 34-6, the minimum rear setback is 10 feet.
 2. In areas where parking garages could be built, as defined on Figure 34-7, buildings shall be placed so as not to preclude future parking garages from being built on the interiors of these blocks. Along Old San Carlos Boulevard blocks with potential parking

garages, this requirement means that principal buildings shall not extend further to the rear of lots than 50 feet back from the right-of-way for Old San Carlos Boulevard.

3. Minimum (rear) setbacks of 25 feet shall also be observed along those portions of properties abutting the town-owned parking lot between Old Carlos Boulevard and the Sky Bridge that had been platted as “Center Street” in Plat Book 9, Page 9.
 - b. Minimum side setbacks are 5 feet from side property lines, except they may be 0 feet for properties fronting on Old San Carlos, Estero Boulevard, and in Times Square (see also § 34-674(b)(1)c).
 - c. Minimum setbacks from water bodies are set forth in § 34-638(d)(3).
- (2) For accessory structures, minimum setbacks are set forth in § 34-1171–1176.

Sec. 34-675. Building size.

(a) **Building frontage.** Building frontage limits (see § 34-663) vary according to the street types designated on Figure 34-6:

- (1) For pedestrian plazas and primary streets except for Crescent Street and for Fifth Avenue east of the Sky Bridge, building frontages shall be at least 70% of the lot frontage.
- (2) For all other streets, building frontages shall be at least 35% of the lot frontage.
- (3) For multiple adjoining lots under single control, or for a single lot with multiple buildings, the percentages above apply to the combination of lot(s) and building(s).
- (4) **Exception for properties between Estero Boulevard and the Gulf:** The required building frontage percentage may be reduced to 35% for properties between Estero Boulevard and the Gulf of Mexico provided that the open space thus created allows open views to the Gulf of Mexico.

DOWNTOWN

(b) *Building height.* Building heights (see § 34-631) shall be limited to:

- (1) For properties that front on the following streets, a maximum of 30 feet above base flood elevation and no taller than two stories:
 - a. Times Square and Bayfront pedestrian plazas (see Figure 34-6)
 - b. North side of First Street
 - c. South side of Estero Boulevard between Old San Carlos Boulevard and the main pedestrian crossing
 - d. Carolina Avenue
- (2) For properties that front on the following streets, a maximum of 30 feet above base flood elevation and no taller than two stories, except that an elevated building without enclosed space on the first story may be three stories tall (but still limited to 30 feet above base flood elevation):
 - a. Lagoon Street
 - b. Crescent Street
 - c. First, Second, Third, and Fifth (east of the Sky Bridge only)
 - d. North side of Estero Boulevard west of Old San Carlos Boulevard and east of Crescent Street
 - e. Primo Drive
 - f. Palermo Circle
 - g. Miramar Street, north of Estero
 - h. Ohio Avenue
 - i. Virginia Avenue
- (3) For properties that front on the following streets, a maximum of 40 feet above base flood elevation and no taller than three stories:
 - a. Old San Carlos Boulevard between Fifth and First Streets
 - b. South side of First and both sides of Second and Third (west of the Sky Bridge only)
 - c. South side of Estero Boulevard east of the main pedestrian crossing
 - d. Canal Street
 - e. Avenues A, C, E, and I
 - f. Alva Drive
 - g. Miramar Street, south of Estero
 - h. Palm Avenue

(c) *Floor area ratio (FAR).* Floor area ratios (see § 34-633) shall not exceed:

- (1) 1.8 for properties fronting on Old San Carlos between Fifth and First Streets and fronting on the Times Square pedestrian plaza (see Figure 34-6).
 - (2) 1.4 for properties fronting on Estero Boulevard and fronting on the Bayfront pedestrian plazas.
 - (3) 1.0 for all other properties in the DOWNTOWN district.
- (d) *Hotel rooms.***
- (1) Along both sides of Old San Carlos Boulevard (properties between Fifth and First Streets that lie within 200 feet east and west of the centerline of Old San Carlos only), a property owner may substitute hotel rooms for allowable office space on upper floors without the limitations otherwise provided by the hotel-room equivalency factor found in § 34-1802. However, these hotel rooms must have at least 250 square feet per rentable unit.
 - (2) In all other properties in the DOWNTOWN district, the number of hotel rooms are limited by the hotel-room equivalency factor found in § 34-1802.

Sec. 34-676. Circulation and parking.

(a) *Off-street parking reductions.* The DOWNTOWN district is planned as a “park-once” district, with preference given to pedestrian movement within the district. On-street parking will be provided by the town along Old San Carlos Boulevard and other public parking is available under the Sky Bridge. For these reasons, substantial reductions are allowed to the normal off-street parking requirements found in § 34-2020. The follow percentages shall be multiplied by the number of off-street parking spaces normally required by § 34-2020 to determine the adjusted off-street parking requirements along various streets in the DOWNTOWN district:

- (1) Old San Carlos Boulevard, multiply by 50%.
- (2) Times Square and Bayfront pedestrian plazas (see Figure 34-6), multiply by 0% for existing building space and multiply by 50% for new building space. No parking spaces may be provided in the Times Square or Bayfront pedestrian plazas, but the required

DOWNTOWN

spaces must be located within 750 feet in single-purpose, shared, or joint-use parking lots (see division 26 of this chapter).

- (3) All other streets in the DOWNTOWN district, and all land on Crescent Street regardless of zoning district, multiply by 67%.

(b) *Parking lot locations.* Off-street parking lots shall be placed in rear yards (see Figure 34-5).

- (1) Off-street parking lots are not permitted in front yards or side yards, except they may be placed in the side yards of buildings on properties that front the beach side of Estero Boulevard if the unbuilt area thus created allows open views to the Gulf of Mexico.
- (2) Off-street parking may be provided under commercial or mixed-use buildings along Old San Carlos Boulevard provided that all under-building parking spaces are separated from sidewalks by usable commercial space at least 20 feet deep that meets all commercial building design guidelines in §§ 34-991–1010. Off-street parking may be provided under commercial or mixed-use buildings at other locations in accordance with § 34-992(c).

(c) *Parking lot interconnections.* Rear-yard parking lots on properties fronting along Old San Carlos Boulevard shall be interconnected to eliminate or minimize driveways to Old San Carlos Boulevard.

- (1) To ensure the effective use of these connections, the first to develop shall be required to make an irrevocable offer of cross-access to the adjacent parcel (prior to issuance of a development order), and must design and build the parking lot to accommodate cross-access.
- (2) When adjacent owners seek development orders, they will also be required to reciprocate with a similar cross-access agreements and then must complete the physical connection.
- (3) Individual property owners shall control all rights to the use of their own parking spaces, but may choose to allow wider use of these spaces for a fee of their choosing or through reciprocal arrangements with other parties.

(d) *Driveway connections.*

- (1) *Properties fronting on Estero Boulevard.* Existing driveways and parking spaces shall be relocated from Estero Boulevard to secondary streets, and new driveways shall connect only to secondary streets, except where these requirements would prohibit all reasonable access to a property.
- (2) *Properties fronting on other primary streets.*
 - a. For properties fronting primary streets other than Estero Boulevard, driveways should be connected to secondary streets whenever possible.
 - b. When a driveway onto a primary street is unavoidable, the driveway shall be shared with an adjoining property if that property also has access only to that primary street. Otherwise, the driveway shall be spaced as far as practical from other driveways or intersections.
- (3) *Properties fronting only on secondary streets.* Driveways may be connected to secondary streets, existing easements, or alleys.
- (4) *Properties adjoining pedestrian plazas.* Driveways and other vehicular access shall not be provided from pedestrian plazas.

DOWNTOWN

(e) **Parking garages.** The town has identified three potential locations for mid-block parking garages through its Old San Carlos Boulevard / Crescent Street Master Plan.

(1) Each potential location is indicated in black on Figure 34-7. Construction of these parking garages is not required by this code, but the regulations for the DOWNTOWN district are designed to place new buildings on these sites so that they will not block a parking garage from being built there in the future.




Figure 34-7

(2) All levels of parking garages must be separated from primary streets and pedestrian plazas by a liner building that provides usable building space at least 20 feet deep (see Figure 34-8).

- a. Liner buildings must be two stories or more in height and must be at least as tall as the parking garage.
- b. Liner buildings may be detached from or attached to the parking garage.
- c. Parking garages and their liner buildings are required to meet the commercial design standards (see §§ 34-991-1010).

(3) Access to a parking garage may be provided as follows:

- a. Access to a secondary street or road easement is preferred.




Figure 34-8

b. Access to a primary street is not permitted except in unusual circumstances where no other access is feasible and when approved as a variance or deviation to this code.

c. Access may not be provided across a pedestrian plaza.

(4) Parking garages can be approved only by rezoning to the Commercial Planned Development zoning district.

(f) **Drive-through lanes.** Drive-through lanes are generally not allowed in the DOWNTOWN district because traffic generated by drive-through lanes harms a pedestrian environment. The only exception to this rule is that Type 1 drive-throughs (see definition in § 34-2) may be approved by special exception on the north side of Estero Boulevard east of Palermo Circle. In this situation, the number of drive-thru lanes is limited to two lanes, and they shall not be accessed directly, for either entrance or exit, from a separate driveway on Estero Boulevard; they may be accessed from any of the secondary streets or from a shared driveway on Estero Boulevard.

DOWNTOWN

Sec. 34-677. Additional requirements.

(a) ***Commercial design standards.*** The commercial design standards (§§ 34-991-1010) shall apply to all commercial and mixed-use buildings, or portions thereof, that are being newly built, and to “substantial improvements” to such buildings as defined in § 6-405.

(b) ***Open space and buffers.*** There are no minimum open space and buffer requirements in the DOWNTOWN district comparable to the standards found in ch. 10, except in three instances:

- (1) Portions of properties that lie east of Palermo Circle and more than 300 feet beyond the north edge of the Estero Boulevard right-of-way shall retain 50% of that portion as open space. This open space may be a stabilized sodded area useable for overflow parking.
- (2) Residential buffers are required between commercial or mixed-use buildings and single-family residential lots for properties on the north side of Estero Boulevard east of Palermo Circle. These buffers shall be constructed in accordance with the buffer requirements of ch. 10 of this code.
- (3) Buffers are required between any off-street parking lot and a public street in accordance with the buffer requirements of ch. 10 of this code.

(c) ***Outdoor sales.*** Merchandise may be sold outdoors in the Downtown zoning district only in accordance with this subsection:

- (1) ***On private property.*** Retail businesses may sell their regular merchandise outdoors on private property between their stores and a street right-of-way on raised porches or on up to two wheeled vending carts that meet the following criteria:
 - a. Carts may contain no signage whatever;
 - b. Carts must be non-motorized, moveable by hand, and no taller than 10 feet;
 - c. Carts must be moved indoors during any hours that the business is not open; and
 - d. Carts shall have integral roofs or umbrellas and use traditional or creative designs. Figure 34-9 shows two suggested cart designs.




Figure 34-9

- (2) ***On public property.*** Retail businesses may extend their operations onto public sidewalks and plazas only as follows:
 - a. These provisions are limited to the Times Square pedestrian plaza (see Figure 34-6), along both sides of Old San Carlos Boulevard, and other locations if explicitly approved by the town council.
 - b. Vending rights are available only to the owner or primary lessee of the private property that immediately abuts the sidewalk or pedestrian plaza; vending rights may not be further sub-leased.
 - c. Vending rights can be used only in the area directly in front of the private property and lying between 90-degree extensions of the side property lines.
 - d. No fixed or moveable equipment may be placed on a public sidewalk or plaza to sell or serve food except as follows:
 1. Tables, umbrellas, and chairs may be placed by restaurants for the use of their customers; no signage is permitted except lettering on umbrellas up to 8 inches in height.
 2. Wheeled food carts are permitted if they meet the following criteria:
 - a- Carts must meet the criteria found in § 34-677(c)(1)b-d;
 - b- Not more than one chair or stool may be provided for the employee; and
 - c- One sign per side of cart may be displayed, with each sign limited to 3 square feet in area.
 3. Along Old San Carlos Boulevard, all tables and carts shall be placed only on the 5-foot bricked furnishing zone

DOWNTOWN

adjoining the curb and shall not otherwise block pedestrian movement along the sidewalk.

e. No merchandise may be displayed on a public sidewalk or plaza except when placed on tables or shelves that are moved indoors during any hours the business is not open and that do not exceed the following dimensions:

1. Maximum height: 3 feet
2. Maximum width parallel to right-of-way line: 8 feet
3. Maximum depth: may not extend more than 2 feet beyond the right-of-way line onto the sidewalk or plaza.

f. Vending rights may be exercised only upon issuance of a permit by the town that sets forth the conditions of private use of a public sidewalk or plaza, including:

1. Additional restrictions on the degree which tables, umbrellas, chairs, and carts may interfere with pedestrian movement;
2. Restrictions on the extent to which food or merchandise not available in the abutting business may be sold;
3. Requirements for keeping the area surrounding the tables or carts from debris and refuse at all times;
4. Insurance requirements;
5. Payment of fees established by the town for vending rights;
6. Limitations on leasing of vending rights, if any; and
7. Other reasonable conditions as determined by the town, including full approval rights over the design of umbrellas, carts, tables, etc.

(d) Sandwich signs. [moved from § 34-1145(g)]

The Town's sign regulations are found in ch. 30 of the land development code, and additional guidance is provided through the design guidelines discussed in § 34-1143(c) above. With certain exceptions, signs in Fort Myers Beach must be placed on private property. In light of the urban character of the Fort Myers Beach Downtown District, Sandwich signs may be placed in the Downtown zoning district abutting or extending over public property such as sidewalks despite the general prohibition in § 30-45 of sandwich-board signs, "A" signs, or other types

of portable signs which are portable and readily movable from place to place. A business may place a single- or double-faced sandwich signs may be placed on the same premises as the business or on a sidewalks directly in front of the premises provided that the sign is placed indoors after business hours, is not illuminated, and, if placed on a public sidewalk, does not exceed 24 inches in width and a total of 6 square feet per side.

Secs. 34-678--34-680. Reserved.

SANTINI

Subdivision III. SANTINI Zoning District

Sec. 34-681. Purpose.

The purpose of the SANTINI district is to provide alternative futures for the Santini Marina Plaza, either a continuation of the current marina and shopping center or their transformation into a pedestrian-oriented neighborhood center.

- (1) The existing stores and marina in the SANTINI district may continue in full operation and may be renovated or redeveloped in accordance with § 34-682.
- (2) As an alternative, the SANTINI district provides a second set of regulations (in § 34-683) that would allow the transformation of the shopping center and marina into a pedestrian-oriented neighborhood center:
 - a. The SANTINI district can become a neighborhood center to serve visitors and the populous south end of the island in accordance with the design concepts in the Fort Myers Beach Comprehensive Plan (see Policies 3-C-1, 3-C-2, and 4-F-2-ii).
 - b. The site could support additional mixed-use buildings if provided with shared parking, a pattern of smaller blocks, and an urban plaza.
 - c. Full realization of this concept will require a partnership between the property owners and the town that will transform the adjoining portion of Estero Boulevard from a rural highway with deep swales into a street with shaded sidewalks and some on-street parking.

Sec. 34-682. District map and applicability.

The area indicated on Figure 34-10 is the outer boundary of the SANTINI district.

- (1) Properties that are zoned in a planned development (PD) district are governed by the terms of the PD zoning resolution rather than the requirements of the SANTINI district, even if the property is shown on Figure 34-10.




Figure 34-10

- (2) For properties zoned into the SANTINI district rather than in a PD district, the applicable regulations are as follows:
 - a. **Continued use of existing buildings.** The regulations in this subdivision apply to the continued use of existing buildings and structures for allowable uses as defined in Tables 34-1 and 34-2 for the SANTINI zoning district.
 - b. **Renovating, enlarging or replacing individual buildings.**
 1. Existing buildings may be renovated, enlarged, or replaced as follows:
 - a- Physical enlargement of existing buildings is permitted provided that the improvements do not constitute a "substantial improvement" as that term is defined in § 6-405 of this code, and
 - b- Replacements for existing buildings are permitted provided that they will not increase the existing floor area ratio, as that term is defined in § 34-633.

SANTINI

2. Renovations, enlargements, and replacements to existing buildings are governed by the regulations for the CM zoning district as provided in Table 34-3 and by the other limitations in this section.
3. The commercial design standards (§§ 34-991–1010) shall apply to all commercial and mixed-use buildings, or portions thereof, that are being newly built.
4. Any specific deviations granted by prior CPD resolutions shall remain in effect for properties that are zoned into the SANTINI district.

(3) **Transformation of existing businesses into a neighborhood center.** Physical enlargements of existing buildings that constitute a “substantial improvement” as that term is defined in § 6-405 must be in the form of a neighborhood center as described in § 34-683.

Sec. 34-683. Creation of neighborhood center.

(a) **Purpose.** This section provides detailed regulations for the transformation of existing businesses into a neighborhood center.

- (1) This transformation may be required by § 34-682(3) or may be chosen by any landowner in the SANTINI district.
- (2) Once this option is chosen or required, all subsections of § 34-683 become mandatory requirements, except where they are clearly inapplicable to a given portion of the property.

(b) **Agreement for streetscape improvements.** Landowners who choose to partially or fully develop their land in the SANTINI district into a neighborhood center may simultaneously request public streetscape improvements by entering into a development agreement with the town (see § 2-91–102).

- (a) This agreement would establish a public/private partnership for the necessary improvements, identifying responsibilities, timing, approximate costs, and funding.
- (2) This agreement would also contain a detailed plan for the redevelopment of the property

consistent with the regulations in the remainder of this section.

(c) **Allowable uses.** Allowable uses for the SANTINI zoning district are defined in Tables 34-1 and 34-2.

(d) **Streets.** Secondary streets and alleys shall be laid out and dedicated to the public generally in accordance with Figure 34-10 to improve circulation for vehicles and pedestrians.

(e) **Plazas.** An urban plaza at least 1/2 acre in size shall be provided along Estero Boulevard as a focal point for mixed-use buildings and as a public gathering place. This plaza may also be used for overflow parking.

(f) **Build-to lines established.** Build-to lines (see § 34-662) vary according to the streets and street types designated on Figure 34-10.

- (1) Build-to lines for all primary streets and streets surrounding the plaza are 0 feet to 5 feet.
- (2) Build-to lines for all secondary streets are 0 feet to 10 feet.
- (3) Awnings, canopies, and marquees over sidewalks and pedestrian walkways are encouraged by the commercial design standards (§ 34-991–1010), especially along Estero Boulevard.
- (4) Compliance with build-to lines is not required for buildings that are used for the storage of boats or for marina accessory uses, or for any buildings extend closer than 40 feet to the waterfront.
- (5) Buildings used for the storage of boats or cars must be separated from Estero Boulevard by a liner building that provides usable building space at least 20 feet deep (see example in Figure 34-8).
 - a. This requirement applies to all buildings that extend closer than 75 feet to Estero Boulevard.
 - b. Liner buildings must be two stories or more in height.
 - c. Liner buildings may be detached from or attached to building space used for the storage of boats or cars.
 - d. Liner buildings must be constructed simultaneously with those portions of

SANTINI

buildings that are subject to this requirement.

- e. Liner buildings and any visible portions of the principal facade of buildings that are used for the storage of boats or cars must meet the commercial design standards (see §§ 34-991–1010).

(g) **Setback lines.** No minimum setbacks are required (see § 34-662).

(h) **Building frontage.** Building frontage limits (see § 34-663) vary according to the street types designated on Figure 34-10:

- (1) For primary streets and streets surrounding the plaza, building frontages shall be at least 70% of the lot frontage.
- (2) For secondary streets, building frontages shall be at least 35% of the lot frontage.
- (3) For multiple adjoining lots under single control, or for a single lot with multiple buildings, the percentages above apply to the combination of lot(s) and building(s).
- (4) Phased redevelopment is permitted provided that a site plan is provided showing how the building frontage percentages will be met upon completion of the redevelopment

(i) **Building height.** Building heights (see § 34-631) shall be limited to:

- (1) For parcels immediately abutting a plaza of at least ½ acre in size and for parcels immediately abutting canals, a maximum of 40 feet above base flood elevation and no taller than three stories.
- (2) For all other parcels, a maximum of 30 feet above base flood elevation and no taller than two stories.

(j) **Floor area ratio (FAR).** Floor area ratios shall not exceed 1.0 (see § 34-633).

(k) **Residential density.** Residential units can be constructed in the SANTINI district up to the maximum density allowed by the Fort Myers Beach Comprehensive Plan.

(l) **Guest units.** Guest units may be substituted for dwelling units in accordance with the equivalency factors found in § 34-1802.

(m) **Reductions to minimum parking requirements.** Neighborhood centers are “park-once” districts with preference given to pedestrian movement. The number of parking spaces normally required by § 34-2020 shall be multiplied by 67% to determine the adjusted parking requirement for the SANTINI district. Adjoining on-street parking spaces may be counted toward this parking requirement.

(n) **Parking location.** Off-street parking may be provided under commercial or mixed-use buildings provided that:

- (1) All under-building parking spaces must be separated from primary streets and the plaza by usable commercial space at least 20 feet deep that meets all commercial design guidelines; and
- (2) Driveways leading to under-building parking spaces must connect to a driveway, secondary street, or alley, and may not be accessed from a primary street or pedestrian plaza.

(o) **Commercial design standards.** The commercial design standards (§§ 34-991–1010) shall apply to all commercial and mixed-use buildings, or portions thereof, that are being newly built, and to “substantial improvements” to such buildings as defined in § 6-405.

Secs. 34-684–34-690. Reserved.

VILLAGE

Subdivision IV. VILLAGE Zoning District

Sec. 34-691. Purpose.

The purpose of the VILLAGE district is to provide alternative futures for the Red Coconut and/or Gulf View Colony, either a continuation of the current land uses or their transformation into a traditional neighborhood pattern.

- (1) The existing residences and businesses in the VILLAGE district may continue in full operation and may be renovated in accordance with §§ 34-692 and 34-694.
- (2) As an alternative, the VILLAGE district provides a second set of regulations that would allow the transformation of either of the existing mobile home and recreational vehicle parks into more permanent and durable housing types in a traditional neighborhood pattern, in accordance with the design concepts in the Fort Myers Beach Comprehensive Plan.




Figure 34-11

Sec. 34-692. District map and applicability.

The area indicated on Figure 34-11 is the outer boundary of the VILLAGE district.

- (1) Properties that have been zoned into a planned development (PD) district are governed by the terms of the PD zoning resolution rather than the requirements of the VILLAGE district, even if the property is shown on Figure 34-11.
- (2) For properties zoned into the VILLAGE district rather than in a PD district, existing residences and businesses may continue in full operation and may be modified in accordance with the following regulations:
 - a. **Continued use of existing mobile homes and recreational vehicles.** The continued use of existing mobile homes and recreational vehicles is permitted in accordance with § 34-694 below.
 - b. **Continued use of and renovations, enlargements, or replacement of existing permanent buildings.**
 1. Existing permanent buildings may be renovated, enlarged, or replaced as follows:
 - a- Renovations and/or physical enlargement are permitted provided

the improvements do not constitute a “substantial improvement” as that term is defined in § 6-405 of this code; or

-b- Replacement buildings are permitted provided that they do not increase the existing floor area ratio, as that term is defined in § 34-633; or

-c- Other renovations, enlargements, and/or replacements are permitted provided they comply with those regulations for the CB zoning district that are found in §§ 34-704–34-706.

2. Allowable uses in these buildings are the same as provided in § 34-703(a) for the CB zoning district.

3. The commercial design standards (§§ 34-991–1010) shall apply to all commercial and mixed-use buildings that are visible from Estero Boulevard, or portions thereof, that are being newly built, and to “substantial improvements” to such buildings as defined in § 6-405.

VILLAGE

(3) Transformation of existing mobile home and recreational vehicle parks. Policies 3-A-5, 3-A-6, and 4-F-2-iii of the Fort Myers Beach Comprehensive Plan have authorized a pre-approved redevelopment option for land in the VILLAGE district.

- a. The following concepts are expected in this redevelopment process:
1. traditional neighborhood design emphasizing streets that are interconnected and dwellings with porches or balconies on the front, primary entrances visible from the street, and cars to the rear (except for on-street parking);
 2. detached houses or cottages (with optional accessory apartments) abutting existing single-family homes;
 3. low-rise townhouses or apartments allowed elsewhere on the site;
 4. walkable narrow streets with shade trees that double as view corridors to the Preserve and Gulf;
 5. open space that allows views to be maintained from Estero Boulevard to the Gulf;
 6. mixed commercial and residential uses along the Bay side of Estero Boulevard;
 7. quiet internal street connections to the north and south;
 8. significantly reduced density from the existing level of 27 RV/mobile homes per acre at the Red Coconut to a maximum level of 15 dwelling units per acre; and
 9. a site design that accommodates a publicly acquired access point to the Matanzas Pass Preserve.
- b. At the option of landowners in the VILLAGE district, a development order may be obtained to redevelop all or part of this property in accordance with the option described in more detail in § 34-693 and generally in accordance with either of the conceptual site plans found in the Community Design Element of the Fort Myers Beach Comprehensive Plan. Until such time as this development order is obtained, the regulations in § 34-693 shall have no effect.

Sec. 34-693. Regulations to obtain development order for pre-approved redevelopment option.

(a) Purpose. This section provides detailed regulations for the pre-approved redevelopment option if that option is chosen by landowners, as described in § 34-692(3).

(b) Allowable uses. Allowable uses in the VILLAGE district are defined in Tables 34-1 and 34-2. If a development order is issued pursuant to § 34-692(3), the additional uses in the “Open” subgroup of Table 34-1 for the residential, lodging, office, and retail groups will be permitted on property that is subject to the development order.

(c) Streets. Secondary streets shall be laid out and dedicated to the public generally in accordance with Figure 34-11 to improve circulation for vehicles and pedestrians.

- (1) Figure 34-11 provides two acceptable options for the new network of secondary streets.
- (2) Under either option, the street design must incorporate the extension of a through street from Donora Boulevard to Lovers Lane that will be permanently accessible by the public.

(d) View corridor. A view corridor at least 50 feet wide shall be provided between Estero Boulevard and the Gulf as a focal point for abutting buildings and as part of a prominent visual corridor to the water. This view corridor need not be available for public use.

(e) Build-to lines established. Build-to lines (see § 34-662) for all streets shall be 0 feet to 10 feet.

(f) Setback lines established. Setback lines (see § 34-662) are established as follows:

- (1) For principal buildings, minimum setbacks are as follows:
 - a. Rear setbacks: 20 feet
 - b. Water body setbacks: see § 34-638(d)(3).
- (2) For accessory structures, minimum setbacks are set forth in § 34-1171-1176.

(g) Building frontage. Building frontage limits (see § 34-663) vary according to the street types designated on Figure 34-11:

- (1) For primary streets, building frontages shall be at least 50% of the lot frontage. This

VILLAGE

percentage may be reduced to 35% for properties between Estero Boulevard and the Gulf of Mexico provided that the open space thus created allows open views to the Gulf.

- (2) For multiple adjoining lots under single control, or for a single lot with multiple buildings, the percentages above apply to the combination of lot(s) and building(s).

(h) **Building height.** Building heights (see § 34-631) shall be limited to:

- (1) For properties that front on the bay side of Estero Boulevard and all streets other than Estero Boulevard, a maximum of 30 feet above base flood elevation and no taller than two stories. However, for mixed-use buildings and for elevated buildings without enclosed space on the first story, the maximum height is three stories (but still limited to 30 feet above base flood elevation).
- (2) For properties that front on the beach side of Estero Boulevard, a maximum of 40 feet above base flood elevation and no taller than three stories.

(i) **Floor area ratio (FAR).** Floor area ratios shall not exceed 1.2.

(j) **Residential density.** Policy 4-F-2-iii of the Fort Myers Beach Comprehensive Plan allows up to 15 dwelling units per acre for redevelopment in accordance with this section. Any land used for roadway or access purposes may be included in this density computation.

(k) **Guest units.** Guest units may be substituted for dwelling units in accordance with the equivalency factors found in § 34-1802.

(l) **Circulation and parking.** Off-street parking may be provided under commercial or mixed-use buildings provided that:

- (1) All under-building parking spaces must be separated from primary streets and the plaza by usable commercial space at least 20 feet deep that meets all commercial building design guidelines; and
- (2) Driveways leading to under-building parking spaces must connect to a secondary street or an alley and may not be accessed from a primary street or pedestrian plaza.

(m) **Commercial design standards.** The commercial design standards (§§ 34-991–1010) shall apply to all commercial and mixed-use buildings that are visible from Estero Boulevard, or portions thereof, that are being newly built, and to “substantial improvements” to such buildings as defined in § 6-405.

Sec. 34-694. Regulations for existing mobile homes and recreational vehicles.

(a) **Definitions.** These phrases, when used in this subdivision, shall have the following meanings:

Park trailer means a transportable recreational vehicle which has a body width not exceeding 14 feet and which is built on a single chassis and is designed to provide seasonal or temporary living quarters when connected to utilities necessary for operation of installed fixtures and appliances. “Park trailers” have a statutory definition in F.S. § 320.01(b) which may change; the use of the term “park trailer” in this subdivision is intended to change with any such statutory changes so as to be consistent with state law.

Transient RV park means a recreational vehicle development designed, intended for, or used by relatively short-stay visitors (transient guests) who bring their transient recreational vehicle with them and remove it at the end of their visit. The individual recreational vehicle site is then ready for another visitor. [definition moved from § 34-2]

Transient recreational vehicle unit means a camping trailer, truck camper, motor home, or travel trailer, motor home, or van conversion (as those terms are defined by F.S. § 320.01(b)) which is brought to the transient recreational vehicle park by the user and is removed from the park at the end of the user’s visit. Park trailers are not considered to be transient recreational vehicles. [definition moved from § 34-2]

(b) **1987 site plan approvals.** Lee County approved site plans for Gulf View Colony and Red Coconut in 1987 to formally acknowledge the right to replace mobile homes and non-transient recreational vehicles in portions of each park in accordance with previous regulations. These site

VILLAGE

plans were approved in accordance with Lee County Ordinance 86-36. The Town of Fort Myers Beach will continue to recognize those rights, which are incorporated into the regulations set forth in this section.

- (1) Sites in Gulf View Colony and Red Coconut or lots located within a park shall not be reconfigured or reduced in dimension so as to increase the density for which the park was originally created. [relocated from § 34-3272(3)c.3]
- (2) No division of any parcel may be permitted which creates a lot with width, depth or area below the minimum requirements stated in this chapter, provided that Contiguous sites lots of record may be combined and redivided to create larger dimension sites lots as long as such recombination includes all parts of all sites lots, and existing allowable density is not increased, and all setback requirements are met. [previous sentence moved from § 34-3272(3)b]
- (3) Sec. 34-2351. Use as permanent residence. The use of a recreational vehicle or park trailer type unit by a permanent resident as a permanent residence, as the terms are defined in F.S. ch. 196, is has been expressly prohibited as of since September 16, 1985. Persons who have established permanent residency within a recreational vehicle park as of September 16, 1985, are exempt from the residency provisions of this section, provided that the proof of residency was established by an affidavit filed with the Lee County prior to October 31, 1985. [subsection moved from § 34-2351]
- (4) Permits shall also be issued for reroofing and roof repairs for any existing mobile home, park model, or recreational vehicle located within a mobile home or recreational vehicle park, regardless of lot size. [moved from § 34-3204]

(c) Gulf View Colony: A site plan for Gulf View Colony was approved by Lee County on February 11, 1987, which showed 59 mobile homes sites plus common recreational features. This plan was drawn by G. H. Taylor and was dated January 10, 1987.

- (1) Lee County approved the replacement of a mobile home or park trailer on all 59 sites. These sites were determined to have been in

compliance with regulations that were in effect at the time of their creation.

- (2) Replacement of mobile homes or park trailers on these sites must meet the following regulations:
 - a. All units mobile homes or recreational vehicles shall have a minimum separation of ten feet between units (body to body) and appurtenances thereto. Each unit shall be permitted to have eaves which encroach not more than one foot into the ten-foot separation. [subsection moved from § 34-3272(3)c.2]
 - b. Replacement mobile homes, park trailers, and additions must meet the floodplain elevation requirements of § 6-472(2), including the limitations on replacements where past flooding has caused "substantial damage" on specific sites.
 - c. A move-on permit must be obtained in accordance with § 34-1923 and the mobile home or park trailer must comply with the tie-down and skirting requirements of that section.
 - d. One freestanding storage shed or utility room, not exceeding 120 feet in floor area and ten feet in height, may be permitted in any type B (nontransient) park provided that:
 1. No storage shed or utility room shall be located closer than five feet to any side or rear lot line or closer than ten feet to any mobile home or park trailer recreational vehicle under separate ownership; and
 2. The shed or room is properly tied down and complies with all building code requirements. [moved from § 34-786(b)]
 - e. Additions to mobile homes or park trailers recreational vehicles may be permitted in nontransient parks on permanent recreational vehicles provided that:
 1. The addition shall not be located closer than five feet to any side or rear lot line or closer than ten feet to any mobile home, park trailer, or addition thereto under separate ownership. The individual recreational vehicle site meets or exceeds the minimum required lot size set forth in this division;

VILLAGE

2. The total floor area of any additions, excluding open decks and stair landings, shall not exceed the total floor area of the mobile home or park trailer, recreational vehicle, and
3. The maximum height of additions shall not exceed ~~one story~~ or the height of the mobile home or park trailer, recreational vehicle, whichever is less.
4. Open decks, up to 120 square feet in area, may be permitted provided all setback requirements are met. Stair landings that are incorporated into a deck shall be calculated in the square footage of the deck.
5. Stairs or stair landings, which are attached to an addition, and which are not incorporated into an open deck, may be permitted to encroach three feet into the side and rear setbacks. No stair landing shall exceed 12 square feet in area. *[moved from § 34-788]*

(d) **Red Coconut:** Parts of a site plan for the Red Coconut were approved by Lee County on June 2, 1987. This plan was drawn by David Depew and was dated May 20, 1987.

- (1) **Sites approved in 1987.** Lee County approved the replacement and potential enlargement of a mobile home or park trailer on each of the following sites: A7-A9, A12-A15, B12, B14-B16, C1, C7, D1, D2, D6, D8-D17, E1-E16, E18-E20, F1-F9, and G2-G12.
 - a. These sites were determined to have been in compliance with regulations that were in effect at the time of their creation.
 - b. Replacement mobile homes or park trailers on these sites must follow the same regulations as provided in § 34-694(c)(2); however, if a mobile home or park trailer incurs "substantial damage" as that term is defined in § 6-405, the landowner also has the option to merge that site into the transient RV park and use the site in accordance with § 34-694(d)(3).
- (2) **Sites not approved in 1987.** Some smaller sites that also contained a mobile home or non-transient recreational vehicle were not approved for larger units in 1987: AA, A1-A6, A10-A11, A16-A17, B1-B11, B13,

C2-C6a, C8-C10, D3-D5, D7-D7A, E17, K2, P2-P3, Z2-Z3, and 1-6 on the bay side of Estero Boulevard. Units on these sites may be replaced only by a unit of equal or smaller size, in accordance with the following regulations:

- a. Any mobile home or non-transient recreational vehicle unit which has been lawfully placed on these sites on any rental lot within any rental park, regardless whether the park has been converted to either cooperative or condominium ownership prior to June 25, 1986, may be replaced by a unit mobile home or park trailer of equal or smaller size. The director may use historical aerial photographs, or previous county or town permits if available, to verify that a replacement unit is not larger than a previous lawful unit, upon proof that the placement of the unit was lawful. Such proof may consist of copies of official tax records, tag registrations or county permits, or may be by affidavit or any other competent evidence. No additions which would cause the total size to exceed the size of the previous lawful unit will be permitted. *[moved from § 34-3204]*
- b. Replacement mobile homes and park trailers must meet the floodplain elevation requirements of § 34-694(c)(2)b; however, if a mobile home or park trailer incurs "substantial damage" as that term is defined in § 6-405, the landowner also has the option to merge that site into the transient RV park and use the site in accordance with § 34-694(d)(3).
- c. A move-on permit must be obtained in accordance with § 34-1923 and the mobile home or park trailer must comply with the tie-down and skirting requirements of that section.
- d. One storage shed or utility room may be permitted if in compliance with § 34-694(c)(2)d.
- e. Additions may not be constructed.
- (3) **Transient RV park.** The remainder of the sites shown on this plan may continue in operation as a transient RV park. These sites can be identified on the 1987 site plan as follows: on the Gulf of Mexico, sites 1-53; on

VILLAGE

the bay side of Estero Boulevard, sites CE1-CE7, CWOO-CW6, CRD, H1-H10, J1-J10, K1, K3-K18, L1-L4, M1-M4, N1-N14, P1, R1-R3, Y-Y-Y-Y, and Z1. The following regulations apply to these 147 sites:

- a. Transient recreational vehicles must comply with the floodplain regulations found in § 6-472(3).
- b. Additions may not be constructed onto transient recreational vehicles.
- c. Storage sheds and other accessory structures may not be placed on individual sites.
- d. All travel trailers, motor homes or camping trailers left unattended for more than two weeks during the months of June through December. For purposes of this section only, the term “unattended” shall be interpreted to mean that the owner of the unit has not provided for a person to be responsible for the unit in the event of a hurricane watch alert as set forth in the following subsection ~~(2)~~^b of this section. *[moved from § 34-762(2)i.2.a]*
- e. All travel trailers, motor homes or camping trailers shall be tied down within 48 hours of the issuance of a hurricane watch for the town county by the National Hurricane Center. Travel trailers, motor homes or camping trailers not tied down shall be removed from the county within 48 hours of such a hurricane watch, or placed within an approved off-lot storage area. *[moved from § 34-762(2)i.2.b]*

Secs. 34-695--34-700. Reserved.

CB (Commercial Boulevard)

Subdivision V. CB Zoning District

Sec. 34-701. Purpose.

The purpose of the CB (Commercial Boulevard) district is provide standards for existing commercial uses and certain other uses along those portions of Estero Boulevard where the “Boulevard” classification of the Fort Myers Beach Comprehensive Plan promotes a mixed-use development pattern.

Sec. 34-702. Applicability.

(a) *Continued use.* The regulations in this subdivision apply to the continued use of existing buildings and structures for allowable uses as defined in § 34-703 on all properties zoned CB.

(b) *Enlarging or replacing buildings for existing commercial uses.* The regulations in this subdivision also apply to the following activities:

- (1) Physical enlargement of buildings or structures housing existing commercial uses, provided that the improvements do not constitute a “substantial improvement” as that term is defined in § 6-405 of this code, and
- (2) Replacement buildings for existing commercial uses that will not increase the existing floor area ratio, as that term is defined in § 34-633.

(c) *Enlarging or replacing buildings for all other allowable uses.* The regulations in this subdivision also apply to the physical enlargement of and replacement buildings for all allowable uses other than existing commercial uses (which are governed by subsection (b)) or new or expanded commercial uses (which are governed by subsection (d)).

(d) *New or expanded commercial uses.* In accordance with Policies 4-B-5 and 4-C-3-iv of the Fort Myers Beach Comprehensive Plan:

- (1) New or expanded commercial uses in the “Boulevard” category of the Fort Myers Beach Comprehensive Plan require rezoning as a Commercial Planned Development (see § 34-951).
- (2) Physical enlargements of existing commercial buildings that constitute a

“substantial improvement” as that term is defined in § 6-405 also require rezoning as a Commercial Planned Development.

- (3) For purposes of this section only, the following types of re-use of existing floor area shall be deemed a continuation of an existing commercial use rather than a new or expanded commercial use:
 - a. an existing office use converted to another office use;
 - b. an existing retail use converted to another retail use or to an office use;
 - c. an existing restaurant converted to another restaurant or to a retail or office use;
 - d. an existing bar or cocktail lounge converted to another bar or cocktail lounge or to a restaurant, retail, or office use.

Sec. 34-703. Allowable uses.

(a) In the CB district, allowable uses are defined as any of the following:

- (1) Those uses defined in Table 34-2 for the CB district;
- (2) Continuation of commercial uses that were lawfully existing on March 3, 2003; and
- (3) Those additional commercial uses of existing floor space as provided by § 34-702(d)(3).

(b) Any landowner wishing to place other new or expanded commercial uses on property that is zoned CB must rezone the property to Commercial Planned Development.

(c) Any landowner wishing to subdivide land that is zoned CB into residential homesites must comply with all of the setback, lot size, intensity, and density regulations for the RC zoning district as described in Table 34-3. Compliance with these regulations shall substitute for the building placement standards that are found in § 34-704 and for the intensity standard found in § 34-705(c).

Sec. 34-704. Building placement.

(a) *Build-to lines established.* Build-to lines (see § 34-662) for Estero Boulevard are established at 5 to 10 feet from front property lines. Awnings, canopies, and marquees over sidewalks and pedestrian walkways are encouraged by the commercial design standards (§§ 34-991–1010).

CB (Commercial Boulevard)

(b) **Setback lines established.** Setback lines (see § 34-662) are established as follows:

- (1) For principal buildings:
 - a. Minimum street setbacks for all streets other than Estero Boulevard are 10 feet.
 - b. Minimum rear setbacks are 20 feet from rear property lines.
 - c. Minimum side setbacks are 5 feet from side property lines.
 - d. Minimum setbacks from water bodies are set forth in § 34-638(d)(3).
- (2) For accessory structures, minimum setbacks are set forth in § 34-1171-1176.

Sec. 34-705. Building size.

(a) **Building frontage.** Building frontage limits (see § 34-663) are established as follows:

- (1) For Estero Boulevard, building frontages shall be at least 50% of the lot frontage. This percentage may be reduced to 35% for properties between Estero Boulevard and the Gulf of Mexico provided that the open space thus created allows open views to the Gulf of Mexico.
- (2) For multiple adjoining lots under single control, or for a single lot with multiple buildings, the percentages above apply to the combination of lot(s) and building(s).

(b) **Building height.** Building heights (see § 34-631) shall be limited to:

- (1) For properties that front on the bay side of Estero Boulevard and all streets other than Estero Boulevard, a maximum of 30 feet above base flood elevation and no taller than two stories, except that an elevated building without enclosed space on the first story may be three stories tall (but still limited to 30 feet above base flood elevation).
- (2) For properties that front on the beach side of Estero Boulevard, a maximum of 40 feet above base flood elevation and no taller than three stories.

(c) **Floor area ratio (FAR).** Floor area ratios (see § 34-633) shall not exceed 1.0.

Sec. 34-706. Circulation and parking.

(a) **Parking lot locations.** Off-street parking lots shall be placed in side or rear yards (see Figure 34-5). Off-street parking lots are not permitted in front yards.

(b) **Under-building parking.** Off-street parking may be provided *under* commercial or mixed-use buildings provided that all under-building parking spaces are screened in accordance with § 34-992(a)(2).

(c) **Parking lot interconnections.** Wherever physically possible, parking lots for abutting properties fronting along Estero Boulevard shall be interconnected to eliminate or minimize driveways to Estero Boulevard.

- (1) To ensure the effective use of these connections, the first to develop shall be required to make an irrevocable offer of cross-access to the adjacent parcel (prior to issuance of a development order), and must design and build the parking lot to accommodate cross-access.
- (2) When adjacent owners seek development orders, they will also be required to reciprocate with a similar cross-access agreements and then must complete the physical connection.
- (3) Individual property owners shall control all rights to the use of their own parking spaces, but may choose to allow wider use of these spaces for a fee of their choosing or through reciprocal arrangements with other parties.

(d) **Driveway connections for properties fronting on Estero Boulevard.** Existing driveways and parking spaces shall be relocated from Estero Boulevard to other streets and new driveways shall connect only to other streets, except where these requirements would prohibit all reasonable access to a property. When a driveway onto Estero Boulevard is unavoidable, the driveway shall be shared with an adjoining property if that property also has access only to Estero Boulevard. Otherwise, the driveway shall be spaced as far as practical from other driveways or intersections.

CB (Commercial Boulevard)

Sec. 34-707. Commercial design standards.

The commercial design standards (§§ 34-991–1010) shall apply to all commercial and mixed-use buildings, or portions thereof, that are being newly built, and to “substantial improvements” to such buildings as defined in § 6-405.

Secs. 34-708--34-930. Reserved.

Planned Development Zoning Districts

~~DIVISION 2. AGRICULTURAL DISTRICTS
[deleted in its entirety]~~

~~DIVISION 3. RESIDENTIAL DISTRICTS
[deleted in its entirety]~~

~~DIVISION 4. RECREATIONAL
VEHICLE PARK DISTRICTS
[deleted in its entirety]~~

~~DIVISION 5. COMMUNITY
FACILITIES DISTRICTS
[deleted in its entirety]~~

~~DIVISION 6. COMMERCIAL DISTRICTS
[deleted in its entirety]~~

~~DIVISION 7. MARINE-
ORIENTED DISTRICTS
[deleted in its entirety]~~

~~DIVISION 8. INDUSTRIAL DISTRICTS
[deleted in its entirety]~~

DIVISION 6 9. PLANNED DEVELOPMENT ZONING DISTRICTS

Subdivision I. Generally

Sec. 34-931. Purpose and effect intent.

(a) **Purpose. Generally.** The general purpose and intent of the various planned development zoning districts is to provide a degree of flexibility for a landowner to propose the development of land in a manner that differs from the specific provisions of this code, and to allow the town council the ability to evaluate such a proposal relative to specific conditions on and around the site and as to its compliance with the Fort Myers Beach Comprehensive Plan, set forth in § 34-612(2). The purpose and intent of specific planned development districts is set forth in subsections (b) through (g) of this section. *[existing subsections (b)-(g) deleted]*

(b) **Effect.** A planned development, once approved through the rezoning process, can only be developed in accordance with the specific master concept plan and special conditions that are contained in the zoning resolution approving the

planned development. See §§ 34-217–220 for details on the effect of planned development zoning.

Sec. 34-932. Regulation of land use in planned developments.

(a) **General requirements and special conditions.**

All uses of land, water, and structures permitted in a planned development shall be subject to:

- (1) the general requirements for planned developments,
- (2) all applicable regulations in this code, except where approval is granted to deviate from one or more of those regulations,

- (3) an adopted master concept plan, and
- (4) various special conditions, ~~as required.~~ (b) Special conditions which may be formulated and applied to address unique aspects of the parcel in the protection of a bona fide public interest:

a. The source of such conditions restrictions may include good planning practice as well as those specifications set forth in the application documents, plus policies and standards set forth in the Fort Myers Beach Comprehensive ~~Lee~~ Plan.

b. ~~(c)~~ All special conditions shall be reasonably related to the proposed development and to any reasonably expected impacts on public services and facilities and the public safety, health, and general welfare. ~~Such special conditions should be pertinent to the mitigation of these impacts.~~

c. ~~All~~ Special conditions shall be adopted as part of the zoning resolution approving and as an appendix to the approved master concept plan which governs the planned development.

~~(d)~~ The standards for use and development of a planned development shall be set forth in the documentation attached to the master concept plan; and, unless modified through the schedule of deviations, where applicable (see § 34-412), such standards shall not be less restrictive than the minimum standards set forth elsewhere in this chapter or other applicable development regulations.

~~Sec. 34-412. Deviations from general zoning regulations.~~ (a) Except where specifically

Planned Development Zoning Districts

suspended or preempted by alternative regulations in this article, or by special conditions adopted to the master concept plan, all general provisions of this chapter shall apply to any planned development. However, to provide

(b) Deviations. To allow design flexibility in developing land through this article, deviations from specific the general provisions of this code chapter, as well as from any separate land development regulation or code, may be permitted where it can be demonstrated in the process of reviewing the concept plan that the planned development will be enhanced and that the intent of such regulations to protect health, safety, and welfare will be served. Other portions of this code may provide additional criteria for certain deviations (for example, see § 34-992(e) regarding deviations from commercial design standards). No deviation may be granted that is inconsistent with the comprehensive plan.

- (1) Such Requested deviations shall be set forth in a separate schedule on the master concept plan or in the application and shall be accompanied by documentation including sample detail drawings, illustrating how each deviation would operate to the benefit, or at least not to the detriment, of the public interest.
- (2) Approved deviations shall be adopted as part of the zoning resolution approving the planned development, set forth as part of the documentation attached to the master concept plan. (b) Deviations may be permitted by this procedure to general or specific standards set forth in this chapter, chapter 10 when specifically requested and approved on the master concept plan, and other development ordinances.

(c) Sec. 34-413: Density or intensity of use. Density or intensity of use permitted in any planned development shall be determined by the town council in the zoning resolution on a case-by-case basis in accordance with the following:

- (1) The range of density or intensity of or the uses permitted or encouraged under the Fort Myers Beach Comprehensive Lee Plan at that location, and
- (2) The availability of adequate capacity of all public facilities and services (in order of precedence, roads, water, sewer, surface

water management, public safety, schools and other public services);

- (3) The level of public services to be provided by the development, and
- (2) ~~(4)~~ The nature of and the density and intensity of existing or proposed development surrounding the project.

In no case, however, shall the density of a planned development be permitted to exceed six units per acre in areas designated as rural or open lands by the Lee Plan.

(d) Phasing. The town council may specify a phasing plan in the resolution in accordance with § 34-220.

(e) Other requirements for planned developments.

- (1) Specific application requirements for planned development zoning districts are set forth in § 34-212-215.
- (2) Procedures to amend a planned development zoning district are set forth in § 34-214 and 34-219.
- (3) Other requirements for planned developments are found in §§ 34-211-410.

Sec. 34-933. Allowable uses of land.

(a) (c) Areas devoted to various uses shall be designated on the concept plan. The application for a planned development shall include a schedule detailing the uses desired; Proposed principal and accessory land uses must be listed on the proposed master concept plan, identifying such uses by citing the same uses allowed by a specific zoning district, or by citing the enumerated uses of one or more use groups or sub-groups as found in Tables 34-1 and 34-2 of this article, conventional zoning districts, use activity groups (§ 34-622), and defined uses (§ 34-2). Approved planned developments that used a different method for enumerating uses shall be interpreted in accordance with the use regulations in effect at the time of that approval.

Sec. 34-933. Permitted uses. Except as specifically indicated to the contrary, the uses listed in § 34-934, pertaining to use regulations for planned development districts, may be permitted in the indicated districts when consistent with the goals, objectives, and policies of the Lee Plan for the land

Planned Development Zoning Districts

use category in which the property is located, and when approved on the enumerated documentation of the master concept plan.

(b) Approved uses shall be adopted as part of the zoning resolution approving the planned development. Uses that are not specifically listed in § 34-934 may also be permitted if, in the opinion of the director, they the uses and their expected impacts are substantially similar to an approved listed permitted use.

Secs. 34-934--34-940. Reserved.

Sec. 34-934. Use regulations table.

Use regulations for planned development districts are as follows:

TABLE 34-934. USE REGULATIONS FOR PLANNED DEVELOPMENT DISTRICTS
[table deleted in its entirety]

Sec. 34-935. Property development regulations:

(a) Minimum area for planned developments.
[deleted in its entirety]

(b) Minimum setbacks of structures, buildings and pavement from development perimeter boundaries. *[deleted in its entirety]*

(c) Uses permitted within required perimeter setback. *[deleted in its entirety]*

(d) Developments on Pine Island. *[deleted in its entirety]*

(e) Minimum lot size, dimensions and setbacks.
[deleted in its entirety]

(f) Height of buildings. *[deleted in its entirety]*

(g) Open space. *[deleted in its entirety]*

Sec. 34-936. General conditions for all land uses.
[deleted in its entirety]

Sec. 34-937. Commercial uses in RPD and MHPD districts. *[deleted in its entirety]*

Sec. 34-938. Industrial uses in CPD district.
[deleted in its entirety]

Sec. 34-939. Recreational vehicle planned developments. *[deleted in its entirety]*

Sec. 34-940. Mixed use planned developments.
[deleted in its entirety]

Subdivision II. RPD (Residential Planned Development) Zoning District

Sec. 34-941. Intent of RPD (Residential Planned Development) zoning district.

The intent of the RPD district is to allow a landowner the ability to submit a specific proposal for a land development that is primarily residential in character and that complies with the Fort Myers Beach comprehensive plan, but which does not meet the specific requirements of a conventional or redevelopment zoning district.

Sec. 34-942. Allowable uses of land.

Allowable principal and accessory land uses in an RPD zoning district shall be established in each zoning resolution in accordance with § 34-933. Certain of the use sub-groups enumerated in Table 34-1 are not available in RPD zoning districts; see footnotes under Table 34-2.

Sec. 34-943. Building placement, size, design, and other property development regulations.

Building placement, size, design, and all other property development regulations in an RPD zoning district shall be the same as for the RM zoning district, unless the zoning resolution specifies otherwise. Exceptions are as follows:

- (1) Compliance with the master concept plan and any special conditions may provide additional restrictions.
- (2) Approved deviations may modify or eliminate restrictions that would otherwise apply.

Sec. 34-944--34-950. Reserved.

Planned Development Zoning Districts

Subdivision III. CPD (Commercial Planned Development) Zoning District

Sec. 34-951. Intent of CPD (Commercial Planned Development) zoning district.

The intent of the CPD district is to allow a landowner the ability to submit a specific proposal for a land development that is primarily non-residential or mixed-use in character and that complies with the Fort Myers Beach comprehensive plan, but which does not meet all of the specific requirements of a conventional or redevelopment zoning district.

Sec. 34-952. Allowable uses of land.

Allowable principal and accessory land uses in a CPD zoning district shall be established in each zoning resolution in accordance with § 34-933.

Sec. 34-953. Building placement, size, design, and other property development regulations.

Building placement, size, design, and all other property development regulations in a CPD zoning district shall be the same as for the CR zoning district for CPDs that are primarily lodging, or for the CB zoning district for all other CPDs, unless the zoning resolution specifies otherwise. Exceptions are as follows:

- (1) Compliance with the master concept plan and any special conditions may provide additional restrictions.
- (2) Approved deviations may modify or eliminate restrictions that would otherwise apply.

Sec. 34-954. Commercial design standards.

The commercial design standards (§§ 34-991–1010) shall apply to all commercial and mixed-use buildings or portions thereof that are being newly built, and to “substantial improvements” to such buildings as defined in § 6-405, on properties that are zoned CPD (commercial planned development).

Sec. 34-955–34-960. Reserved.

Subdivision IV. Former Planned Development Zoning Districts

Sec. 34-961. Former MPD zoning district.

The MPD (mixed-use planned development) zoning district had been assigned to certain developments which had received zoning approval prior to major amendments to this code. MPD zoning was automatically converted to CPD zoning through revisions to this chapter which became effective on March 3, 2003. All rights and restrictions previously authorized by MPD zoning resolutions remain in full force and effect after the conversion to CPD zoning.

DIVISION 10. SPECIAL PURPOSE DISTRICTS

Subdivision I. In General [deleted in its entirety]

Subdivision II. Environmentally Critical District [moved to § 34-652]

Subdivision III. Airport Hazard District [deleted in its entirety]

Subdivision IV. Planned Unit Development District

Sec. 34-1031. Applicability.

Sec. 34-962. Former PUD zoning district.

(a) The PUD (planned unit development) zoning district had been assigned to certain is intended to recognize and provide for those developments which had received preliminary or final approval as a planned unit development or which had been scheduled for a PUD hearing before the local planning agency prior to September 30, 1985. PUD zoning was automatically converted to CPD zoning through revisions to this chapter which became effective on March 3, 2003. All rights and restrictions previously authorized by PUD zoning resolutions remain in full force and effect after the conversion to CPD zoning. Subsequent to September 30, 1985, no application for preliminary approval of a development of a planned unit development shall be accepted: (b) Certain sections

Planned Development Zoning Districts

of the PUD district regulations are hereby retained so as to allow completion of these developments which have received preliminary approval prior to August 1, 1986. All other sections concerned with preapplication and preliminary approval procedures are stricken.

Sec. 34-963-34-990. Reserved.

~~Sec. 34-1032. Purpose and intent. [deleted in its entirety]~~

~~Sec. 34-1033. Definitions. [deleted in its entirety]~~

~~Sec. 34-1034. Conflicting provisions. [deleted in its entirety]~~

~~Sec. 34-1035. Compliance with other regulations. [deleted in its entirety]~~

~~Sec. 34-1036. Procedure for approval, effect of PUD zoning. [deleted in its entirety]~~

~~Sec. 34-1037. Contents of final development plan. [deleted in its entirety]~~

~~Sec. 34-1038. Changes to final development plan. [deleted in its entirety]~~

~~Sec. 34-1039. Amendments to built planned unit developments. [deleted in its entirety]~~

~~Sec. 34-1040. Area, density and setback requirements, permitted uses. [deleted in its entirety]~~

~~Sec. 34-1041. General development standards; required improvements. [deleted in its entirety]~~

~~Secs. 34-1042-34-1070. Reserved.~~

DIVISION 7.
COMMERCIAL DESIGN STANDARDS

Sec. 34-991. Purpose and intent.

The purposes of design regulations for commercial buildings include:

- (1) Encouraging traditional building forms that reinforce the pedestrian orientation and desired visual quality of the Town of Fort Myers Beach.
- (2) Creating usable outdoor space through the arrangement of compatible commercial buildings along street frontages.
- (3) Encouraging buildings of compatible type and scale to have creative ornamentation using varied architectural styles.
- (4) Enhancing the town's business districts as attractive destinations for recreation, entertainment, and shopping.
- (5) Maintaining and enhancing the town's sense of place and its property values.
- (6) Implementing the design concepts in the Fort Myers Beach Comprehensive Plan.

Sec. 34-992. Applicability and compliance.

(a) ***Applicability.*** Except where this code specifically provides otherwise, these commercial design standards apply to all commercial and mixed-use buildings or portions thereof that are being newly built, and to "substantial improvements" to such buildings as defined in § 6-405, on properties that are zoned in any of the following zoning districts:

- (1) SANTOS (§ 34-648);
- (2) DOWNTOWN (§ 34-671-680);
- (3) SANTINI (§ 34-681-690);
- (4) VILLAGE (§ 34-691-700);
- (5) CB (§ 34-701-710); and
- (6) CPD (commercial planned development) (§ 34-951-960), or that lie within the redevelopment overlay districts described in §§ 34-1141-1146.

(b) ~~(1)~~ Commercial buildings on properties with a ~~CPD~~ zoning resolution that incorporated specific architectural elevations shall be required to comply with these standards to the extent that the standards are not inconsistent with the approved elevations.

(c) ~~(2)~~ Commercial buildings such as hotels that will not contain commercial uses below base flood

elevation shall not be required to comply with the ground-floor window and retail standards except along Old San Carlos Boulevard (see § 34-676b). However, the principal facades of these buildings must screen underbuilding parking areas in a manner acceptable to the town manager or designee.

(d) ***Compliance determinations.*** Compliance with these standards shall be determined as follows:

- (1) An applicant may seek conceptual or final approval of a specific building and site design during the commercial planned development rezoning process (see § 34-931). The resolution approving a commercial planned development may include specific site plans and building elevations and shall specify the extent to which these plans and elevations have or have not been determined to meet these commercial design standards and whether any deviations to these standards have been granted.

(2) Unless final approval has been granted pursuant to subsection (1), the town manager shall make a determination of substantial compliance with these standards before a development order can be issued pursuant to ch. 10 of this code, or before a building permit can be issued if a development order is not applicable.

a. Compliance determinations of the town manager are administrative decisions which may be appealed in accordance with article II of this chapter.

b. The town manager shall provide written notice of each compliance determination to the town council within five calendar days. The town council, by majority vote at a public meeting within 30 days of the compliance determination, may file an appeal that will be heard by the town council in conformance with the procedures and standards in § 34-86.

c. Compliance determinations made by the town manager shall not become effective until the 30-day appeal period has passed without an appeal having been filed.

(e) ***Variances and deviations.*** Requests to vary from a substantive provision of these standards may be filed using the variance procedures and evaluated using the findings in § 34-87, or may be requested during planned development rezonings as a

deviation as described in § 34-932(b)(c). The following are acceptable justifications for variances or deviations from these commercial design standards (in addition to the general requirements of § 34-932(b)):

- (1) The proposed substitution of materials or function accomplishes substantially the same goals as the required provisions in these standards and would make an equal or greater contribution to the public realm of the Town of Fort Myers Beach; or
- (2) The proposed building is a civic building, which is expected to be more visually prominent than a typical commercial building; or
- (3) There are exceptional or extraordinary conditions that are inherent to the property in question, that do not apply generally to other nearby properties, and that are not the result of actions of the applicant.

Sec. 34-993. Definitions.

Arcade means a series of columns topped by arches that support a permanent roof over a sidewalk.

Awning means a flexible roof-like cover that extends out from an exterior wall and shields a window, doorway, sidewalk, or other space below from the elements.

Balcony means an open portion of an upper floor extending beyond (or indented into) a building's exterior wall.

Bay window means a series of windows which project beyond the wall of a building to form an alcove within.

Canopy means an awning-like projection from a wall that is made of rigid materials and is permanently attached to the principal facade of a building.

Civic building means a building that is allowed greater design flexibility due the prominence of its function and often its location. For purposes of these standards, civic buildings include buildings operated by governmental entities and certain privately owned buildings that serve religious, charitable, cultural, educational, or other public purposes.

Colonnade is similar to an arcade except that it is supported by vertical columns without arches.

Commercial building means, for purposes of these standards, any building used in whole or in part for any of the following uses: retail, office, hotel or motel rooms, institutional uses, commercial storage, restaurants, bars, and similar uses.

Cornice means a decorative horizontal feature that projects outward near the top of an exterior wall.

Courtyard means an unroofed area surrounded by buildings.

Expression line means a decorative horizontal feature that projects outward from an exterior wall to delineate the top of the first story of a building.

Facade, principal means the exterior wall of a building that is roughly parallel to a right-of-way or which faces a plaza or public park, and also that portion of a building's side wall that faces a pedestrian way or parking lot. Along the east side of Old San Carlos Boulevard only, the rear wall of buildings shall also be considered a principal facade whenever it is visible from the Matanzas Pass sky bridge.

Lintel means a structural or merely decorative horizontal member spanning a window opening.

Plaza means an unroofed public open space designed for pedestrians that is open to public sidewalks on at least one side.

Porch means a covered entrance to a building.

Sill means is a piece of wood, stone, concrete, or similar material protruding from the bottom of a window frame.

Stoop means a small elevated entrance platform or staircase leading to the entrance of a building.

Sec. 34-994. Exterior walls.

(a) *Generally*. These standards require commercial buildings to have traditional pedestrian-oriented exteriors and to be clad with typical Florida building materials that are durable and appropriate to the visual environment and climate. Design

flexibility and creativity is encouraged using ornamentation from a wide variety of architectural styles.

(b) **Finish materials for walls.** Exterior walls are the most visible part of most buildings. Their exterior finishes shall be as follows:

- (1) Any of the following materials may be used for exterior walls and for columns, arches, and piers:
 - i. Concrete block with stucco (CBS)
 - b. Reinforced concrete (with smooth finish or with stucco)
 - c. Natural stone or brick
 - d. Wood, pressure-treated or naturally decay-resistant species
- (2) Exterior walls may also be covered with fiber-reinforced cement panels or boards, or with cast (simulated) stone or brick.
- (3) Synthetic stucco (an exterior cladding system with a stucco-like outer finish applied over insulating boards) may be used as an exterior wall covering except on principal facades.
- (4) Other materials for exterior walls may be used only if approved as a deviation from this section through the planned development rezoning process or when explicit approval has been granted to vary from these regulations (see § 34-992).
- (5) Fastenings that are required to dry-floodproof the first story of commercial buildings shall be integrated into the design of principal facades or be visually unobtrusive.

(c) **Types of exterior walls.** Principal facades are defined in § 34-993 and their requirements are described in § 34-995. Exterior walls that are *not* defined as principal facades require a lesser degree of finish and transparency, but must meet the following requirements:

- (1) Transparent windows must cover at least 30% of the wall area below the expression line and at least 10% of the wall area between the expression line and the cornice.
- (2) All windows must have their glazing set back at least 3 inches from the surface plane of the wall, or set back at least 2 inches when wood frame construction is used.
- (3) Rectangular window openings shall be oriented vertically (except for transom windows).

Sec. 34-995. Principal facade walls.

(a) **Facade elements.** Principal facades are the primary faces of buildings. Being in full public view, they shall be given special architectural treatment.

- (1) All principal facades shall have a prominent cornice and expression line, a working entrance, and windows (except for side-wall facades where entrances are not required).




Figure 34-12

- (2) Buildings wider than 75 feet shall incorporate vertical elements in the principal facade to mimic smaller-scale development.
- (3) Principal facades facing a primary street, plaza, or public park may not have blank walls (without doors or windows) greater than 10 feet in length.
- (4) Expression lines and cornices shall be a decorative molding or jog in the surface plane of the building that extend at least 3 inches out from the principal facade, or a permanent canopy may serve as an expression line.
- (5) Awnings may not hide or substitute for required features such as expression lines and cornices.
- (6) Entrances and windows are addressed in subsections (b) and (c) below.

(b) **Entrances.** A primary entrance and views into the first floor of commercial buildings are fundamental to creating an interesting and safe pedestrian environment.

- (1) The primary entrance to all buildings shall face the street.
- (2) Corner buildings shall have their primary entrance face either the intersection or the street of greater importance.

- (3) Additional ground floor retail spaces within the same building shall all have their respective primary entrances face streets unless the retail spaces do not adjoin an exterior wall along a street.
- (4) Where building frontages exceed 50 feet, operable doors or entrances with public access shall be provided along streets at intervals averaging no greater than 50 feet.





Figure 34-13

(c) **Windows.** Every principal facade must contain transparent windows on each story.

(1) **All windows.**

- a. Rectangular window openings on principal facades shall be oriented vertically (except for transom windows).
- b. All windows must:
 - 1. contain visible sills and lintels on the exterior of the wall, and
 - 2. have their glazing set back at least 3 inches from the surface plane of the

wall, or set back at least 2 inches when wood frame construction is used.

- c. Glass in windows and doors, whether integrally tinted or with applied film, must transmit at least 50% of visible daylight.
- d. See § 34-995(e)(1) regarding awnings.

(2) **First-story windows.** In order to provide clear views inward and to provide natural surveillance of exterior spaces, the first story of every commercial building's principal facade shall have transparent windows meeting the following requirements:

- a. Window openings shall cover at least 60% of the wall area below the expression line;
- b. The bottoms of the window opening can be no higher than 30 inches from sidewalk level; and
- c. These windows shall be maintained so that they provide continuous view of interior spaces lit from within. Private interior spaces such as offices may use operable interior blinds for privacy.

(3) **Upper-story windows.**

- a. All stories above the first story of every commercial building's principal facade shall contain between 15% and 75% of the wall area with transparent windows.
- b. No single pane of glass may exceed 36 square feet in area.

(d) **Corner buildings.** For buildings located at the intersection of two streets, the corner of the building at the intersection may be angled, curved, or chamfered. The distance from the corner shall not exceed 20 feet measured from the intersection of the right-of-way lines to the end of the angled or curved wall segment, unless a greater amount is required by the visibility triangles in § 34-662(b)(4).

(e) **Facade projections.** Facade projections add visual interest to buildings. Some projections also provide protection from sun and rain for those passing by, others provide additional floor space for the building. The following types of facade projections are permitted as indicated below. At least one of these facade projections is required on each principal facade of all commercial buildings. Along both sides of Old San Carlos Boulevard, a continuous awning or canopy is required over the sidewalk except where the sidewalk is being shaded by an arcade or colonnade.

(1) Awnings and canopies:




Figure 34-14

- a. Awnings and canopies may extend forward of the build-to line (see § 34-662) and may encroach into a street right-of-way.
- b. Awning or canopies extending from the first story cannot exceed the following dimensions:
 - 1. Depth: 5 feet (minimum) and strongly overlapping the sidewalk, but no closer than 2 feet to an existing or planned curb (see § 34-995(e) regarding Old San Carlos Boulevard)
 - 2. Height: the lowest point on an awning or canopy shall be between 9 feet and 12 feet above sidewalk level
 - 3. Length: 25% to 100% of the front of the building
- c. There are no minimum or maximum dimensions for awnings or canopies extending from a second story or higher.
- d. Awnings shall be covered with fabric. High-gloss or plasticized fabrics are prohibited. Backlighting of awnings is prohibited.

(2) Balconies:




Figure 34-15

- a. Balconies may extend forward of the build-to line (see § 34-662) and may encroach into a street right-of-way.
- b. Balconies cannot exceed the following dimensions:
 - 1. Depth: 6 feet minimum for second story balconies; and no closer than 2 feet to the existing or planned curb
 - 2. Height: 10 feet minimum if overhanging a sidewalk
 - 3. Length: 25% to 100% of the front of the building
 - 4. Top of railing: 2-3/4" minimum
- c. Balconies may have roofs, but are required to be open, un-airconditioned parts of the buildings.
- d. On corners, balconies may wrap around to the side of the building.

(3) Bay windows:

- a. Bay windows may extend forward of the build-to line (see § 34-662) but may not encroach into a street right-of-way.
- b. Awning or canopies extending from the first story cannot exceed the following dimensions:
 - 1. Depth: 3 feet (minimum)
 - 2. Height: 10 feet minimum above sidewalk
 - 3. Length: 6 feet minimum
- c. Bay windows shall have the same details required for principal facades: sills, lintels, cornices, and expression lines.




Figure 34-16

(4) Porches:




Figure 34-17

- a. Front porches may extend forward of the build-to line (see § 34-662) but may not encroach into a street right-of-way.
- b. Front porches cannot exceed the following dimensions:
 - 1. Depth: 8 feet (minimum)
 - 2. Length: 25% to 90% of the front of the building; however, no more than 25% of the floor area of a porch shall not be screened if the porch extends forward of the build-to line.
 - 3. Top of railing: 2-3/4" minimum
- c. Front porches may have multi-story verandas and/or balconies above.
- d. Front porches are required to be open, un-airconditioned parts of a building.

(5) Stoops:

- a. Stoops may extend forward of the build-to line (see § 34-662) but may not encroach into a street right-of-way or sidewalk without specific approval by the town.
- b. ~~Front porches~~ Stoops cannot exceed the following dimensions:
 - 1. Depth: 6 feet (minimum)
 - 2. Length: 5 feet (minimum)
 - 3. ~~Top of railing: 2-3/4" minimum~~
- c. Stoops may be roofed or unroofed but may not be screened or otherwise enclosed.




Figure 34-125

(6) Arcades and colonnades:




Figure 34-20

- a. Arcades and colonnades may extend forward of the build-to line (see § 34-662) and may encroach into a street right-of-way if explicit permission is granted by the town.
- b. Arcades and colonnades cannot exceed the following dimensions:
 - 1. Depth: 7 feet minimum from the building front to the inside face of the column
 - 2. No part of the column shall be closer than 2 feet to the existing or planned curb
 - 3. Height: 10 feet minimum above sidewalk
 - 4. Length: 75% to 100% of the front of the building
 - 5. Top of porch railing: 2-3/4" minimum
- c. Open multi-story verandas, awnings, balconies, and enclosed useable space can be constructed above the colonnade.
- d. Arcades and colonnades shall only be constructed where the minimum depth can be obtained.
- e. On corners, arcades and colonnades may wrap around to the side of the building.
- f. Columns shall be spaced no farther apart than they are tall.
- g. Minimum column dimensions with enclosed space above shall be 8 inches.
- h. Minimum column dimension without enclosed space above:
 - 1. Rectangular columns: 6 inches
 - 2. Round columns: 6 inches in diameter

Sec. 34-996. Roofs.

(a) Definitions.

Dormer means a projection from a sloping roof that contains a window and its own roof.

Gable roof means a ridged roof forming a gable at both ends.

Hip roof means a roof with pitched ends and sides.

Mansard roof means a roof having two slopes with the lower slope steeper than the upper, or a single steep slope topped with a flat roof, enclosing the building's top floor. A modern variant is a partial sloped roof that is attached near the top of an exterior wall in place of a traditional cornice or parapet, creating the visual effect of a sloped roof on a flat-roofed building but without enclosing any floor space.

Parapet means a short vertical extension of a wall that rises above roof level, hiding the roof's edge and any roof-mounted mechanical equipment.

Shed roof means a pitched roof that has only one slope.




Figure 34-21

(b) Roof types permitted. Commercial buildings may have any of the following roof types: hip roofs, gable roofs, shed roofs, flat roofs with parapets, or mansard roofs.

- (1) All flat roofs, and any shed roof with a slope of less than 2 inches vertical per 12 inches horizontal, must have their edges along all streets concealed with parapets.
- (2) All hip roofs and gable roofs, and any shed roof with a slope of more than 2 inches

vertical per 12 inches horizontal, must have overhangs of at least 18 inches.

- a. Exposed rafter ends (or tabs) are encouraged.
 - b. Wide overhangs are encouraged and can be supported with decorative brackets.
- (3) Mansard roofs are permitted only when the lowest sloped surface begins above a cornice line and then slopes upward and inward.
 - (4) Small towers, cupolas, and widow's walks are encouraged (see § 34-631 for maximum dimensions).
 - (5) Dormers are permitted and encouraged on sloped roofs.
 - (6) Skylight glazing must be flat to the pitch of the roof if the skylight is visible from a primary street, plaza, or public park.

(c) Roofing materials permitted. Commercial building roofs may be constructed with one or more of the following roofing materials:

- (1) METAL:
 - a. Steel (galvanized, enameled, or terne-coated)
 - b. Stainless steel
 - c. Copper
 - d. Aluminum
- (2) SHINGLES:
 - a. Asphalt (laminated dimensional shingles only)
 - b. Fiber-reinforced cement
 - c. Metal (same as (a)(1))
- (3) TILES:
 - a. Clay or terra cotta
 - b. Concrete
- (4) FLAT ROOFS:
 - a. Any materials allowed by applicable building codes
- (5) GUTTERS AND DOWNSPOUTS:
 - a. Metal (same as (c)(1))

(d) Other roof types and materials. Other types of roofs and roofing materials are prohibited unless explicitly approved in accordance with § 34-992.

Sec. 34-997. Plazas and courtyards.

(a) **Generally.** New commercial buildings are generally oriented to public sidewalks. This section addresses other public open spaces that also can affect the orientation of commercial buildings.

(b) **Plazas.** This code contains “build-to lines” (see § 34-662) that require new commercial buildings to be placed near public sidewalks. These build-to regulations allow up to 25% of a building’s frontage to be recessed 10 feet. Plazas meeting the following requirements are permitted to be recessed further than the standard 10 feet:

- (1) The plaza cannot exceed 25% of a building’s frontage.
- (2) The plaza is strictly for pedestrian usage and cannot be used to park vehicles.
- (3) All building walls that surround the plaza must meet the design criteria for principal facades.

(c) **Courtyards.** New commercial buildings that are on larger lots may include interior courtyards designed for public or private usage.

- (1) If vehicular circulation is allowed through a courtyard, the only parking permitted will be in parallel spaces.
- (2) Courtyards intended for public use are encouraged to have clear visual linkages between the courtyard and public sidewalks.

(d) **Pedestrian passages.** Pedestrian passages, with or without a lane for vehicles, can be provided on private property to connect a courtyard to the sidewalk system, to provide walkways to parking lots behind buildings, or to provide additional retail frontages.

Sec. 34-998. Signage.

(a) **Signs generally.** Chapter 30 of this code regulates signs within the town. The following types of signs are not permitted: billboards; signs elevated on poles; and signs extending perpendicular from a building’s facade. New business signs are allowed generally as follows:

- (1) Signs can be painted or attached directly onto buildings walls.
- (2) Low freestanding signs can be built near the ground (except for business located in a multi-occupancy complex having five or more businesses).
- (3) Signs can be mounted onto a marquee that extends out from the front of a building.

(b) **Purpose of this section.** Conventional ground signs are inappropriate for pedestrian-oriented commercial buildings, as are large plastic signs designed to be viewed from a distance. The purpose of this section is to restrict inappropriate wall signs and to replace the ground-sign option with a greater selection of signs that either project out from a building’s principal facade or extend above the top of the facade.


(c) **Ground signs.** Ground signs, as defined in ch. 30, are not permitted for buildings designed in accordance with these standards.

(d) **Wall signs.** Figure 34-22 shows examples of acceptable wall signs that are placed flat against a principal facade. Internally lit box signs of plastic and/or metal are not permitted.

(e) **Projecting signs.** Figure 34-23 shows examples of acceptable signs that project out from a principal facade, and Figure 34-24 shows examples of acceptable signs that extend above the top of a facade. Projecting signs of these types are permitted notwithstanding any prohibitions in ch. 30, provided they are approved in accordance with § 34-992.

(f) **Location of projecting signs.** Signs designed in accordance with this section may extend over public sidewalks, but must maintain a minimum clear height above sidewalks of 9 feet. Signs shall not extend closer than 2 feet to an existing or planned curb.

Signs flat against a facade:



Sign is centered within the symmetrical arrangement of the window above and shopfront below

Internally lit letters

Internally lit letters

The sign runs horizontally along the expression line




External lighting

Sign is centered above the main entrance at the top of the facade

External lighting

Top edge of the facade is sculpted to create a focal spot for the sign



Elegant and reserved cast bronze address plate located at pedestrian eye level

Individual letters are mounted directly on the facade above the main entrance



Internally lit box signs of plastic or metal are designed for commercial strips and are not appropriate for pedestrian oriented streets


Signs that project out from a facade:



Discreetly located external lighting


Sign painted on the face of a canvas awning over entry

Small projecting signs can be combined with flat wall signs



Signs on the sides of awnings are directly in the line of sight of pedestrians


Vertical projecting signs are visible down the street



A sign projecting from the corner of a building is visible along two streets

A second lower sign catches the eye of pedestrians passing in front of the entrance

Signs hanging from the ceiling of a colonnade are visible to pedestrians



Ground signs are designed to fit in deep setbacks of a suburban strip and are not appropriate on pedestrian-oriented streets

Figure 34-23


Figure 34-22

Signs that extend above the top of a facade:



Signs extending above the tops of buildings are visible from a great distance

This distinctive sign, made of individual letters projecting from the front of the facade and extending above the cornice line, is memorable to shoppers and is visible from many directions



A second lower sign marks the entrance to the store



Projecting signs which break the skyline are visible from a variety of distances and serve as beacons when lit at night

A lower marquee sign caters to people on foot and in cars passing directly in front

Signs extending above the roof stand out against the sky, adding an architectural flair to a shops identity



Pole signs are designed to fit in deep setbacks of a suburban strip and are not appropriate on pedestrian-oriented streets

Billboards cater entirely to motorists traveling at high speeds





Figure 34-24

(g) *Size of signs.* Maximum gross area of all signs on a given facade shall not exceed 32 square feet.


(h) *Illumination of signs.* Signs shall be illuminated externally only, except that individual letters and symbols may be internally lit.

(i) *Placement of signs on principal facades.* The following illustration Figure 34-25 shows correct and incorrect placement of signs on principal facades.



- Signs are coordinated in size and placement with the building and storefront

DO THIS



- Building sign conceals the cornice
- Over-varied shapes create visual confusion
- Awning sign covers the masonry piers
- Sale sign too large for storefront and poorly placed in display window

NOT THIS

Figure 34-25

Secs. 34-999-1168. Reserved.

DIVISION 11. OVERLAY DISTRICTS

Subdivision I. In General
[deleted in its entirety]

Subdivision II. State Road 80 Overlay District
[deleted in its entirety]

Subdivision III. Pondella Road Overlay District
[deleted in its entirety]

Subdivision IV. Redevelopment Overlay District
[deleted in its entirety]

Subdivision V. The Bonita Town Center Overlay District
[deleted in its entirety]

Subdivision VI. The Fort Myers Beach Overlay District

Sec. 34-1141. Purpose and intent.

(a) *Purpose and affected area.* This redevelopment overlay district is designed to stimulate the revitalization of the original commercial district on Estero Island. This district is known as the Downtown of Fort Myers Beach and is described in a set of maps attached hereto and incorporated herein by reference. One of these maps, entitled Proposed Land Use by District, shows four distinct districts: (1) Old San Carlos; (2) Times Square; (3) Crescent Street; and (4) Estero/Beachfront. Some regulations herein apply only to one or more of these districts, which are referred to by these names (for example, permitted uses in Table 1). In other cases the context indicates that special regulations only apply to parcels directly fronting on one of these streets (for example street setbacks in Table 2).

(b) *Scope.* The revitalization of the Fort Myers Beach Downtown District will include the renovation and re-use of existing buildings and the construction of new buildings. It will also include the installation of public works, including plazas, sidewalks, changes in vehicular circulation, public and shared parking, and other streetscape improvements.

(c) *Optional nature of these regulations.* Individual landowners may choose to build or rebuild in full compliance with the provisions of this

redevelopment overlay district, or may choose to follow all existing Fort Myers Beach regulations. However, should a landowner elect to use any of the modified development regulations in § 34-1145 below, he or she must comply with all of the requirements of this redevelopment overlay district on that property.

(d) *Authority.* The Fort Myers Beach Downtown District lies at the heart of the pre-incorporation Estero Island community redevelopment area. This redevelopment overlay district is consistent with and helps to implement the adopted component redevelopment plan for Estero Island. This redevelopment overlay district also complies with all requirements for such districts found in §§ 34-1122 through 34-1132 of the Fort Myers Beach land development code.

Sec. 34-1142. Elements of the redevelopment overlay district.

This redevelopment overlay district includes two distinct elements. The first is the master plan itself (§ 34-1143), which depicts the desired redevelopment plan for the Fort Myers Beach Downtown District including public and private improvements. The second is a set of modified development regulations (§ 34-1145) which enable and encourage private landowners to rehabilitate existing buildings or construct new buildings. Both elements of the redevelopment overlay district are needed to ensure the redevelopment of the business district in the old Florida/Caribbean style as shown in the master plan.

Sec. 34-1143. The master plan.

The master plan for the Fort Myers Beach Downtown District contains three separate components as described in the following subsections:

(a) *Master site plan.* A reduced copy of the master site plan for the Fort Myers Beach Downtown District is included in Appendix L. Full-sized copies of this drawing are available at the Town Hall.

(b) *Storm water management master plan.* A reduced copy of the storm water management plan for the Fort Myers Beach Downtown District is included in Appendix L. Surface water flows will

continue to be directed away from Old San Carlos Drive and Estero Boulevard and towards Matanzas Pass under this plan, but water quality treatment and minimal storm attenuation will be added. Necessary facilities, to retrofit the existing storm sewer system for a regional exfiltration system are included in the future phases of the master plan implementation. Full-sized copies of this drawing and the remainder of the plan are available from the Town Hall.

(c) *Design guidelines.* Design guidelines for the Fort Myers Beach Downtown District are being adopted by administrative code. These guidelines provide technical and design assistance for exterior commercial building renovations and new construction. They are designed to encourage owners and tenants to preserve and improve the unique character of the business district, and to stimulate creative design solutions while promoting a sense of relatedness among properties. These guidelines are not regulations that control land-use decisions, and they contain no mandatory review process. They are designed simply to encourage the proper maintenance and improvement of the visual character of the Fort Myers Beach Downtown District as a pedestrian-oriented retail and community center.

Sec. 34-1144. ~~Limitations on approvals:~~

(a) *Record-keeping.* The staff of the Town of Fort Myers Beach shall maintain detailed records of development and redevelopment that is approved using the modified development regulations in § 34-1145 below. These records shall include cumulative totals of square footage of new commercial space and the resulting number of parking spaces (both the number required by general Town regulations and the number actually being provided by those developing and redeveloping land in the Fort Myers Beach Downtown District).

(b) *New development prior to public improvements.* Lee County's Community Redevelopment Agency is constructing major public improvements in the Fort Myers Beach Downtown District that were planned and funded prior to incorporation and will include substantial pedestrian and automobile infrastructure improvements. If actual development activity recorded pursuant to § 34-1144 (a) exceeds a cumulative total of 25,000 square feet of commercial space or a reduction of 100 parking spaces below general Town regulations

prior to the letting of contracts to construct on-street parking and the core surface water management system, then the Town shall immediately undertake an analysis of actual demand for these public facilities in the Fort Myers Beach Downtown District. The results of this analysis shall be presented to the town council which shall decide whether to initiate the public improvements or to repeal or modify these redevelopment overlay regulations so that adequate public facilities will be available when needed by new development. However, this provision shall not be interpreted to supersede the general concurrency requirements of ch. 2 of the land development code.

Sec. 34-1145. ~~Modified development regulations:~~

(a) *Optional nature of this section.* All landowners in the Fort Myers Beach Downtown District are encouraged to develop or redevelop their property in conformance with the overall master plan and the detailed design guidelines referred to in § 34-1143(c). Should a landowner choose to avail himself of the modified development regulations contained in this section, then compliance with all applicable portions of the redevelopment overlay district will be mandatory for that property and for any abutting lot(s) or adjacent building(s) under the same ownership or control, for a period of 10 years. Nothing in this ordinance shall require any landowner to participate in any of its provisions unless that landowner elects to do so. A landowner's decision to use these regulations shall be made in writing on a form supplied by the Town. This form shall acknowledge that this decision runs with the land for the stated period. Fort Myers Beach shall record this form in the Official Record books of Lee County.

(b) *Modified development regulations.* The remainder of the provisions of this ordinance assume that a landowner in the Fort Myers Beach Downtown District has elected in writing to comply in full with this redevelopment overlay district. All Fort Myers Beach regulations shall remain in effect except as explicitly modified through this ordinance.

(c) *Permitted uses.* The permitted uses of land are normally determined by its zoning classification. At present, the district is zoned C-1, CPD and RM-2. Regardless of these underlying zoning classifications, the permitted uses of land in this redevelopment overlay district shall be in

accordance with Table 1. The table then shows those specific uses that are permitted in the Fort Myers Beach Downtown District on the ground floor and/or outdoors facing the primary walking zone (facing the right-of-way of Old San Carlos Boulevard). [remainder of subsection (c) and all of Table 1 deleted]

(d) *Property development regulations.* In the same manner as for Table 1, new property development regulations for the Fort Myers Beach Downtown District are shown in Table 2. The terminology and notes used in this table are the same as contained in Table 34-844 of the land development code, except as specifically noted.

TABLE 2

DIMENSIONAL REGULATIONS	SPECIAL NOTES OR REGULATIONS	G-1 ZONING DISTRICT	FORT MYERS BEACH DOWNTOWN DISTRICT (ALL PORTIONS)
Maximum density	34-2142, 2221, 2222	Note (1)	Note (1)
Minimum lot area and dimensions:			
— Minimum lot size:			
— Residential uses (square feet):			
— First two units in same building		7,500	7,500 (a)
— Each add'l unit in same building		3,000	3,000
— Nonresidential uses (square feet):			
— Corner lot		7,500	5,000
— Interior lot		7,500	2,500
— Minimum lot width (feet)		75	25
— Minimum lot depth (feet)		100	100
Minimum setbacks:			
— Street (feet)	34-2191 et seq. Note (3)	Variable according to the functional classification of the street or road	(b), (c)
— Side yard (feet)	Note (5)		0 (c)
— Rear yard (feet)			25 (d)
— Water body (feet):			
— Gulf of Mexico			N/A
— Other (feet)	34-2194(a), (c)	(see § 34-2192)	25
		15	
		25	
		N/A	
		25	
Maximum height (feet)	34-2171 et seq.	40	40 (f)
Maximum lot coverage (percent of total lot area)		40%	60% (g), (h), (i)

[Original notes from Table 34-844, reprinted here only when referenced above]

- (1) Residential development shall not exceed that density permitted by the Lee Plan for the land use category in which the property is located.
- (2) Modifications to required setbacks for arterial or collector streets, or for solar or wind energy purposes, are permitted only by special permit. See § 34-2191 et seq.
- (5) No side yard setback is required from common lot line for two-family attached or townhouse.

Notes applying to the Fort Myers Beach Downtown District only:

- (a) Along Crescent Street only. Maximum bonus density allowed for multifamily residential use with the additional density for affordable housing only; multifamily lot sizes may be as small as 5,000 square feet.
- (b) No setback to right-of-way allowed along Old San Carlos, Crescent Street, and Estero Boulevard south to Miramar Avenue; standard front setbacks apply at all other locations; ground-level sidewalks or patios along Old San Carlos and Estero may be recessed as an arcade with building above.
- (c) Existing structures in Times Square may be expanded at grade to the street right-of-ways without providing additional parking. Expansion above the ground level requires parking to code.
- (d) Along Old San Carlos, 30 feet from front setback at grade, 50 feet from front setback above grade.
- (e) Along Crescent Street, minimum 5 feet one side with 50% lot width total setback required.
- (f) Above Base Flood Elevation.
- (g) Parking garage exempt along Old San Carlos
- (h) Governed by setback requirements along Crescent Street
- (i) 100% lot coverage requirements along Crescent Street

(e) *Off-street parking.* Off-street parking is generally required in accordance with § 34-2011 et seq. of the land development code. Those requirements assume that patrons of each land use will arrive in a private automobile that will be parked in a private lot on the same premises. The Fort Myers Beach Downtown District differs in several ways from most conventional development: its location on Estero Island allows some arrivals on foot or by bicycle, trolley, or boat; the proposed intensity of related uses will increase the number of destinations for each automobile trip; shared parking lots are encouraged by this overlay district; and some on-street parking will be provided. In response to these conditions, the following modifications to the land development code shall apply:

- (1) *Location of off-street parking spaces.* Off-street parking spaces shall not be placed between the principal building and the street. This parking shall be provided in parking lots located generally behind the principal building, in order to de-emphasize the visual effect of large parking lots and to allow the front walls of buildings to become an integral part of the pedestrian-oriented streetscape being created through the master plan.
- (2) *Access, location, and design of parking spaces.* Notwithstanding any conflicting provisions of § 34-2013 and 34-2015 of the land development code:
 - a. Parking lots may be accessed by alleys, and parking spaces may be directly accessed from alleys, provided such alleys are improved in accordance with this section.
 - b. Distinct parking lot entrances to streets or alleys shall be at least 12 feet wide for one-

way entrances and 20 feet wide for two-way entrances:

(3) ~~Required number of parking spaces.~~ The number of off-street parking spaces required for any given land use by § 34-2020 shall be reduced by one-third.

(4) ~~Joint use of off-street parking lots.~~

Notwithstanding any conflicting provisions of § 34-2018 of the land development code:

a. Joint or shared use of off-street parking is specifically encouraged in the Fort Myers Beach Downtown District. To this end, joint-use parking may be approved administratively by the town manager as an alternative to the special permit process found in § 34-203(g)(5), in accordance with the following provisions of this subsection (4):

b. Joint or shared parking lots must be located on the same block as the land uses they serve. Signs shall be placed to inform motorists of the allowable use of shared lots. Applicants are also encouraged to include joint space for off-street loading in these lots:

c. In joint or shared lots, the same parking space may fully satisfy the off-street parking requirement for two different land uses provided their peak parking demands clearly occur at different times. When the peak demands do not clearly occur at different times, each two parking spaces can replace three parking spaces that would otherwise be required by the combined uses (after the reduction found in subsection (3) above):

d. Town administrative approval for joint or shared use of off-street parking can be granted only when all users of the shared lot have chosen to be governed by this redevelopment overlay district in accordance with § 34-1145(a), and (b) above. Requests for administrative approval shall include the following:

1. A notarized statement from all property owners involved indicating the use of each property and to what extent the activities of each separate building or use which create a demand for parking shall occur at different times.
2. Written agreements, covenants, contracts and the like, acceptable to the Town, which ensure that the parking

area is to be used jointly and establish the responsibility for maintenance:

e. Administrative approvals granted by the Town shall be recorded in the same manner as other administrative approvals granted under the land development code:

(f) ~~Off-street loading.~~ Space for off-street loading is generally required in accordance with § 34-1981 et seq. of the land development code. Conventional development is designed so that the unloading of products or materials from large trucks occurs entirely off-street, often in space earmarked for that purpose. The Fort Myers Beach Downtown District differs from conventional development by eliminating large retailers and industrial uses, both of which usually require a separate area for off-street loading to or from large trucks. In addition, the more intense clustering of commercial uses along street frontages precludes a separate loading space for each use. Accordingly, and notwithstanding any conflicting provisions of § 34-1981 et seq. of the land development code:

(1) ~~Off-street loading area.~~ [moved to § 34-1986(c)(4)]

(2) ~~Interference with parking areas.~~ [moved to § 34-1981(b)]

(g) ~~Sandwich signs.~~ [moved to § 34-677(d)]

(h) ~~Development standards.~~ In a similar manner as for Tables 1 and 2, new development standards for the Fort Myers Beach Downtown District are shown in Table 3. The terminology in this table follows that in ch. 10 of the land development code, except as specifically noted:

TABLE 3

TYPE OF DEVELOPMENT STANDARD	FOUND WHERE IN-LAND DEVELOPMENT CODE	SUBSTANCE OF CURRENT REGULATIONS	FORT MYERS BEACH DOWNTOWN DISTRICT (ALL PORTIONS)
Open space:	10-413(b)		
— small developments		20%	Note (a)
— large developments		30%	Note (a)
Minimum required buffering:			
— commercial adjoining existing residential development	10-414(a)	15-foot buffer and 8-foot-high fence, wall or berm	None except at parking lots
— commercial adjoining street rights-of-way	10-415(b)	10-foot-wide landscaped strip	Note (b)

Storm-water detention	10-321 et seq.	Required for each individual parcel	See § 34-1143(b)
Intersection separation	10-285	Arterials: 660 ft. Collectors: 330 ft. Local streets: 125 ft. Access roads or access ways: 60 ft.	Estero Blvd.: note (c) Other streets: note (d)

Notes applying to the Fort Myers Beach business district only:

(a) ~~There is no minimum open space requirement comparable to that required by § 10-413.~~

(b) ~~There is no minimum buffer requirement adjoining rights-of-way comparable to that required by § 10-414(f).~~

(c) ~~Vehicular access to private parking spaces shall be via the side streets.~~

(d) ~~Vehicular access to parking spaces shall be via the side streets wherever possible. New access points shall be allowed to streets only where side street access is not shown in the master plan (see § 34-1143), or where side street access is not feasible or inferior to the circulation pattern shown in the master plan (as determined by the town manager).~~

(i) *Building height limitations.* Building heights are limited to 40' above Base Flood Elevation allowing a maximum of a three story building. Additional building heights in return for greater setbacks is not an available option under the master plan.

(j) *Building regulations.* The purpose of this subsection is to encourage the continued use or reuse of existing buildings in the Fort Myers Beach Downtown District and to encourage the creation of awnings and canopies over sidewalks and pedestrian walkways. Accordingly, and notwithstanding any conflicting provisions of ch. 6 of the land development code:

(1) *Existing uses.* Existing buildings may continue their existing use, provided such buildings are maintained in a safe and sanitary condition and such use was legal at the time of adoption of this ordinance. Buildings left vacant for a time period exceeding 2 years shall be analyzed prior to reoccupancy for structural strength, stability, sanitation, adequate light and indoor air quality, adequate plumbing, mechanical, gas, and electrical systems, and safety to life and property from fire and other hazards affecting the safe use and occupancy of the building. The Building Official may waive one or more of the above requirements based upon the type occupancy being requested. Findings of the analysis shall be submitted to the Building Official as a part of the application for a permit to reoccupy the building.

~~(2) *Alterations, Repairs, and Rehabilitation.* Alterations, repairs, or rehabilitation work may be made to any existing building without requiring the building to comply with all the requirements of the building codes provided that the alteration, repair, or rehabilitation work conforms to the requirements of the Building, Plumbing, Mechanical, Gas, and Electrical Codes for new construction. The Building Official shall determine the extent to which the remainder of the building shall be made to conform to the requirements of these codes for existing construction, consistent with the purposes of this subsection.~~

~~(3) *Change of a building's use or occupant.* When a new use is proposed for an existing building, or a new occupant wishes to occupy an existing building, the following shall apply:~~

- a. If the occupancy classification of an existing building or structure is changed to a more hazardous occupancy (based on the life safety and fire hazard involved), the building, electrical, gas, mechanical, and plumbing systems shall be made to conform to the intent of the technical codes as required by the Building Official.
- b. If a new use falls within the same occupancy classification as the previous use, the requirement in subsection a. shall not apply.
- c. The mere change of occupant within the same occupancy classification, or the upgrading of a certificate of compliance to a certificate of occupancy, shall not cause the requirement in subsection a. to apply.

~~(4) *Awnings and canopies.* The installation of awnings and canopies over sidewalks and pedestrian walkways is specifically encouraged (see design guidelines referred to in § 34-1143(c) above). Awnings and canopies that extend over public property are regulated by ch. 22 of the Standard Building Code. In order to allow and encourage the implementation of the master plan, landowners may construct fixed awnings and canopies that extend over public property to the same extent as allowed by the Standard Building Code for movable awnings, notwithstanding the limitations found in § 34-2191 of the land development code.~~

~~Sec. 34-1146. Procedures for approval and for appeals of administrative decisions.~~

~~(a) *Approval process.* In order to minimize the time required for review of permit requests in the Fort Myers Beach Downtown District, all staff review shall occur simultaneously.~~

~~(b) *Appeals of administrative decisions.* Administrative decisions may be appealed in accordance with existing procedures for such appeals.~~

ARTICLE IV. ~~VII~~
SUPPLEMENTARY DISTRICT
SUPPLEMENTAL REGULATIONS²

DIVISION 1. GENERALLY

Sec. 34-~~1169~~ 1141. Purpose and applicability of article.

The purpose of this article is to provide rules and regulations which supplement, modify, or further explain rules and regulations found elsewhere in this chapter, and, unless specifically noted to the contrary, the provisions of this article apply to all zoning districts.

Sec. 34-~~1170~~ 1142. Purpose of supplemental regulations.

(a) Regulations over and above those imposed by other sections of this chapter are necessary for certain uses which, because of their uniqueness or potential for substantial impact on surrounding land uses, warrant minimum standards which cannot properly be addressed in general provisions or property development regulations set forth in specific districts. The purpose of the supplemental regulations set forth in this article is to set forth the detailed regulations, including but not limited to the bulk, layout, yard size, and lot area, that apply to these uses.

~~(b) Some of the uses provided for in this article will exceed the minimum thresholds for developments of county impact (see § 34-203) and will be required to apply for approval through the planned development procedure. The Board of County Commissioners may modify any of the requirements of this article in accordance with the procedures for a planned development application approval.~~

~~(b) (c) The supplemental regulations set out in this article shall apply to the specified use regardless of whether it is a use permitted by right, special permit or special exception, planned development rezoning, development of county impact or~~

² ~~Cross reference(s)-Development design standards, § 10-251 et seq~~

temporary use permit, as specified in the district use regulations in division 2 of article III of this chapter.

~~Secs. 34-1143--34-1170. Reserved.~~

**DIVISION 2. ACCESSORY USES,
BUILDINGS, AND STRUCTURES**

Sec. 34-1171. Applicability of division.

This division provides minimum regulations for those accessory uses, buildings, and structures customarily incidental and subordinate to the principal use or building, which are not specifically regulated elsewhere in this chapter.

Sec. 34-1172. Definitions.

For purposes of this division only, certain words or terms shall mean the following:

Accessory use means a use of a structure or premises which is customarily incidental and subordinate to the principal use of the structure or premises.

Commercial accessory use means the use of a structure or premises that is customarily incidental and subordinate to the principal use of a commercial structure or premises. See Use, principal. Typical commercial accessory uses are: Parking lots, accessory; Storage, indoor; and Telephone booth or pay telephone station. Various divisions of article IV of this chapter describe permitted commercial accessory uses. Uses that are listed separately on Table 34-1 of this code, such as drive-throughs and automobile fuel pumps, are not commercial accessory uses and are permitted only in zoning districts where they are explicitly identified in Tables 34-1 and 34-2.

Open-mesh screen means meshed wire or cloth fabric to prevent insects from entering the facility, including the structural members framing the screening material.

Residential accessory uses. See § 34-622(c)(42). means the use of a structure or premises that is customarily incidental and subordinate to the principal use of a residential structure. See Use, principal. Typical residential accessory uses are: carports and garages (§ 34-1013); decks, gazebos,

patios, and screen enclosures; dock, personal (§ 34-1863); fences and walls (division 17 in article IV); garage sales or yard sales (§ 34-2); recreation facilities, personal; seawalls (ch. 26); and storage sheds. Division 2 and other portions of article IV provide regulations for many residential accessory uses.

Resort accessory use means the use of a structure or premises that is customarily incidental and subordinate to a resort. See Use, principal. Typical resort accessory uses are: Amusement devices (§§ 34-2141–2145 and 34-3042); Golf courses; Parasailing operations office (ch. 27); Personal watercraft operations office (ch. 27); and Rental of beach furniture (ch. 14).

Roofed means any structure or building with a roof which is intended to be impervious to weather.

Cross reference(s)–Definitions and rules of construction generally, § 1-2.

Sec. 34-1173. Development regulations.

(a) Permitted structures and uses. Unless specifically indicated to the contrary, accessory uses; and related buildings and structures that are customarily recognized as clearly incidental and subordinate to the principal use of the property are permitted by right when located on the same lot or parcel and in the same zoning category as the principal use, provided that, in conjunction with a permitted principal use, approved special exception or approved special permit subject to the county building code, this chapter, and all other applicable regulations:

(b) Time of construction.

- (1) Uses that are listed separately on Table 34-1 of this code, such as drive-throughs and automobile fuel pumps, are not accessory uses and are permitted only in zoning districts where they are explicitly identified in Tables 34-1 and 34-2. However, this limitation does not apply to uses that are explicitly listed in the definitions of residential, commercial, or resort accessory uses.
- (2) All uses, buildings, and structures must comply with all applicable development regulations and building codes.
- (3) (†) Accessory buildings or structures may be built concurrently with a principal building or structure but, except as provided in

subsection (b)(2) of this section herein, no accessory use, building, or structure shall be commenced, erected, placed, or moved onto a lot or parcel prior to the principal use, building, or structure. (‡) Exceptions are as follows:

a. Agricultural accessory structures in the AG district:

a. b. Fences or walls when in compliance with division 17 of this article.

b. c. Seawalls or retaining walls (see § 26-43(a) § 34-1863).

c. d. Docks accessory to residential uses, personal (see § 26-43(a) § 34-1863). Only permitted if the lot meets the minimum lot size and dimensions required for a principal use.

(3) Accessory buildings or structures may be built concurrently with a principal building or structure:

(c) Attachment to principal building. Authorized accessory buildings or structures may be erected as part of the principal building or may be connected to it by a roofed porch, patio, or breezeway, or similar structure, or they may be completely detached, provided that:

- (1) Any accessory building or structure which is structurally a part of the principal building shall comply in all respects with the regulations for a principal building.
- (2) Any accessory building or structure not structurally made a part of the principal building shall comply with the location requirements set forth in § 34-1174.

Sec. 34-1174. Location and setbacks generally.

(a) Permitted locations. Except as may be provided elsewhere in this chapter, all accessory uses, buildings, and structures must be located on the same premises and must have the same zoning district or zoning classification as the principal use (see also § 34-616(b)). For purposes of this section, the a zoning classification contains must consist of the following groups of zoning districts:

(1) Districts described in article VI, division 2, of this chapter (agricultural districts);

(1) (‡) Residential districts – RS, RC, RM, and SANTOS – described in article III VI, division 3, of this chapter; and (residential districts);

- ~~(3) Districts described in article VI, division 4, of this chapter (recreational vehicle park districts);~~
- ~~(4) Districts described in article VI, division 5, of this chapter (community facilities districts);~~
- ~~(2) (5) Commercial districts – CR, CM, CO, and CB – described in article III VI, division 6, of this chapter, (commercial districts);~~
- ~~(6) Districts described in article VI, division 7, of this chapter (marine-oriented districts);~~
- ~~(7) Districts described in article VI, division 8, of this chapter (industrial districts).~~

(b) **Setback from streets.** No accessory use, building, or structure shall be located closer to a street right-of-way line or street easement than the principal building, except for fences and wall as provided for in division 17, for garbage enclosures as provided for in § 6-11, as provided for in the exceptions to setbacks in § 34-638(d) division 30, subdivision III, of this article, or as set forth in this subsection.

~~(1) Accessory uses, buildings or structures in the RSC-1, RSC-2, RSA, RS, RM, TFC, TF and AG zoning districts may be closer to the street than the principal building as long as a minimum setback of 100 feet is maintained.~~

~~(1) (2) Accessory uses, buildings, and structures may be located on through lots as follows. For purposes of this subsection only, secondary street is defined as the street opposite the street which provides principal vehicular access as determined by the prior development pattern of that block.~~

- ~~a. On through lots with no dedicated buffer easement or residential project fence or wall, accessory uses, buildings, and structures may be placed closer to the secondary street than the principal building as long as the minimum setbacks for streets as set forth in § 34-638 division 30, subdivision III, of this article are maintained.~~
- ~~b. On through lots with a dedicated buffer easement of ten feet or more (located on the property) and immediately adjacent to the secondary street, accessory uses, buildings and structures shall not encroach into the easement.~~
- ~~c. On through lots with an abutting residential project fence or wall accessory use, buildings and structures shall be set~~

~~back a minimum of five feet from the property line.~~

~~(2) (3) In the following cases, accessory uses, buildings, and structures may be closer to the street than the principal building, but shall not be closer than the minimum setbacks for streets as set forth in § 34-638, division 30, subdivision III, of this article.~~

- ~~a. Accessory uses, buildings, and structures in the RSC-2 zoning district.~~
- ~~b. Any lot in which the rear lot line abuts a body of water.~~
 - ~~a. c. Swimming pools, tennis courts, shuffleboard courts, and other similar recreational facilities accessory to a multiple-family or townhouse development, or a hotel/motel, or a mobile home or recreational vehicle development, provided that: 1. they are part of a planned development or a site plan approved in accordance with ch. 10, and~~
 - ~~2. They are aesthetically landscaped with berming or buffering which is adequate to screen the use from the street so as to prevent it from being a traffic distraction.~~
- ~~d. Garages or carports for residential, commercial or industrial uses.~~
- ~~b. e. Outdoor display of merchandise, where permitted, subject to the provisions of division 36 of this article, and ch. 30, pertaining to signs.~~

~~(c) **Setback from bodies of water.** No building or structure (except marine structures, docks and seawalls, which are subject to the setback requirements as set forth in ch. 26, article II) may be located closer to a bay, canal, or other body of water than the minimum setbacks required in § 34-2194 § 34-638(c)(3).~~

~~(d) **Setbacks from side and rear property lines.** Unless the side or rear property line abuts a body of water (see § 34-638(d) 2194), the following setbacks shall apply:~~

- ~~(1) *Agricultural accessory buildings and structures.* [deleted in its entirety]~~
- ~~(1) (2) **Residential accessory buildings and structures.** Except as provided in §§ 34-1175 and 34-1176, all accessory residential buildings and structures shall be set back a minimum of;~~

- a. Five feet from any rear property line that does not have access to an alley.
- b. Zero feet from any rear property line that is served by an alley.
- b. For non-waterfront lots, five feet from any side property line.
- c. For waterfront lots, the same distance as is required from any side property line for principal buildings in that zoning district (see § 34-638), and shall be no closer to a side property line than the minimum required side setback for the district in which the property is located, or ten feet, whichever is less.

(2) ~~(3)~~ **Commercial and resort industrial accessory buildings and structures.** All accessory buildings and structures for a principal commercial or resort industrial use shall be set back:

- a. ~~a minimum of ten feet from rear and side lot lines when abutting a commercial or industrial zoning district; and~~
- a. b. In accordance with the side and rear setback requirements for a principal building in that zoning district for the district in which located or the minimum buffering requirements as set forth in ch. 10, whichever is greater, when abutting any district other than commercial or resort, or industrial.
- b. When abutting another commercial or resort zoning district:
 - 1. Rear setbacks are not required.
 - 2. For non-waterfront lots, side setbacks are not required.
 - 3. For waterfront lots, the same distance as is required from any side property line for principal buildings in that zoning district (see § 34-638).

(e) Administrative setback variances. Under certain limited circumstances, administrative variances can be granted to minimum setbacks as provided in § 34-268.

(f) (e) Prohibited locations. Nothing contained in this chapter shall be construed as permitting placement of any accessory building or structure within a utility or other easement prohibiting such building or structure, or closer to adjacent property than permitted by the minimum buffer requirements set forth in ch. 10, or closer to any other building than permitted by the town county building code.

(g) (f) Signs. Signs are subject only to the setback requirements as set forth in ch. 30.

(h) Fences. Fences are subject to the setback requirements in division 17 of this chapter.

Sec. 34-1175. Satellite dishes and amateur radio antenna/towers.

(a) **Satellite dishes.** Satellite dishes shall be permitted as a residential accessory uses subject to the following:

- (1) Dishes shall comply with the minimum maintain a ten-foot setback from all side and rear property lines setbacks for the zoning district in which located; and
- (2) Satellite dishes shall not be placed closer to the street right-of-way than the principal building, ~~and~~
- ~~(3) The height of the dish shall not extend beyond the height of the principal structure on the same lot.~~

(b) ~~All commercial storage and display of satellite dishes shall meet the requirements of division 36 of this article: Amateur radio antenna/towers.~~

- (1) Amateur radio antenna/towers up to 50 feet in height are permitted in all zoning districts provided that antenna/tower supports and peripheral anchors are located entirely within the boundaries of the property and in the rear or side yard.
- (2) Amateur radio antenna/towers over 50 feet in height may be permitted by special exception in any zoning district.

Sec. 34-1176. Swimming pools, tennis courts, porches, decks, and similar recreational facilities.

(a) **Applicability.** The regulations set out in this section apply to all swimming pools, tennis courts, shuffleboard courts, porches, decks, and other similar recreational facilities which are accessory to a permitted use, and which are not specifically regulated elsewhere in this chapter.

(b) **Location and setbacks.**

- (1) **Personal, private, and limited facilities.**
 - a. **Nonroofed facilities.** All swimming pools, tennis courts, decks, and other similar nonroofed accessory facilities shall comply with the following setback requirements:

1. Street setbacks as set forth in §§ 34-1174(b) and ~~34-638, 2192~~.
2. Water setbacks as set forth in ~~§ 34-2194~~ § 34-638(d)(3).
3. Rear lot line setback as set forth in § 34-1174(d).
4. Side lot line setbacks as set forth in § 34-1174(d).

b. *Open-mesh screen enclosures.* Swimming pools, patios, decks, and other similar recreational facilities may be enclosed with an open-mesh screen enclosure provided that the enclosure complies with the setback requirements set forth in § 34-1174, and provided further that:

1. At least three sides of the enclosure are open-mesh screening from a height of 3 1/2 feet above grade to the top of the enclosure.
2. Enclosures with any two or more sides enclosed by opaque material shall be required to comply with all setbacks required for a principal building.

It shall be the responsibility of the applicant to increase all required setbacks sufficient to provide maintenance access around the pool whenever the pool is proposed to be enclosed with open-mesh screening or fencing. A minimum increase in setbacks of three feet is recommended.

c. *Roofed open-mesh enclosures.* Open-mesh screen enclosures may be covered by a solid roof (impervious to weather) provided that:

1. If structurally part of the principal building, the enclosure shall comply with all setback requirements for the principal building.
2. Except when in compliance with the setback requirements for principal buildings, a solid roof over a screen enclosure shall be constructed as a flat roof with the pitch no greater than the minimum required for rain runoff.

(2) *Commercial and public facilities.* All pools, tennis courts, and other similar recreational facilities owned or operated as a commercial or public establishment shall comply with the setback regulations for the zoning district in which located.

(c) **Fencing.**

(1) *In-ground swimming pools, hot tubs, and spas.* Every swimming pool, hot tub, spa, or similar facility shall be enclosed by a fence, wall, screen enclosure or other structure, not less than four feet in height, constructed or installed so as to prevent unauthorized access to the pool by persons not residing on the property. For purposes of this subsection, the height of the structure shall be measured from the ground level outside of the area so enclosed. The enclosure may be permitted to contain gates, provided they are self-closing and self-latching.

(2) *Aboveground swimming pools, hot tubs, and spas.* Aboveground pools, hot tubs, spas, and similar facilities shall fulfill either the enclosure requirements for in-ground pools or shall be so constructed that the lowest entry point (other than a ladder or ramp) is a minimum of four feet above ground level. A ladder or ramp providing access shall be constructed or installed so as to prevent unauthorized use.

(3) *Exception.* A spa, hot tub, or other similar facility which has a solid cover (not a floating blanket) which prevents access to the facility when not in use shall be permitted in lieu of fencing or enclosure requirements.

(4) *Tennis courts.* Fences used to enclose tennis courts shall not exceed 12 feet in height above the playing surface.

(d) **Lighting.** Lighting used to illuminate a swimming pool, tennis court, or other recreational facility shall be directed away from adjacent properties and streets, and shall shine only on the subject site.

(e) **Commercial use.** No swimming pool, tennis court, or other recreational facility permitted as a residential accessory use shall be operated as a business.

Sec. 34-1177. Accessory apartments not requiring owner-occupancy on the premises.

~~(a) Purpose.~~ The purpose of this section is to facilitate the provision of affordable housing or to strengthen the family unit or to provide increased opportunities for housing the elderly and persons with special needs.

~~(a) (b) Applicability.~~ This section sets forth the requirements for accessory apartments on larger lots, when subordinate to a single-family detached dwelling unit, with no requirement that the property owner live on the premises. If a property owner lives on the premises, an existing accessory apartment that does not meet the requirements of this section may be legal under the provisions of § 34-1178. The requirements of this section apply to accessory apartments whether they are listed as a permitted use or a use by special exception.

~~(b) (c) Definition.~~ For purposes of this section, the term “accessory apartment” means a dwelling living unit, with or without cooking facilities, constructed subordinate to a single-family dwelling unit that could be made and available for rent or lease.

~~(c) (d) Off-street parking.~~ In addition to the requirements of § 34-~~2020(d)(1)a~~, one additional space shall be required for the accessory apartment; and all required parking must be provided on the site.

~~(d) (e) Maximum floor area; use; floodplain regulations.~~

(1) *Attached apartments.* If the accessory apartment is constructed as part of the principal building, the maximum floor area of the accessory apartment shall not exceed 50 percent of the floor area of the main dwelling unit.

(2) *Detached apartments.* If the accessory apartment is not constructed as part of the main dwelling unit, the maximum floor area shall be 850 ~~500~~ square feet or 50 percent of the floor area of the main dwelling unit, whichever is less. ~~In no event shall the maximum lot coverage permitted for the zoning district in which the property is located be exceeded.~~

(3) *Use.* The accessory apartment shall be limited to one family, as defined in this chapter.

~~(4) Floodplain and other regulations.~~ Nothing in this section shall be construed to waive the floodplain regulations in ch. 6, article IV or other regulations in this code, except as explicitly set forth.

~~(e) (f) Minimum lot size.~~ An accessory apartment may be permitted on a lawfully existing lot of record which conforms to the minimum lot size of the district in which it is located. However, in no case shall the lot area be less than 6,000 square feet.

~~(g) Garage conversions.~~

~~(1) Attached garages.~~ An attached garage may be converted to an accessory apartment.

~~(2) Detached garages.~~ A detached garage may be converted to an accessory apartment provided that the garage is not closer to the street right-of-way or easement than the principal dwelling unit. In no instance shall the conversion be permitted where the garage encroaches in the front setback. The minimum number of parking spaces shall be maintained after the conversion of an attached or detached garage.

~~(f) (h) Appearance.~~ The entrance to the accessory apartment, when constructed as part of the principal residence, should be designed in such a manner as to retain the appearance of a single-family residence.

~~(g) (i) Density.~~ ~~(1)~~ An accessory apartment, for the purposes of this section density, is termed a dwelling unit and the resulting density must comply in accordance with the Fort Myers Beach Comprehensive Lee Plan. ~~(2) For the purposes of establishing eligibility for bonus densities, an accessory apartment shall be considered an affordable unit.~~

Sec. 34-1178. Accessory apartments in owner-occupied homes.

(a) **Purpose.** The purpose of this section is to recognize and legalize certain existing accessory apartments where the immediate presence of a property owner is presumed to mitigate any negative effects that might result from the use or rental of such apartments.

(b) **Applicability.** This section sets forth special requirements for a single accessory apartment in an owner-occupied home. ~~The requirements of this section are applicable in any zoning district that allows residential uses without regard to the zoning district limitations provided in Table 34-694.~~ Nothing in this section authorizes or legalizes any construction that is not allowed by the flood-hazard regulations found in §§ 6-401 through 6-475 of this code.

(c) **Definition.** For purposes of this section, the term “accessory apartment” means a single living unit no larger than 850 square feet, with or without cooking facilities, that ~~was~~ is in existence as of December 15, 1997. For such an accessory apartment to remain lawful under this section, the property owner or an immediate family member must be in residence on the premises, or on an immediately adjoining lot, during any period when the apartment is not vacant.

(d) **Density.** An accessory apartment that meets the requirements of this section is ~~not termed a living unit but not~~ a dwelling unit as defined by the Fort Myers Beach Comprehensive ~~Use~~ Plan and is not counted in residential density computations (see § 34-632(5)b.).

~~Sec. 34-1179. Commercial fishing equipment storage as accessory use to residence in Greater Pine Island area. [deleted in its entirety]~~

Sec. 34-1179. Trucks and commercial vehicles in residentially zoned districts.

Except for daytime deliveries or service calls, the following types of trucks or commercial vehicles may not be parked or stored on any lot in a conventional or redevelopment zoning district. Planned development zoning districts may allow the parking of these trucks if explicitly permitted by its zoning resolution:

- (1) A tractor-trailer or semi-trailer truck; or
- (2) A truck with two or more rear axles; or
- (3) A truck with a gross vehicle weight rating (GVWR) in excess of 12,000 pounds; or
- (4) Any truck and trailer combination resulting in a combined gross vehicle weight rating (GVWR) in excess of 12,000 pounds.

~~Sec. 34-1180. Additional dwelling unit on lot in agricultural districts. [deleted in its entirety]~~

Secs. 34-1180~~1~~--34-1200. Reserved.

**DIVISION 3. ADULT ENTERTAINMENT,
ADULT BOOKSTORES AND
MESSAGE PARLORS
SEXUALLY-ORIENTED BUSINESSES**

Sec. 34-1201. Applicability of division.

This division shall apply to all sexually-oriented businesses (as defined in the Fort Myers Beach Sexually Oriented Businesses Regulation Ordinance, Ord. 96-04), zoning districts wherein bookstores, entertainment or message parlors would be permitted by right or by special exception.

Sec. 34-1202. Definitions.

Sexually-oriented business means a sexually-oriented business as defined in the Fort Myers Beach Sexually Oriented Businesses Regulation Ordinance, Ord. 96-04.

[previous definitions deleted in their entirety]

Sec. 34-1203. Purpose of division.

The purpose of this division is to provide reasonable regulations to alleviate the adverse effects of sexually-oriented businesses ~~adult~~ bookstores, adult exhibitions and message parlors on adjacent and nearby uses of land.

Sec. 34-1204. Prohibited locations.

(~~a~~) No use of land for purposes governed by this division shall be located closer than 1,000 feet, measured on a straight line, from:

- (1) The closest wall of any building containing a similar use; or

- (2) ~~(b) No use of land for purposes governed by this division shall be located closer than 1,000 feet, measured on a straight line, from Any district which allows residential uses; or~~
- (3) ~~(c) No use of land for purposes governed by this division shall be located closer than 1,000 feet, measured on a straight line, from Any hotel, motel, restaurant, school (noncommercial), day care center (child), park, playground, place of worship, religious facility, public recreation facility, or cultural facility. center, rooming house, boarding house or hospital.~~

Secs. 34-1205--34-1230. Reserved.

**DIVISION 4. AIRCRAFT
LANDING FACILITIES, PRIVATE**

~~Sec. 34-1231. Permit required. [deleted in its entirety]~~

~~Sec. 34-1232. State permit. [deleted in its entirety]~~

~~Sec. 34-1233. Land area and site. [deleted in its entirety]~~

~~Sec. 34-1234. Building setbacks. [deleted in its entirety]~~

~~Sec. 34-1235. Setbacks for approach zones. [deleted in its entirety]~~

~~Sec. 34-1236. Compliance with height restrictions. [deleted in its entirety]~~

~~Sec. 34-1237. Repair of aircraft and machinery. [deleted in its entirety]~~

Secs. 34-1231-18. Use of engine-propelled aircraft.

(a) No person shall take off or land any aircraft that is propelled by an engine within the limits of the Town of Fort Myers Beach unless the aircraft is registered with the Federal Aviation Administration or an aircraft owned by a governmental agency.

(b) In accordance with FAA requirements, no aircraft, as defined in subsection (a), shall fly over the land of the Town of Fort Myers Beach.

Secs. 34-12329--34-1260. Reserved.

DIVISION 5. ALCOHOLIC BEVERAGES

Sec. 34-1261. Definitions.

For purposes of this division and when referred to elsewhere in this chapter, certain terms or phrases shall have the following meaning:

Alcoholic beverage means distilled spirits and all beverages, other than medicine, intended for human consumption and containing one-half of one percent or more alcohol by volume.

Beer, wine, and liquor have the same meanings as provided in F.S. chs. 563, 564, and 565, respectively.

~~*Bottle club* [deleted]~~

Full course meals means items on a menu at a restaurant which include soups and salads, main dishes with side orders, and desserts.

Kitchen, commercial means a facility used for the preparation of food which is sold to the public and that is subject to state and local health department inspections.

Liquor license means a license issued by the state for the retail sale, service, and consumption of liquor.

~~*Noise* [deleted]~~

~~*Package sales* [deleted]~~

Park, only when used in this division, means a park facility which is owned, leased, or operated by a governmental agency. It does not include beach access strips.

Sale of, only when used in this division, includes the term "or service."

~~*Cross reference(s)--Definitions and rules of construction generally, § 1-2.*~~

Sec. 34-1262. Compliance with applicable regulations.

No structure, building, establishment, or premises shall be occupied, used, or maintained for the purpose of the retail sale, service, or consumption of

alcoholic beverages except in conformity with all applicable town county regulations, including this chapter, and with the applicable state regulations.

Sec. 34-1263. Sale for off-premises consumption.

~~(a) Package stores which have only a 1-APS state liquor license are exempt from this section, except for subsection (c) of this section.~~

(a) Where permitted. ~~(b)~~ The sale of alcoholic beverages for consumption off the premises shall be allowed in any zoning district where retail stores are a permitted use, provided that package stores must meet the additional regulations set forth in subsection (d) of this section. as a permitted use as follows, provided that the regulations set forth in subsection (c) of this section are met:

- (1) in any zoning district wherein package stores are listed as a permitted use, only when the establishment is licensed only as a package store, and
- (2) In any retail sales establishment wherein the sale of alcoholic beverages for consumption off-site is clearly incidental to other retail sales commodities, such as in a grocery store, supermarket, or drugstore, and limited to PS series liquor licenses.

(b) Sealed containers only. ~~(c)~~ Only alcoholic beverages in original factory-sealed containers shall be permitted to be sold for off-premises consumption.

(c) State liquor laws. ~~(d)~~ In addition to the requirements of subsections (a) through (c) of this section, Any establishment primarily engaged in the sale of alcoholic beverages for consumption off-site shall also be required to comply with all applicable state liquor laws and § 1 of Ordinance No. 76-9 of the county.

(d) Location of package stores. ~~(e)~~ No package store or other establishment *primarily* engaged in the retail sale of liquor for consumption off-site shall be permitted closer than 500 feet to any place of worship, religious facility, school (noncommercial), day care center (child), park, or dwelling unit, or 500 feet from any other establishment primarily engaged in the sale of alcoholic beverages.

- (1) For purposes of this subsection, the distance shall be measured in a straight line from any public entrance or exit of the establishment to the nearest property line of the place of worship, religious facility, school (noncommercial), day care center (child), park, or dwelling unit, or any public entrance or exit of any other establishment primarily engaged in the sale of alcoholic beverages.
- (2) Where an establishment for the sale of alcoholic beverages is located in conformity with the provisions of this subsection, and a place of worship, religious facility, school (noncommercial), day care center (child), park, or dwelling unit is subsequently established in the proximity of such existing establishment, then the separation requirements shall not apply.
- (3) Notwithstanding subsection ~~(c)~~(d) (1) of this section, where a package store is located in a multiple-occupancy complex shopping center which is 25,000 square feet or greater in size, or in a retail sales establishment wherein the sale of alcoholic beverages for consumption off-site is clearly incidental to other retail sales commodities, such as in a grocery store, supermarket, or drugstore, the separation requirements from any dwelling unit shall not apply.
- (4) In any ~~PD~~; planned development zoning district; where the applicant is contemplating the sale of alcoholic beverages for consumption off the premises in an establishment which cannot meet the distance requirements set forth in subsection (d) ~~(e)~~ of this section, the applicant shall request a deviation from the requirements of subsection (d) ~~(e)~~.

Sec. 34-1264. Sale or service for on-premises consumption.

(a) Approval required. The sale or service of alcoholic beverages for consumption on the premises shall not be permitted until such location has been approved by the town county as follows:

- (1) Administrative approval. The director ~~of the department of community development~~ may shall administratively approve the sale or service of alcoholic beverages for consumption on the premises when in conjunction with the following uses if the proposed use satisfies the requirements

otherwise set forth in this division. When circumstances so warrant the director may ~~shall~~ determine that administrative approval is not the appropriate action and that the applicant must instead apply for approval as a special exception permit. Such circumstances may include the previous denial ~~by the director or by a hearing board~~ of a similar use at that location, the record of public opposition to a similar use at that location, and similar circumstances. When the director has approved a request for consumption on the premises at a location where the actual building has not been constructed, the director shall not, ~~within one year's time,~~ approve another request for consumption on the premises ~~within one year's time,~~ which could potentially violate the distance requirements. If the first building is completed within less than ~~the one year~~ timeframe, and it can be shown ~~is physically demonstrable~~ that the second use would not violate the prescribed distance requirements, ~~then~~ the director may approve the second location subject to all other requirements contained in this division.

a. ~~County-owned airports, including liquor, beer, malt liquor and wine in restaurants, bars, lounges, concessions, concession stands and package stores at county-owned airports;~~

a. b. Bars or cocktail lounges located in commercial and industrial zoning districts which permit bars or cocktail lounges, provided the standards set forth in subsections (b)(1) and (3) of this section are met;

c. Bottle clubs in commercial and industrial zoning districts which permit bars or cocktail lounges, provided the standards set forth in subsections (b)(1) and (3) of this section are met;

d. Bowling alleys, provided the standards set forth in subsections (b)(2)a and (b)(3) of this section are met;

b. Charter, party fishing boat, or cruise ship, provided the standards of section (b)(3) are met. The COP approval is specific to the charter, party fishing boat, or cruise ship operating from a specific location and does not run with the land nor is it transferable.

c. e. Clubs and fraternal or membership organizations located in commercial and

industrial zoning districts, where permitted, provided the standards set forth in subsections (b)(2)~~d~~ f and (b)(3) of this section are met;

d. f. Cocktail lounges in golf course, tennis clubs, or indoor racquetball clubs, provided the standards set forth in subsections (b)(2)~~c~~ d and ~~e~~ and (b)(3) of this section are met;

e. g. Hotels/motels, provided the standards set forth in subsections (b)(2)~~b~~ c and (b)(3) of this section are met; and

f. h. Restaurants groups II, III and IV, and restaurants with brew public license requirements, provided the standards set forth in subsections (b)(2)~~a~~ b and (b)(3) of this section are met.

(2) Special exception permit.

a. A special exception permit for consumption on the premises shall be required for:

1. Any establishment not covered by subsection (a)(1) of this section; or
2. Any establishment which provides outdoor seating areas for its patrons consuming alcoholic beverages, except that a group II, III, or IV restaurant may have outdoor seating approved administratively provided the outdoor seating area is not within 500 feet of a place of worship, religious facility, school (noncommercial), day care center (child), park, or dwelling unit under separate ownership.

b. The burden of proof that the granting of the special exception permit will not have any adverse effect on surrounding properties ~~shall lie~~ with the applicant.

c. A single special exception permit for consumption on the premises for a multiple-occupancy complex shopping center in a conventional zoning district shall be sufficient to permit consumption on the premises in every restaurant which exists or may be established within the multiple-occupancy complex shopping center.

(3) Planned developments and planned unit developments.

a. No administrative approval is necessary where an individual establishment or other facility proposing consumption on the premises is explicitly designated on the

master concept plan and is included on the approved schedule of uses.

- b. If consumption on the premises is shown as a permitted use on the approved schedule of uses for a multiple-occupancy complex shopping center, no administrative approval for consumption on the premises shall be required for restaurants within the multiple-occupancy complex shopping center.
- c. Consumption on the premises ~~shall not be permitted for other uses within planned developments and planned unit developments~~ require without an administrative approval or a special exception permit.

(b) Location; parking.

(1) Prohibited locations.

- a. Except as may be exempted in subsections (a)(1) ~~of this section or as exempted in subsection (b)(2) of this section~~, no establishment for the sale or service of alcoholic beverages for consumption on the premises shall be located within 500 feet of:
1. ~~Five hundred feet of any~~ A place of worship, religious facility, school (noncommercial), day care center (child), or park;
 2. ~~Five hundred feet of~~ A dwelling unit under separate ownership, except when approved as part of a planned development; or
 3. ~~Five hundred feet of any~~ Another establishment primarily engaged in the sale of alcoholic beverages for consumption on the premises, excluding those uses listed under subsection (b)(2) of this section.

Distance shall be measured from any public entrance or exit of the establishment in a straight line to the nearest property line of the place of worship, religious facility, school (noncommercial), day care center (child), dwelling unit, or park, or to the closest public entrance or exit of any other establishment primarily engaged in the sale of alcoholic beverages.

- b. Where an establishment for the sale of alcoholic beverages is located in conformity with the provisions of this subsection, and a place of worship,

religious facility, school (noncommercial), day care center (child), park or dwelling unit is subsequently established in the proximity of such existing establishment, then the separation requirements shall not apply.

(2) Exceptions to location standards. Exceptions to location standards are as follows:

~~a. Bowling alleys [deleted in its entirety]~~

~~a. b. Restaurants groups II, III and IV,~~ provided that:

1. The restaurant is in full compliance with state requirements;
2. The restaurant serves cooked, full-course meals, prepared daily on the premises; and
3. Only a service bar is used and the sale or service of alcoholic beverages is only to patrons ~~ordering being served~~ meals, or, if the restaurant contains a cocktail lounge for patrons waiting to be seated at dining tables, the lounge shall be ~~so~~ located so that there is no indication from the outside of the structure that the cocktail lounge is within the building.
4. The other requirements of § 34-1264(k) shall be met.

~~b. c. Hotels/motels (4-COP-S license only); ; provided that nightclubs, cabarets, cocktail lounges or bars shall be located within the hotel or motel and under the same roof, which contains at least 100 guestrooms under the same roof, and provided further that the exterior of any such building shall not have storefronts or give the appearance of commercial or mercantile activity as viewed from the highways.~~

1. The hotel/motel contains at least 100 guest rooms under the same roof and that bars or cocktail lounges are located within the hotel or motel and under the same roof; and

2. The exterior of the building must not have storefronts or give the appearance of commercial or mercantile activity visible from the street.

If the use contains windows visible which may be seen from the street highway, the windows shall be of fixed, obscure glass. ~~Such nightclub~~ Access to the cocktail lounge or bar must or cabaret shall be entered only through the lobby; and no

Additional entrances ~~are not shall be~~ permitted unless the ~~An additional~~ entrance or door ~~shall be permitted when~~ the entrance or door opens into an enclosed courtyard or patio (away from the street side) which is enclosed and which is not The additional entrance may not be visible from the street. A fire door or exit shall be permitted, provided that the door or exit is equipped with panic type hardware and locks and is maintained in a locked position except in an emergency.

~~c. d. Golf course clubhouses (H-C (golf club) license only)~~, provided that:

1. The golf course consists of at least nine holes, with a clubhouse, locker rooms, and attendant golf facilities, and comprises in all at least 35 acres of land.
2. Failure of such club to maintain the golf course, clubhouse, and golf facilities shall automatically terminate the privilege of the cocktail lounge and sale of beer from the refreshment stands.

~~e. Tennis clubs and indoor racquetball clubs [deleted in its entirety]~~

~~d. f. Clubs and fraternal or Membership organizations (H-C license only)~~, provided that:

1. such club or organization conforms to all the requirements of a private club as stated in F.S. ch. 561 and other applicable state laws, and
2. providing that there are no signs of any type exhibited or displayed or other indications visible that can be seen from the exterior of the clubhouse, building, or structure that alcoholic beverages are served.

Before a certificate of use and occupancy to serve alcoholic beverages will be issued, the applicant must submit necessary data to prove that it is eligible for the use and complies with F.S. ch. 561 or other applicable state laws, provided, anything to the contrary notwithstanding. These requirements must be complied with, even though the club intends to serve only beer or wine:

- (3) **Parking.** Restaurants providing alcoholic beverages for consumption on the premises must comply with the parking requirements

set forth in § 34-2020(2). Any bar or cocktail lounge must provide parking in accordance with § 34-2020(2). All other uses must meet the parking requirements of the principal use.

(c) **Procedure for approval.**

(1) **Administrative approval.**

a. **Application.** An applicant for a consumption on the premises permit shall submit, on a form provided by the county, the following information on a form provided by the town:

1. The name, address, and telephone number of the applicant.
2. The name, address, and telephone number of the owner of the premises, if not the applicant.
3. A notarized authorization from the property owner to apply for the permit.
4. Location by STRAP and street address.
5. Type of state liquor license being requested.
6. A site plan, drawn to scale, showing:
 - i. The property in question, including all buildings on the property and adjacent property;
 - ii. Entrances to and exits from the building to be used by the public;
 - iii. A parking plan, including entrances and exits;
 - iv. The floor area of the building and proposed seating capacity. If a restaurant is proposing a bar or lounge for patrons waiting to be seated in the restaurant, the floor area and seating area of the lounge shall be shown in addition to the restaurant seating area.
7. A town county map marked to indicate all of the property within 500 feet of the building to be used for consumption on the premises.
8. An notarized affidavit executed by the applicant indicating that no place of worship, religious facilities, day care centers (child), noncommercial schools, dwelling units or parks are located within 500 feet of the building to be used.

~~b. Additional requirements for bottle clubs. [deleted in its entirety]~~

~~b. c. Findings by director.~~ Prior to approving a permit approval, the director shall

~~conclude~~ ascertain that all applicable standards have been met. In addition, the director shall make the following findings of fact:

1. There will be no apparent deleterious effect ~~of such use~~ upon surrounding properties and the immediate neighborhood as represented by property owners within 500 feet of the premises.
2. The premises are suitable in regard to their location, site characteristics, and intended purpose. Lighting ~~on the permitted premises shall~~ must be shuttered and shielded from surrounding properties.

(2) ***Special exception permit***

- a. Applications for special ~~exceptions~~ permits shall be submitted on forms supplied by the town ~~county~~ and shall contain the same information as required for administrative approval.
- b. Advertisements and public hearings shall be conducted in accordance with the requirements set forth in article II of this chapter.

(d) ***Temporary one-day permit***

- (1) ***Intent; applicability.*** It is the intent of this subsection to require that nonprofit and for-profit organizations and establishments in the town ~~unincorporated area of the county~~ obtain a one-day temporary alcoholic beverage permit for the sale of alcoholic beverages at the specific location where an event is held. This subsection will pertain to but not necessarily be limited to the following uses:

- a. Grand openings or open houses at residential; ~~or commercial or industrial~~ developments;
- b. Special outdoor holiday or celebration events at bars and restaurants ~~which are or are not already special permitted~~;
- c. Weddings and other special occasions at clubhouses;
- d. Political rallies or events;
- e. Block parties; and
- f. Carnivals.

- (2) Only twelve temporary alcoholic beverage permits may be issued per year to a specific location. If more than twelve permits are

sought per year for a specific location, then the location must obtain a permanent alcoholic beverage special exception permit. If the event for which the temporary alcoholic beverage permit is sought continues for longer than one day, the applicant may petition the director for an extended permit. A temporary alcoholic beverage permit may not be issued for more than three days.

(3) ~~(2)~~ ***Procedure for approval.***

- a. Any owner, lessee, or tenant seeking approval for consumption on the premises for a temporary alcoholic beverage permit, must submit a written request to the director ~~department of community development~~. The written request must include:

1. The name and address of the applicant;
2. A general description of the exact site where alcoholic beverages are to be sold and consumed;
3. The type of alcoholic beverages to be sold and consumed; and
4. ~~The payment of~~ A fee in accordance with the adopted fee schedule.

- b. The director will make a final decision within ten working days. The decision will be in the form of approval, approval with conditions or denial. The director may forward the request to other appropriate agencies for comment.

- c. The town council ~~Board of County Commissioners~~ will review all requests for temporary alcoholic beverage permits where an event will run longer than three days. Under no circumstances will a temporary alcoholic beverage permit be issued for more than ten days.

(e) ***Expiration of approval.*** After the following time periods, the administrative or special exception permit approval of a location for the sale and consumption of alcoholic beverages for consumption on the premises granted in accordance with pursuant to this section shall expire after the following periods of time, and shall thereafter become null and void:

- (1) In the case of an existing structure, the approval shall expire six months from the date of approval unless, within that period of time, operation of the alcoholic beverage establishment has commenced. For purposes of this subsection, the term "operation" shall

be defined as the sale of alcoholic beverages in the normal course of business.

- (2) In the case of a new structure, the approval shall expire one year from the date of approval unless, within that period of time, operation of the alcoholic beverage establishment has commenced. ~~However, if substantial construction is completed; The director may grant one extension of up to six months if construction is substantially complete.~~

(f) **Transfer of permit.** Alcoholic beverage permits, ~~as noted in subsection 34-1264(i) excluding permits for bottle clubs, issued by virtue of this section are shall be deemed to be a privilege running with the land. The Sale of the real property which has been granted an alcoholic beverage permit shall automatically vest the purchaser thereof with all rights and obligations originally granted to or imposed on the applicant. Such privilege may not be separated from the fee simple interest in the realty.~~

(g) **Expansion of area designated for permit.** The area designated for an alcoholic beverage permit cannot be expanded without filing a new application for an alcoholic beverage permit in accordance with the requirements contained in this chapter. The new application must cover both the existing designated area as well as the proposed expanded area. All areas approved must be under the same alcoholic beverage permit and subject to uniform rules and regulations.


(h) **Nonconforming establishments.**

- (1) **Expansion.** A legally existing establishment engaged in the sale or service of alcoholic beverages which is made nonconforming by reason of new the regulations contained in this chapter section shall not be expanded without a special exception permit. The term "expansion," as used in this subsection, shall include the enlargement of space for such use and uses incidental thereto, the expansion of a beer and wine bar to include intoxicating liquor, as that term is defined by the Florida Statutes, and the expansion of a bar use to a nightclub use. Nothing in this subsection; ~~however, shall be deemed may be construed as an attempt to modify any prohibition or diminish make less restrictive any requirement of the laws of the state.~~

- (2) **Abandonment.** An establishment engaged in the sale or service of alcoholic beverages Any uses, created and established in a legal manner, which may thereafter become a nonconforming; use due to a change in regulations, as provided in division 3 of article V of this chapter. Nonconforming uses may continue until there is an abandonment of the permitted location for a continuous nine- six-month period. For purposes of this subsection, the term "abandonment" shall mean failure to use the location for consumption on the premises purposes as authorized by the special exception, permit or administrative approval, or other approval. Once a nonconforming use is abandoned, it cannot be reestablished unless it can conforms to the requirements of this chapter; and ~~such use may be reestablished only after issuance of new permits are issued.~~

(i) **Revocation of permit or approval.**

- (1) The town council Board of County Commissioners has the authority to revoke an alcoholic beverage special exception, permit or administrative approval, or other approval upon any of the following grounds:
- A determination that an application for special exception permit or administrative approval contains knowingly false or misleading information.
 - Violation by the permit holder of any provision of this chapter, or violation of any state statute which results in the revocation of the permit holder's state alcoholic beverage license by the state alcoholic beverage license board or any successor regulatory authority.
 - Repeated violation of any town county ordinance at the location within the 12-month period preceding the revocation hearing.
 - Failure to renew a state liquor license, or written declaration of abandonment by the tenant and owner of the premises if under lease, or by the owner himself if not under lease.
 - Abandonment of the premises. An establishment which continually maintains (renews) its state liquor license, even though it has suspended active business with the public, shall not be deemed to



have been abandoned for purposes of this subsection.

- f. Violation by the permit holder of any condition imposed upon the issuance of the special exception or administrative approval permit.
 - g. Violation of any of the minimum standards of the special exception permit.
- (2) Prior to revoking an administrative approval, ~~or special exception, or other approval permit~~ for alcoholic beverages, the town council Board of County Commissioners shall conduct a public hearing at which the permit holder may appear and present evidence and testimony concerning the proposed revocation. At the hearing, the town council board may revoke the permit if a violation described in this subsection is established by a preponderance of the evidence. The permit holder shall be notified of the grounds upon which revocation is sought prior to any hearing, and shall be given notice of the time and place of the hearing in the same manner as set forth in article II of this chapter.
- (3) When an alcoholic beverage permit is revoked in accordance with pursuant to the terms of this subsection, ~~no the town may not consider a~~ petition requesting an alcoholic beverage permit shall be considered by the ~~county~~ for on the property for a period of 12 months from the date of final action on the revocation.
- (4) Upon written demand of the town council, any owner or operator of an establishment with a COP license shall, ~~upon written demand of the Board of County Commissioners~~, must make, under oath, a statement itemizing the what percentage of his gross receipts that are from the sale of alcoholic beverages. Failure to comply with such demand within 60 days of the date of demand shall be grounds for revocation of the special exception, administrative approval, or other approval permit.

(j) **Appeals.** All appeals of decisions by the director shall be in accordance with pursuant to procedures set forth in § 34-86 article II or article IV of this chapter for appeals of administrative decisions.

(k) **Alcoholic beverages in restaurants.** The sale of alcoholic beverages for on-premises consumption

in restaurants (see § 34-1264(b)(2)) must conform to the following regulations:

- (1) The sale of alcoholic beverages must be incidental to the sale of food, and restaurants permitted to serve alcohol shall provide that food service facilities will remain open serving appropriate food items on the menu at all times coincident with the sale of alcoholic beverages.
- (2) The sale of alcoholic beverages shall be permitted only when it accounts for no more than 49% of the combined gross sales attributable to the sale of food and all beverages during any continuous twelve-month period.
- (3) Restaurants selling alcoholic beverages shall keep separate books and records reflecting the gross sales of food and nonalcoholic beverages and the gross sales of alcoholic beverages for each month. The failure to keep the books and records required herein shall be a violation of this code.
- (4) The town manager or designee may, during normal working hours, request to inspect and audit the books and records of the business from which alcoholic beverages sales are made wholly for the purpose of verifying that the gross sales of alcoholic beverages are no more than 49% of the gross sales of food and all beverages during any continuous twelve-month period. Refusal of an owner or operator of such business to allow said inspection shall be a violation of this code. Should the audit reveal that this requirement is not being met, the town manager shall initiate enforcement proceedings for a violation of this code.
- (5) For any restaurant which has been selling alcoholic beverages for less than twelve months, the provisions of this section shall be interpreted and applied with respect to said lesser period of time.
- (6) These regulations may be enforced through the normal code enforcement procedures ~~in § 1-5 of this code (for example, § 1-5, or article V of ch.2)~~. In addition to these procedures, violations of these regulations may be restricted by injunction initiated by the Town of Fort Myers Beach, by any citizen thereof, or by any person affected by the violation of such regulations.

Secs. 34-1265--34-1290. Reserved.

DIVISION 6. ANIMALS

Sec. 34-1291. Keeping of animals. Applicability of division:

The keeping, raising, or breeding of ~~horses and other~~ any livestock, including poultry, ~~of all kinds~~ usually and customarily considered as farm animals, and the keeping, raising, or breeding of reptiles, marine life, or animals not indigenous to the state, shall not be permitted ~~only as set forth in this division~~. This shall not be interpreted as applying to pet stores or hobbyists keeping aquariums or domestic tropical birds in their own homes.

~~Sec. 34-1292. Horses and other equines. [deleted in its entirety]~~

~~Sec. 34-1293. Goats, sheep and swine. [deleted in its entirety]~~

~~Sec. 34-1294. Noncommercial poultry raising. [deleted in its entirety]~~

~~Sec. 34-1295. Dairy barns, commercial poultry raising. [deleted in its entirety]~~

~~Sec. 34-1296. Other setbacks, exceptions to setback requirements. [deleted in its entirety]~~

~~Sec. 34-1297. Activities requiring special approval. [deleted in its entirety]~~

Secs. 34-12928--34-1320. Reserved.

DIVISION 7. ANIMAL CLINICS AND KENNELS FACILITIES

Sec. 34-1321. Permitted activities.

(a) Kennels, animal clinics, and boarding facilities are limited to the raising, breeding, treating, boarding, training, grooming, and sale of domestic animals.

(b) Kennels, animal clinics, and boarding facilities are permitted in any zoning district where Offices, general or medical are a permitted use.

Sec. 34-1322. Enclosure of facilities.

(a) Except as specifically provided in this ~~division~~, All animal clinics, animal kennels, and boarding facilities shall be completely enclosed within an air conditioned, soundproof building and shall have no outdoor cages, pens, runs, or exercise facilities.

~~(1) Completely enclosed facilities.~~

~~(2) Facilities not completely enclosed. [deleted in its entirety]~~

Secs. 34-1323--34-1350. Reserved.

DIVISION 8. AUTOMOTIVE BUSINESSES; DISPLAY, RENTAL, REPAIR, OR STORAGE OF VEHICLES OR EQUIPMENT

Sec. 34-1351. Automobile repair and service.

(a) All services performed by an automobile repair and service establishment, including repair, painting, and body work activities, shall be performed within a completely enclosed building.

(b) Whenever an automotive repair and service establishment is within 75 feet of a residential use, all refuse and vehicle parts shall be stored within a completely enclosed area.

(c) New or expanded automobile repair establishments can be permitted only through approval of a suitable planned development zoning district (see § 34-620(d)).

Sec. 34-1352. Display, sale, rental, or storage facilities for motor vehicles, boats, recreational vehicles, trailers, mobile homes or equipment.

(a) Applicability. This section applies to all establishments engaged in the outdoor display, sale, rental, or storage of motor vehicles, boats, recreational vehicles, trailers, construction equipment, and similar vehicles and equipment. mobile homes, construction or farm equipment, or other similar items, except water-oriented rental establishments: outdoors, regulated by § 34-3151.

(b) New or expanded Prohibited uses. New or expanded establishments can be permitted only through approval of a suitable planned development zoning district (see § 34-620(d)).

(1) ~~Except as provided in this section, No units shall be used as sales offices or storage space. Any sales office or storage space, other than for the units, shall be in a conventional building.~~

(2) ~~A mobile home may be used as an office for sales of mobile home lots or units which are located within the mobile home development only.~~

(c) *Setbacks.*

(1) All buildings and structures shall comply with the setback requirements for the zoning district in which the use is located.

(2) All items covered by this section which are displayed or offered for sale ~~or rent~~ shall be set back a minimum of ten feet from any property line, unless ch. 10 sets forth a different setback, in which case the greater setback will apply.

(d) *Display and parking areas.*

(1) No parking space or loading zone required by the parking regulations set forth in this chapter shall be used for the display of merchandise.

(2) Areas used for display may be grass or other surface, provided it is maintained in a sightly, dustfree manner.

(e) *Storage areas.* Areas used for the commercial storage of motor vehicles, ~~boats~~, trailers, recreational vehicles, mobile homes and construction ~~or farm~~ equipment which is not being displayed for sale or rent shall be enclosed (see division 36 of this article), unless Storage, open is permitted through approval of a suitable planned development zoning district (see § 34-620(d)).

(f) *Lighting.* Artificial lighting used to illuminate the premises shall be directed away from adjacent properties and streets, shining only on the subject site.

Sec. 34-1353 Automobile rental.

New or expanded establishments renting automobiles or trucks must obtain a special exception for Automobile rental in accordance with division 2 of article III of this chapter.

Secs. 34-1354--34-1380. Reserved.

DIVISION 9. BUS DEPOTS, STATIONS AND TRANSIT TERMINALS

Sec. 34-1381. Purpose of division.

The purpose of this division is to set forth standards and criteria for the safe and efficient development of transit bus stations/depots and bus terminals whereby they may be permitted by right or special exception: in accordance with Tables 34-1 and 34-2. A central transit terminal is encouraged by Policy 7-D-1 of the Fort Myers Beach Comprehensive Plan to connect local trolleys and taxis with an airport shuttle service.

Sec. 34-1382. Site plan.

All applications for a ~~special exception or change of use for a bus station/depot or bus transit~~ terminal shall include a site plan, drawn to scale, indicating but not limited to following:

- (1) The location of the bus stalls.
- (2) Commuter parking, if provided.
- (3) Taxi waiting stalls.
- (4) Circulation pattern of the buses including within and through the parking lot.
- (5) ~~Bus ingress and egress points to or from the parking lot.~~
- (5) ~~(6)~~ The location of the any building housing the bus station/depot or bus transit terminal and the area designated for a waiting area, to include the storage and handling of luggage and parcels.

Sec. 34-1383. Access.

(a) The site plan shall be designed so that the location of ingress and egress points and turning radii are adequate for the anticipated vehicles, and the turning radii for buses are in accordance with the design standards as depicted in the latest edition of the publication of the American Association of State Highway and Transportation Officials (AASHTO), A Policy on Geometric Design of Highways and Streets, in order to provide safe and efficient maneuverability.

(b) All buses exiting a parking lot must enter the street right-of-way in a forward motion.

(c) The site plan shall ensure safe and adequate access to collector or arterial streets.

Sec. 34-1384. Parking generally.

(a) *Off-street Parking.* The parking for a bus station/depot or bus transit terminal where the loading and unloading of passengers, luggage, or parcels may occur shall meet the following minimum requirements:

- ~~(1) One parking space, excluding parking space for buses, shall be required per 100 square feet of total floor area dedicated to passenger waiting area, and one space shall be required per 1,000 square feet of total floor area dedicated to ticket sales or baggage or parcel handling areas.~~
- (1) (2) Parking spaces shall be required for all buses using the site. A minimum of one bus parking space shall be required for each bus carrier using the facility. If arrival and departure times run concurrently, then additional parking must be provided to ensure that each bus has a separate parking space.
- (2) (3) The parking spaces for each bus stall shall be designated by signage and pavement markings and:
- (4) Each bus parking stall shall be a minimum of 12 feet by 50 feet in size for parallel or diagonal parking.
- (5) All required parking shall have a paved, dustfree, all-weather surface.
- (3) (6) For every 12 daily scheduled bus arrivals and departures, or a portion thereof, at locations where passengers may disembark, one parking space for taxicabs and one parking space for commuters shall be required.

(b) *On-street parking.* In some instances, it may be appropriate for a transit terminal bus station/depot to have the buses parked within an adjacent road right-of-way. In all such instances, the location of the bus turnout, proximity to the transit terminal, bus station/depot and how the bus will enter and exit the turnout must be shown on the site plan.

Sec. 34-1385. Parking for bus terminals: *[deleted in its entirety]*

Sec. 34-1386. Modification of parking requirements: *[deleted in its entirety]*

Sec. 34-1387. Expansion of existing bus station/depot: *[deleted in its entirety]*

Secs. 34-1385--34-1410. Reserved.

**DIVISION 10.
CARE AND ASSISTED LIVING FACILITIES
AND CENTERS**

Sec. 34-1411. Assisted living facilities. Adult congregate living facilities

(a) *Location.* Adult congregate Assisted living facilities (AGLF's) may be located in zoning districts by right or by special exception, as specified in the district use regulations, but provided that they are ~~shall be~~ subject to the maximum density ranges for the land use category applicable to the subject property, with density ~~shall be~~ calculated in accordance with §§ 34-1415, 91 through 1495 division 12, subdivision H, of this article.

(b) *Design.*

- (1) An adult congregate assisted living facility permitted in a zoning district which permits only single-family residences shall must be designed so as to appear as, and be compatible with, adjacent residential buildings, a single-family residence.
- (2) An adult congregate living facility permitted in a zoning district which permits only single-family, two-family attached or duplex dwelling units shall be designed so as to be compatible with such dwelling units.
- (3) An adult congregate living facility permitted in a multiple-family zoning district shall be designed so as to be compatible with surrounding multiple-family buildings.
- (4) An adult congregate living facility permitted in a CF district shall be designed so as to be compatible with the type of dwelling units which are adjacent thereto.

(c) *Lot dimensions and setbacks.* Adult congregate living facilities shall be subject to the property development regulations applicable to the zoning district within which they are located.

(c) (d) *Parking.* For parking requirements, see § 34-2020(d)(1). *[remainder of subsection deleted]*

Secs. 34-1412, 34-1413. Reserved.

Sec. 34-1414. Continuing care facilities.

(a) *Generally.* Continuing care facilities (CCF's) may only be located in a CFPD or RPD district, if as enumerated on the master concept plan, provided that:

- (1) Continuing care facilities shall be subject to the maximum density ranges for the land use category applicable to the subject property, with density shall be calculated in accordance with § 34-1415, subsection (c) of this section.
- (2) ~~A continuing care facility must contain one or more health care facilities group I or H, for on-site patient care.~~

(b) *Design; required facilities.*

- (1) A continuing care facility shall provide housing for older persons pursuant to title VII USC.
- (2) A continuing care facility must provide full common dining facilities on the site. Individual units may be equipped with kitchens, but an average of at least one meal a day must be provided by the continuing care facility for all residents.
- (3) A continuing care facility must incorporate one or more resident services on the site, such as banking facilities, barbershops, or beauty shops, pharmacies, and laundry or dry cleaning.
- (4) A continuing care facility must provide a shuttle bus service or similar transportation service for residents.

~~(d) *Lot dimensions and setbacks.* Continuing care facilities shall be subject to the property development regulations applicable in the CFPD district.~~

~~(c) *(e) Parking.* For parking requirements, see § 34-2020(d)(1) et seq. division 26 of this article.~~

Sec. 34-1415. Density equivalents.

[content moved from § 34-1494]

(a) Where assisted living facilities (ALF), continuing care facilities (CCF), or other “group quarters” are provided in living units, each of which has its own cooking facilities, density equivalents will be calculated on a 1:1 ratio.

(b) Except as may be specifically set forth elsewhere in this chapter, where assisted living

facilities, continuing care facilities, or other “group quarters” are provided in living units or other facilities wherein each unit does not have individual cooking facilities and where meals are served at a central dining facility or are brought to the occupants from a central kitchen, density equivalents will be calculated at the ratio of four people being equivalent to one dwelling unit.

(c) Independent living units within a licensed continuing care facility will be calculated on the basis of two independent living units being equivalent to one residential dwelling unit.

Secs. 34-1416--34-1440. Reserved.

DIVISION 11. COMMERCIAL ANTENNAS AND COMMUNICATION TOWERS

~~Sec. 34-1441. Required approvals. *[deleted in its entirety]*~~

~~Sec. 34-1442. Location generally, compliance with airport hazard regulations. *[deleted in its entirety]*~~

~~Sec. 34-1443. Protection of adjacent property. *[deleted in its entirety]*~~

~~Sec. 34-1444. Setbacks for accessory buildings. *[deleted in its entirety]*~~

~~Sec. 34-1445. Fencing. *[deleted in its entirety]*~~

~~Sec. 34-1446. Warning signs for high-voltage facilities. *[deleted in its entirety]*~~

Sec. 34-1441. Purpose and intent.

(a) The purpose of this division is to regulate commercial antennas, the structures on which they are located, and communication towers.

(b) Cellular telephones and other personal communications services rely on a network of antennas. Due to its location, Fort Myers Beach can be served partially by nearby antennas on the mainland and partially by antennas placed on tall buildings within the town. Only rarely, if ever, will a free-standing communications tower be needed to support any type of commercial antenna. These regulations are designed to facilitate the location of commercial antennas on tall buildings and also to

provide a procedure for approving a new communication tower where it can be demonstrated conclusively that one is required.

(c) Amateur radio antenna/towers and satellite dishes are not regulated by this division; see § 34-1175.

Sec. 34-1442. Definitions

For purposes of this division, certain terms are defined as follows:

Alternative support structure means any man-made structure, except communication towers, including, but not limited to, buildings, power poles, light poles, clock towers, bell towers, steeples, water towers, and other similar structures suitable for the attachment of commercial antennas.

Commercial antenna means an exterior apparatus used for transmitting and/or receiving radio-frequency signals for the convenience of users not employed or residing on the premises.

Communication tower means a tower structure that is designed and constructed primarily to elevate one or more commercial antennas for communications purposes, whether such tower is mounted on the ground or on another structure.

Old tower means a communication tower that existed or was granted a special exception prior to March 3, 2003.

New tower means a communication tower that requires approval under this section.

Sec. 34-1443. Commercial antennas mounted on alternative support structures.

(a) Zoning districts. Commercial antennas on alternative support structures may be approved in all zoning districts, except that no commercial antenna may be permitted on a single family, duplex, or two-family home or its accessory building or structure.

(b) Administrative approval required. The town manager may issue administrative approval for commercial antennas to be mounted on alternative support structures when they comply with the standards in subsection (c) and the remainder of this code. The town manager's decision may be appealed in accordance with § 34-86.

(c) Standards. Commercial antennas mounted on alternative support structures must meet the following standards:

- (1) Neither the antenna, its supporting structure, or any ancillary structure may extend more than 10 feet above the highest existing point of the roof; and
- (2) The antenna and related structures including equipment rooms shall be concealed from view or designed and maintained to blend into the surrounding environment.
 - a. Concealment may be accomplished using parapet walls or existing mechanical facilities, or through the use of screening devices such as lattice enclosures.
 - b. Blending may be accomplished through the physical arrangement of antenna elements and through painting or coating of surfaces to match the primary structure in a way that makes them visually unobtrusive.

(d) Nonconformities. The installation of a commercial antenna on a nonconforming building or a building containing a nonconforming use will not be deemed to constitute the expansion of the nonconformity.

Sec. 34-1444. Commercial antennas mounted on communication towers.

(a) Required zoning approvals. New communication towers suitable for commercial antennas may be approved by special exception, as provided in division 2 of article III of this chapter, subject to the additional requirements of this division. Special exception applications for communication towers must also include the same documentation required by Lee County through its land development code.

(b) Required sharing of communication towers. The owner/operator of any proposed new communication tower must enter into an agreement (shared-use plan agreement) with the town or county requiring the owner/operator of the proposed tower to honor all reasonably and technically feasible requests for shared use of the tower for additional commercial antennas.

- (1) New towers must be designed to withstand a wind load of at least 120 mph (TIA/EIA Standard 222-F) and must accommodate three additional carriers with a minimum

wind loading of 160 sq. ft. factored area including the mounting bracket.

- (3) Once a shared-use plan for a tower is approved, additional antennas may be added to that tower in accordance with the approved shared-use plan without additional special exception approval.

(c) Development standards for communication towers. The owner/operator of any new communication tower must also obtain a development order and comply with the specific development standards for communication towers required by Lee County through its land development code.

~~Secs. 34-14465--34-1550+470. Reserved.~~

~~DIVISION 12. DENSITY~~

~~Subdivision I. In General
[deleted in its entirety]~~

~~Subdivision II. Residential Development~~

~~Sec. 34-1491. Applicability of subdivision:
[deleted in its entirety]~~

~~Sec. 34-1492. Definitions:
[deleted in its entirety]~~

~~Sec. 34-1493. Calculation of total permissible housing units.~~

~~The Lee Plan establishes a standard and maximum residential density range permissible for each residential land use category. The procedure set forth in this section shall be used to determine the standard residential density as well as the total number of housing units which may be permitted within a development.~~

- ~~(1) Proposed developments. [deleted in its entirety, content moved to § 34-632]
(2) Existing developments and lots. [deleted in its entirety, content moved to § 34-3273]~~

~~Sec. 34-1494. Density equivalents:
[subject moved to 34-1415]~~

~~Sec. 34-1495. Density limitations for specific areas:
[deleted in its entirety]~~

~~Subdivision III.~~

~~Housing Density Bonus for Provision of Low- and Moderate-Income Housing
[deleted in its entirety]~~

~~Subdivision IV. Captiva Island
[deleted in its entirety]~~

DIVISION 12-A. DRUG PARAPHERNALIA

Sec. 34-1551. Drug paraphernalia defined.

The term “drug paraphernalia” means all equipment, products, and materials of any kind which are used, intended for use, or designed for use in planting, propagating, cultivating, growing, harvesting, manufacturing, compounding, converting, producing, processing, preparing, testing, analyzing, packaging, repackaging, storing, containing, concealing, transporting, injecting, ingesting, inhaling, or otherwise introducing into the human body a controlled substance in violation of state law. Drug paraphernalia includes, but is not limited to:

- (1) Kits used, intended for use, or designed for use in the planting, propagating, cultivating, growing, or harvesting of any species of plant which is a controlled substance or from which a controlled substance can be derived.
- (2) Kits used, intended for use, or designed for use in manufacturing, compounding, converting, producing, processing, or preparing controlled substances.
- (3) Isomerization devices used, intended for use, or designed for use in increasing the potency of any species of plant which is a controlled substance.
- (4) Testing equipment used, intended for use, or designed for use in identifying, or in analyzing the strength, effectiveness, or purity of, controlled substances.
- (5) Scales and balances used, intended for use, or designed for use in weighing or measuring controlled substances.
- (6) Diluents and adulterants, such as quinine hydrochloride, mannitol, mannite, dextrose, and lactose, used, intended for use, or designed for use in cutting controlled substances.
- (7) Separation gins and sifters used, intended for use, or designed for use in removing twigs

and seeds from, or in otherwise cleaning or refining, cannabis.

- (8) Blenders, bowls, containers, spoons, and mixing devices used, intended for use, or designed for use in compounding controlled substances.
- (9) Capsules, balloons, envelopes, and other containers used, intended for use, or designed for use in packaging small quantities of controlled substances.
- (10) Containers and other objects used, intended for use, or designed for use in storing, concealing, or transporting controlled substances.
- (11) Hypodermic syringes, needles, and other objects used, intended for use, or designed for use in parenterally injecting controlled substances into the human body.
- (12) Objects used, intended for use, or designed for use in ingesting, inhaling, or otherwise introducing cannabis, cocaine, hashish, hashish oil, or nitrous oxide into the human body, such as:
 - a. Metal, wooden, acrylic, glass, stone, plastic, or ceramic pipes, with or without screens, permanent screens, hashish heads, or punctured metal bowls.
 - b. Water pipes.
 - c. Carburetion tubes and devices.
 - d. Smoking and carburetion masks.
 - e. Roach clips, meaning objects used to hold burning material, such as a cannabis cigarette, that has become too small or too short to be held in the hand.
 - f. Miniature cocaine spoons and cocaine vials.
 - g. Chamber pipes.
 - h. Carburetor pipes.
 - i. Electric pipes.
 - j. Air-driven pipes.
 - k. Chillums.
 - l. Bongs.
 - m. Ice pipes or chillers.
 - n. A cartridge or canister, which means a small metal device used to contain nitrous oxide.
 - o. A charger, sometimes referred to as a "cracker," which means a small metal or plastic device that contains an interior pin that may be used to expel nitrous oxide from a cartridge or container.

- p. A charging bottle, which means a device that may be used to expel nitrous oxide from a cartridge or canister.
- q. A whip-it, which means a device that may be used to expel nitrous oxide.

Sec. 34-1552. Determination of paraphernalia.

In determining whether an object is drug paraphernalia, the hearing examiner, court, jury, or other enforcing authority shall consider, in addition to all other logically relevant factors, the following:

- (1) Statements by an owner or by anyone in control of the object concerning its use.
- (2) The proximity of the object, in time and space, to a direct violation of state law.
- (3) The proximity of the object to controlled substances.
- (4) The existence of any residue of controlled substances on the object.
- (5) Direct or circumstantial evidence of the intent of an owner, or of anyone in control of the object, to deliver it to persons who he or she knows, or should reasonably know, intend to use the object to facilitate a violation of state law. The innocence of an owner, or of anyone in control of the object, as to a direct violation of this code or state law shall not prevent a finding that the object is intended for use, or designed for use, as drug paraphernalia.
- (6) Instructions, oral or written, provided with the object concerning its use.
- (7) Descriptive materials accompanying the object which explain or depict its use.
- (8) Any advertising concerning its use.
- (9) The manner in which the object is displayed for sale.
- (10) Whether the owner, or anyone in control of the object, is a legitimate supplier of like or related items to the community, such as a licensed distributor of or dealer in tobacco products.
- (11) Direct or circumstantial evidence of the ratio of sales of the object or objects to the total sales of the business enterprise.
- (12) The existence and scope of legitimate uses for the object in the community.
- (13) Expert testimony concerning its use.

Sec. 34-1553. Manufacture and delivery of drug paraphernalia.

No land or structure shall be used or permitted to be used, and no structure shall hereafter be erected, constructed, moved, altered, or maintained in any zoning district, for the purpose of delivering, possessing with intent to deliver, or manufacturing with intent to deliver drug paraphernalia, knowing, or under circumstances where one reasonably should know, that it will be used:

- (1) To plant, propagate, cultivate, grow, harvest, manufacture, compound, convert, produce, process, prepare, test, analyze, pack, repack, store, contain, or conceal a controlled substance in violation of state law; or
- (2) To inject, ingest, inhale, or otherwise introduce into the human body a controlled substance in violation of state law.

Secs. 34-1554--34-1570. Reserved.

DIVISION 13. ENVIRONMENTALLY SENSITIVE AREAS

Sec. 34-1571. Purpose of division; areas of concern.

Several of the goals, objectives, and policies set forth in the Fort Myers Beach Comprehensive Lee Plan address development as it relates to the preservation, protection, enhancement, and restoration of the ~~coastal and inland~~ natural resources of the town county.

- (1) Coastal resources including: The coastal zone is of special concern. The coastal zone includes but is not limited to the following natural systems:
 - a. Marine: Gulf of Mexico.
 - b. Estuarine: Coastal bays, coastal lagoons, coastal tributaries, forested saltwater wetlands, nonforested saltwater wetlands and sea grass beds.
 - c. Terrestrial: Beaches, dunes, coastal ridge, overwash plain, and zones of archaeological sensitivity (see ch. 22).
- (2) Other natural resources including: areas of concern which may require special regulations are:
 - a. Wetlands as defined in this code. Resource protection areas, as defined ch. 14, article IV, pertaining to wetlands protection.

b. Areas which provide critical habitat of rare and endangered plant and animal species listed in the publication Official Lists of Endangered and Potentially Endangered Fauna and Flora in Florida, ~~of the state game and fresh water fish commission~~; as periodically updated.

~~c. Areas which have significant impact upon the quality of groundwater and receiving waters.~~

~~d. Transition zones, which are lands that may be seasonally inundated for periods of from one to three months as indicated by water marks, and do not have depressional soils and are characterized by a mixture of plant species typical of uplands and wetlands.~~

c. Significant Areas of rare and unique upland habitats (RU) as indicated in the Lee County's 1988 coastal study, including but not limited to the following:

1. Sand scrub (320).
2. Coastal scrub (322).
3. Those pine flatwoods (411) which can be categorized as mature due to the absence of severe impacts caused by logging, drainage, and exotic infestation.
4. Slash pine/midstory oak (412).
5. Tropical hardwood (426).
6. Live oak hammock (427).
7. Cabbage palm hammock (428).

The numbered references are to the Florida Land Use Cover and Forms Classification System (FLUCFCS), level III (FDOT, 1985).

Sec. 34-1572. Applicability of division.

All areas proposed for development or rezoning which are designated as Wetlands resource protection or transition zone areas on the future land use ~~plan~~ map, or which come under the criteria set forth in § 34-1571, shall be subject to the general as well as the specific regulations set forth in this division.

Sec. 34-1573. Environmental assessment report.

When environmentally sensitive ecosystems occur, as identified by the town county, the U.S. Army Corps of Engineers, the state department of environmental protection, the South Florida Water

Management District or other applicable regulatory agency, the developer or applicant shall prepare an environmental assessment that examines the existing conditions, addresses the environmental impacts, and proposes means and mechanisms to protect, conserve, or preserve the environmental and natural resources of these ecosystems.

Sec. 34-1574. Compliance with applicable regulations; new roads, development, or expansion of existing facilities.

(a) Any use permitted or permissible in environmentally sensitive areas shall be subject to all applicable state and federal regulations as well as applicable town county regulations.

(b) Except in instances of overriding public interest, new roads, private land development, or the expansion of existing facilities within Wetlands or on the sandy beaches that are designated in the Recreation category in the Fort Myers Beach Comprehensive Plan resource protection and transitional zones shall be prohibited.

Sec. 34-1575. Coastal zones.

(a) Development, other than minor structures, is prohibited shall not be allowed seaward of the coastal construction control line as established by the state department of environmental protection, as such line existed in 1988. This line has been incorporated into the future land use map of the Fort Myers Beach Comprehensive Plan as the landward boundary of the beachfront Recreation category (see also Policy 5-D-1.v), and as the landward boundary of the EC zoning district (see § 34-652).

(b) For purposes of this section, minor structures mean:

- (1) pile-supported elevated dune and beach walk-over structures,
- (2) beach access ramps and walkways,
- (3) stairways,
- (4) fences, and
- (5) pile-supported viewing platforms, boardwalks and lifeguard support stands.

(c) Minor structures do not include structures supported by or extensions of the principal structure. The minor structures identified as acceptable in this section are considered expendable under design wind, wave, and storm forces.

~~(b) Development within the coastal zone must be compatible with protection of natural systems and in accordance with applicable coastal construction codes.~~

~~(d) (c)~~ No vehicular or foot traffic from developments or access strips to crossovers will be allowed to cross over directly on dune ridges or beach escarpments. Access to the beach must be via elevated dune walkovers.

- ~~(e) (d)~~ No development will be permitted which:
- ~~(1) Could restrict, impede, impound or otherwise interfere with tidal flow or drainage in coastal zone waters, or~~
 - ~~(2) alters the dune system, except for excavations for the installation of pilings necessary for the construction of elevated structures as permitted by the state department of environmental protection.~~

Sec. 34-1576. Reserved. Islands: *[deleted in its entirety]*

Sec. 34-1577. Wetlands.

(a) Any development in or around wetlands shall be designed to protect the values and functions of the wetlands as set forth in ch. 14, article IV.

(b) No wetland shall be drained, filled, or excavated unless and except as part of an approved restoration or mitigation program.

Sec. 34-1578. Floodplains: *[deleted in its entirety]*

Secs. 34-1579--34-1610. Reserved.

**DIVISION 14. ESSENTIAL SERVICES,
ESSENTIAL SERVICE EQUIPMENT, AND
ESSENTIAL SERVICE BUILDINGS
AND FACILITIES**

Sec. 34-1611. Purpose of division.

The purpose of this division is to set forth the development regulations for uses defined in § 34-2 as essential services, and essential service equipment, and essential service buildings, facilities group I (§ 34-622(c)(13)).

Sec. 34-1612. Where permitted uses.

(a) ~~All buildings or structures classified as essential services, as defined in § 34-2, or as essential service facilities group I (§ 34-622(c)(13)), are permitted by right as shown in Table 34-1 in all zoning districts when necessary for the day-to-day operation of the service, subject to the requirements set forth in this division.~~

(b) ~~New or expanded essential service equipment, as defined in § 34-2, is permitted by right as shown in Table 34-1 when necessary for the day-to-day operation of the service, subject to the requirements set forth in this division.~~

(c) ~~New or expanded essential service buildings, as defined in § 34-2, are permitted by special exception as shown in Table 34-1 if the building(s) are sited, constructed, and maintained to appear as a conventional building that would be permitted in the site's zoning district. All other new or expanded essential service buildings can be permitted only through approval of a suitable planned development zoning district (see § 34-620(d)).~~

Sec. 34-1613. Reserved. Setbacks: *[deleted in its entirety]*

Sec. 34-1614. Height of structures in visibility triangle.

No portion of any building or structure regulated by this division which exceeds two three feet in height shall be permitted within the visibility triangle set forth in § 34-3131, pertaining to vehicle visibility.

Sec. 34-1615. Maximum number of structures per residential block.

Not more than one structure or group of structures which collectively regulated by this division exceeding 150 cubic feet in volume shall be permitted on the same side of a street within any residential block, unless a minimum separation of four lot widths is observed between the structures.

Sec. 34-1616. Screening and buffering. Safety requirements:

~~All facilities regulated by this division shall comply with the safety requirements of the National Electrical Safety Code.~~

(a) Structures or equipment (excluding transmission poles) exceeding 3 feet in height, or which individually or collectively on the same parcel exceed 27 cubic feet in volume, must be of neutral, non-glare color or finish so as to make them as visually unobtrusive as possible.

(b) Structures or equipment (excluding transmission poles) exceeding 3 feet in height, or which individually or collectively on the same parcel exceed 80 cubic feet in volume, must be of neutral, non-glare color or finish and be shielded on all sides by shrubs at least 3 feet high at time of planting consistent with the requirements of § 10-420.

Sec. 34-1617. Exemptions from property development regulations.

~~Facilities classified as Essential services or essential service equipment facilities group I shall be exempt from the property development regulations which set forth minimum lot size, area, and dimensions, and setbacks.~~

Secs. 34-1618--34-1650. Reserved.

DIVISION 15. EXCAVATIONS ACTIVITIES

Subdivision I. Generally

Sec. 34-1651. Required approvals.

~~(a) Excavation for mining purposes. [deleted in its entirety]~~

~~(b) Excavations for purpose of water retention.~~

~~(1) No manmade water detention or retention bodies shall be commenced prior to receiving approval in accordance with the provisions of ch. 10. A certificate to dig shall be obtained prior to receiving ~~the granting of~~ approval to excavate for all properties located within Level 1 or Level 2 zones of archaeological sensitivity pursuant to ch. 22.~~

~~(2) This subsection shall not apply to water retention excavations one acre or less in area for bona fide agricultural purposes, or for maintenance and clearing of existing manmade water bodies.~~

~~(c) Excavations for purpose of oil or gas exploration. [deleted in its entirety]~~

Secs. 34-1652--34-1710 ~~1670~~. Reserved.

Subdivision II. Mining
[deleted in its entirety]

DIVISION 16. RESERVED

FARM PRODUCE STANDS, U-PICK OPERATIONS, ROADSIDE STANDS AND PORTABLE KIOSKS
[deleted in its entirety]

Secs. 34-171~~18~~--34-1740. Reserved.

**DIVISION 17. FENCES, WALLS,
AND ENTRANCE GATES
AND GATEHOUSES**

Sec. 34-1741. Applicability of division.

This division shall apply to all fences, walls, gatehouses, and entrance gates which are not specifically exempted in this division. This division shall not apply to seawalls (see ch. 26 § 34-1863 for regulations on seawalls).

Sec. 34-1742. Design and construction of fences and walls. Building permit.

(a) **Building permits required.** Except as provided in subsection (b) of this section or as may be specifically provided elsewhere in this chapter, All fences and walls that are over 25 inches in height shall comply with established building permit procedures.


(b) Exceptions are as follows:

- (1) Fences or walls less than 25 inches in height.
- (2) Fences used for bona fide agricultural purposes.


(b) **Design.** All fences and walls on each property must have reasonably uniform or complementary materials and design. Figure 34-27 shows several recommended designs for fences and walls.

(c) **Materials.** Fences and walls must be constructed of traditional building materials including brick, stone, stucco over concrete block, finished concrete, metal, vinyl, wood (natural, stained, or painted), and composite products manufactured specifically for fences and walls. Non-traditional fence materials such as tires, mufflers, hubcaps are prohibited. Chain link and other wire fences are not permitted in front yards (the area between a street right-of-way or easement and the minimum required street setback or build-to line).


(d) **Finished sides.** Fences and walls must be constructed to present a finished side to adjoining lots and any abutting rights-of-way. Where there is an existing fence, wall, or continuous landscape hedge on the adjoining parcel, the director may waive this provision administratively.




Wood privacy fence (side or rear yard only)




Concrete, stucco, and wood




Concrete, stucco, and planter



Wood picket fence



Wrought/cast iron and hedge



Concrete, stucco, and cast iron

Figure 34-27

(e) **Maintenance.** After construction, fences and walls must be maintained with all original components and they must remain substantially vertical to serve their functions and aesthetic purposes. Structural integrity must not be compromised to the point that the fence would present a danger of flight or destruction during high winds.

Sec. 34-1743. Construction of fences.

(a) All fences shall be of sound construction and not detract from the surrounding area.

(f) **Dangerous fences.** (b) No barbed wire, spire tips, sharp objects, or electrically charged fences shall be erected except that a fence 72 inches high with three strands of barbed wire on top of the fence with six-inch spacing between the strands of barbed wire may be required or approved by the director around structures or equipment of potential hazard

to residents or passersby not otherwise protected. However, chain link and other non-decorative wire fences may not be used in front yards (the area between a street right-of-way or easement and the minimum required street setback or build-to line), on a parcel which is located in or within 100 feet of any residential area or residential zoning district under separate ownership, provided that the parcel is not already separated from the residential area or residential zoning district by a commercial or industrial zoned property or by an intervening street right-of-way or easement over 25 feet in width. This shall not be interpreted to mean that bona fide agricultural uses cannot use barbed wire or electrically charged fences to control livestock when located in districts permitting the raising, keeping or breeding of livestock. Also, this subsection shall not prohibit the use of barbed wire for temporary security fences around construction materials or equipment in conjunction with an active construction project.

Sec. 34-1743. Reserved.

Sec. 34-1744. Location and height of fences and walls.

- (a) **Setbacks.** Except as may be specifically permitted or required by other sections of this chapter or chapter 10, no fence or wall, excluding seawalls, shall be erected, placed, or maintained:
- (1) **Within** Closer than five feet to any street right-of-way or street easement.
 - (2) Closer to the Gulf of Mexico than permitted by ch. 6, article III.
 - (3) Closer than five feet to the mean high-water line along natural water bodies, including canals created from sovereign lands, except that, where the canal is seawalled, the fence may be built **immediately** landward **or on top** of the seawall.

(b) **Height.** The maximum height for fences and walls, measured from the existing elevation of the abutting property, is illustrated in Figure 34-28 and described as follows: Except as may be specifically provided for elsewhere in this chapter, fences and walls may be erected, placed and maintained along any property line or on any residentially zoned property provided:

- (1) **Front yards.** In residential areas; Any fence or wall located **in a front yard** (between a street right-of-way or easement and the

minimum required street setback or build-to line) shall not exceed **42 inches** three feet in height, except where a lesser height is




Figure 34-28

required to meet that fences may be increased to a maximum height of four feet provided that such fence is of open-mesh screening and does not interfere with vehicle visibility requirements (see § 34-3131) at traffic access points.

- (2) A residential project fence or wall may be increased to a maximum height of eight feet around the perimeter of the project upon a finding by the county engineer that there is no interference with vehicle visibility requirements (see § 34-3131) at traffic access points.
- (3) **Side and rear yards.** Except for a residential project fence; Any fence or wall located in a side or rear yard shall not exceed shall be limited to a maximum height of six feet in height, in the rear and side yards of residential areas. A fence within 25 feet of a body of water shall be of open mesh screening above a height of 3 1/2 feet.
 - a. For purposes of this requirement, the side yard does not include any shall be considered as that portion of the lot between a street and extending from the

minimum required street setback or build-to line to the rear lot line.

b. Where a side or rear yard slopes downward from the street, a fence may be up to seven feet above the elevation of the abutting property to avoid unnecessary variations in the height of a fence.

(3) Near water bodies. Within 25 feet of a body of water, those portions of a fence that exceed 42 inches in height cannot be more than 25% opaque (as viewed from perpendicular to the fence).

(4) Exceptions:

a. Architectural features. Fences and walls for residential project fences may include occasional architectural features such as columns, posts, gates, and arbors; cupolas; fountains; parapets, etc.; at a height not exceeding 84 inches twice the fence or wall height. All such features must be visually compatible with the fence or wall design project and abutting properties.

b. Administrative setback variances. Under certain limited circumstances, administrative variances can be granted to minimum setbacks as provided in § 34-268.

b. Enclosure of high-voltage transformers. See § 34-1748.

(c) Determination of grade. For residential fences, other than residential project fences, grade shall be determined as the existing elevation of the lot. However, any fill placed on the lot which exceeds the average grade of the street shall be included in determining the maximum fence height.

Sec. 34-1745. Buffer for commercial and industrial uses.

All Some land commercial and industrial uses are required to shall provide a perimeter buffers in accordance with § 10-416, as required in ch.10:

Sec. 34-1746. Reserved. Visibility at entrances and exits. *[deleted in its entirety]*

Sec. 34-1747. Construction in easements.

Nothing in this division shall be construed so as to permit the construction or placing of any construction within a public or private easement which prohibits such construction or placement.

Sec. 34-1748. Enclosure of high-voltage transformers and other utility equipment.

(a) All substation high-voltage transformers and any other utility structures or equipment of potential hazard to residents or passersby not otherwise protected shall be completely enclosed by a chainlink fence not less than eight feet in height. On top of the fence shall be three strands of barbed wire with a six-inch spacing in between each strand. However, chain link and other non-decorative wire fences may not be used in front yards (the area between a street right-of-way or easement and the minimum required street setback or build-to line).

(b) ~~Distribution transformers shall comply with National Electrical Safety Code requirements.~~

Sec. 34-1749. Entrance gates and gatehouses.

(a) Entrance gates are not permitted on public or private streets. Decorative entrance features that do not restrict access may be placed along public or private streets provided permission is granted by the town and others entity with authority over the right-of-way or easement.

(b) Entrance gates may be placed on private property to control access to a parking lot that lawfully rents parking spaces to the general public. Adequate stacking space must be provided in front of the gate to avoid interference with traffic flow on adjoining streets. The following regulations apply to any entrance gate or gatehouse which controls access to three or more dwelling units or recreational vehicles, or any commercial, industrial or recreational facility:

(1) An entrance gate or gatehouse not approved as part of a planned development is permitted by right provided it is not located on a publicly dedicated street or right-of-way, and:

a. The gate or gatehouse is located a minimum of 100 feet back from any public street right-of-way or easement; or

b. The gate or gatehouse is designed in such a manner that a minimum of five vehicles or one vehicle per dwelling unit, whichever is less, can pull safely off the public street while waiting to enter; or

c. The development provides a deceleration=turning lane adjacent to the existing pavement for a distance of 300 feet leading into the access drive or road unless

otherwise required by the department of transportation and engineering services:

(c) ~~(2)~~ Access for emergency vehicles must be provided to any existing entrance gates on private streets.

(1) ~~a.~~ Any security gate or similar device that is not manned 24 hours per day must be equipped with an override mechanism acceptable to the local emergency services agencies or an override switch installed in a glass-covered box for the use of emergency vehicles.

(2) ~~b.~~ If an emergency necessitates the breaking of an entrance gate, the cost of repairing the gate and the emergency vehicle if applicable, will be the responsibility of the owner or operator of the gate.

(3) Extension of fences or walls to an entrance gate or gatehouse:

a. A fence or wall may be extended into the required setback where it abuts an entrance gate or gatehouse, provided vehicle visibility requirements (see § 34-3131) are met.

Sec. 34-1750. Walls and fences along limited access or controlled access streets: *[deleted in its entirety]*

Secs. 34-1750+--34-1770. Reserved.

DIVISION 18. HOME OCCUPATIONS; LIVE/WORK AND WORK/LIVE DWELLINGS

Sec. 34-1771. Intent of division.

It is the intent of this division to allow the operation of:

- (1) Home occupations, by right, in all districts permitting dwelling units, but to regulate them so that the average neighbor, under normal circumstances, will not be disturbed or inconvenienced by them; and
- (2) Live/work and work/live dwelling units, by right or by special exception as specified in Tables 34-1 and 34-2 in § 34-622, but to regulate them so that their mixed-use character is compatible with their neighborhood and is maintained over time.

Sec. 34-1772. Home occupations. Permitted uses; operation:

(a) Any use of a residence for a home occupation as defined by this chapter shall be clearly incidental and subordinate to its use for residential purposes by its occupants and thus is considered to be a residential accessory use and is permitted in accordance with the regulations in this section in all zoning districts except EC.

(b) Such use shall be conducted entirely within the dwelling unit or customary accessory building.

(c) No employees or contractors other than members of the household immediate family residing in the dwelling shall be permitted to work at the residence, but may be employed to work elsewhere provided that the employees do not regularly come to the residence for equipment, vehicles, or supplies employed in the home occupation. Under special conditions, such as a handicapped person or retiree needing clerical assistance, the director may grant administrative approval to allow one employee who is not a resident of the home to work at the residence.

(d) There shall be no exterior indication that the dwelling is being used for any purpose other than a residence, except that one nonilluminated nameplate, not exceeding one square foot (144 square inches) in area, may be attached to the building on or next to the entrance.

(e) No commodities, stores, or display of products on the premises shall be visible from the street or surrounding residential area, and no outdoor display or storage of materials, goods, supplies, or equipment used in the home occupation shall be permitted on the premises. Vehicles and trailers for use by the business may not be parked or stored on the premises unless completely enclosed within a building.

(f) No equipment shall be used which creates noise, vibration, glare, fumes, or odors, or electrical interference outside the dwelling unit that are objectionable to the normal senses. ~~No equipment or process shall be used which creates visual or audible interference in any radio or television receiver off the premises or causes fluctuations in line voltage off the premises.~~

(g) A home occupation shall not No use permitted by this division shall generate greater volumes of traffic than would otherwise be expected by normal residential uses. (h), and a home occupation shall not No use that attracts more than an average of ten total visits per week from customers, clients, and suppliers, to the dwelling unit may be permitted under this section.

Sec. 34-1773. Live/work dwelling units.

(a) A live/work dwelling unit is defined by this chapter as a single dwelling unit in a detached building, or in a multifamily or mixed-use building, that also accommodates limited commercial uses within the dwelling unit.

(b) The predominate use of a live/work unit is residential, and commercial activity is a secondary use. The quiet enjoyment expectations of residential neighbors takes precedence over the work needs of a live/work unit.

(c) Commercial uses in live/work units must be conducted entirely within the unit or customary residential accessory building.

(d) Up to two employees or contractors other than members of the immediate family residing in the dwelling may work in a live/work unit.

(e) Ground signs and pole signs are not permitted. Signage for live/work units is limited to up to four square feet of nonilluminated nameplates or blade signs that are attached to the building on or next to the entrance.

(f) No commodities, stores, or display of products on the premises shall be visible from the street or surrounding residential area, and no outdoor display or storage of materials, goods, supplies, or equipment used in the live/work unit shall be permitted on the premises.

(g) Required parking spaces shall be in accordance with the residential parking standards in § 34-2020, plus 1 space per employee.

(h) No equipment shall be used which creates noise, vibration, glare, fumes, or odors outside the dwelling unit that are objectionable to the normal senses.

(i) Commercial uses in live/work units are limited to Office, general or medical as defined by this chapter (see § 34-2). However, due to the residential nature of live/work units, visits from customers, clients, and suppliers shall average no more than a total of thirty visits per week.

Sec. 34-1774. Work/live dwelling units.

(a) A work/live dwelling unit is defined by this chapter as a single dwelling unit in a detached building, or in a multifamily, mixed-use, or commercial building, where the predominate use of the unit is commercial.

(b) Because the predominate use of a work/live unit is commercial, customary commercial impacts may take precedence over the quiet enjoyment expectations of residential neighbors.

(c) Commercial uses in work/live units must be conducted entirely within the unit or customary accessory building.

(d) Signs shall be in accordance with the standards for business signs in ch. 30.

(e) Required parking spaces shall be in accordance with the commercial parking standards in § 34-2020, plus 2 spaces for the dwelling unit.

(f) Commercial uses in work/live units are limited to Office, general or medical; Personal services; Restaurant; and Retail store, small, as defined by this chapter (see § 34-2).

Secs. 34-1775--34-1800. Reserved.

**DIVISION 19. HOTELS, AND MOTELS,
AND BED-AND-BREAKFAST INNS**

Sec. 34-1801. Definitions.

(a) Bed-and-breakfast inn means a public lodging establishment with nine or fewer guest units that serves breakfast to overnight guests. A bed-and-breakfast inn may be located in a single building or in a cluster of separate buildings.

(b) Guest unit means a room or group of rooms in a hotel/motel or bed-and-breakfast inn that are designed to be used as temporary accommodations for one or more people traveling together. All guest units provide for sleeping and sanitation, although sanitation may be provided through shared bathrooms.

(c) For the purposes of this division, a Hotel/motel is defined as means a building, or group of buildings on the same premises and under single control, consisting of ten or more sleeping rooms which are kept, used, maintained, or advertised as, or held out to the public to be, a place where sleeping accommodations are supplied for pay to transient guests for periods of one day or longer, or tenants. Hotels/motels are further categorized as efficiency or business:

(d) Lock-off accommodations means a single guest unit or living unit designed in such a manner that at least one room and a bathroom can be physically locked off from the main unit and occupied as a separate unit. Each portion may have a separate outside entry or share a common foyer with separate lockable interior doors, or may share a lockable door or doors separating the two units.

(e) Hotels/motels and bed-and-breakfast inns must be registered accordingly with the Florida department of business and professional regulation revenue as a bona fide hotel/motel operation and will be are required to pay the levied tourist development tax as promulgated by the county. Hotels/motels and bed-and-breakfast inns which are not registered with the department of revenue or hotels/motels do not paying the tourist tax will be subject to the density limitations and property development regulations for multiple family buildings.

~~(1) Efficiency hotel [deleted in its entirety]~~

~~(2) Business hotel [deleted in its entirety]~~

~~(3) Kitchen facilities [deleted in its entirety]~~

Sec. 34-1802. Size of guest units.

(a) Method of measurement. For purposes of this division, the size of a guest unit is the actual square footage within each guest unit including balconies and private patios, but not including common facilities such as corridors, stairways, shared bathrooms, or other common spaces including utility areas or parking spaces.

(b) Hotels/motels. Individual guest units in a hotel/motel must be at least 180 square feet in size, except as provided in § 34-1803(b)(2).

(5) Minimum floor area per unit	120 sq. ft.	120 sq. ft.
(6) Maximum floor area per unit	350 sq. ft.	550 sq. ft.

(c) Bed-and-breakfast inns. Individual guest units in a bed-and-breakfast inn must be at least 120 square feet in size.

Sec. 34-1803. Allowable intensity. Property development regulations:

Property development regulations for uses subject to this division are as follows:

	Business Efficiency	
(1) Minimum lot dimensions:		
a: Area	2 acres	20,000 s.f.
b: Lot width	150 feet	100 feet
c: Lot depth	200 feet	100 feet
(2) Setbacks:		
a: Street	In accordance with section 34-2192	
b: Water body	In accordance with section 34-2194	
c: Side and rear yards	20 feet	
(4) Rental units permitted		
a: Density multiplier for hotel/motel rental units (compared to dwelling units allowed under the Lee Plan future land use map)	1.0 units equal one dwelling unit	1.0 units equal one dwelling unit
b: Any proposed hotel/motel or expansion which will result in more than 50 rental units will be permitted only as a planned development.		
c: A hotel/motel development submitted for approval as a planned development may exceed the equivalency factors in (4)a., if approved through the deviation process; provided all other aspects of the development (height, traffic, intensity of use, etc.) are found to be compatible with the surrounding area.		
d: Where a development proposes to have both types of rental units, the number of units will be prorated.		

(a) Hotels/motels. When a hotel/motel is permitted on a property, guest units can be substituted for the dwelling units that would be allowed on that property (see § 34-632 regarding density). The maximum number of guest units can

be computed by multiplying the maximum number of dwelling units by the appropriate equivalency factors:

- (1) The following table indicates the equivalency factors that apply to properties in various land-use categories in the Fort Myers Beach Comprehensive Plan:

<u>Comprehensive Plan land-use category:</u>	<u>Equivalency factors for guest units of various sizes¹ (in square feet):</u>		
	<u>< 450</u>	<u>450 to 750</u>	<u>750 to 1,000</u>
<u>Mixed Residential</u>	<u>2.0</u>	<u>1.5</u>	<u>1.0</u>
<u>Boulevard</u>	<u>2.5</u>	<u>2.0</u>	<u>1.5</u>
<u>Pedestrian Comm.²</u>	<u>3.0</u>	<u>2.5</u>	<u>2.0</u>
<u>(all others)</u>	<u>0.0</u>	<u>0.0</u>	<u>0.0</u>

¹ see § 34-1802

² see also § 34-1803(b)

- (2) Guests units exceeding these equivalency factors or exceeding 1,000 square feet each may be allowed under exceptional circumstances as described in the Comprehensive Plan if approved as a deviation through a planned development rezoning. Before approving such a deviation, the town council must find that:
- All other aspects of the development (height, traffic, intensity of use, etc.) are compatible with the surrounding area;
 - The proposal clearly exceeds all standards of the Fort Myers Beach Comprehensive Plan; and
 - In no case can equivalency factor increases exceed the maximum intensities allowed by the Fort Myers Beach Comprehensive Plan.
- (3) Where lock-off accommodations are provided, each keyed room will be counted as a separate guest unit.

(b) *Hotels on Old San Carlos Boulevard.* The 1999 Old San Carlos Boulevard – Crescent Street Master Plan encourages mixed-use buildings with second and third floors over shops on Old San Carlos Boulevard. To help implement this plan, an alternate method is provided by Comprehensive Plan Policy 4-C-6 for computing maximum hotel intensities for properties between Fifth to First Streets that lie within 200 feet east and west of the centerline of Old San Carlos Boulevard. In this situation and location only:

- (1) Guest units may be substituted for otherwise allowable office space without using the

equivalency factors in § 34-1803(a), provided that all other requirements of this code are met including minimum parking requirements and maximum floor-area-ratios.

- (2) These guest units must contain at least 250 square feet each.
- (3) The standard height limit at this location is three stories. Under no circumstances may a deviation be granted that would allow these guest units in any building taller than four stories. (The ground level is counted as the first story.)

(c) *Bed-and-breakfast inns.* The intensity of bed-and-breakfast inns shall be calculated in the same manner as for hotel/motels, except that inns with three or fewer guest rooms per building are exempt from the requirement to use equivalency factors to measure their intensity.

Sec. 34-1804. Parking.

(3) Parking:

a: Spaces per rental unit 1.2 1.5

(a) *Hotels/motels.* The minimum requirement for off-street parking is 1.2 parking spaces for guest units up to 450 square feet and 1.5 spaces for each larger guest unit. b: Ancillary uses located in separate buildings and available to nonguests must provide parking spaces in accordance with meet the requirements of division 26 of this article.

- Where lock-off accommodations are provided, each “keyed room” will be calculated as a separate unit.
- Where a development proposes to have both types of rental units, the number of parking spaces will be prorated.

(b) *Bed-and-breakfast inns.* The minimum requirement for off-street parking is 1 parking space for each guest room plus 1 space for the owners’ quarters.

Sec. 34-1805. Additional regulations for bed-and-breakfast inns.

(a) Whenever guests are present, the owner or operator must live on the premises or on abutting property, or if the inn is in a cluster of separate buildings the owner or operator must live in one of the buildings.

(b) The maximum continuous length of stay for guests is 90 days.

(c) Each guest unit must be accessed by a common corridor or outside door rather than through another guest unit or dwelling unit.

(d) Food service is limited to breakfast and/or snacks and may be served only to overnight guests.

(e) A single non-illuminated identification sign up to four square feet in area may be mounted onto each building.

Sec. 34-1806. Replacing a nonconforming hotel/motel.

A nonconforming hotel/motel can be replaced in one of the following manners:

- (1) In full conformance with all current provisions of this code as they apply to a new hotel/motel on vacant land; or
- (2) In the same manner as provided for enlargements to the various types of nonconforming buildings as provided in § 34-3234; or
- (3) As provided in the pre-disaster buildback regulations found in § 34-3237 or the post-disaster buildback regulations found in § 34-3238.

Sec. 34-1807.3. Conversions.

Any hotel or motel proposing to convert to timeshare or dwelling units, or any residential building proposing to convert to timeshare or hotel/motel units, will be required to comply with density limitations of the Fort Myers Beach Comprehensive Plan, all applicable parking regulations, and all other regulations of this code including equivalency factors that affect chapter affecting the proposed use. If the existing hotel/motel, timeshare, or residential building being converted exceeds the density or intensity limits of the comprehensive plan or this code, the conversion must use the pre-disaster buildback regulations found in § 34-3237 or the post-disaster buildback regulations found in § 34-3238 in order to rebuild at up to the existing density or intensity. Interior square footage, as defined in § 34-3238(2)d. for residential and in § 34-3238(2)e for hotel/motel and timeshare, may be exchanged during this process on square-foot for square-foot basis.

Sec. 34-1804. Subordinate uses.

For regulations pertaining to subordinate uses, refer to § 34-3021.

Sec. 34-1805. Density limitation for Captiva Island. [deleted in its entirety]

Secs. 34-1806--34-1830. Reserved.

**DIVISION 20. RESERVED
JUNK, SCRAP OR SALVAGE YARDS, DUMPS
AND SANITARY LANDFILLS
[deleted in its entirety]**

Secs. 34-1831--34-1860. Reserved.

**DIVISION 21. MARINE FACILITIES,
STRUCTURES, AND EQUIPMENT*
AND LIVE-ABOARD VESSELS***

**Cross reference(s)--Marina design, § 10-257; marine facilities and structures generally, ch. 26; marine sanitation, § 26-111 et seq. marine-oriented districts, § 34-871 et seq.*

Sec. 34-1861. Boats, floating structures, floating equipment, and live-aboards.

(a) No boat, floating structure, or other floating equipment shall be moored to mangroves except for emergency purposes.

(b) No person shall discharge or permit or control or command to discharge any raw sewage, garbage, trash, or other waste materials into the waters of the town county.

(c) No boats, floating structures, or other floating equipment designed to accommodate one or more living units, or designed or used for retail sales, shall be permitted to anchor, moor, tie up, or otherwise be attached to any wharf, pier, or other structure emanating from real property or to real property itself within the town unincorporated areas of the county except in conformity with the regulations contained in this chapter and all other applicable town county ordinances.

(d) Except as provided in this subsection, no person shall live aboard any vessel under his command or control, which is moored to real property or to any dock, pier, seawall, or other structure attached to real property in the town.

unincorporated area of the county, except at a marina (see § 34-1862) which is properly zoned for such use under the provisions of this chapter. The provisions of this subsection shall not apply to:

- (1) Live-aboard vessels equipped with an approved discharge device that is listed by the United States Coast Guard as an approved marine sanitation device, and occupied by a licensed captain and his immediate family;
- (2) Commercial vessels, such as commercial fishing boats, tugs, barges, salvage vessels, passenger vessels, or cargo vessels, when used in commerce and navigation; or
- (3) The mooring of any vessel necessitated by an emergency.
- (4) Live-aboard vessels at a marina which is properly zoned for such use (see § 26-116).
- (5) Live-aboard vessels lawfully occupying a berth in a public mooring field managed by the town, provided the vessel is in compliance with all regulations.

The exceptions granted by subsections (d)(1) and (2) of this section are not intended to apply to personal fishing boats used for recreation or to fishermen with marine products licenses.

Sec. 34-1862. Reserved. ~~Marinas, fish houses, and docking facilities: [deleted in its entirety]~~

Sec. 34-1863. Construction and maintenance of docks, seawalls, and other structures designed for use on or adjacent to waterways.

Construction, placement, erection, and maintenance of docks, mooring piles, seawalls, watercraft landing facilities, and other structures designed for use on or adjacent to waterways shall be in compliance with established building permit procedures and with ch. 26, article II. See also division 2 of this article regarding accessory uses, buildings, and structures.

Secs. 34-1864--34-1890. Reserved.

DIVISION 22. RESERVED
FARM LABOR HOUSING
[deleted in its entirety]

Secs. 34-1891--34-1920. Reserved.

DIVISION 23. MOBILE HOMES

Sec. 34-1921. Mobile home subdivisions.

(a) New or expanded mobile home subdivisions are not allowed in the Town of Fort Myers Beach.

(b) A mobile home cannot be substantially improved or placed on any lot in any subdivision except:

(1) to replace an existing mobile home, provided that:

a. a mobile home is in lawful existence on that lot and the lot has not been vacant for more than nine months,

b. the replacement or substantially improved mobile home is elevated so that its lowest floor is at or above the base flood elevation, in accordance with § 6-472(2)a, and

c. the move-on permit requirements of § 34-1923 are met; or

(2) on a temporary basis in accordance with § 34-3046.

Sec. 34-1922. Mobile home parks.

(a) New or expanded mobile home parks are not allowed in the Town of Fort Myers Beach.

(b) A mobile home cannot be substantially improved or placed in any existing mobile home park except in some parts of the VILLAGE zoning district in accordance with the regulations set forth in subdivision III of division 5 of article III of this chapter, and in accordance with the elevation requirements of § 6-472(2)b, and the move-on permit requirements of § 34-1923.

Sec. 34-1923†. Move-on permit requirements.

(a) This section applies to mobile homes, and also to park trailers as that term is defined in § 34-694, in those zoning districts where either are permitted.

(b) No mobile home shall be relocated or moved onto any property without first obtaining a move-on permit from the ~~director, division of codes and building services.~~

(c) ~~Sec. 34-1922. Tiedowns.~~ All mobile homes shall be tied down in accordance with local, state, and federal and insurance regulations, including § 6-471(2) of this code and F.S. § 320.8325.

(d) ~~Sec. 34-1923. Skirting.~~ All mobile homes shall have removable skirting around the entire perimeter.

- (1) Skirting shall be of a durable material such as decorative block, concrete block, fiberglass, aluminum or vegetation. Junk doors or other scrap material is prohibited.
- (2) Skirting shall be maintained at all times by the resident.

Secs. 34-1924--34-1950. Reserved.

~~DIVISION 24:
MODEL HOMES, UNITS
AND DISPLAY CENTERS
[deleted in its entirety]~~

DIVISION 24. MOVING OF BUILDINGS

Sec. 34-~~1951~~209. Building relocation permit.
[moved from § 34-209]

(a) *Compliance with applicable regulations.*

When a building is moved to any location within the town, the building or part thereof shall be made to conform to applicable provisions of the Florida Building Code and to all the provisions of this chapter within 90 days of the date of issuance of the moving permit.

(b) *Contents of application.* Any person desiring to relocate or move a building must first file with the director a written application on an official form. The application must include the following information furnished by the applicant and must be accompanied by the required application fee:

- (1) The present use of the building.
- (2) The proposed use of the building.
- (3) The building's present location and proposed new location by STRAP number, as well as by street numbers.
- (4) Certified survey of the proposed site with ground elevations, flood zone, and required elevation.
- (5) Plot plan showing lot dimensions, setbacks, location of existing structures, and location of building drawn to scale no more than ½-inch equals one inch and no less than one inch equals 50 feet. The plot plan should depict the roof overhang as well as the foundation.

- (6) Construction details, drawn to a scale of no larger than one-half inch equals one foot and no smaller than one-eighth inch equals one foot, including the following:
 - a. Foundation layout with connection details.
 - b. Floor plan, existing and proposed.
 - c. Mechanical plans, including air conditioning, electric system, and plumbing plans.
 - d. Elevations, front, side, and rear.
 - e. Flood elevations for the proposed new location shall be shown on the foundation layout and elevations.
- (7) Current termite inspection by licensed pest controller.
- (8) Photographs showing all sides of the building and the site where the building is proposed to be located.
- (9) Proof of notice to all owners of property abutting or across the street from the site where the building is proposed to be located.
- (10) A detailed written statement describing all proposed exterior alterations to the building after it is relocated. At a minimum, these details shall include methods and materials, and construction details as appropriate, regarding:
 - a. The height and method of elevating the building above grade;
 - b. Any proposed enclosure of space below the lowest habitable floor;
 - c. Any changes to exterior doors, windows, siding, awnings, and shutters;
 - d. Any porches or decks to be built, modified, or eliminated; and
 - e. Any changes to the roof other than routine maintenance or replacement with similar materials.

(c) **Criteria for suitability of building to proposed site.** The town manager shall determine whether the building to be relocated is suitable for its proposed site under one of the following categories:

- (1) **Historic buildings.** For buildings that, after relocation, would be eligible for historic designation pursuant to § 22-204(a)-(d):
 - a. Is the proposed use of the building permitted by the zoning district?
 - b. Has the property owner consented to historic designation of the site after the building is relocated?

- c. Has the property owner proposed improvements that restore the building while retaining its essential historic characteristics, consistent with the criteria in § 22-101-103?

- (2) **Other buildings.** For all other buildings:
 - a. Is the proposed use of the building permitted by the zoning district and similar to existing uses in the neighborhood?
 - b. Is the building reasonably compatible with the neighborhood when considering factors such as its size, age, and condition? If not, has the property owner proposed sufficient renovations or improvements to the building to achieve compatibility?

The town manager may place reasonable conditions on suitability decisions to bring applications up to these criteria or to ensure the performance of proposed improvements or renovations. Suitability decisions pursuant to this subsection are administrative decisions which may be appealed in accordance with § 34-86, article II of this chapter.

(d) **Inspection of building.** The director will have the building inspected to determine:

- (1) If the building can be brought into compliance in all respects with this chapter and other town regulations pertaining to the area to which the building is to be moved.
- (2) If the building is structurally sound and either complies with applicable portions of the Florida Building Code and other codes adopted by the town or can be brought into compliance with such codes.

(e) **Rejection of application.** The director must reject any application if:

- (1) The building fails to meet the suitability criteria in subsection (c), as determined by the town manager, or the inspection criteria in subsection (d) of this section;
- (2) In the opinion of the director, the moving of any building will cause serious injury to persons or property;
- (3) The building to be moved has deteriorated due to fire or other element to more than 50 percent of its market value, as that term is defined in § 6-405; or
- (4) The moving of the building will violate any of the requirements of the Florida Building Code, this code or other applicable town regulations.

Except for decisions as to the Florida Building Code, such decisions are administrative decisions which may be appealed in accordance with § 34-86, ~~§ 34-145(a)~~ article II of this chapter.

(f) Approval of building relocation permit.

- (1) Upon approval of the application for building relocation, a licensed building relocation contractor representing the applicant must:
 - a. Apply for and receive all required permits from the departments of transportation of the county or state, if county or state roads will be used during the relocation;
 - b. Pay the required fees and obtain the building relocation permit and appropriate sub-permits.
- (2) Any building being moved for which a permit was granted may not remain in or on the streets for more than 24 48 hours unless an extension of an additional 24 hours is approved by the town manager.

Secs. 34-1952--34-1980. Reserved.

**DIVISION 25.
OFF-STREET LOADING AREAS**

Sec. 34-1981. Applicability of division.

(a) The off-street loading requirements of this division shall apply to commercial, ~~industrial~~, and other nonresidential uses.

(b) *[moved here from § 34-1145(f)(2)]*
Establishments are encouraged to schedule deliveries before or after their normal business hours. Deliveries that are made during normal hours may not obstruct parking aisles or parking entrances.

Sec. 34-1982. Access.

(a) Street access to off-street loading areas shall observe the same provisions as set forth for ~~off-street parking lots~~ in § 34-2013.

(b) Except as provided in § 34-1987, off-street loading areas shall be spatially or physically separated from ~~off-street parking areas~~ and pedestrian walkways.

~~(c) Service roads shall be a minimum of 12 feet wide for one-way usage and 24 feet for two-way operations.~~

Sec. 34-1983. Lighting, maintenance, and drainage.

Site lighting, maintenance, and drainage required for off-street loading areas shall comply with the provision of §§ 34-2015 and 34-2017.

Sec. 34-1984. Other use of loading areas.

Except as provided in § 34-2019, off-street loading areas shall not be utilized for the sale, repair, dismantling, or servicing of any vehicles or equipment, except on an emergency or temporary basis.

Sec. 34-1985. Screening.

When any off-street loading area is located adjacent to a residential use or zoning district, and is not otherwise entirely visually screened from it at ground level, there shall be provided a continuous visual screen along the lot line abutting the residential use in accordance with division 17 of this article or ch. 10, whichever is the most restrictive.

Sec. 34-1986. Loading area required; loading plan; location of loading area.

(a) All commercial, ~~industrial~~, and other nonresidential uses on sites larger than 1 acre shall be provided with an off-street loading area for receiving and shipment of commodities.

(b) A plan for off-street loading areas shall be provided as part of the site plan submitted in accordance with the regulations and procedures set forth in ch. 10, or, if the development is exempt from ch. 10, then a plan shall be submitted at time of application for a building permit and be reviewed by the ~~director zoning and development review division~~ for consistency with this division and this chapter.

(c) The location of all off-street loading areas shall embody the following provisions:

- (1) The required loading area shall be provided on the same lot or parcel it serves or within 300 feet of that parcel.

- (2) The surfaced portions of all loading areas, excluding driveways, shall observe a 20-foot setback from all right-of-way lines and a ten-foot setback from all property under separate ownership or control.
- (3) Loading spaces shall be so located as not to obstruct or otherwise hinder or endanger the movement of vehicles and pedestrians.
- (4) ~~[moved here from 34-1145(f)(1)] Off-street loading areas shall not be placed between the principal building and a the street right-of-way line. A separate loading area is not required, but when provided, the surfaced portions of loading areas are not required to be set back from side or rear lot lines.~~

Sec. 34-1987. Number of spaces.

- (a) Establishments which normally receive or ship commodities via small panel trucks or vans shall not be required to provide off-street loading areas and may utilize the parking area, provided:
 - (1) Deliveries normally are received before or after normal hours open to the public.
 - (2) No delivery truck remains in the parking lot for more than four hours.
 - (3) Deliveries do not interfere with normal pedestrian or vehicle movements.
- (b) Establishments which receive or ship goods via large semitrailer or full trailer trucks shall provide a minimum of one loading space for the first 10,000 square feet of floor area, plus one space for each additional 20,000 square feet of floor area or major fraction thereof.

Secs. 34-1988--34-2010. Reserved.

DIVISION 26. OFF-STREET PARKING

Sec. 34-2011. Types of parking facilities.

Parking facilities in the Town of Fort Myers Beach take a variety of forms, generally classified as follows:

(a) **Single-purpose parking lots.** Single-purpose parking lots are designed to serve individual businesses, condominiums, or shopping centers. Single-purpose parking lots are usually located on the same site as the use they serve and may include parking spaces under a building or in a parking garage.

- (1) Most single-purpose parking lots are considered by this code to be accessory uses of land (§ 34-1171) and thus can be built to serve any permitted principal use on the same parcel of land.
- (2) Some single-purpose parking lots serve two or more non-abutting parcels, as provided in § 34-2018 for joint-use parking lots.
- (3) Surplus spaces in some single-purpose parking lots may be rented to the general public during peak periods, as provided in subsection 34-2019(a).

(b) **Shared parking lots.** Shared parking lots are open to the public, generally for a fee, regardless of the destination of the person parking there. Shared parking lots may be operated as a private business or by a governmental entity, and may include a surface parking lot and/or a parking garage.

- (1) Seasonal shared parking lots may obtain temporary use permits administratively for up to three-year periods as provided in § 34-2022 of this chapter.
- (2) Permanent shared parking lots are considered a principal use of a parcel of land and may be approved in certain zoning districts by special exception.
- (3) Parking garages that operate in whole or part as shared parking lots are also considered a principal use of land and may be approved only through the Commercial Planned Development zoning district (see §§ 34-620(d) and 34-676(e)).

(c) **On-street parking.** Governmental entities sometimes provide on-street parking spaces, usually with parking meters, that are available for use by the public regardless of their destination. On-street

parking is closely related to the functioning of the adjoining street and is provided as a public works project rather than being regulated as a land development activity by this code.

~~Sec. 34-2011. Applicability of division. [moved to 34-2020(a-b)]~~

Sec. 34-2012. Definitions.

For purpose of this division only, certain words or phrases are defined as follows:

~~*Drive-up.* The terms “drive-up” and “drive-through” are synonymous.~~

Employees means the regular working staff, whether paid, volunteer, or otherwise, at maximum strength and in full-time equivalent numbers, necessary to operate, maintain, or service any given facility or use under normal levels of service.

High turnover applies to parking lots wherein numerous vehicles are parked for relatively short periods of time ranging from a few minutes to several hours. Customer parking for retail stores, restaurants, bars, offices, commercial or similar establishments is considered to be high turnover.

Low turnover applies to parking wherein vehicles are parked for relatively long periods of time, such as employee parking during the day, uses such as beach parking or marina parking where customers typically leave their cars for periods of several hours or more, and or overnight parking in residential developments.

Parking aisle means an accessway within a parking lot which provides direct access to individual parking spaces.

Parking lot means an area of land designed, used, or intended for ~~the~~ parking of five or more vehicles.

Parking lot entrance means the accessway which provides ingress or egress from a street right-of-way or easement to a parking lot.

Parking space means an area of land designed or intended for ~~the~~ parking of one vehicle. Some parking spaces are designated as disabled handicapped spaces or standard spaces, depending on the purpose of the space.

Sec. 34-2013. Access.

~~(a) All parking lots shall be designed so as to permit vehicles exiting the parking lot to enter the street right-of-way or easement in a forward motion. [subject moved to § 34-2015(6)]~~

~~(a)~~ (b) Each parking lot shall have a distinct parking lot entrance. Such entrance shall meet the requirements of ch. 10, as well as the following:

- (1) Minimum width at the property line street for one-way entrances is 10 15 feet.
- (2) Minimum width at the property line street for two-way entrances is 20 25 feet.
- (3) Maximum width at the property line street is 25 35 feet.

The director department of transportation and engineering may determine that high traffic volumes, truck traffic, or other special circumstances warrant other requirements.

~~(b)~~ (c) Parking lot entrances shall not exceed a six percent grade for 20 feet into any lot or parcel, nor shall a parking lot entrance enter a street right-of-way or easement at an angle of less than 90 degrees unless a lesser angle is approved by the director of transportation and engineering services.

Sec. 34-2014. Parking plan.

A parking plan shall be required for all uses, except single-family residence, ~~duplex, and~~ two-family ~~attached and single-family mobile home~~ dwelling units, and shall be submitted for review and approval in accordance with ch. 10. Developments which are not required to be approved in accordance with ~~exempt from~~ chapter 10 shall submit plans to the director zoning and development review division prior to issuance of a building permit. The plan shall accurately designate the required parking spaces, parking aisles, and parking lot entrance, as well as the relation of any ~~the~~ off-street parking facilities to the uses or structures such facilities are designed to serve.

Sec. 34-2015. Location and design generally.

The location and design of all parking lots shall embody the following provisions:

(1) Location of single-purpose parking lots.

Except for parking lots specifically zoned CP or as provided for in § 34-2018, All required Parking spaces that are required to support

specific land uses (see § 34-2020) shall be provided on the same premises and within the same or similar type zoning district as the use which they serve, except in the Downtown zoning district as provided in § 34-676(a). Joint-use parking lots are regulated by § 34-2018.

- (2) **Location of shared parking lots.** Shared parking lots may be constructed as follows:
 - a. Seasonal shared parking lots may obtain temporary use permits administratively for up to three-year periods as provided in § 34-2022 of this chapter. The location and certain design features of seasonal parking lots are regulated by § 34-2022.
 - b. Permanent shared parking lots are considered a principal use of a parcel of land and may be approved in certain zoning districts by special exception.
 - c. Parking garages that operate in whole or part as shared parking lots are also considered a principal use of land and may be approved only through the CPD (commercial planned development) zoning district (see §§ 34-620(d) and 34-676(e)).
- (3) **Design.**
 - a. In addition to the requirements set forth in this division, all parking lots shall be designed in accordance with the setback, buffer, landscaping, and drainage, and other requirements set forth in ch. 10.
 - b. **Lighting.** If the parking lot is to be used at night, adequate lighting shall be provided for the driveways, ingress, and egress points, and parking areas of all commercial and industrial uses. Such lighting shall be so arranged and directed as to eliminate glare on any other use, and must comply with applicable sea turtle lighting restrictions in ch. 14.
 - c. **Stacking.** All individual parking spaces shall be accessible at all times from a parking aisle intended to provide access to the space. Stacking of vehicles (one behind the other) shall be permitted only where each dwelling unit has a specific garage or driveway appurtenant to it and in valet parking facilities wherein parking is performed only by employees of the facility.
 - d. **Exiting.** All parking lots spaces shall be provided with sufficient maneuvering room so as to allow an exiting vehicle to leave the parking lot in a forward motion, except where approved by the director under the following conditions:

- 1. The right-of-way is a local street and:
 - a- there is insufficient room on the parcel for vehicles to turn and exit in a forward direction, and
 - b- the number of parking spaces backing out are no more than the minimum required by this division to serve existing buildings; or
- b. The parking spaces are in the “Pedestrian Commercial” category of the comprehensive plan and do not unduly interfere with critical congested road segments or the normal usage of existing or proposed sidewalks.
- (6) **End spaces.** Parking lots utilizing 90° parking with dead-end aisles shall provide a turning bay for those spaces at the end of the aisle.
- (7) **e. Pedestrian system.** In any parking lot where more than one tier of parking spaces is to be developed, walkways a pedestrian system shall be provided which accommodates safe and convenient pedestrian movement from vehicles to building entrances and other walking destinations. If these walkways cross major parking aisles, the walkway shall be clearly differentiated from the surface of the aisle.

Sec. 34-2016. Dimensional requirements; delineation of parking spaces.

In addition to satisfying all other provisions of this division, the arrangement and spacing of off-street parking lots shall conform to the following requirements:

- (1) **Minimum dimensional requirements.** Minimum aisle widths and parking space dimensions shall be as follows:

Angle of Parking	AISLE WIDTHS		PARKING SPACES	
	One-Way (feet)	Two-Way (feet)	Width (feet)	Length (feet)
Parallel	10 ±2	20	7	20
30°	±2	±2		
45° - 50°	11 ±2	20 ±2	8.5	
55° - 60°	14 ±8	22 ±4	8.5	
70° - 75°	17	22	8.5	
90°	20 ±2	22 ±4	8.5	18

(2) Effect of minimum dimensions on size of parking lots. The following table illustrates the effect of the minimum aisle and parking space dimensions on the size of parking lots, keyed to the dimensions indicated in Figure 34-29.

<u>DIMENSION (in feet):</u>	<u>45°</u>	<u>60°</u>	<u>75°</u>	<u>90°</u>
<u>Stall width</u>	<u>A 8.5</u>	<u>8.5</u>	<u>8.5</u>	<u>8.5</u>
<u>Stall width (parallel to aisle)</u>	<u>B 12.0</u>	<u>9.8</u>	<u>8.8</u>	<u>8.5</u>
<u>Aisle width (one-way travel)</u>	<u>C 11.0</u>	<u>14.0</u>	<u>17.0</u>	<u>20.0</u>
<u>Stall depth (interlock)</u>	<u>D 15.3</u>	<u>17.5</u>	<u>18.6</u>	<u>18.0</u>
<u>Stall depth (to wall)</u>	<u>E 17.5</u>	<u>19.1</u>	<u>19.4</u>	<u>18.0</u>
<u>Module (interlocking)</u>	<u>F 41.6</u>	<u>49.0</u>	<u>54.2</u>	<u>56.0</u>
<u>Module (wall to interlock)</u>	<u>G 43.9</u>	<u>50.6</u>	<u>55.0</u>	<u>56.0</u>
<u>Module (wall to wall)</u>	<u>46.0</u>	<u>52.2</u>	<u>55.8</u>	<u>56.0</u>




Figure 34-29

(3) Disabled Parking space dimensions.

Individual disabled parking space dimensions shall be as follows: a. Handicapped parking (aff): 12 feet by 18 feet. Parking access aisles must be no less than 5 feet wide and must be part of an accessible route to the building or facility entrance. However, the individual parking space dimensions do not preclude guarantee compliance with the Americans with Disabilities Act (ADA) of 1990.

- b. High and low turnover parking lots:
1. 90° parking: 9 feet by 18 feet.
 2. 30°, 45° or 60° parking: 8 1/2 feet by 18 feet.
 3. Parallel parking: 7 feet by 22 feet.

(4) Delineation of spaces.

- a. Paved parking lots.
1. Parking spaces shall be delineated by all-weather painted lines, not less than

four inches in width, centered on the dividing line between spaces.

2. ~~Parking spaces which do not abut a curb, fence, wall, or other structure shall be provided with a parking block set two feet from the end of the parking space.~~ Parking spaces for the disabled must be prominently outlined with blue paint, and must be repainted when necessary to be clearly distinguishable as a parking space designated for persons who have disabilities. Signs erected after October 1, 1996 must indicate the penalty for illegal use of these spaces.

b. Unpaved parking lots.

1. Perimeter parking spaces in unpaved parking lots shall be delineated by placing a parking block ~~three~~ two feet from the end of the parking space and centered between the sides of the space.
2. Where the If a perimeter space abuts a structure, the space may be indicated on the structure, in which case parking blocks shall not be required.

c. Temporary parking lots. (See § 34-2022.)

~~Where temporary parking lots are permitted, the Individual spaces do not need to be delineated provided the end of each space and all aisles are clearly delineated with temporary posts and ropes. [moved to § 34-2022(b)(5)]~~

Sec. 34-2017. Parking lot surfaces.

(a) High turnover parking lots. (1) Parking aisles: Except as provided in subsection (d) of this section, all high turnover parking lot aisles and parking spaces shall be provided with a paved; dustfree, all-weather surface, except for the open space beyond parking blocks. (2) Parking spaces: All parking spaces, except those seaward of the coastal construction control line, shall have a paved; dustfree, all-weather surface from the aisle to the parking block or curb. All handicapped parking spaces, including handicapped parking spaces seaward of the coastal construction control line, shall be paved with asphalt or concrete to provide a smooth surface without gaps or holes which would create a danger to the user. For all other parking spaces, The term "paved" shall be interpreted to mean and include asphalt, concrete, brick, paving blocks, porous (pervious) asphalt or concrete.

paving block and other similar types of treatments. Clean (washed) angular gravel (such as FDOT #57 stone) may also be used if stabilized as provided in subsection (b)(1).

(1) Any parking spaces that may be permitted, excluding handicapped parking spaces, located seaward of the 1978 coastal construction control line shall be stabilized with best management practices treatments approved by the director, county administrator or his designee.

(2) All disabled parking spaces, including disabled parking spaces seaward of the coastal construction control line, shall be provided without gaps or holes that would create a danger to the user.

(b) **Low turnover parking lots.** (1) Due to the low volume of vehicle turnover in this type lot, alternative unpaved surfaces may also be permitted provided that the areas are adequately drained and continuously maintained in a dustfree manner.

(1) Alternative surfaces may include stabilized surfaces of grass or clean (washed) angular gravel over a well-drained base, crushed shell or other similar porous materials. Stabilization may be accomplished by turfblocks (concrete or plastic) or proprietary cellular or modular porous paving systems installed in accordance with manufacturers' specifications.

(2) Crushed limerock that has not been washed or otherwise processed to remove fine particles will be permitted as a surface material only when designed, placed, and maintained in a manner that will:
a. prevent the flow of sediment-laden runoff from the lot, and
b. keep the surface dust-free at all times.

(3) Parking on grass or other unimproved surfaces such as sand or dirt as approved parking shall be prohibited.

(4) Handicapped Disabled spaces must be paved with asphalt or concrete to provided with a smooth surface without gaps or holes which would create a danger to the user.

(c) **Temporary parking lots.** Temporary parking lots do not need to be surfaced, and may be maintained as a grass area or in a dustfree manner. *[subject moved to 34-2022(b)(6)]*

(c) **Reduced surfacing standards** Director discretion.

(1) The zoning director is authorized to permit portions of high turnover parking lots (including parking lot aisles), to meet the surfacing standards for low turnover parking lots (§ 34-2017(b), above) when the reduced surfacing standard will be used in those portions of the parking lot expected to receive the lightest usage, such as overflow or employee parking areas, under the following circumstances:

a. The property is not located in the intensive development or central urban land use categories;

b. The proposed parking lot will contain no more than 25 spaces;

c. The proposed alternative surface will be adequately drained; and

d. The proposed alternative surface is consistent with the uses and the parking lot surfaces in the surrounding neighborhood.

(2) This subsection may not be construed inconsistently with the Americans with Disability Act (ADA) of 1990.

(3) ~~The director's decision is discretionary in nature and may not be appealed pursuant to § 34-145(a) of this chapter.~~

(d) **Reservation of spaces for future use.** When a use or activity is required by this chapter to provide more than ten high turnover parking spaces, the zoning director may approve leaving up to 25 percent of the required spaces as landscaped areas reserved for future use, provided that:

(1) The applicant clearly shows ~~on the site plan~~ the reserved parking spaces on the site plan;

(2) The reserved parking areas shall not be counted towards meeting the minimum open space or landscaping or buffering requirements of this chapter or chapter 10;

(3) All drainage facilities shall be calculated and built as though the reserved parking areas were impervious surfaces; and

(4) The reserved parking areas shall not be used for any purpose other than landscaped open space or temporary overflow parking during special holiday seasons or sales.

Should the property owner decide to pave the reserved area for parking, he shall submit the original site plan or development order approval to the zoning director, who is hereby authorized to approve the paving provided that such paving

does not include any new entrances onto a public street. If the parking areas does involve new entrances, then a small project limited review development order is required.

Sec. 34-2018. Joint use of off-street parking lots.

(a) A single-purpose parking lot can provide some or all of the required parking spaces for two or more unrelated businesses, provided that such joint-use parking lot:

- (1) is built on a site where a commercial parking lot is permitted, and
- (2) is placed on the site so as not to violate any applicable build-to lines or block visibility of vehicles (see § 34-3131), and
- (3) is built to the same standards as a single-purpose parking lot, and
- (4) (a) Except where specifically approved as part of a planned development district, joint use of off-street parking lots shall be permitted only after application for and approval of a special permit (see § 34-203(c)(7)).
(b) Such shared parking lots shall be is located within 750 300 feet of, and contiguous to, each use and shall not be separated by a street right-of-way or easement which exceeds 25 feet in width.

(b) (c) No part of a parking lot used, designed or intended to satisfy required off-street parking for any use, shall be used to offset the parking requirements for another use unless The peak parking demands of the different uses clearly must occur at different times. The director may require an applicant to provide a technical analysis of the timing and magnitude of the proposed parking demands.

(c) Applications for joint-use parking lots must include: (5) Joint parking. a. The following shall be submitted with the application:

- (1) A notarized statement from all property owners involved indicating the use of each property and forecasting that the peak level of activities of each separate building or use which create a demand for parking will shall occur at different times.
- (2) Written agreements, covenants, contracts and the like, acceptable to the county, which ensure that the parking area is to be used jointly and establish the responsibility for

maintenance: A draft joint-use parking agreement, acceptable to the town attorney, that:

- a. specifically identifies the designated spaces that are subject to the agreement;
 - b. includes a statement indicating that the parties understand that these designated spaces cannot be counted to support any use other than those identified in the agreement;
 - c. identifies the current property uses, property owners, and the entity responsible for maintenance of the parking area.
 - d. (3) includes a backup plan to provide sufficient parking if the joint agreement is violated by either party.
- (3) Upon approval of the agreement by the town attorney, the agreement(s) must be recorded in the Lee County public records at the applicant's expense.
- b. Violation of the agreement for joint use of off-street parking is sufficient grounds for revocation of the special permit.
[relocated from § 34-203(g)(5)]

Sec. 34-2019. Other use of off-street parking lots.

(a) Parking spaces that are not in daily use and are located in parking lots having ten or more parking spaces and meeting the other requirements of this division may be rented to the general public during peak periods.

(b) (2) The following structures and uses may be approved in parking lots by the director provided that a site plan is submitted showing that the structure will not reduce the parking spaces required for the principal use, or create a traffic or pedestrian hazard:

- (1 a) Charitable or other similar dropoff collection stations.
- (2 b) Aluminum can or other similar receiving machines or facilities.
- (3 c) Photo pickup stations.
- (4 d) Telephone booths and pay telephone stations.
- (5 e) Automatic teller machines (ATM's).
- (6 f) Other similar uses which do not unreasonably interfere with the normal functioning of the parking lot.

(c) Except as provided in this section and for ancillary temporary uses as provided in § 34-3048,

required off-street parking areas shall ~~not in no~~ instance be utilized for the sale, display, or storage of merchandise, or for repair, dismantling, or servicing of any vehicles or equipment. ~~(1)~~ This shall not be interpreted to prohibit a residential property owner from the occasional servicing of his own noncommercial vehicle or conducting normal residential accessory uses.

Sec. 34-2020. Required parking spaces.

All uses permitted under this chapter shall be subject to the following minimum requirements:

Sec. 34-2011. Applicability of division:

(a) **New developments.** All New residential and nonresidential uses are ~~shall be~~ required to provide off-street parking spaces in single-purpose parking lots in accordance with the standards regulations specified in this section, division as modified by certain reductions as provided in the DOWNTOWN and SANTINI zoning districts (see division 5 of article III).

(b) **Existing developments.** ~~(1)~~ Existing buildings and uses ~~which have existing off-street parking spaces~~ may be modernized, altered, or repaired without providing additional parking spaces, provided there is no increase in total floor area or capacity. ~~Buildings which have been damaged in excess of 50 percent shall be required to comply with all applicable regulations.~~

~~(1 2)~~ Existing buildings or uses ~~which are~~ enlarged in terms of floor area shall provide additional parking spaces; for the enlarged floor area in accordance with the standards specified in this section this division, for the total floor area.

~~(2 3)~~ When the use of a building is changed to a different use which is required to have more parking than exists, the additional parking shall be provided in accordance with the standards specified in this section.

(c) **Bicycle parking.** Commercial, multifamily, and mixed-use buildings may eliminate one required parking space by providing and maintaining a bicycle rack able to hold four bicycles.

~~(c) Developments on islands without direct vehicular access to mainland: [deleted in its entirety]~~

(d) **Minimum parking standards.**

(1) **RESIDENTIAL USES.** ~~Dwelling, housing and living units.~~ For all common parking lots, in addition to the spaces required in this subsection, additional parking spaces equal to ten percent of the total required shall be provided to accommodate guest parking:

a. **Dwelling units with individual driveways:** ~~Single-family, duplex, two-family attached, and mobile home units.~~ The minimum requirement is 2.0 spaces for each dwelling unit. Stacking of vehicles in the driveway is permitted.

b. **Townhouses.** Minimum requirements are as follows:

1. For townhouses with individual parking driveways, 2.0 spaces per dwelling unit. Stacking is permitted.

2. For townhouses sharing a common parking lot, 2.0 spaces per dwelling unit. Stacking is not permitted.

b. c. **Dwelling units with common parking lots:** ~~Multiple-family buildings.~~ Minimum requirements are as follows:

1. Studio or efficiency: 1.0 1.25 spaces per unit.

2. One bedroom: 1.25 1.5 spaces per unit.

3. Two bedrooms: 1.25 1.75 spaces per unit.

4. Three or more bedrooms: 1.5 2.0 spaces per unit.

5. Live/work units: 2.0 spaces per unit. Stacking of vehicles is not permitted except as provided in § 34-2015(5).

c. **Timeshare units:** Parking requirements are the same as for multiple-family buildings. If lock-off accommodations are provided, parking for the lock-off units will be calculated at 0.5 extra spaces per lock-off unit.

d. **Living units without kitchens:** Living units that do not contain customary cooking facilities within the individual units but instead have a central kitchen for food preparation and where meals are served in a central dining area or individual rooms must calculate parking requirements as follows: one parking space per four residents or four beds (whichever is greater), plus ten percent.

d. ~~Adult congregate living facilities. See § 34-1411.~~

e. Group quarters, excluding living units subjects to § 34-2020(d)(1)d. adult congregate living facilities. The minimum requirement is one parking space per bedroom or one space per two beds, whichever is greater.

f. Hotels and motels. See division 19 of this article.

g. Health care facilities groups I and II; social services groups III and IV. The minimum requirement is one space per four beds.

h. Continuing care facilities. The minimum requirement is 0.75 space per one-bedroom living unit and 0.875 space per two-bedroom living unit. Requirements for adult congregate living facility units and health care facilities shall be calculated as provided in subsections (1)d and g of this section.

(2) COMMERCIAL USES.

a. Animal clinics. The minimum requirement is five spaces per veterinarian plus one space per employee.

b. Animal kennels. The minimum requirement is five spaces.

c. Automotive repair and service, automotive service stations. The minimum requirement is four spaces per service stall plus one space per employee.

d. Banks and financial establishments. The minimum requirement is one space per 300 square feet of total floor area. See also subsection (2)h of this section pertaining to drive-up facilities.

e. Bars and cocktail lounges. The minimum requirement is 15 ~~21~~ spaces per 1,000 square feet of total floor area. If outdoor seating is provided, an additional one space per four outdoor seats or 75 ~~50~~ square feet of outdoor seating area (whichever is greater) must be provided. See also subsection (2)h of this section, pertaining to restaurants, and subsection (4) ~~5~~ of this section.

f. Barbershops, beauty shops, etc. The minimum requirement is three spaces per operator (chair) or one space per 100 square feet of gross floor area, whichever is greater, with a minimum of five spaces.

b. Bed-and-breakfast inns. The minimum requirement is 1 parking space for each

guest room plus 1 space for the owners' quarters.

c. g. Car washes. The minimum requirement is two spaces per car wash stall or space, plus drive-through facilities (see subsection (2)d of this section). Each individual car wash stall or space may count as one of the required two parking spaces per stall.

d. h. Drive-through facilities. Where permitted, any commercial establishment providing drive-through service providing drive-through service windows or stalls shall provide separate vehicle stacking for those uses. For the purpose of this section, a stacking unit is defined as 18 feet in length and 9 feet in width. The total number of stacking units required is to be based on the type of business, as follows:

1. Banks and financial establishments: Stacking lanes to accommodate three ~~five~~ cars per window.

2. Car washes: Stacking to accommodate one car per service stall or three cars, whichever is greater.

3. Restaurants: New or expanded drive-through facilities are not permitted for restaurants (see § 34-620(f)). For existing drive-through facilities that are being lawfully reconfigured, stacking lanes to accommodate six ~~ten~~ cars per service lane, with a minimum of four ~~five~~ spaces preceding the menu board.

4. Other: i. Photo dropoff, laundry dropoff or other similar type dropoff facilities: Stacking for two ~~three~~ cars.
ii. All other: Stacking to accommodate three ~~five~~ cars per service lane.

e. Hotels and motels. The minimum requirement is 1.2 parking spaces for each guest unit up to 450 square feet and 1.5 spaces for each larger guest unit.

i. Funeral homes: *[deleted in its entirety]*

f. j. Offices, excluding medical. This category includes offices of all types not specifically listed elsewhere, including banks and medical facilities, but not limited to business services group I; contractors and builders, insurance companies, nonstore retailers, personal services group IV, social services group I, and other similar offices. The minimum requirement is 2 one spaces per 1,000 ~~300~~

square feet of total floor area. See also subsection (2)d. of this section pertaining to vehicle stacking for drive-through facilities.

k. Offices, medical and health care facilities group III. The minimum requirement is one space per 200 square feet of total floor area.

g. Personal services. The minimum requirement is 5 spaces per 1,000 square feet.

h. Restaurants. With the exceptions noted below, the minimum parking requirements for restaurants is 8 spaces per 1,000 square feet of total floor area plus any outdoor seating area.

1. Restaurants/bakeries. When a store such as a bakery provides seating for customers to eat the bakery products made on the premises, the store must provide a minimum of one parking space per table or 50 square feet of seating area (whichever is greater) in addition to the parking required for the bakery.

1. Accessory restaurant. When a restaurant is located within the same building as the principal use, and is clearly provided primarily for the employees and customers of the principal use, no additional parking spaces are required. In all other cases, parking shall be as follows: The minimum requirement is 14 spaces per 1,000 square feet of total floor area, plus 14 spaces per 1,000 square feet of all area used for outdoor seating.

2. Bars and cocktail lounges. If the restaurant contains a cocktail lounge or bar, the minimum requirement is 8 14 spaces per 1,000 square feet of total floor area plus 5 seven additional spaces per 1,000 square feet of floor area used for the bar or cocktail lounge. If outdoor seating is provided, parking must also be provided for the area used for outdoor seating at these same rates.

3. Restaurants, fast food. The minimum requirement is 16 spaces per 1,000 square feet of total floor area plus one space per four outdoor seats, except as provided for in § 34-2021. See also

subsection (2) h. of this section pertaining to drive-up facilities.

i. iii. Retail stores or business establishments, freestanding. This subsection applies to individual retail or business establishments, on separate parcels. The minimum number of parking spaces required shall be as specified in this subsection, but in no case shall be less than five spaces. Any retail establishment proposing drive-through facilities shall also meet the requirements of subsection (d)(2)d h of this section.

1. Building materials and sales (retail).

The minimum requirement is one space per 300 square feet of indoor sales and office area, plus one space per employee.

Convenience food and beverage stores. The minimum requirement is 4 spaces per 1,000 square feet of total floor area. If more than 20% of the total floor area or 600 square feet, whichever is less, is used for the preparation and/or sale of food or beverages in a ready-to-consume state, parking for this area will be calculated the same as a restaurant. One parking space per four pumps will be credited against the required parking.

2. Other retail or business establishments.

Small products or commodities. This category includes stores specializing primarily in small (handheld) products, and is intended to include convenience stores, clothing stores, department stores, drugstores, food stores, hardware stores, hobby, toy and game shops, package stores, personal services groups I and H (excluding barbershops, beauty shops, specialty retail shops groups I, H and III, used merchandise stores group I, variety stores, and other similar type stores. The minimum parking requirement is 3 one spaces for each 1,000 200 square feet of total floor area. Required parking for areas within the principal building which are used only for dead storage and are not available to the public shall be computed at the rate of 2 one spaces per 1,000 600 square feet.

3. Large products or commodities. [deleted in its entirety]

4. ~~Very large products or commodities.~~
[deleted in its entirety]
- n. ~~Schools and studios, commercial.~~ [deleted in its entirety]
- (3) ~~Commercial/industrial uses.~~
- a. ~~Manufacturing.~~ [deleted in its entirety]
- b. ~~Processing and warehousing.~~ [deleted in its entirety]
- c. ~~Services not listed elsewhere.~~ [deleted in its entirety]
- d. ~~Terminal, freight.~~ [deleted in its entirety]
- e. ~~Warehousing, private.~~ [deleted in its entirety]
- f. ~~Warehousing, public.~~ [deleted in its entirety]
- i. ~~g. Warehousing; (mini-warehouses).~~ The minimum requirement is 1 space per 25 ~~ten~~ storage units ~~cubicles~~, with a minimum of 3 ~~five~~ spaces.
- k. ~~h. Wholesale establishments.~~ The minimum requirement is 1 space per company vehicle plus 1 space per 1,000 square feet of total floor area.
- (3) ~~(4) MISCELLANEOUS USES.~~
- a. ~~Airports.~~ [deleted in its entirety]
- b. ~~Boat ramps.~~ [deleted in its entirety]
- c. ~~Bowling alleys.~~ [deleted in its entirety]
- d. ~~Clubs, fraternal or membership organizations.~~ [deleted in its entirety]
- e. ~~Day care centers.~~ [deleted in its entirety]
- a. ~~f. Educational institutions, including public, private and parochial.~~
1. ~~Public schools.~~ Parking shall be provided in compliance with state law.
2. ~~Private or parochial schools and day care centers.~~
- i. ~~Elementary and middle schools.~~ The minimum requirement is one space per employee plus one space for each 40 students.
- ii. ~~High schools.~~ [deleted in its entirety]
- iii. ~~Colleges, universities and trade and vocational institutions.~~ [deleted in its entirety]
- g. ~~Essential service facilities.~~ The minimum requirement is one space per employee on the largest shift
- q. ~~Flea markets.~~ The minimum requirement is one space per 100 square feet of display area.
- h. ~~Golf courses.~~ [deleted in its entirety]
- i. ~~Hospitals (health care facilities group IV).~~ The minimum requirement is one space per bed, excluding bassinets and gurneys, plus one space per employee on the largest shift.
- b. ~~j. Marinas and other water-oriented uses.~~ Minimum requirements are as follows:
1. ~~Boat slips: One Two~~ spaces per two ~~three~~ slips.
2. ~~Boat ramps.~~ See subsection (4)b of this section.
2. ~~3. Dry storage:~~ One space per six ~~four~~ unit stalls.
3. ~~4. Charter or party fishing boat services:~~ One space per three people based on maximum passenger capacity of the boats using the dock or loading facility.
4. ~~5. Cruise ships:~~ One space per three people based on the maximum passenger and crew capacity of the ship.
5. ~~Water taxis: Dedicated parking spaces are not required at stopping points for water taxis or water shuttles.~~
6. ~~Other uses: Other uses including accessory or ancillary marina uses such as restaurants, bars, or lounges, boat sales, etc. must be calculated separately in compliance with this division. Refer to subsection (5) of this section.~~
- k. ~~Miniature golf.~~ [deleted in its entirety]
- c. ~~Museums, art galleries, libraries, and other similar uses not covered elsewhere:~~ The minimum requirement is one parking space for each 500 square feet of total floor area.
- d. ~~t. Places of worship and religious facilities.~~ Refer to division 27 of this article.
- e. ~~m. Recreation facilities, indoor; commercial.~~ The minimum requirement is There shall be provided at least one parking space for each 150 ~~100~~ square feet of total floor area.
- n. ~~Recreation facilities, outdoor, commercial.~~ The parking requirement shall be determined by the director if the use is not listed in this section.
- o. ~~Tennis courts, commercial.~~ [deleted in its entirety]
- f. ~~p. Theaters, auditoriums, meeting halls, stadia, arenas and other similar places of public assembly, museums, art galleries,~~

libraries, and other similar uses not covered elsewhere. For such uses, there shall be provided either one parking space for each 300 square feet of total floor area; ~~or~~ The minimum requirement is one parking space for each four seats plus one space per employee, whichever of the two is greater. (See subsection (7) of this section.)

g. f. Carnivals, fairs, and amusement attractions and devices.

1. ~~There shall be provided a~~ The minimum requirement is five of ten parking spaces provided for each permanent amusement device.
2. ~~If such uses are located in an existing parking lot, the parking lot must have enough spaces to comply with the minimum requirements for both the principal use and the carnival, fair or amusement attraction or device. Prior to obtaining a temporary use permit (see division 37 of this article) for the temporary use of a parking lot for a carnival, fair or amusement attraction or device, the applicant shall submit a site plan showing that there will be no net loss or reduction in the number of parking spaces required for any existing principal use which relies on the parking lot.~~
3. ~~Such uses may not be located in an existing parking lot which is already nonconforming as to the number of spaces needed for the existing uses.~~

(4) ~~(5)~~ **COMBINED USES.** The number of parking spaces required for combined uses shall be the total of the spaces required for each separate use established by this schedule. Exceptions are as follows:

- a. Joint use of parking lots. except As provided in § 34-2018, and as provided for in this section.
- b. ~~α.~~ **Multiple-occupancy complexes.** This subsection applies to shopping centers and other multiple-occupancy complexes where five or more individual business office or retail establishments are located and which all share a common parking area. Specifically excluded from this subsection are: ~~(i)~~ theaters and hotels. ~~located outside of shopping centers or in~~

~~shopping centers smaller than 100,000 square feet, (ii) bowling alleys, and (iii) bars and cocktail lounges, and restaurants located outside of shopping centers or in shopping centers smaller than 50,000 square feet. Minimum requirements are as follows: [remainder deleted]~~

1. If the complex contains less than 25% of its gross floor area as restaurants, 2 spaces per 1,000 square feet.
2. If the complex contains 25% to 50% of its gross floor area as restaurants, 4 spaces per 1,000 square feet.
3. If the complex contains 50% to 75% of its gross floor area as restaurants, 6 spaces per 1,000 square feet.
4. If the complex contains over 75% of its gross floor area as restaurants, 8 spaces per 1,000 square feet.

~~b. Planned developments: [deleted in its entirety]~~

~~(5) (6)~~ **USES NOT SPECIFICALLY LISTED.** Requirements of Off-street parking for uses not specifically mentioned in this chapter shall be the same as for the uses most similar to the one sought, it being the intent to require all uses to provide off-street parking.

~~(7) BENCH AND PEW SEATING: [deleted in its entirety]~~

Sec. 34-2021. Reserved. Exception for fast order food establishments located in multiple use complex: ~~[deleted in its entirety]~~

Sec. 34-2022. Seasonal Temporary parking lots.

~~(a)~~ No temporary use permits for temporary parking lots shall be issued on Captiva Island or within the Gasparilla Island conservation district.

~~(a b)~~ In other areas of the county, Temporary use permits (see §§ 34-224, 34-3041, and 34-3049) may be issued for seasonal temporary parking lots, subject to the following: (i) Temporary parking lots shall be allowed, in conjunction with an approved temporary use permit. Approval of seasonal parking lots can be for a single period of up to 8 months long, commencing on November 15 and continuing until July 15 (subsection 34-2022(b)); or for a single period of up to 3 years on a year-around basis (subsection 34-2022(c)). For the purposes of this

subsection, temporary permits for seasonal temporary parking lots may also be issued for all or part of such time period and shall not be limited to 30 days as set forth in § 34-3041(d).

(b) A seasonal parking lot approved for a single period of up to 8 months must comply with the following regulations:

- ~~(2)~~ 1) A seasonal temporary parking lot shall only be permitted on vacant commercially or industrial zoned property or commercially or industrial zoned property with structures; provided that, on properties with structures, the structures are vacant and remain vacant.
- ~~(3)~~ 2) Temporary parking lots shall only be permitted when adjacent to a collector or arterial road or within 660 feet of a collector or arterial road. However, in no instance shall ingress and egress to seasonal parking lots shall not be through a residential neighborhood or residentially zoned district.
- ~~(4)~~ 3) The applicant must submit to the director a parking plan, drawn to scale, indicating but not limited to the following: the location of access points, ropes, and posts, and the circulation pattern within the parking lot.
- ~~(5)~~ 4) Individual spaces in seasonal parking lots do not need to be delineated provided the end of each space and all aisles are clearly delineated with temporary posts and ropes. The delineation of spaces for temporary parking lots shall be in accordance with § 34-2016(2)c.
- ~~(6)~~ 5) The temporary Seasonal parking lots do not need to be surfaced, and may surface shall be maintained as a grass area or otherwise in a dust-free manner, in accordance with § 34-2017(c).
- ~~(7)~~ 6) The temporary Seasonal parking lots shall be designed so as to permit vehicles exiting the lot to enter the street right-of-way in a forward motion. The seasonal temporary parking lot, where applicable, shall utilize an existing entrance or exit, except that no additional traffic shall be directed onto residential streets. Where no access exists, a the parking lot plan showing an acceptable temporary access point(s) may be approved shall be reviewed by the director county department of transportation and engineering.
- ~~(8)~~ 7) If the temporary seasonal parking lot is to be used at night, adequate lighting shall be

provided for the driveway's ingress and egress points. The lighting shall be directed to eliminate glare on any other use.

- ~~(9)~~ 8) The temporary seasonal parking lot shall be secured in a manner which will not permit ingress and egress except during the designated hours of operation.
- ~~(10)~~ 9) The temporary seasonal parking lot shall not adjoin or be less than ten feet from residential uses or residentially zoned property.
- ~~(11)~~ 10) A parking attendant shall be required during the posted hours of operation of the temporary seasonal parking lot.
- ~~(12)~~ 11) The temporary seasonal parking lot shall only be used for the parking of operable motor vehicles, with no overnight parking or camping. No other temporary or permanent use of the property shall be allowed during the life of the temporary use permit for parking.
- ~~(13)~~ § 34-3048, pertaining to ancillary uses permitted in off-street parking lots, shall not apply to this section.
- ~~(14)~~ 12) The maximum hours of operation shall be from 7:00 a.m. until 10:00 p.m., unless extended by the director in writing.
- ~~(15)~~ 13) The parking spaces created through the approval of temporary seasonal parking lots shall not be used for calculating off-street parking requirements as set out in § 34-2020.
- ~~(16)~~ Where approval for a temporary parking lot will extend beyond 30 days, the requirements of subsection (b)(17) of this section shall apply.
- ~~(14)~~ b. At intersections of parking lot entrances or exits with a street right-of-way or easement, no obstruction shall be planted or erected which materially obstructs the driver's view of approaching traffic or pedestrians (see § 34-3131).
- ~~(15)~~ c. Temporary Seasonal parking lot signs must comply with requirements for commercial development special occasion signs in § 30-151, except that the signs may remain in use for the duration of the temporary use permit. These signs must be created and displayed in a professional manner. The town manager may require the removal of any signs that do not comply with these standards, or which remain

visible after the expiration of the temporary use permit.

- (16) The town manager may require visual screening between a seasonal parking lot and any residentially zoned or used property. If additional screening is requested by the town manager, it must be installed within 30 days of written notice to the property owner or parking lot operator or the temporary use permit will be null and void.

(c) A seasonal parking lot approved for a single period of up to 3 years must comply with subsection 34-2022(b) and with the following additional regulations:

- (1) Compliance with all applicable regulations must be demonstrated on a paving, grading, and drainage plan acceptable to the director.
- (2) (17) a. Where a temporary seasonal parking lot abuts residentially zoned or used property, that portion of the parking lot shall be buffered by a continuous visual screen with a minimum opacity of 50 75 percent and a minimum height of three four feet. This screen may contain a combination of walls, fences, railings, and shrubs. Walls, fences, and railings may not exceed the maximum heights established by this code. The visual screen may be located as close as up to one foot from the right-of-way or street easement line but not closer than five feet from the edge of a travel lane. The town manager may require more extensive screening if the height, character, and location of the screen does not or may not adequately protect the abutting property from excessive impacts from the temporary seasonal parking lot. Additional screening as requested by the town manager must be installed within 30 days of written notice to the property owner or parking lot operator, or the temporary use permit will be null and void.

b. *[moved to 34-2022(b)(16)]*

c. *[moved to 34-2022(b)(17)]*

- (3) Where a seasonal parking lot abuts a street, that portion of the parking lot shall be buffered by a continuous visual screen with a minimum opacity of 25 percent and a minimum height of three feet. This screen may contain a combination of walls, fences, railings, and shrubs. The visual screen may

be located up to one foot from the right-of-way or street easement line.

- (4) Seasonal parking lot signs must comply with requirements for individual business establishment signs in § 30-153. These signs must be created and displayed in a professional manner. The town manager may require the removal of any signs that do not comply with these standards, or which remain visible after the expiration of the temporary use permit.

(d) Seasonal parking lots remaining in use for longer than three years are considered to be permanent shared parking lots and must be constructed to this divisions's standards for single-purpose parking lots, including landscape buffering. Permanent shared parking lots must be approved by special exception (see § 34-2015(2)b.).

Secs. 34-2023--34-2030 ~~2050~~. Reserved.

DIVISION 26-A. **PERFORMANCE STANDARDS**

Sec. 34-2031 ~~623~~. Performance standards, environmental quality.

All uses and activities permitted by right, ~~special permit~~, special exception, or temporary use permit in any zoning district, including planned development districts, shall be constructed, maintained, and operated so as to:

- (1) comply with all local, state, and federal air, water and noise, and water pollution standards, and
- (2) not adversely impact water quality.

Sec. 34-2032. Performance standards, creation of nuisance.

All uses and activities permitted by right, special exception, or temporary use permit in any zoning district, including planned development districts, shall be constructed, maintained, and operated so as to:

- (1) not be injurious or offensive and thereby constitute a nuisance to the owners and occupants of adjacent premises, nearby residents, or to the community, by reason of the emission or creation of noise, vibration, smoke, dust, or other particulate matter, toxic

or noxious waste materials, odors, fire or explosive hazard, or glare; ~~and nor shall anything be placed, constructed or maintained that would in any way constitute a nuisance to owners or residents or to the community, or adversely impact water quality and water needs.~~

- (2) not cause light from a point source of light to be directed, reflected, or refracted beyond the boundary of the parcel or lot, onto adjacent or nearby residentially zoned or used property or onto any public right-of-way, and thereby constitute a nuisance to owners or occupants of adjacent premises, nearby residents, or to the community; and
- (3) ensure all point sources of light and all other devices for producing artificial light are shielded, filtered, or directed in such a manner as to not cause light trespass.

Secs. 34-2033--34-2050. Reserved.

DIVISION 27. PLACES OF WORSHIP AND RELIGIOUS FACILITIES

Sec. 34-2051. Property development regulations.

(a) *Noncommercial or nonindustrial districts.*
[deleted in its entirety]

(b) *Commercial and industrial districts.* All places of worship and all religious facilities located in a zone permitting both residential and commercial uses as principal uses shall adhere to the commercial property development regulations of that zoning district.

Sec. 34-2052. Parking.

(a) *Places of worship.* Parking for places of worship shall be provided at the ratio of one parking space for each three seats within the sanctuary or main assembly hall, whichever is greater. ~~See § 34-2020(7) for computation of parking requirements for pew seats.~~ Where benches, pews or other similar seating arrangements are used, each 24 lineal inches shall be counted as one seat.

(b) *Religious facilities.* Parking for religious facilities shall be the same as for places of worship, with additional parking for ancillary facilities as required in division 26 of this article; provided that,

where the ancillary facilities will not be used at the same time, parking shall be based upon the peak anticipated attendance at any one time, for all facilities.

(c) *Parking on grass.* Up to ~~75~~ 50 percent of the parking spaces required for the sanctuary or main assembly hall of a place of worship may be provided as parking on grass, provided the regulations set forth in the following sections of division 26 of this article, pertaining to ~~off-street~~ parking requirements, are met:

- (1) ~~§ 34-2013, concerning parking lot access.~~
- (2) ~~§ 34-2014, concerning parking plans.~~
- (3) ~~§ 34-2015(1), concerning location.~~
- (4) ~~§ 34-2015(2), concerning design, subsections a, c and d.~~
- (5) ~~§ 34-2016(1)b, concerning dimensional requirements.~~
- (6) ~~§ 34-2016(3), concerning aisle widths.~~

Sec. 34-2053. Expansion of existing place of worship.

Expansion of existing places of worship, lawfully existing as of August 1, 1986, by right or by special exception, is hereby declared a legal use. Additions, renovations, or other expansion of the main place of assembly may be permitted upon application for and approval of a building permit in accordance with all applicable town county regulations, ~~without the requirement of special exception approval. Any expansion which would constitute a religious facility will require a special exception, except in those zoning districts where permitted by right.~~

Secs. 34-2054--34-2080. Reserved.

DIVISION 28. RESERVED PLANT NURSERIES *[deleted in its entirety]*

Secs. 34-2081--34-2110. Reserved.

DIVISION 29. PRIVATE CLUBS, FRATERNAL CLUBS AND MEMBERSHIP ORGANIZATIONS CLUBS

Sec. 34-2111. Applicability of district use regulations to membership organizations.

The listing in this code of limited enumeration of a private, fraternal, or membership organizations club use is not meant to limit or abridge the rights of assembly in any way. Such organizations are not prohibited from meeting in various traditional and appropriate places. For example, a service club's weekly meeting at a restaurant in a district not otherwise allowing a fraternal, membership organization, or private clubs shall not constitute a zoning violation. However, where such an organization is the principal user of real property for meetings, entertainment, and food and beverage service, such a meeting place, hall, or clubhouse shall be permitted only where this use is explicitly enumerated.

Secs. 34-2112--34-2140. Reserved.

**DIVISION 30:
PROPERTY DEVELOPMENT REGULATIONS**

*Subdivision I. In General
[deleted in its entirety; content
has been moved to § 34-637]*

*Subdivision II. Height
[deleted in its entirety; content
has been moved to § 34-631]*

*Subdivision III. Setbacks
[moved to § 34-638]*

*Subdivision IV. Lots
[deleted in its entirety]*

*Subdivision V. Gasparilla Island
[deleted in its entirety]*

*Subdivision VI. McGregor Boulevard
[deleted in its entirety]*

**DIVISION 30.
SPORTS/AMUSEMENT PARKS AND
RECREATIONAL FACILITIES**

[relocated from division 35 of this chapter]

Sec. 34-2141, 2471. Applicability of division.

(a) The regulations set forth in this division for recreation specific sports/amusement parks and facilities are in addition to any other applicable regulations. In the case of conflict, the most restrictive regulations shall apply.

(b) This chapter defines five types of recreation facilities (see § 34-2):

- (1) Recreation facilities, commercial, which are permitted by special exception in certain zoning districts.
- (2) Recreation facilities, personal, which are considered to be residential accessory uses.
- (3) Recreation facilities, private ON-SITE, which are permitted by right in certain zoning districts.
- (4) Recreation facilities, private OFF-SITE, which are permitted by special exception in certain zoning districts.
- (5) Recreation facilities, public, which are permitted by right in certain zoning districts.

(c) This chapter also defines Park, neighborhood and Park, community or regional (see § 34-2), both of which are permitted by right in certain zoning districts.

Sec. 34-2472. Required approvals. *[deleted in its entirety]*

Sec. 34-2142, 2473. Minimum lot area and setbacks.

(a) All sports/amusement parks and recreation facilities, whether a principal use or accessory use, shall be located on property meeting the minimum lot size and dimensions of the zoning district in which located as well as any additional area, width, or depth required to permit full compliance with all setbacks, ground cover, open space, buffering, drainage, and parking requirements as set forth in this chapter or ch. 10, whichever is most applicable.

~~Sec. 34-2474. Setbacks.~~

~~(b) (a) Minimum setbacks for uses subject to this division are as follows:~~

- ~~(1) Street setbacks shall be as set forth in § 34-2192.~~
- ~~(2) Water body setbacks shall be as set forth in § 34-2194.~~
- ~~(3) Side and rear setbacks shall be as set forth in the property development regulations of the zoning district in which located, except as provided in this division.~~

~~(c) (b) Additional setback requirements for specific uses are as follows:~~

- ~~(1) Recreation facilities, commercial outdoor sports/amusement parks, amusement devices, and water slides. Amusement devices, water slides, miniature golf, and other commercial outdoor sports/amusement parks and recreation sports/amusement parks and recreation facilities not specifically regulated shall be located not less than 50 feet or a distance equal to the height of the structure or device, whichever is greater, from any property under separate ownership, provided further that such setback shall be 100 feet from any adjacent property with residential zoning zoned RS, TF, TFC, RM, MH or RPD, or any existing residential use.~~

~~(2) Arenas, stadiums and racetracks. [deleted in its entirety]~~

~~(3) Bleachers and other seating facilities. [deleted in its entirety]~~

~~(4) Drive-in theaters. [deleted in its entirety]~~

~~(5) Golf driving range not part of an approved golf course. [deleted in its entirety]~~

~~(2) (6) Recreation halls and private clubs. Recreation halls and ancillary facilities and membership organizations private clubs shall be located at least 40 feet from any residential dwelling and situated in a manner so as to encourage pedestrian and bicycle traffic.~~

~~(7) Outdoor shooting ranges. [deleted in its entirety]~~

~~(3) (8) Other facilities. The following Other facilities are specifically regulated elsewhere in this code, such as swimming pools and tennis courts in division 2 of this article. chapter:~~

~~a. Marinas, § 34-1862.~~

~~b. Stables, boarding and commercial, division 6 of this article.~~

~~c. Swimming pools and tennis courts, division 2 of this article.~~

~~Sec. 34-2475. Access. [deleted in its entirety]~~

Sec. 34-2143, 2476. Accessory uses.

(a) Accessory uses, buildings, or structures for sports/amusement parks and recreational facilities which are customarily incidental to the principal use may be permitted. Such uses include but are not limited to restroom facilities, maintenance sheds, refreshment stands (with no alcoholic beverages unless approved in accordance with division 5 of this article), pro shops (where applicable), and administrative offices.

~~(b) During daylight hours, drive-in theater parking areas may be used for a flea market, provided no buildings are erected in connection with such use. Drive-in theaters may also be used to provide off-site parking for arenas, stadiums, etc., in accordance with § 34-2478, if approved by the Board of County Commissioners.~~

~~(b) (c) Food and beverage service, limited, is permitted in any recreation hall; provided, however, no alcoholic beverages shall be distributed or consumed on the premises except in compliance with division 5 of this article.~~

Sec. 34-2144, 2477. Lighting.

Artificial lighting used to illuminate the premises of sports/amusement parks and recreational facilities shall be directed away from adjacent properties and streets.

~~Sec. 34-2478. Parking. [deleted in its entirety]~~

Sec. 34-2145, 2479. Sound systems.

Sound systems for sports/amusement parks and recreational facilities shall meet the requirements of the town's county noise control ordinance, Ordinance Nos. 96-24 as may be amended from time to time 82-32 and 83-22.

Secs. 34-2146--34-2350. Reserved.

**DIVISION 31. RECREATIONAL VEHICLES
AS PERMANENT RESIDENCES**

~~Sec. 34-2351. Use as permanent residence. [moved
to § 34-694(a)]~~

Sec. 34-2351. Recreational vehicle subdivisions.

(a) New or expanded recreational vehicle subdivisions are not allowed in the Town of Fort Myers Beach.

(b) A recreational vehicle cannot be substantially improved or placed on any lot in any subdivision except:

- (1) for parking of a single recreational vehicle for purposes of dead storage, or
- (2) on a temporary basis in accordance with § 34-3046.

Sec. 34-2352. Recreational vehicle parks.

(a) New or expanded recreational vehicle parks are not allowed in the Town of Fort Myers Beach.

(b) A recreational vehicle cannot be substantially improved or placed in any existing recreational vehicle park except in the VILLAGE zoning district in accordance with the regulations set forth in subdivision III of division 5 of article III of this chapter, and in accordance with the requirements of § 6-472(3).

~~Secs. 34-23532--34-2380. Reserved.~~

DIVISION 32. SCHOOLS

Sec. 34-2381. All schools.

(a) All schools, whether run by government, religious, or non-profit agencies or operated as businesses, may be located only in the following categories on the future land use map in accordance with Policy 4-B-14 of the comprehensive plan:

- (1) Mixed Residential,
- (2) Boulevard,
- (3) Pedestrian Commercial, or
- (4) Recreation (but never seaward of the 1978 coastal construction control line).

(b) The maximum intensity of new or expanded schools shall not exceed a floor area ratio of 0.50 (see § 34-633).

Sec. 34-2382†. Noncommercial schools.

(a) Public schools. Permitted districts: All noncommercial schools constructed by the district school board on land owned by the district school board are permitted by right in any zoning district, provided the site complies with § 34-2381(a). Also permitted by right in any zoning district is Florida Gulf Coast University, located in the Lee Plan University Campus category, including all facilities normally associated with a public university. Development of Florida Gulf Coast University will be in accord with a campus master plan adopted pursuant to F.S. § 240.155.

(b) Other noncommercial schools. All Other noncommercial schools are permitted by right or are required to obtain special exception approval prior to any new construction or expansion of an existing facility, in accordance with the district use regulations in, provided the site complies with § 34-2381(a).

(b) Access. Access requirements for new schools are as follows:

- (1) Whenever possible, elementary schools will have access to local or collector streets, and
- (2) Secondary schools must have access to a collector or arterial street.

(c) Location. No school site will be approved which, in the opinion of the hearing examiner, is exposed to physical constraints, hazards or nuisances which are detrimental to the health and safety of students and to the general operation of the school:

Sec. 34-2383. Schools operated as businesses.

Schools that are operated as private businesses are permitted wherever this code allows *Offices, general and medical* (see division 2 of article III of this chapter), provided the site complies with § 34-2381(a).

~~Secs. 34-23842--34-23902410. Reserved.~~

DIVISION 32-A. SHORT-TERM RENTALS

Sec. 34-2391. Restrictions on weekly rentals in certain zoning districts.

Table 34-2 restricts the rental of any permitted dwelling unit in certain zoning districts to a single family during any one-month period, with a minimum stay of one week (see the "Restricted" sub-group of the "Lodging" use group in Table 34-1). The following exceptions apply to this restriction:

- (1) This restriction on weekly rentals does not apply to:
 - a. Any land between Estero Boulevard and the Gulf of Mexico.
 - b. Any land directly adjoining the bay side of Estero Boulevard.
 - c. Any dwelling unit that is recognized by the Town of Fort Myers Beach as having had pre-existing weekly rentals as of January 1, 2003, when registered in accordance with § 34-2392.
- (2) Dwellings units on property that qualifies for any of these exceptions may be rented to a single family for periods of one week or longer, without the once-per-month maximum that would otherwise have applied.

Sec. 34-2392. Registry of certain pre-existing weekly rentals.

(a) Dwelling units in certain zoning districts are not permitted to be rented to more than a single family during any one-month period due to restrictions found in Tables 34-1 and 34-2. The owner of any such dwelling unit that was being lawfully used for weekly rentals during the 12-month period prior to January 1, 2003, may apply for registration under this section to continue weekly rentals.

- (1) Upon verification by the town and placement of such dwelling units on a registry of pre-existing weekly rentals, the owners of registered dwelling units may continue to rent those units to a single family for periods of one week or longer, without the once-per-month maximum that would otherwise have applied.
- (2) This right shall run with the land and shall not be affected by the transfer of the property to subsequent owners.

- (3) If weekly rentals of a particular dwelling unit are terminated for any reason for any 12-month period, weekly rentals may not thereafter be reinstated in that dwelling unit.
- (4) Dwelling units on land that is not affected by the restrictions in Tables 34-1 and 34-2 limiting rentals to no more than a single family during any one-month period should not be submitted for registration. Such units will not be placed on the registry of pre-existing weekly rentals.

(b) Applications for annual registration of lawful pre-existing weekly rental units shall be submitted to the town manager by June 1, 2003. Each application must include:

- (1) Name of the applicant, if different than the property owner, and the applicant's mailing address and telephone number.
- (2) Name of current property owner (and previous owner, if property has been transferred since January 1, 2003).
- (3) Street address and STRAP number of parcel.
- (4) Number of rental dwelling units at that address that are part of the application.
- (5) Evidence of lawful pre-existing weekly rental use of each dwelling unit in the application as of January 1, 2003. Such evidence may include:
 - a. Evidence that each dwelling unit was licensed by the state of Florida as a "resort dwelling" or as a public lodging establishment, in accordance with F.S. § 509.241.
 - b. Evidence of regular payment of Lee County's 3% tourist development tax on rentals of each dwelling unit.
 - c. Evidence of regular payment of Florida's 6% sales tax on rentals of each dwelling unit.
 - d. Signed rental contracts or income tax returns.
- (6) A local telephone number with a contact that is available 24 hours a day.
- (7) Payment of an application fee established by the town.
- (8) Notarized signatures of the property owner (and the applicant, if different than the property owner) attesting to the truth and accuracy of all information submitted with the application and consenting to inspection of the premises at reasonable hours to

determine compliance with town and fire codes.

(c) The town manager will evaluate each application and notify applicants in writing within 60 days whether each dwelling unit is being registered with the town as a pre-existing weekly rental unit or whether the dwelling unit does not qualify for such registration. Reasons for disqualification will be stated in the written notice. All applications and written responses are public records and will be available for inspection at town hall.

(d) Decisions by the town manager pursuant to this subsection may be appealed to the town council by the applicant or adjoining property owner in accordance with § 34-86. In addition to the criteria in this subsection, the town council may consider evidence submitted by the appellant alleging equitable considerations for registration of a dwelling unit despite noncompliance with a particular requirement of this division. The town council shall consider the advice of the town attorney when evaluating allegations for equitable relief.

(e) Registrants must supplement their application within 30 days if they change the local telephone number for the contact that must be available 24 hours a day.

(f) Beginning on June 1, 2004 and every year thereafter, renewal applications are due for all registered weekly rental units.

- (1) The renewal application shall be the same as the original application except that evidence of subsections (b)(5)a, (b)(5)b, and (b)(5)c shall be mandatory for every renewal period.
- (2) Registrants who continue weekly rentals after failing to complete a renewal application and obtaining registration for another year will be in violation of this code.

Sec. 34-2393. Code of conduct for short-term rentals.

(a) The town hereby establishes a code of conduct that applies to operators and guests of all short-term rental units, including those on the registry of pre-existing weekly rentals and also those rentals between one week and one month that

are permitted by right in accordance with Table 34-2. The code of conduct is as follows:

- (1) **Maximum Occupancy:** Occupancy of each short-term rental unit must be consistent with the definition of “family” that is found in § 34-2 of this code, which defines a family as one or more persons occupying a dwelling unit and living as a single, nonprofit housekeeping unit, provided that a group of five or more adults who are not related by blood, marriage, or adoption shall not be deemed to constitute a family.
- (2) **Refuse Collection:** Refuse containers shall not be moved to the street more than 24 hours prior to scheduled curbside collections nor remain there more than 24 hours after scheduled collections, as required by § 6-11 of the Fort Myers Beach land development code. In addition, if a property owner or property manager is unable to comply with this requirement around the weekly pick-up day, arrangements for additional refuse collection must be secured by the operator.
- (3) **Quiet Hours:** Between the hours of 10:00 PM and 7:00 AM, all guests shall observe quiet hours. This means all outdoor activity, including swimming, shall be kept to a reasonable noise level that is non-intrusive and respectful of neighbors. Town of Fort Myers Beach Ordinance 96-24 sets limits on noise levels during quiet hours and these levels must be obeyed by all guests.
- (4) **Mandatory Evacuations:** All guests staying in short-term rental units must comply with mandatory evacuations due to hurricanes and tropical storms, as required by state and local laws.

(b) Operators are required to provide guests with the town’s code of conduct for short-term rentals.

- (1) The town shall provide operators with a printed version of the code of conduct and a standardized agreement for compliance.
- (2) The operator shall provide guests of short-term rental units with the code of conduct and obtain the signature of guests on the agreement indicating that they are aware of and intend to comply with the code of conduct.
- (3) The code of conduct shall also be posted at the primary entrance/exit to each short-term rental unit.

(c) Operators must provide the town with a current local telephone number of a contact for each short-term rental unit. This telephone number must be answered 24 hours a day to respond to complaints. These telephone numbers are public records and will be available at town hall during regular business hours.

Sec. 34-2394. Enforcement and penalties.

(a) The director is authorized to pursue any one or combination of the enforcement mechanisms provided in this code (for example, § 1-5, or article V of ch. 2) for any violation of this division.

(b) Persons who may be charged with a violation of this division include property owners, operators, rental agents, guests, and any other person using the structure where the violation has been committed.

(c) For properties on the registry of pre-existing weekly rentals (see § 34-2392), the following additional requirements shall apply:

(1) Violations of F.S. ch. 509 shall also be considered to be violations of this division as follows:

a. Failure to maintain licensure or any other provisions of ch. 509.

b. Failure to eject guests who indulge in any conduct which disturbs the peace and comfort, as provided by § 509.141.

(2) Repeated violations of this division on a registered property shall lead to cumulative penalties. These penalties shall accrue as follows whenever a violation results in a fine being imposed on or paid or whenever a finding of violation is made by a judge or code enforcement hearing examiner:

a. First violation: \$250 fine.

b. Second violation: \$500 fine.

c. Third violation: six-month suspension of registration under § 34-2392.

d. Fourth violation: two-year suspension of registration under § 34-2392.

After any period of three years during which there were no fines imposed or paid and no formal findings of violations of this division, the next violation shall be deemed to be the first violation for purposes of this section.

Sec. 34-2395–34-2410. Reserved.

DIVISION 33. SIGNS

Sec. 34-2411. Location and construction.

All on-site and off-site signs shall be located, erected, and constructed in accordance with ch. 30.

Secs. 34-2412--34-2440. Reserved.

**DIVISION 34. SPECIAL SETBACK
REGULATIONS FOR SPECIFIC USES
*[deleted in its entirety]***

DIVISION 34. SPECIAL EVENTS

Sec. 34-2441. Special events defined.

A special event is any social, commercial, or fraternal gathering for the purpose of entertaining, instructing, viewing a competition, or for any other reason that would assemble an unusual concentration of people in one location. Specifically excluded from this definition are any gatherings formed and/or sponsored by any recognized religion or religious society.

Sec. 34-2442. Permits for special events.

(a) The Town of Fort Myers has established a permitting process for special events through Ordinances 98-01 and 00-16 and any future amendments.

(b) No person, corporation, partnership, or other entity shall advertise or sell or furnish tickets for a special event within the boundaries of the town, and no such event shall be conducted or maintained, unless and until that person or entity has obtained a permit from the town to conduct such event.

(c) Special events on the beach shall also comply with § 14-11 of this code.

Secs. 34-2443--34-2470. Reserved.

DIVISION 35. RESERVED
SPORTS/AMUSEMENT PARKS AND
RECREATIONAL FACILITIES
[relocated to division 30 of this chapter]

Secs. 34-2471~~80~~--34-3000. Reserved.

DIVISION 36. STORAGE FACILITIES AND
OUTDOOR DISPLAY OF MERCHANDISE

Sec. 34-3001. Applicability of division.

(a) Except as provided in this section, the regulations set forth in this division shall apply to all outdoor display of merchandise which is offered for sale or rent, and to all storage facilities as defined in this division.

(b) The provisions of the division do not apply to the display, sale, or rental of motor vehicles, boats, recreational vehicles, trailers, mobile homes, construction or farm equipment (see § 34-1352); or to junk, scrap or salvage yards (see division 20 of this article); or to refuse, trash dumps and sanitary landfills (see division 20 of this article); or to garage or yard sales by residents of dwelling units on their own property in accordance with this code (see § 34-2 622(c)(42)); or to the mooring or docking of aircraft or watercraft.

~~Sec. 34-3002. General setback requirements.~~
~~*[deleted in its entirety]*~~

Sec. 34-3002 1712. Mobile vendors prohibited.

(a) Mobile vendors includes a person who sells food or other product or service to the public from a mobile dispensing vehicle which is self-propelled or otherwise readily moveable from place to place either operated from a base facility or not operated from a base facility.

(b) No mobile vendor shall be permitted to make sales from a vehicle while stopped on the right-of-way or other public property within the limits of the Town of Fort Myers Beach, except in accordance with § 34-3004.

Sec. 34-3003. Reserved. Lighting. *[moved to § 34-3004(c)]*

Sec. 34-3004. Outdoor display of merchandise for sale or rent.

~~(a) *Display setbacks.* *[deleted in its entirety]*~~

~~(b) *Display area.* *[deleted in its entirety]*~~

(a) Outdoor sales includes all sales or display of merchandise, food, and beverages between the outer wall of stores and public rights-of-way or, where permitted, on public rights-of-way, but does not include merchandise visible through windows or sold to customers using pass-through windows.

(b) This code allow outdoor display and sales of merchandise only as follows:

- (1) In farmers' markets or other special events authorized by the town;
- (2) Beach furniture (in accordance with § 14-5);
- (3) Bicycles, motorbikes, and motorcycles (by dealers or rental agencies in zoning districts where they are permitted);
- (4) Boats (by boat dealers in zoning districts where they are permitted);
- (5) Personal watercraft (in accordance with § 27-49);
- (6) Lawn and garden ornaments (by retail stores in zoning districts where they are permitted), provided the merchandise collectively does not exceed a height of 4 feet and a width (parallel to the right-of-way) of 8 feet;
- (7) On private property in the Downtown zoning district (in accordance with § 34-677(c)(1)); and
- (8) On public property in parts of the Downtown zoning district (in accordance with § 34-677(c)(2)).

(c) Artificial lighting used to illuminate premises subject to this division shall be directed away from adjacent properties and streets, shining only on the subject site. *[moved from § 34-3003]*

(d) The outdoor display and sales of merchandise, food, and beverages is prohibited within the town limits, except in accordance with this section.

Sec. 34-3005. Storage facilities.

(a) **Indoor storage.**

- (1) *Permitted districts.* Except for warehouses and miniwarehouses, indoor storage is permitted within any zoning district when

accessory to the permitted principal use of the property. Warehouses and miniwarehouses are permitted only in zoning districts for which it is specifically stated that such uses are permitted.

- (2) *Setbacks.* All buildings used for indoor storage which are located on the same lot as the principal building shall comply with the setback requirements for accessory buildings. Buildings used for indoor storage which are not on the same lot as the principal building, but are on the same premises, shall meet the setbacks set forth in the district regulations for principal buildings.

(b) *Open storage.*

- (1) *Fencing and screening.* All commercial ~~or industrial~~ outdoor storage shall be shielded behind a continuous visual screening at least eight feet in height when visible from a residential use or residential zoning district, and six feet in height when visible from any street right-of-way or street easement. ~~The fence shall be located not less than five feet from the right-of-way or street easement line (see division 17 of this article):~~
- (2) *Storage area.* Storage areas do not need to be paved. Grass or other ground cover may be used provided it is kept in a sightly and dustfree manner.

(c) *Use of vehicles, truck trailers, or shipping containers for storage.* Vehicles, truck trailers, shipping containers, and other similar structures may not be used to store goods, produce, or other commodities unless approved on a temporary basis in accordance with § 34-3044.

(d) ~~(c)~~ *Bulk storage of flammable liquids.*

- (1) *Firewalls or dikes required.* Whenever aboveground tanks for storage of gasoline, gas, oil, or other flammable liquids are located on any land where such use is permitted, such tanks shall be surrounded by an unpierced firewall or dike of such height and dimensions as to contain the maximum capacity of the tanks. All storage tanks and adjacent structures shall meet the requirements of the Board of Fire Underwriters.
- (2) *Exceptions.* Storage tanks containing liquified petroleum, commonly known as

bottled gas, are specifically excluded from the provisions of this subsection.

Secs. 34-3006--34-3020. Reserved.

DIVISION 37. SUBORDINATE AND TEMPORARY USES

Subdivision I. In General

Sec. 34-3021. Subordinate uses.

(a) *Purpose.* The purpose of this section is to provide for certain commercial uses provided such uses are clearly subordinate to a permitted principal uses of Cultural facilities; Hotels/motels; Multiple-family buildings; Park, community or regional; or Resorts. and are in compliance with the regulations set forth in this section:

~~(b) *Subordinate commercial uses for mobile home or recreational vehicle developments.*~~
~~[deleted in its entirety]~~

(b) *Permitted uses; restrictions.* (c) ~~Other subordinate commercial uses:~~

- (1) The subsection applies to subordinate commercial uses for hotels/motels, multiple-family buildings, social services groups III and IV (§ 34-622(c)(46)), health care facilities groups I, H, and IV (§ 34-622(c)(20)), cultural facilities groups I and H (§ 34-622(c)(10)), and office complexes containing 50,000 square feet or more of floor area on the same premises. The uses listed in subsection (b c)(2) of this section shall be permitted when clearly subordinate to the principal use, subject to the following requirements:
- a. The ~~subordinate~~ retail use shall be totally within the building(s) housing the principal use;
- b. The ~~subordinate~~ retail use shall not occupy more than ten percent of the total floor area of the principal use; and
- c. Public access to the ~~subordinate~~ commercial uses shall not be evident from any abutting street.
- (2) Uses permitted are:
- a. ~~Personal services~~ groups I and H (§ 34-622(c)(33)).
- b. Pharmacy:

- ~~b. c. Specialty Retail store, small groups I and H (§ 34-622(c)(47)).~~
- ~~c. d. Restaurant group H (§ 34-622(c)(43)).~~
- ~~e. Rental or leasing establishment group I (§ 34-622(c)(39)).~~

Secs. 34-3022--34-3040. Reserved.

Subdivision II. Temporary Uses

Sec. 34-3041. Generally.

(a) **Purpose.** The purpose of this subdivision is to specify regulations applicable to certain temporary uses which, because of their impact on surrounding land uses, require a temporary use permit.

(b) **Permit required.** No temporary use shall be established until a temporary use permit has been obtained from the ~~department~~ director in accordance with the requirements of § 34-3050. Some temporary uses may qualify as special events that are regulated by Ordinance 98-01 as amended, or may qualify as special events on or near the beach, which are further regulated by § 14-11 of this code.

(c) **Lighting.** No permanent or temporary lighting shall be installed without an electrical permit and inspection.

(d) **Time limit.**

- (1) All uses shall be confined to the dates specified by the director, on the temporary use permit; provided, however, that:
 - a. Except as provided for seasonal parking lots in §§ 34-2022 and for other uses where specifically provided in §§ 34-3043 through 34-3048 ~~3047~~, the director may not authorize a temporary use for ~~the~~ more than 30 days; and
 - b. If no time period is specified on the temporary use permit, then the temporary use permit will expire and the use must be abated within 30 days from the date of issuance.
- (2) A temporary use permit may not be renewed or reissued to the same applicant or on the same premises for a similar use for a period of six months from the date of expiration of the previous temporary use permit.

(e) **Hours of operation.** Hours of operation shall be confined to those specified in the permit.

(f) **Cleanup.** The site shall be cleared of all debris at the end of the temporary use and all temporary structures shall be removed within 48 hours after termination of the use. A cash bond of a minimum of \$25.00 and not to exceed \$5,000.00 ~~shall be posted~~ or a signed contract with a disposal firm may ~~shall~~ be required as a part of the application for a temporary use permit to ensure that the premises will be cleared of all debris during and after the event.

(g) **Traffic control.** Traffic control as may be required by the county sheriff's department and the county department of transportation shall be arranged and paid for by the applicant.

(h) **Damage to public right-of-way.** A cash bond of a minimum of \$25.00 and not to exceed \$5,000.00 may ~~shall be required~~ posted ~~with county~~ to ensure the repair of any damage resulting to any public right-of-way as a result of the event. ~~Any bond meeting the standards in subsection (f) of this section shall also be deemed sufficient to meet the requirements of this subsection.~~

Sec. 34-3042. Carnivals, fairs, circuses, and amusement devices.

(a) **Location of amusement devices and other structures.** Refer to § 34-2142(a) and (b) for setback requirements.

- ~~(1) Setback from street for amusement devices: [deleted]~~
- ~~(2) Setback from bodies of water for amusement devices: [deleted]~~
- ~~(3) Setbacks from side and rear property lines for amusement devices: [deleted]~~
- ~~(4) Setbacks from habitable structures for amusement devices: [deleted]~~
- ~~(5) Placement of amusement devices in easement: [deleted]~~
- ~~(6) General setback requirements: [deleted]~~

(b) **Off-street parking.** Refer to § 34-2020(3)g. ~~(4)r~~ for off-street parking requirements.

(c) **Hours of operation.** The hours of operation shall be limited to 10:00 a.m. to 10:00 p.m., unless otherwise extended by the director in writing.

~~(d) Excluded areas.~~ No temporary use permits under this section shall be issued for Captiva Island or within the Gasparilla Island conservation district.

~~(d) (e) Special event permit.~~ In addition to a temporary use permit, a carnival, fair, circus, or amusement device, or other event may shall be subject to the provisions of the town's county's special events ordinance, No. 98-01 as amended (see also division 34 of this article). permit, as applicable.

Sec. 34-3043. Christmas tree sales.

(a) Christmas tree sales may be permitted in any ~~agricultural, commercial, or industrial~~ district, provided that:

- (1) No parking lot required for another use shall be used for display of trees; and
- (2) Temporary off-street parking for at least five vehicles shall be provided utilizing an existing or approved parking lot entrance or driveway.

(b) The maximum length of time for display and open-lot sales shall be 45 days.

Sec. 34-3044. Temporary contractor's office and equipment storage shed.

A contractor's office or construction equipment shed may be permitted in any district where use is incidental to an ongoing construction project with an active building permit or development order. Such office or shed shall not contain sleeping or cooking accommodations. The contractor's office and construction shed shall be removed within 30 days of the date of final inspection for the project.

~~Sec. 34-3045. Horse shows and exhibitions.
[deleted in its entirety]~~

Sec. 34-3045. Alcoholic beverages.

Temporary one-day permits for the service of alcoholic beverages may be permitted in accordance with § 34-1264(d)

Sec. 34-3046. Temporary use of mobile home.

(a) ***Rehabilitation or construction of residence following disaster.***

- (1) When fire or natural or human-caused disaster has rendered a single-family residence unfit for human habitation, the temporary use of a mobile home or recreational vehicle located on the single-family lot during rehabilitation of the original residence or construction of a new residence may be permitted subject to the regulations set out in this section.
- (2) The maximum duration length of the use shall be 18 months after the date the President of the United States issues a disaster declaration. If no disaster declaration is issued, the maximum duration of the use is 6 months, but The director may extend the permit once for a period not to exceed 60 days in the event of circumstances beyond the control of the owner. Application for an extension shall be made at least 15 days prior to expiration of the original permit. ~~Additional extensions may only be allowed by the board of zoning adjustments.~~

(b) Rehabilitation or construction of damaged business or commercial uses following disaster.

- (1) Business or commercial uses damaged by a major or catastrophic disaster that are necessary for the public health and safety or that will aid in restoring the community's economic base may be permitted to use a mobile home or similar type structure to carry out their activities until the damaged structure(s) is rebuilt or replaced according to applicable development or redevelopment regulations.
- (2) The maximum duration of the temporary use is 9 months after the date the President of the United States issues a disaster declaration. If no disaster declaration is issued, the maximum duration of the use is 6 months. The director may extend the permit once for a period not to exceed 60 days in the event of circumstances beyond the control of the owner. Application for an extension shall be made prior to expiration of the original permit.

~~(b) Construction of residence in AG district.
[deleted in its entirety]~~

(c) ***Conditions for use.***

- (1) Required water and sanitary facilities must be provided.

- (2) The mobile home or recreational vehicle shall be removed from the property within ten days of the issuance of after the certificate of occupancy is issued for the new or rehabilitated residence, business, or commercial use, or upon expiration of the temporary use permit, whichever occurs first.
- (3) Placement or setting of the mobile home, shall adhere to ch. 6, article IV, pertaining to floodplain management.

Sec. 34-3047. Temporary telephone distribution equipment.

Telephone distribution equipment may be granted a temporary permit during planning and construction of permanent facilities, provided that:

- (1) The equipment is less than six feet in height and 300 cubic feet in volume; and
- (2) The maximum length of the use shall be six months, but the director may extend the permit once for a period not to exceed six additional months in the event of circumstances beyond the control of the telephone company. Application for an extension shall be made at least 15 days prior to expiration of the original permit. ~~Additional extensions may only be allowed by the board of zoning adjustments.~~

Sec. 34-3048. Ancillary temporary uses in parking lots.

(a) The following ancillary temporary uses may be permitted in parking lots upon application and issuance of a temporary use permit (see § 34-3050 ~~210~~):

- (1) Seasonal promotions.
- (2) Sidewalk or parking lot sales.
- (3) Fairs and carnivals (see § 34-3042).
- (4) Tent sales.
- (5) Flea markets by nonprofit organizations.
- (6) Welcome stations operated by non-profit organizations that provide information without the sale or distribution of any product or service may be approved for a maximum of 90 days.

(b) In approving a temporary use permit, the director shall require that the area of the lot to be used is clearly defined and that the use will not obstruct pedestrian and vehicular movements to portions of the lot not so used.

Sec. 34-3049. Seasonal Temporary parking lots.

Seasonal Temporary parking lots may be permitted in commercial and industrial zoning districts, ~~excluding commercial and industrial zoning districts on Captiva Island and within the Gasparilla Island conservation district~~, provided that they are in compliance with § 34-2022.

Sec. 34-3050~~210~~. Temporary use permits.
[moved from § 34-210]

(a) *Applicability.* ~~The county,~~ or Any person desiring to conduct any of the temporary uses described in ~~article VII, division 37, this subdivision H, of this chapter~~ shall be required to submit an application for a temporary use permit.

(b) *Initiation of application.* An application for a temporary use permit may be initiated by the town county or any individual authorized in accordance with § 34-201(a).

(c) *Submission of application.*

- (1) No application shall be accepted unless it is presented on the official forms provided by the director department.
- (2) Before an application may be accepted, it must fully comply with all information requirements enumerated in the application form as well as the requirements set forth in subsection (d) of this section.
- (3) The applicant shall ensure that an application is accurate and complete. Any additional expenses necessitated because of any inaccurate or incomplete information submitted shall be borne by the applicant.

(d) *Additional required information.* In addition to the application information, the applicant shall submit satisfactory evidence of the following:

- (1) Evidence shall be submitted that adequate sanitary facilities meeting the approval of the county health department are provided.
- (2) Evidence shall be submitted that sounds emanating from the temporary use shall not adversely affect any surrounding property.
- (3) Evidence shall be submitted that all requirements as to providing sufficient parking and loading space are assured.
- (4) When deemed necessary, a bond shall be posted, in addition to an agreement with a responsible person sufficient to guarantee

that the ground area used during the conduct of the activity is restored to a condition acceptable to the director department.

- (5) All applications for temporary permits, excluding those for the temporary use of mobile homes during construction of a residence following a natural disaster (see § 34-3046), shall provide public liability and property damage insurance. This requirement may be waived by the town council Board of County Commissioners at a regular meeting, after advertisement on the agenda.
- (6) Evidence shall be submitted that, where applicable, the applicant for a proposed use has complied with town ordinances No. 91-26 of the county, pertaining to special events, including Ordinances No. 98-1, 00-16, and any later amendments (see also division 34 of this article).
- (7) Evidence shall be submitted that the law enforcement and fire agencies who will be coordinating traffic control or emergency services have been advised of the plans for a temporary use and that they are satisfied with all aspects under their jurisdiction.

(e) *Inspection following expiration of permit; refund of bonds.* Upon expiration of the temporary permit, the director department shall inspect the premises to ensure that the grounds have been cleared of all signs and debris resulting from the temporary use and shall inspect the public right-of-way for damages caused by the temporary use. Within 45 days after a satisfactory inspection report is filed, the director department shall process a refund of the bonds. An unsatisfactory inspection report shall be sufficient grounds for the town county to retain all or part of the bonds posted to cover the costs which the town county would incur for cleanup or repairs.

Secs. 34-3051--34-3054. Reserved.

Subdivision III. Special Events

Sec. 34-3055. Special events.

(a) A special event is any social, commercial, or fraternal gathering for the purpose of entertaining, instructing, viewing a competition, or for any other reason that would assemble an unusual concentration of people in one location.

(b) See division 34 of this chapter for a summary of permitting rules for special events.

Secs. 34-3056--34-3060. Reserved.

DIVISION 38. TALL STRUCTURES

Sec. 34-3061+008. Permit for tall structures.

(a) ~~It shall be the duty of the director to administer and enforce the requirements prescribed in this subdivision within the territorial limits over which the county has jurisdiction through the permitting process. The director shall implement airspace notification procedures through the use of the county airspace notification map, as developed by the county port authority, to assist the department in determining when a proposed structure or object would require a tall structures permit. This airspace notification map shall be reviewed annually with the county port authority's attorney and executive director, or their designees, to ensure currency. The various surfaces displayed on the county airspace notification map are defined as follows. The penetration of the imaginary surfaces outlined in this section shall require review by the county port authority under the provisions provided in this section:~~

- ~~(1) *Publicly owned, public-use county airports.*
[deleted in its entirety]~~
- ~~(2) *Other county airports.*
[deleted in its entirety]~~
- ~~(3) *Heliports.* Any construction or alteration of a greater height than an imaginary surface extending outward and upward from any point of any public or private state-licensed county heliport at a slope of 25 to 1 (one foot vertically for every 25 feet horizontally) for a distance up to a height of 125 feet above mean sea level.~~
- ~~(4) *Airport surveillance radar notification areas.*
[deleted in its entirety]~~
- ~~(5) *Other areas.* Any construction or alteration of a greater height than 125 feet above mean sea level shall require a tall structures permit.
(b) ~~If the director determines, for any proposed construction, including adding height to any existing structures, and for all alterations, repairs or additions that will change the use of the structure, or for erecting, altering or repairing any object of natural growth, that the height of the~~~~

~~proposed structure or object exceeds the height limitations outlined on the county airspace notification map as determined by the director, then the An~~ applicant is required to obtain a tall structures permit prior to the issuance of any further development orders or permits.

(b) ~~(c)~~ Applications for a tall structures permit shall include the height and location of derricks, draglines, cranes, and other boom-equipped machinery, if such machinery is to be used during construction.

(1) ~~(d)~~ Applicants intending to use derricks, draglines, cranes, and other boom-equipped machinery for such construction, reconstruction, or alteration as is consistent with the provisions of this ~~subdivision~~ shall, when the machine operating height exceeds the height limitations imposed by this ~~subdivision~~, require a tall structures permit.

(2) Upon obtaining this permit through the procedures outlined in this section, the applicant shall mark, or mark and light, the machine to reflect conformity with the Federal Aviation Administration's or the county port authority's standards for marking and lighting obstructions, whichever is more restrictive, and shall be required in such cases to inform the county port authority, through this tall structures permit process, of the location, height, and time of operation for such construction equipment use prior to the issuance of any construction permit to the applicant.

(c) ~~(e)~~ The permitting procedures for a tall structures permit are outlined as follows. If a tall structures permit application is deemed necessary by the director, ~~as determined through the use of the county airspace notification map~~; the following procedures shall apply:

- (1) The ~~director~~ department shall give a written notice to the applicant that a tall structures permit is required and that no further permits or development orders can be issued until a tall structures permit is obtained.
- (2) The applicant shall then submit a completed tall structures permit application to the Lee County Port Authority, 16000 Chamberlin Parkway, Ft. Myers, Florida 33913. The county port authority shall review the

application, and the following procedures will apply:

- a. If the county port authority determines that the proposed construction or alteration represented in the application does not violate the provisions of Federal Aviation Regulations, part 77, or the provisions of this ~~subdivision~~ or any other application of federal or state rules and regulations or does not adversely affect the airspace surrounding any county airport, the port authority shall indicate such determination on the tall structures permit application. The signed tall structures permit application will then be returned to the applicant. The applicant shall present the tall structures permit application to the administrative director in order that a tall structures permit may be issued. If the signed tall structures permit application is accompanied with stipulations of compliance as determined by the county port authority, it is the responsibility of the administrative director to ensure that these stipulations are adequately addressed prior to the issuance of a tall structures permit.
- b. If the county port authority determines that the proposed construction or alteration violates the notification criteria of Federal Aviation Regulations, part 77, or otherwise violates any provisions of this ~~subdivision~~ or any other applicable federal or state rules or regulations, the county port authority will notify the applicant in writing that the proposed construction or alteration may adversely affect the airspace surrounding county airports and require that a notice of proposed construction or alteration be filed with the Federal Aviation Administration for review through the submittal of Federal Aviation Administration Form 7460-1 as required by Federal Aviation Regulations, part 77. The county port authority shall suspend the tall structures permit application process until Federal Aviation Administration findings of aeronautical effect are received and reviewed.
- c. It is the responsibility of the applicant to forward the Federal Aviation Administration's findings of aeronautical effect, along with a copy of the completed original Federal Aviation Administration

- Form 7460-1, to the county port authority in order to continue the tall structures permit process.
- d. The tall structures permit application shall not be issued if the proposed construction or alteration is found to violate the provisions of this subdivision or any other applicable federal or state rules or regulations. No tall structures permit will be issued if all Federal Aviation Administration and county port authority comments are not addressed to the satisfaction of the county port authority. The applicant shall be forwarded a written notice if the tall structures permit is denied, from the county port authority. This written notice shall specify the reason for objections and suggestions for compliance under this subdivision and all other applicable federal or state rules and regulations.
- e. After reviewing the Federal Aviation Administration's comments pertaining to the Federal Aviation Administration Form 7460-1, if the county port authority determines that the proposed construction or alteration does not adversely affect any other requirements pertaining to county airports, the port authority shall return to the applicant the signed tall structures permit application. The applicant shall present a copy of the tall structures permit application, along with all port authority comments and stipulations, to the director in order that a tall structures permit may be issued. If the signed tall structures permit application is accompanied with stipulations of compliance, it is the responsibility of the director to ensure that these stipulations are adequately addressed prior to the issuance of a tall structures permit.

(d) ~~(f)~~ If the director determines that all procedures and application approvals are in compliance with the provisions outlined in this section, then a tall structures permit will be issued to the applicant.

- (1) ~~(g)~~ No tall structures permit shall be issued prior to obtaining a determination of acceptability and compliance from the county port authority.

- (2) ~~(h)~~ Temporary or conditional tall structures permits pending completion of the Federal Aviation Administration's or the county port authority's review shall not be issued.

Secs. 34-3062--34-3065. Reserved.

**DIVISION 38-A TATTOO STUDIOS
AND BODY-PIERCING SALONS**

Sec. 34-3066. Purpose of division.

This division regulates the placement of tattoo studios and body-piercing salons. The purpose is to avoid the proliferation or concentration of such establishments in the Town of Fort Myers Beach.

Sec. 34-3067. Definitions.

Body-piercing means for commercial purposes the act of penetrating the skin to make, generally permanent in nature, a hole, mark, or scar. "Body piercing" does not include the use of a mechanized, presterilized ear-piercing system that penetrates the outer perimeter or lobe of the ear or both.

Body-piercing salon means any temporary or permanent place, structure, or business that is licensed under the provisions of F.S. § 381.0075 to perform body piercing.

Establishment means a body-piercing salon or tattoo studio as defined in this division, but does not include the practice of any state-licensed physician or osteopath who may attempt to cover up existing tattoos.

Tattooing means the placement of indelible pigment, inks, or scarification beneath the skin by use of needles for the purpose of adornment or art. "Tattooing" includes the practice of permanent makeup and micropigmentation.

Tattoo studio means any temporary or permanent place, structure, or business used for the practice of tattooing.

Sec. 34-3068. Minimum spacing required for new or relocated establishments.

No new or relocated tattoo studio or body-piercing salon shall be placed within 2,000 feet of

any lawfully existing establishment as defined in § 34-3067. This distance shall be measured from any public entrance or exit of the new or relocated establishment in a straight line to the nearest property line of the existing establishment.

Sec. 34-3069. Destruction by natural disaster.

If a building containing a lawfully existing establishment as defined in § 34-3067 is damaged or destroyed by a natural disaster, including fire, tropical storm, or hurricane, the establishment may be relocated within 1,000 feet of its original location on land that is properly zoned for this use, without regard for the 2,000-foot limitation in § 34-3068.

Secs. 34-3070–34-3100. Reserved.

~~DIVISION 38. UNITS OF HIGH IMPACT
[deleted in its entirety]~~

DIVISION 39. USE, OCCUPANCY, AND CONSTRUCTION, AND MOVING REGULATIONS

Sec. 34-3101. Compliance with applicable regulations.

No building, structure, land, or water shall hereafter be used or occupied, and no building, structure or part thereof shall hereafter be erected, constructed, reconstructed, located, moved, or structurally altered, and no land shall be cleared, graded, excavated, or filled, or otherwise altered, except in conformity with the regulations specified in this chapter for the district in which it is located, the Fort Myers Beach Comprehensive ~~Lee~~ Plan and all other applicable town county ordinances.

Sec. 34-3102. Reserved. Number of principal buildings on lot. *[deleted in its entirety]*

Sec. 34-3103. Permit for moving building.

No building or part of any building shall be relocated or moved through or across any sidewalk, street, alley, or highway within the town unincorporated area of the county unless a permit has first been obtained from the ~~director division of codes and building services~~ in accordance with the procedures and application requirements for

building relocation as set forth in ~~§ 34-1951, 34-209,~~ as well as a structure moving permit from the department of transportation and engineering services in accordance with the structures moving ordinance if so adopted. Buildings or structures that have been designated as historic resources pursuant to ch. 22 shall also obtain a certificate of appropriateness as provided in § 22-105.

~~Sec. 34-3104. Clearing, grading, or filling of land.~~
[substance moved to § 34-3101]

Secs. 34-31045--34-3130. Reserved.

DIVISION 40. VEHICLE VISIBILITY

Sec. 34-3131. Vehicle visibility at intersections.

(a) **Corner lots; driveways on Estero Boulevard.** On all corner lots, and on all driveways entering onto Estero Boulevard, no obstruction shall be planted or erected which materially obstructs traffic visibility within the triangular space bounded by the two intersecting right-of-way lines visibility triangle as shown in Figure 34-30, and a straight line connecting the two points on the street right-of-way lines 25 feet from their intersection. No structures (except along Old San Carlos Boulevard) or at and plantings masses shall be permitted between two three feet and six ten feet above the average grade of each street within this triangular space.




Figure 34-30

(b) **All other driveways and parking lot entrances.** At all other intersections of driveways or parking lot entrances with a street right-of-way or easement, no obstruction shall be planted or erected which materially obstructs the driver's view of approaching traffic or pedestrians within a visibility triangle as shown in Figure 34-31 on both sides of

the driveway. No structures (except along Old San Carlos Boulevard) or plantings shall be permitted between two feet and six feet above the average grade of each street within this triangular space.




Figure 34-31

Secs. 34-3132--34-3150. Reserved.

**DIVISION 41.
WATER-ORIENTED RENTALS ACTIVITIES**

Sec. 34-3151. Water-oriented rental establishments; outdoors.

(a) *Applicability.* This section addresses is to provide specific standards for those outdoor rental activities that may be permitted on occur on commercially zoned property adjacent to the Gulf of Mexico and are not located fully within a building. This section is supplemented by the specific standards for personal watercraft rental businesses and parasail activities that are found in ch. 27 of this code.

(b) *Permitted districts.* These activities Water-oriented rentals are permitted only in resorts as resort accessory uses and in certain zoning districts where permitted by right or by special exception (see division 2 of article III of this chapter). commercial zoning districts that permit boat rentals and leasing or rental establishments, group I. Locations for personal watercraft rental businesses and parasail activities are further restricted by § 27-51(a).

(c) *Location.* The activity or activities must be located on development properties, landward of the water body setback line for the Gulf of Mexico, unless approved by special permit, and must be situated so that they are not readily visible from any

public street right-of-way or easement. There may not be any indication from any street that these activities are this activity is occurring except as allowed by § 27-51(c)(5).

(d) *Setbacks.* The activity must may be located no closer than ten feet to within the side property lines and may not be permitted seaward of the minimum waterbody setback for the Gulf of Mexico as set forth in § 34-2194 § 34-638(d)(3), without a special permit. Exceptions are:

- (1) Beach chairs and umbrellas may be displayed or placed anywhere landward of the mean high water line.
- (2) Personal watercraft rental operations and parasail activities that are authorized by this code are permitted seaward of the mean high water line as set forth in ch. 27.

(e) *Time limitations.* The rental activity may not occur after sunset or before sunrise, and movement of personal watercraft is further restricted by § 27-49(4). Artificial lighting is prohibited.

(f) *Storage during sea turtle nesting season.* No structures or equipment of any kind may be left on the beach before or after regular business hours between the hours of 9:00 PM and 7:00 AM from May 1 until October 31. See also §§ 14-5, 14-78, and 27-49(9). The equipment not being displayed for rent must be stored in an enclosed structure or removed from the property when not in use.

(g) *Signage.* The only signage permitted shall be those signs specifically authorized by § 27-51(c). Signage visible from any street right-of-way or street easement is prohibited. Only one on-site identification sign will be permitted. The sign must be located on the beach side of the building, facing the beach and may not exceed 25 square feet.

(h) *Parking.* A minimum of five parking spaces will be provided for the outdoor water-oriented rental establishments. Any other use of the property must comply with the off-street parking requirements set forth in article VII, division 26 of this chapter.

Secs. 34-3152--34-3200. Reserved.

**ARTICLE V. VIII.
NONCONFORMITIES³**

DIVISION 1. GENERALLY

Sec. 34-3201. Purpose of article.

The regulations of this chapter code and various amendments thereto have caused or will cause some lots, structures or buildings, or uses, or lots to no longer conform with one or more provisions of this code, of lots, structures or buildings, to be nonconforming.

- (1) It is the purpose of this article to set forth the rules and regulations regarding those nonconforming lots, structures or buildings, and uses, or lots which were created by the adoption of this chapter code or amendments thereto.
- (2) Nothing contained in this article is intended to preclude the enforcement of federal, state, and other local regulations that may be applicable.

Sec. 34-3202. Three types of nonconformities nonconforming use defined.

(a) ***Three types of nonconformities.*** There are three distinct types of nonconformities recognized by this article, with a separate division devoted to each. In situations where there is more than one type of nonconformity, for example a nonconforming use in a nonconforming building, all relevant divisions shall apply.

(b) ***Nonconforming building.*** For purposes of this article, the term “nonconforming building” means a building or structure, or portion thereof, which was lawful prior to the adoption of any ordinance from which this code is derived, or the adoption of any revision or amendment to this code, or the adoption or amendment to the comprehensive plan, but which fails, by reason of such adoption, revision, or amendment, to conform to specific requirements where the building or structure is located due to its size, dimension, location on the

³ Cross reference(s)–Nonconforming marine structures, § 26-48; nonconforming structures on the beach, § 27-51(c)(6); nonconforming beach rental licenses, § 27-53, § 27-55; nonconforming signs generally, § 30-565; nonconforming signs on Captiva Island, § 30-251 et seq.

lot, number of dwelling units or guest units, building type, or compliance with floodplain regulations. See division 2 of this article for regulations on nonconforming buildings.

(c) ***Nonconforming use.*** For purposes of this article, the term “nonconforming use” means a use or activity which was lawful prior to the adoption of the any ordinance from which this chapter code is derived, or the adoption of any revision or amendment to of this code, or the adoption or amendment to the comprehensive plan, but which fails, by reason of such adoption, revision, or amendment, to conform to the use requirements of the zoning district in which where the property is located. See division 3 of this article for regulations on nonconforming uses.

(d) ***Nonconforming lot.*** For purposes of this article, the term “nonconforming lot” means a lot of which the area, dimension, or location was “lawful” (see definition in §34-2) prior to the adoption of any ordinance from which this code is derived, or prior to the adoption of any revision or amendment to this code, and which fails by reason of such adoption, revision, amendment, or rezoning to conform to the requirements where the lot is located. However, a lot which no longer conforms due to the adoption or revision of any comprehensive plan can only be developed in accordance with § 34-3274. See division 4 of this article for regulations on nonconforming lots.

Sec. 34-3203. Illegal buildings, uses, and lots.

If a building, use, or lot was not lawful when created and cannot be lawfully modified to comply with this code, it shall not be considered nonconforming but shall be deemed an illegal building, use, or lot and thus not afforded the protection provided by this article to nonconforming buildings, uses, or lots.

- (1) Illegal buildings or uses must be lawfully modified to comply with this code or must be removed in accordance with § 34-1(c).
- (2) Illegal lots must be lawfully combined with adjoining land so as to conform with this code, or must remain vacant but still be maintained in accordance with the property maintenance code in division 1, article I, ch. 6 of this code and other town regulations.

Sec. 34-3204. Amortization.

Notwithstanding the general provisions of this article, other portions of this code may require that specific types of nonconforming buildings and uses must be modified into conformance with this code, or be eliminated, by a specific date. Such dates are established to allow owners a reasonable period to amortize the value of the nonconforming building or use.

Sec. 34-3205. Reserved.

Sec. 34-3203. Enlargement or expansion of nonconforming structure:
[moved to § 34-3234(a)]

Sec. 34-3204. Mobile home and recreational vehicle unit replacements and roof repairs:

Any mobile home or recreational vehicle unit which has been lawfully placed on any rental lot within any rental park, regardless whether the park has been converted to either cooperative or condominium ownership prior to June 25, 1986, may be replaced by a unit of equal or smaller size upon proof that the placement of the unit was lawful. Such proof may consist of copies of official tax records, tag registrations or county permits, or may be by affidavit or any other competent evidence:
[subject relocated to § 34-694(a)(1)c.]

Permits shall also be issued for reroofing and roof repairs for any existing mobile home or recreational vehicle located within a mobile home or recreational vehicle park, regardless of lot size.
[moved to §§ 34-694(c) & 34-3233(a)(4)]

Sec. 34-3205. Uses approved by special exception or permit:
[moved to § 34-3246]

Sec. 34-3206. Nonconformities created by public acquisition, eminent domain proceedings:

Public acquisition of a portion of a lot might cause the remainder to become nonconforming as to area, width, depth, setbacks, floor area ratio, or required parking.

- (1) To minimize the adverse effects of such acquisition, previous lawful buildings, structures, or lots that might be rendered

nonconforming as to compliance with a specific requirement of this code shall be deemed conforming with that requirement rather than nonconforming.

- (2) This applies whether the acquisition occurred by eminent domain, purchase, or a publicly accepted donation of land or easements.

A structure, lot, tract, or parcel of land that has been or will be rendered nonconforming as to area, width, depth, setbacks, lot coverage, or parking because of a taking through eminent domain proceedings or by the voluntary sale of a parcel of land under the threat of eminent domain proceedings by a governmental authority, after October 15, 1992, will be deemed conforming under the terms of this chapter.

Secs. 34-3207--34-3230. Reserved.

**DIVISION 2:
NONCONFORMING USE OF LAND**

Sec. 34-3221. Generally:
[redundant with division 3 of this article]

A nonconforming use of land may be continued subject to the provisions of this division:

Sec. 34-3222. Enlargement or replacement:
[redundant with §§ 34-3242 and 34-3243]

No nonconforming use of land shall be extended or enlarged, or replaced by another use not specifically permitted in the zoning district concerned:

Sec. 34-3223. Discontinuance:
[redundant with § 34-3244]

No land used in whole or in part for a nonconforming use, which use is subsequently discontinued for a continuous period of six calendar months, shall again be used except in conformity with the regulations then in effect. The intent of the owner, lessee, or other user shall not be relevant in determining whether the use has been discontinued:

Sec. 34-3224. Erection of additional structures:
[moved to § 34-3242(b)]

Secs. 34-3225--34-3240. Reserved:

**DIVISION 2, 3:
NONCONFORMING BUILDINGS
AND USE OF BUILDINGS**

**Sec. 34-32341. Nonconforming buildings defined,
and structures:**

For purposes of this division, the term “*nonconforming building or structure*” means a building or structure, or portion thereof, which was lawful prior to the adoption of the any ordinance from which this chapter code is derived, or the adoption of any revision or amendment to ~~of~~ this chapter, code, or the adoption or amendment to the comprehensive plan, but which fails, by reason of such adoption, revision, or amendment, to conform to specific the proper development requirements of the zoning district in which where the building or structure is located due to its size, dimension, location on the lot, number of dwelling units or guest units, building type, or compliance with floodplain regulations, ~~or location on the lot.~~

Sec. 34-3232. Continued use of a nonconforming building.

The occupancy of a nonconforming building structure may be continued so long as it remains otherwise lawful. However, if the specific use of a nonconforming building is itself nonconforming, then that use is also subject to the provisions of division 3 of this article, ~~subject to the following provisions:~~

- (1) Except as provided in § 34-3203, no such building or structure may be enlarged, altered, or repaired in a way which, in the opinion of the department director or his designee, increases its nonconformity, but any structure or building or portion thereof may be altered to decrease its nonconformity. If there is more than one structure on a property with a legally nonconforming use, a limited expansion may be allowed subject to there being a determination that there will be an improvement to neighborhood compatibility. The limited expansion shall be to allow a structure or portion of a structure to be destroyed and the equivalent square footage replaced by expansion of another existing structure if the department director makes a determination that such expansion would not be detrimental to the neighborhood

and such expansion is less than 50 percent of the current assessed value of the structure which will be expanded. Any expansion must also conform to setback requirements and all other requirements for the zoning district in which the property is located.

- (2) Except as provided in this section:

- a. Any nonconforming structure or building, or portion thereof, that is substantially improved (reconstructed, rehabilitated, altered, or demolished) to the extent that the cost of such improvement equals or exceeds a cumulative total of 50 percent of the current assessed value of the structure before the start of construction of the improvement) shall only be reconstructed at, but not to exceed, the lawful density or intensity existing at the time of destruction; provided, however, that the reconstruction of the structure is consistent with federal, state, and local regulations, and all the other provisions of this chapter. Any such alteration, demolition, reconstruction, or rebuilding shall be recorded with the division of codes and building services for the purpose of establishing the value upon which subsequent alterations, demolition, reconstructions, or rehabilitations shall be based:

- b. Structures which have been damaged by fire or other natural forces to the extent that the cost of their reconstruction or repair exceeds 50 percent of the replacement cost of the structure may be reconstructed at, but not to exceed, the legally documented actual use, density, and intensity existing at the time of destruction; thereby allowing such structures to be rebuilt or replaced to the size, style, and type of their original construction, including their original square footage; provided, however, that the affected structure, as rebuilt or replaced, complies with all applicable federal, and state regulations, local building and life safety regulations, and other local regulations which do not preclude reconstruction otherwise intended by the Lee Plan and Ordinance No. 90-61 of the county, as amended from time to time.

- (3) A lawfully existing single-family residence or mobile home damaged by fire or other natural forces may be repaired or replaced;

provided the new unit is no larger in area, width, and depth than the size of unit being replaced.

- (4) Repairs, reconstruction, or renewal of an existing structure, building, or portion thereof, for the purpose of its maintenance shall be permitted.
[subject moved to § 34-3233(a)]
However, repairs, reconstruction, or renewal of structural elements shall be reviewed by the director of the division of codes and building services to determine applicability under this section, or whether such repairs shall be considered under subsection (b)(2)a of this section. For purposes of this section, a change in the roofline from a flat roof to a peaked roof shall constitute an alteration as indicated in subsection (b)(2)a of this section, provided that there is no increase in floor area. [subject moved to § 34-3233(b)]

Sec. 34-3233. Repairing a nonconforming building.

(a) Internal repairs, reconstruction, and renewal may be made to nonconforming buildings in accordance with this section.

- (1) A nonconforming building may be altered to decrease its nonconformity.
- (2) Awnings and canopies may be attached to nonconforming buildings as provided in § 34-638(d)(1)d.
- (3) Commercial antennas may be installed on nonconforming buildings in accordance with § 34-1443(d).
- (4) Permits may shall also be issued for reroofing and roof repairs for any existing mobile home or recreational vehicle located within a mobile home or recreational vehicle park, regardless of lot size.
[subsection (4) moved from § 34-3204]

(b) Internal repairs, reconstruction, and renewal of certain nonconforming buildings are limited in scope because the town desires for these buildings to be reconstructed in compliance with this code.

- (1) The limitations in this subsection apply only to buildings that are nonconforming:
 - a. due to *density* or *intensity* (see § 34-3234(b)(3)), or
 - b. due to *floodplain regulations* (see § 34-3234(b)(4)), or
 - c. due to *building type* (see § 34-3234(b)(5)).

- (2) For such nonconforming buildings, the director shall determine whether the repairs, reconstruction, or renewal, alone or in conjunction with other permitted improvements or enlargements, are major enough to be considered a “substantial improvement,” as that term is defined in § 6-405. See § 34-3234(b)(1) for details.

Sec. 34-3234. Enlarging a nonconforming building.

(a) The following types of A nonconforming buildings may be physically enlarged, either laterally or vertically, so long as they it remains otherwise lawful, as follows: and the enlargement is in accordance with the regulations in this subsection:

Sec. 34-3203. Enlargement or expansion of nonconforming structure:

- (1) (a) structures *If nonconforming due to setbacks*. A nonconforming building structure which is lawful in all respects with the exception of a setback requirement or build-to line (see § 34-662) may be enlarged, provided that:
 - a. (1) The enlargement is otherwise permitted; and
 - b. (2) The enlargement itself, including any enlargement which increases the height or volume of the structure, complies with all the setback requirements and fully complies with any applicable build-to lines.
 - c. Also see § 34-268 regarding certain administrative setback variances that may be available for nonconforming buildings.
- (2) (b) structures *If nonconforming due to lot area*. A nonconforming building structure which is lawful in all respects with the exception of lot area requirements may be enlarged, provided that:
 - a. (1) The enlargement is otherwise permitted;
 - b. (2) All other property development requirements such as setbacks, height, bulk, lot coverage, floor area ratio, density, intensity, parking, and open space are met, and
 - (3) The enlargement does not increase the density or intensity of use.
- (3) (c) structures *If nonconforming due to height*. A nonconforming building structure

which is lawful in all respects with the exception of height restrictions may be enlarged, provided that:

- a. ~~(1)~~ The enlargement is otherwise permitted; and
- b. ~~(2)~~ The enlargement itself complies with current height and setback requirements.

(4) ~~(d) structures~~ ***If nonconforming due to bulk or lot coverage floor area ratio.*** A nonconforming building structure which is lawful in all respects with the exception of bulk or lot coverage floor-area-ratio shall not be enlarged.

(b) Certain other types of nonconforming buildings have special limitations on the extent to which they may be repaired and physically enlarged because the town desires for these buildings to be reconstructed in compliance with this code.

(1) The combined cost of enlargements and any repairs to such nonconforming buildings or structures shall be reviewed by the director to determine whether they are major enough to be considered a “substantial improvement,” as that term is defined in § 6-405.

a. If the improvements do not constitute a “substantial improvement,” their value shall be recorded with the director for the purpose of establishing the extent of allowable future repairs, enlargements, or replacements, using the same methodology as for improvements in the floodplain (article IV of ch. 6).

b. If the improvements constitute a “substantial improvement,” they will be approved only if they result in the building fully complying with all regulations for new buildings on vacant land, except as provided in the buildback regulations found in §§ 34-3237 and 34-3238.

(2) These special limitations on “substantial improvements” apply to the following types of nonconforming buildings, in addition to the specific limitations provided below for each type.

(3) ***If nonconforming due to density or intensity.*** A building, or a group of buildings or structures, may be nonconforming because there are more residential dwelling units, or more guest units, or a greater floor-area-ratio, than currently permitted by this chapter or by the Fort Myers Beach Comprehensive Plan. Substantial improvements to such buildings

may not physically enlarge them, either laterally or vertically, and they may not be replaced, except under one of the following three circumstances:

- a. If the enlargement or replacement complies entirely with this code and the comprehensive plan as they apply to new buildings on vacant land, including the current density limits on dwelling units and guest units, current height limits, and current caps on floor-area-ratio; or
- b. If the replacement has been approved by the town council in accordance with the pre-disaster buildback regulations, as described in § 34-3237; or
- c. If the building is damaged or destroyed by a natural disaster and its replacement meets all requirements of the post-disaster buildback regulations, as described in § 34-3238.

(4) ***If nonconforming due to floodplain regulations.*** A nonconforming building whose lowest floor does not meet the base flood elevation requirements for new buildings can only be expanded in accordance with the standards in § 6-472.

- (5) ***If nonconforming due to building type.*** Certain buildings are nonconforming due to fundamental design and construction differences between them and new buildings that are permitted in the same zoning district.
- a. ***Building type described.*** Examples include recreational vehicles or mobile homes in zoning districts that do not permit them; automobile service stations or drive-through facilities in pedestrian-oriented commercial districts, and storefront buildings in residential districts. However, buildings that might be considered nonconforming solely due to technical changes in the building codes (which are described in article II of ch. 6) are not classified as nonconforming buildings for the purposes of this article and may be expanded if they are otherwise in conformance with all requirements for their location.
 - b. ***Mobile homes outside mobile home parks.*** See § 34-1921.
 - c. ***Mobile homes in mobile home parks.*** See §§ 34-694 and 34-1922.
 - d. ***Other nonconforming building types.*** Other buildings that are nonconforming due to

building type cannot be “substantially improved” as described in § 6-405 unless they are altered to eliminate this type of nonconformity.

Sec. 34-3235. Moving a nonconforming building.

(a) ~~(5)~~ Should a nonconforming building structure be moved on-site for any reason, for any distance whatever, it shall not be moved unless the relocation decreases the nonconformity.

(b) A nonconforming building that is being moved off-site shall only be placed on its new site in full conformance with this code.

(c) See §§ 34-223 and 34-3103 regarding permits for moving buildings.

~~(6) Any portion of a nonconforming structure which becomes physically unsafe or unlawful due to lack of repairs and maintenance, and which is declared unsafe or unlawful by a duly authorized county official, but which the owner wishes to repair, restore, or rebuild; shall be repaired, restored, or rebuilt in conformance with the provisions of this chapter. Excluded from this provision are buildings which have been designated as historic by ch. 22.~~

Sec. 34-3236. Replacing a nonconforming building.

Nonconforming buildings can be replaced in one of the following manners:

- (1) In full conformance with all current provisions of this code as they apply to new buildings on vacant land; or
- (2) In the same manner as provided for enlargements to the various types of nonconforming buildings as provided in § 34-3234; or
- (3) As provided by the buildback regulations found in §§ 34-3237 and 34-3238.

Sec. 34-3237. Pre-disaster buildback.

Owners of buildings or groups of buildings that exceed the density, intensity, or height limits for new buildings may seek permission from the town council to voluntarily replace those buildings at up to the existing lawful density or intensity and up to the existing height in accordance with Policy 4-E-1

of the Fort Myers Beach Comprehensive Plan, as follows:

- (1) The replacement building must meet the floodplain regulations for new buildings, as provided in article IV of ch. 6.
- (2) The replacement building must meet the coastal construction requirements, as provided in article III of ch. 6 and in state regulations.
- (3) The replacement building must comply with all current building, life safety, and accessibility codes.
- (4) The replacement building cannot exceed the lawful density and intensity of the existing building:
 - a. as measured for residential buildings in § 34-3238(2)d.;
 - b. as measured for hotel/motels in § 34-3238(2)e.; or
 - c. as measured for all other buildings by the gross square footage.
- (5) Each specific pre-disaster buildback proposal must be proposed to the town council through the planned development rezoning process (see division 6 of article III of this chapter), along with any proposed deviations from this code.
- (6) The town council will approve, modify, or deny each such request based on its opinion of the degree of conformance of the specific proposal with the Fort Myers Beach comprehensive plan, specifically including the plan’s land-use and community design policies, pedestrian orientation, and natural resource criteria.
- (7) If the lowest floor of the rebuilt building must be elevated higher than the existing building to comply with current floodplain or coastal regulations, then the total height of the rebuilt building can be increased by the same amount. However, any pre-disaster buildback request for additional height beyond that increment must comply with Policy 4-C-4 of the comprehensive plan in the same manner as that policy would apply to an entirely new building on vacant land.

Sec. 34-3238. Post-disaster buildback.

Owners of buildings or groups of buildings that exceed the density, intensity, or height limits for new buildings and that are damaged or destroyed by a natural disaster, including fire, tropical storms, and

hurricanes, shall be permitted to replace those buildings at up to their existing lawful density, intensity, and/or height in accordance with Policy 4-D-1 of the Fort Myers Beach Comprehensive Plan.

(1) ***Less than 50% damage.*** If the cost to repair the damaged building is less than 50% of the building's value and the repair is thus not a "substantial improvement" as that term is defined in § 6-405, then the following rules shall apply:

- i. The repairs may be made without bringing the building into full compliance with the requirements of this code for building size, dimension, location on the lot, number of dwelling units or guest units, building type, or compliance with floodplain regulations.
- b. The repairs may not physically enlarge the building either laterally or vertically.
- c. All repairs must comply with all current building, life safety, and accessibility codes.

(2) ***More than 50% damage.*** If the cost to repair or rebuild the damaged building is more than 50% of the building's value and is thus a "substantial improvement" as that term is defined in § 6-405, then the following rules shall apply:

- a. The building must meet the floodplain regulations for new buildings, as provided in article IV of ch. 6.
- b. The building must meet the coastal construction requirements, as provided in article III of ch. 6 and in state regulations.
- c. The building must comply with all current building, life safety, and accessibility codes.

Residential buildings. A rebuilt residential building may exceed the density limits for new buildings on vacant land, but cannot exceed the legally documented number of dwelling units in the building immediately before the natural disaster.

1. All dwelling units legally existing prior to the natural disaster may be rebuilt, provided the total interior square footage of the rebuilt dwelling units does not exceed the interior square footage of the previous dwelling units. For purposes of this subsection, interior square footage excludes hallways, stair towers, elevators, open balconies, underbuilding parking, and similar

common or non-air-conditioned space. These excluded spaces are not limited by the floor area ratios in Table 34-3.

2. At the owner's option, this same square footage can be used for fewer but larger dwelling units.

3. Also at the owner's option, the size of the new building may instead be determined by this code's current regulations for new buildings on the same site.

Hotels/motels. A rebuilt hotel/motel may exceed the intensity limits for new hotel/motel buildings on vacant land, but cannot exceed the documented number of lawful guest units in the building immediately before the natural disaster.

1. All guest units lawfully existing prior to the natural disaster may be rebuilt, provided the total interior square footage of the rebuilt guest units does not exceed the interior square footage of the previous guest units. However, interior square footage in the new building may be increased by 30 square feet for each bathroom to reflect current code requirements for larger bathrooms, and any lawfully existing guest units that are smaller than the minimum sizes required by this code may be enlarged to meet the minimum size requirements. For purposes of this subsection, interior square footage excludes hallways, stair towers, elevators, open balconies, underbuilding parking, and similar common or non-air-conditioned space. These excluded spaces are not limited by the floor area ratios in Table 34-3.

2. At the owner's option, this same square footage can be used for fewer but larger guest units.

3. Also at the owner's option, the size of the new building may instead be determined by this code's current regulations for new hotel/motel buildings on the same site.

All buildings. The new building must comply with all other zoning and development regulations except where compliance with such regulations would preclude reconstruction otherwise intended by Policy 4-D-1 of the comprehensive plan. Specifically:

1. If the lowest floor of the rebuilt building must be elevated higher than the damaged or destroyed building to comply with current floodplain or coastal regulations, then the total height of the rebuilt building can be increased by the same amount.
2. If a rebuilt building must be set back further from any property lines due to current requirements of this code, then the volume of the building so reduced can be rebuilt elsewhere on the site, including one or more extra stories on the building if in the opinion of the director there is no other suitable location to replace the volume.
3. If current open space or buffer regulations cannot be met, those requirements may be waived administratively by the director.

Secs. 34-3239--34-3240. Reserved.

DIVISION 3. NONCONFORMING USES

Sec. 34-3241. Nonconforming uses generally, of buildings:

(a) For purposes of this division, the term "nonconforming use" means a use or activity which was lawful prior to the adoption of any ordinance from which this code is derived, or the adoption of any revision or amendment to this code, or the adoption or amendment to the comprehensive plan, but which fails, by reason of such adoption, revision, or amendment, to conform to the use requirements where the property is located.

(b) A residential use may not conform because it contains one or more dwelling units more than are permitted under current regulations. If the extra dwelling unit(s) were fully lawful at the time they were created, for the purposes of this article they shall be deemed a nonconforming building rather than a nonconforming use. The regulations governing nonconforming buildings are found in division 2 of this article; see especially § 34-3234(b)(3) for restrictions on expanding buildings that are nonconforming due to density or intensity.

(c) A nonconforming use of a building, land, or building and land in combination; may be continued subject to the following provisions: limitations found in this division. If the nonconforming use is located in a nonconforming building, the additional requirements of division 2 of this article shall also apply to the building.

Sec. 34-3242. Enlarging a nonconforming use.

(a) (1) Enlargement or Replacement: No such nonconforming use of a building, or building and land in combination; shall be extended or enlarged:

- (1) by having any buildings or structures replaced or expanded in physical size; or
- (2) by any increase in land or water area devoted to the nonconforming use; or
- (3) by any increase in the size or number or vehicles and boats, or increase in the capacity of services such as parking lots that would expand the operation of the nonconforming use.

(b) Sec. 34-3224. Erection of additional structures: No additional structures which does not conform to the requirements of this chapter shall be erected in connection with a nonconforming use of land.

(c) Nonconforming establishments that sell, serve, or allow the consumption of alcoholic beverages are further limited by § 34-1264(h).

(d) The installation of a commercial antenna on a building containing a nonconforming use will not be deemed to constitute an expansion of the nonconforming use (see § 34-1443(d)).

Sec. 34-3243. Replacing a nonconforming use.

No nonconforming use shall be or replaced by another building or use not specifically permitted in the use regulations for the zoning district in which the where the nonconforming use building is located.

Sec. 34-3244. Discontinuing a nonconforming use.

(2) Discontinuance: When a nonconforming use of a building, land, or building and land in combination is discontinued or abandoned for nine six consecutive months (except when government

action impedes access to the land), the use building, or building and land in combination, shall not thereafter be used carried out or reestablished except in conformance with all current the regulations, of the district in which it is located. This subsection shall not apply to seasonal agricultural uses.

Sec. 34-3245. Repairing a building containing a nonconforming use.

~~(3) Repair and maintenance.~~ a. Only ordinary repairs and maintenance, including repairs or replacement of roof covering, walls, fixtures, wiring, or plumbing, shall be permitted on any building or structure devoted to a nonconforming use. In no case shall such repairs include structural alterations.

b. If a nonconforming structure or portion of a structure containing a nonconforming use becomes physically unsafe or unlawful due to lack of repairs and maintenance, and is declared by any duly authorized official to be unsafe or unlawful by reason of physical condition, it shall not thereafter be restored, repaired, or rebuilt except in conformity with the regulations for the district in which located.

Sec. 34-324605. Nonconforming uses approved by special exception or permit.

Uses approved by special exception or other permits which were issued or granted by the town council or board of county commissioners before the effective date of any the ordinance from which this chapter code is derived, and which are no longer permitted in the zoning district where located, shall be considered to be nonconforming uses and subject to the provisions of this article if the actual use was in operation within two years after its approval by special exception or other permit and has not thereafter been discontinued or abandoned for any nine consecutive months.

Secs. 34-32473--34-3270. Reserved.

DIVISION 4. NONCONFORMING LOTS

Sec. 34-3271. Definition of nonconforming lot defined.

(a) Lot means a parcel of land that has been created from a larger parcel and whose precise

dimensions and location were identified through public notice (see § 34-3272).
[modified from the previous definition, which was found in § 34-2]

(b) For purposes of this division, the term “Nonconforming or substandard lot” means a lot of which the area, dimension, or location was “lawful” (see definition in § 34-2) prior to the adoption of the any ordinance from which this chapter code is derived, or prior to the adoption of any revision or amendment to of this chapter, code, or prior to being rezoned, and which fails by reason of such adoption, revision, or amendment, or rezoning to conform to the requirements where for the zoning district in which the lot is located. However, a lot which no longer conforms due to the adoption or revision of any comprehensive plan can only be developed in accordance with § 34-3274.

(c) See § 34-3234(a)(2) for the situation where a nonconforming building with a conforming use exists on a lot whose lot area is smaller than required by its zoning district.

~~Sec. 34-3272. Lot of record defined; general development standards:~~

For the purposes of this division only, a lot of record is a lot which conformed to the minimum lot size for the use permitted for that lot in its zoning district at such time that the lot was created, but which lot fails to conform to the minimum lot size requirements which are established by this chapter.

Sec. 34-3272. Determining when a lot was created.

(1) For the purpose of this division, a lot is deemed to have been “created” on such date that one of the following conditions occur, provided the configuration of the lot was not later altered:

- (1) a. Individual deed. The date that a deed for the lot containing its full legal description was is lawfully recorded in the official public records books in the office of the clerk of the circuit court of the county;
- (2) b. Subdivision plat. The date that a subdivision plat has been lawfully recorded in the plat books in the office of the clerk of the circuit court public records of the county, if the individual lot is clearly identified as a part of that the subdivision;

c. The date that a site plan for a development was approved by the board of county commissioners pursuant to resolution, as long as the development subsequently recorded a subdivision plat that has been approved by the board of county commissioners in the public records of the county, if the lot is a part of the subdivision; or

d. In the case of mobile home or recreational vehicle parks, *[remainder of subsection deleted; portions applicable to Fort Myers Beach have been relocated to § 34-691-700]*

- (2) The remaining lot after condemnation shall be deemed a lot of record in accordance with § 34-3206. *[moved to § 34-3273(7)]*

Sec. 34-3273. General requirements for residential uses on nonconforming lots.

(3) Nonconforming lots of record may be developed subject to the following provisions:

- (1) a. All other regulations of this chapter shall be met, except as modified by this division.
- (2) A residential building may be placed on a single nonconforming lot provided the lot has at least 40 feet in width, 75 feet in depth, and 4,000 square feet in area.
[substance moved from § 34-3273(b)(2)]
- (3) Minimum residential setbacks on nonconforming lots shall be as follows:
 - a. Street setbacks shall be as set forth in the regulations for the applicable zoning district.
 - b. Side, rear, and water body setbacks shall be as set forth for lots in the RC zoning district (see Table 34-3).
 - c. Certain nonconforming lots may qualify for an administrative setback variance (see § 34-268).
- (4) Any development on nonconforming lots must comply with all density restrictions of the Fort Myers Beach Comprehensive Plan.
 - i. Density computations shall be in accordance with § 34-632.
 - b. If density computations do not allow even one dwelling unit on a nonconforming lot, one single-family residence may still be permitted if a minimum-use determination is obtained in accordance with § 34-3274.
- (5) b. No division of any nonconforming lot parcel may be permitted which creates a lot with width, depth, or area below the minimum requirements stated in this chapter,

except for combinations and redivisions in accordance with § 34-3275, provided that contiguous lots of record may be combined and redivided to create larger dimension lots as long as such recombination includes all parts of all lots, and existing allowable density is not increased, and all setback requirements are met. [subject of remainder of subsection moved to § 34-3275(a)]

c. For mobile home or recreational vehicle lots of record, the following shall also apply: *[remainder of subsection deleted; portions applicable to Fort Myers Beach have been relocated to § 34-694]*

- (6) (4) The burden of proof for demonstrating that a the lot is legally a nonconforming lot in accordance with this division, and lawfully existed at the specified date, shall be with the owner.
- (7) (2) The remaining lot after condemnation shall be deemed a lot of record treated in accordance with § 34-3206. *[moved from § 34-3272(2)]*

Sec. 34-32743. Minimum use determinations.

Construction of single-family residence:

(a) A single-family residence may also be constructed on a nonconforming lot of record which does not comply with the density requirements of the Fort Myers Beach Comprehensive ~~Lee~~ Plan, provided the owner receives a favorable administrative interpretation of the single-family residence provision (also known as a minimum use determination) in accordance with the ~~Lee~~ Plan: ch. 15 of the Fort Myers Beach Comprehensive Plan.

(b) To qualify for a minimum use determination, the following additional requirements must be met:

- (1) Minimum lot requirements:
 - a. Lot area of 4,000 square feet if the lot was created prior to 1962; or
 - b. Lot width of 50 feet and lot area of 5,000 square feet if part of a platted subdivision recorded between 1962 and 1984; or
 - c. Lot area of 7,500 square feet if not part of a platted subdivision created between 1962 and 1984; or
 - d. Lot width, depth, and area were in conformance with the zoning regulations if created after 1984; or
 - e. Lot sizes were explicitly approved as part of a planned development rezoning.

(2) Ownership requirements:

- a. Prior to November 21, 2000, the lot shall have been vacant or shall have been improved with one structure located wholly on this lot.
- b. If a structure had been placed on two or more adjoining lots at any time prior to November 21, 2000, the individual lots shall not qualify for this determination.

(c) Lots qualifying for a minimum use determination may not place the home, accessory structures, or driveways on any land in the "Wetlands" or "Recreation" category on the future land use map of the comprehensive plan.

(d) The rights granted by a minimum use determination run with the lot and are available to any subsequent owner if the lot is transferred in its entirety.

(e) Applications for a minimum use determination shall be filed with the town clerk in accordance with ch. 15 of the comprehensive plan. Complete applications will be reviewed by the legal counsel for the local planning agency (see § 34-125(3)) and may be referred to the local planning agency for a decision (see § 34-120(6)).

(b) A single-family residence may also be constructed on a lot of record which *does* comply with the density requirements of the Lee Plan, as long as the lot was lawfully created prior to June 1962 and the following conditions are met:

- (1) Lots existing in the AG-2 or AG-3 zoning district require a minimum width of 75 feet, a minimum depth of 100 feet and a lot area not less than 7,500 square feet.
- (2) Lots existing in any other zoning district which permits the construction of a single-family residence require a minimum of 40 feet in width and 75 feet in depth, and a lot area not less than 4,000 square feet.
[substance moved to § 34-3273(2)]
- (3) The use of any single lot of record for any residential use other than a single-family residential use is prohibited where the area of the lot is less than 6,000 square feet. Neither a guest house nor servants' quarters shall be permitted on a single lot of record having less than 7,500 square feet, or which is occupied by any dwelling unit or units other than one single-family residence.

(c) A single-family residence may also be constructed on a lot which complies with the density requirements of the Lee Plan, as long as the lot is part of a plat approved by the Board of County Commissioners and lawfully recorded in the public records of the county after June 1962.

Sec. 34-3275. Combining nonconforming lots.

(a) Abutting nonconforming lots may be combined and redivided to create larger dimension lots as long as such recombination includes all parts of all lots, allowable density is not increased, and all setback requirements are met. Under these conditions the new lots do not need to meet this code's dimensional requirements for new lots.
[subject moved from § 34-3272]

(b) If two or more abutting nonconforming lots each qualify for the right to construct a single-family residence, and if the lots or parcels are located in a zoning district that permits two-family dwellings, the property owner may combine the lots to build a single two-family building in lieu of constructing two single-family residences.
[moved from 34-1493(2)b.]

Sec. 34-3276. Placement of Replacing a mobile home or recreational vehicle on a nonconforming lot.

A single-family mobile home or a recreational vehicle may be replaced on a nonconforming lot of record *only* if allowed by the zoning district regulations and *only* in accordance with § 34-3234(b)(5), which lot is located within a mobile home or recreational vehicle park, as applicable, provided, however, that the park was properly zoned or approved by special permit for mobile home or recreational vehicle use, and provided further that minimum requirements as set forth in this section were met at the time the lot was created. These requirements are as follows:
[remainder of subsection deleted]

Sec. 34-3277. Commercial or industrial use on a nonconforming lot.

(a) A commercial or industrial use of land may be commenced on a single nonconforming lot of record lawfully existing on February 4, 1978, on the effective date of the ordinance from which this chapter is derived, subject to the specific limitations

and regulations set forth in this section, provided ~~however~~, that the lot is zoned for such use. However, the lot must be appropriately located and adequate in size and dimension to accommodate the use contemplated and all spatial requirements, i.e., proposed structures, setbacks, parking, access, surface water management facilities, and, where required, buffers; in addition to these specific requirements:

(1) **Lots created prior to 1962.** If the nonconforming lot was lawfully created prior to June 1962, it must be at least 4,000 square feet in area and have a minimum width of 40 feet and a minimum depth of 75 feet.

Minimum setbacks for structures are as follows:

- a. Street setbacks, build-to lines, and water body setbacks shall be as set forth in the regulations for the applicable zoning district.
- b. Side setbacks shall be 20 percent of lot width, or 15 feet, whichever is less.
- c. Rear setbacks shall be one-half of the lot depth less the street setback, or five feet, whichever is greater, but not more than 25 feet.

(2) **Lots created 1962–1978.** If the nonconforming lot was created between June 1962 and January 5, 1978, and was lawfully existing on February 4, 1978, it must be at least 7,500 square feet in area and have a minimum width of 75 feet and a minimum depth of 100 feet. Minimum setbacks for structures are as follows:

- a. Street setbacks, build-to lines, and water body setbacks shall be as set forth in the regulations for the applicable zoning district.
- b. Side setbacks shall be 15 feet.
- c. Rear setbacks shall be one-half the lot depth less the street setback, or five feet, whichever is greater, but not more than 25 feet.

(b) ~~(3)~~ Nothing in this division section shall be construed to prohibit the rezoning of nonconforming lots ~~of record~~ into commercial or industrial districts where the public interest is served by such a rezoning.

RESOLUTION OF THE TOWN COUNCIL OF
THE TOWN OF FORT MYERS BEACH, FLORIDA

RESOLUTION NUMBER 04-16

A RESOLUTION OF THE TOWN OF FORT MYERS BEACH ADOPTING AN OFFICIAL ZONING MAP THAT REFLECTS THE ZONING DISTRICTS ASSIGNED BY THE INTERIM ZONING MAP IN ORDINANCE 03-03 AND OTHER ZONING RESOLUTIONS ADOPTED BY LEE COUNTY AND THE TOWN OF FORT MYERS BEACH THROUGH APRIL 1, 2004, ALL IN ACCORDANCE WITH SECTION 34-614 OF THE TOWN'S LAND DEVELOPMENT CODE.

WHEREAS, the Town of Fort Myers has adopted Ordinance 03-03 providing a new zoning chapter (Chapter 34) for the town's land development code; and

WHEREAS, Division 1 of Article III of the zoning chapter provides the procedures for adopting an Official Zoning Map; and

WHEREAS, Section 34-614 of the new land development code mandates the adoption by resolution of an official zoning map to reflect the new zoning district boundaries adopted by Ordinance 03-03's "interim zoning map" and to also reflect past approvals of variances, special exceptions, special permits, and similar approvals that have not expired or believed to have become obsolete or unnecessary due to changed regulations or conditions; and

WHEREAS, public hearings were legally and properly advertised to consider the adoption of the Official Zoning Map; and

WHEREAS, a public hearing was held before the Local Planning Agency (LPA) on April 20, 2004, when the LPA gave full and complete consideration to the recommendations provided and to any public testimony; and

WHEREAS, as a result of that consideration the LPA recommended that the Town Council approve a resolution containing the Official Zoning Map and also approve a second resolution (04-17) containing a "Historic Zoning Map" that shows the zoning districts and other approvals that were in effect up until March 3, 2003; and

WHEREAS, public hearings were held by the Town Council on May 17, 2004, at which time the Town Council considered the provisions of Section 34-614, the interim zoning map adopted by Ordinance 03-03, prior approvals of Lee County and the Town of Fort Myers Beach, the recommendations provided to the Town Council, and any public testimony.


NOW THEREFORE BE IT RESOLVED that the Town of Fort Myers hereby adopts Exhibit A as the Official Zoning Map in accordance with Section 34-614 of the Fort Myers Beach Land Development Code. This Official Zoning Map shows the new zoning districts that were applied to all land in the town by the Interim Zoning Map that had been adopted as part of Ordinance 03-03, as modified by later rezonings and as modified by variances, special exceptions, special permits, and similar approvals that were approved by resolution through April 1, 2004. Exhibit A contains eleven map sheets that show the new zoning districts and additional key numbers that are further explained by ten pages of notes that provide a record and index of variances, special exceptions, special permits, and similar approvals. Exhibit B describes each zoning district shown on the Official Zoning Map and provides a reference to the Land Development Code section containing details about that district.

The foregoing resolution was adopted by the Fort Myers Beach Town Council upon a motion by Council Member Rynearson which was seconded by Council Member Van Duzer. Upon being put to a vote, the result was as follows:


Bill Thomas	aye
Garr Reynolds	aye
Don Massucco	aye
Howard Rynearson	aye
W. H. "Bill" Van Duzer	aye

DULY PASSED AND ENACTED this 17th day of May, 2004.


ATTEST:

By: 
Marsha Segal-George, Town Clerk

TOWN OF FORT MYERS BEACH

By: 
Bill Thomas, Mayor


Approved as to form by:


Richard V.S. Roosa, Town Attorney



Republic of the Philippines - Zoning Ordinance

Approved by the Board of Zoning Appeals
on the 15th day of May 1994
for the purpose of amending the zoning ordinance



South Central County Map
from the year 1900
as shown on the original map
of the County of Santa Clara, California




Exhibit A Fort Myers Beach Official Zoning Map
(updated through April 1, 2004)

-- Zoning districts are surrounded by solid line --
-- For dotted outlines, see table for key --








Exhibit A Fort Myers Beach Official Zoning Map

(Updated through April 1, 2004)

- Zoning districts are surrounded by solid line -
- For dotted outlines, see table for key -






Exhibit A - Fort Myers Beach Official Zoning Map
(Updated through April 1, 2004)

-- Zoning districts are surrounded by solid line --
-- For dotted outlines, see table for key --






Exhibit A - Fort Myers Beach Official Zoning Map

(Updated through April 1, 2004)

- Zoning districts are surrounded by solid line -
- For dotted outlines, see table for key -






Exhibit A - Fort Myers Council Official Zoning Map
Revised through April 1, 2004

Zoning districts are surrounded by solid line
City districts are surrounded by dotted/dashed line



EC

EC

EC

EC

EC

EC

RM 487

RS

RS

RS

RC

RC

CB

RM

RM

RM

BAYVIEW BLVD

PALMVIEW BLVD

SUNVIEW BLVD

CLEARVIEW BLVD

ALBATROSS BLVD

480

6

607

ALBATROSS ST

TRIS ST

473

2

478

474

472

470

468

466

464

462

460

BORET ST

ESTERO BLVD

2

485

483

481

479

477

482

480

478

476

Exhibit A - Town of Pine Bluff, Arkansas Official Zoning Map
 Adopted by Council Resolution No. 1, 2001
 Zoning Districts are color-coded by color key
 For district address, see table of law







Exhibit A : Fort Myers Beach Official Zoning Map
(updated through April 1, 2004)

- Zoning districts are surrounded by solid line -
- For dotted outlines, see table for key -







Exhibit A - Fort Myers Beach Official Zoning Map
 (Updated through April 1, 2005)

-- Zoning districts are surrounded by solid line --
 -- For dotted outlines, see table for key --






Exhibit A - Fort Myers Beach Official Zoning Map

(Updated through April 1, 2001)

- Zoning districts are surrounded by solid line -
- For dotted outlines, see table for key -

Zoning districts were assigned to all parcels by the interim zoning map in Ordinance 03-03. Some parcels have also been subject to individual zoning actions; those parcels are indicated with a key number on the maps in this resolution, with each key number explained by a corresponding note below.

- 1 administrative variance to 14.1' for street setback with conditions (ASV-96-011, 9/4/96, 96-08-163.09A)
- 2 variance to 2' for water setback with conditions (ZB-85-248, 11/25/85, 85-9-15)
- 3 special permit for COP in theater with conditions (FMB-99-46, 12/13/99, 99-09-245.01S 01.01); administrative interpretations of LDC upheld (FMB-98-07, 4/6/98, 98-01-227.07S)
- 6 variance to 15' for street setback with conditions (93-11-04-V-01, 11/4/93)
- 8 variance to allow accessory structures in front half of lot, with conditions (Z-81-486, 11/23/81, 81-11-16)
- 10 variance to 15' for water setback (90-4-12-V-7, 4/12/90)
- 13 variance to 6' for side setback with conditions (FMB-97-21, 6/2/97, 97-03-111.05V)
- 14 variance to allow accessory structures in front half of lot, with conditions (Z-81-469, 10/26/81, 81-10-32)
- 18 variance to 35' for side setback, variance to 98.5' for building height, variance to allow 66 efficiency units, variance to 1,975 square feet for each efficiency unit, with site plan and conditions (FMB-97-34, 9/7/97, 97-08-063.05V); special permit for COP with conditions (FMB-97-10, 3/17/97, 96-09-166-02S)
- 19 variance to 30' setback in Z-79-206 denied (ZAB-83-347, 11/14/83, 83-9-6); variances to 3' for side setback, to 0' for water setback, and to allow parking in side (N) setback, with conditions (ZAB-82-227, 9/20/82, 82-6-25); variance to 30' for side (N) setback (Z-79-206, 8/20/79, 79-7-40)
- 20 variance to setback (Z-70-119, 9/1/70, 70-7-4)
- 24 rezoned to amended RPD with site plan and conditions (Z-93-072, 11/15/93, 91-10-15-DCI-1(b)); administrative amendment to RPD with site plan and conditions (PD-92-020, 12/12/92, 91-10-15-DCI-1(a)); rezoned to RPD with site plan and conditions (Z-91-102, 12/9/91, 91-10-15-DCI-1)
- 31 variances to allow pool, restroom, and tennis courts in front half of lot and to allow parking in side setback, with conditions (Z-82-12, 2/15/82, 82-1-19)
- 32 special permit for COP/bar & cocktail lounge, variance to 500' separation, with conditions (Z-88-291, 11/14/88, 88-10-10)
- 33 addendum to stipulated settlement agreement (5/19/03); amendment to stipulated settlement agreement (3/30/01); stipulated settlement agreement resolving Bay Beach litigation (99-1042-CA-JBR, 2/23/01); legislative interpretation of LDC for Bay Beach (FMB-99-27, 7/1/99, 99-05-085.07S)
- 34 addendum to stipulated settlement agreement (5/19/03); amendment to stipulated settlement agreement (3/30/01); stipulated settlement agreement resolving Bay Beach litigation (99-1042-CA-JBR, 2/23/01); legislative interpretation of LDC for Bay Beach (FMB-99-27, 7/1/99, 99-05-085.07S); variance to 10' for water setback with conditions (94-08-11-V-01, 8/11/94, 94-08-11-V-01)
- 37 rezoned to amended CPD (retail stores) with site plan and conditions (FMB-03-06, 3/17/03, DCI2002-00057); administrative approval for COP in restaurant with conditions (COP-94-011, 6/15/94); rezoned to CPD (restaurant and retail building) with site plan and conditions (Z-92-017, 6/15/92, 92-3-17-DCI-1)
- 39 rezoned to amended CPD (retail store) with site plan and conditions (FMB-97-35, 10/27/97, 96-12-206.02Z); rezoned to CPD (retail store) with site plan and conditions (FMB-97-24, 7/7/97, 96-12-206.02Z 01.01)
- 42 addendum to stipulated settlement agreement (5/19/03); amendment to stipulated settlement agreement (3/30/01); stipulated settlement agreement resolving Bay Beach litigation (99-1042-CA-JBR, 2/23/01); legislative interpretation of LDC for Bay Beach (FMB-99-27, 7/1/99, 99-05-085.07S); variances to 0' for street setback and to 5' for water setback, with conditions (ZB-83-358, 9/26/83, 83-9-19)
- 43 administrative variance to 5.7' for side setback with conditions (ASV-95-24, 11/28/95, 95-11-147.09A)
- 44 addendum to stipulated settlement agreement (5/19/03); amendment to stipulated settlement agreement (3/30/01); stipulated settlement agreement resolving Bay Beach litigation (99-1042-CA-JBR, 2/23/01); legislative interpretation of LDC for Bay Beach (FMB-99-27, 7/1/99, 99-05-085.07S); special exception for on-site sign with variances to street, side, rear, and water setbacks (Z-81-142, 4/27/81, 81-4-9)
- 47 addendum to stipulated settlement agreement (5/19/03); amendment to stipulated settlement agreement (3/30/01); stipulated settlement agreement resolving Bay Beach litigation (99-1042-CA-JBR, 2/23/01); legislative interpretation of LDC for Bay Beach (FMB-99-27, 7/1/99, 99-05-085.07S); administrative amendment to Bay Beach plan with site plan and conditions (PD-98-66, 9/22/98, 95-02-206.13A)
- 49 administrative approval for COP in restaurant with conditions (COP2004-00002, 1/27/04); variance to allow a 32' SF identification sign with advertising (FMB-01-13, 6/4/01, VAR2001-00020); administrative approval for COP in restaurant with conditions (COP-97-008, 7/3/97, 96-12-068.01A); special exception for COP (ZB-85-15,

- 1/28/85, 85-1-16); special permit for COP (Z-76-141/141A, 9/1/76, 76-7-19)
- 51 DRI approval granted for Bay Beach Docks, with conditions (Z-94-048, 12/5/94, 94-10-18-DRI-1)
- 52 rezoned to amended CPD (marina and restaurant) with site plan and conditions (Z-94-013, 5/16/94, 88-09-08-DCI(c)); rezoned to CPD (marina and restaurant) with site plan and conditions (Z-88-268/268A, 10/24/88, 88-9-8 DCI)
- 54 variances in lot size and setbacks with conditions (Z-74-366, 12/9/74, 74-11-18)
- 58 rezoned to amended CPD (marina and restaurant) with site plan and conditions (Z-94-013, 5/16/94, 88-09-08-DCI(c)); special permit for COP/outdoor seating with conditions (93-12-09-SP-05, 12/9/93); administrative amendment to CPD with site plan and conditions (PD-90-011, 4/18/90, 88-9-8 DCI (b)); rezoned to amended CPD (marina and miniature golf) with site plan and conditions (Z-89-043, 6/12/89, 88-9-8-DCI(a)); rezoned to CPD (marina and restaurant) with site plan and conditions (Z-88-268/268A, 10/24/88, 88-9-8-DCI)
- 59 variance to allow accessory structures in front half of lot, with conditions (Z-81-244, 6/1/81, 81-5-42)
- 61 addendum to stipulated settlement agreement (5/19/03); administrative interpretation of LDC overturned: proposed cabanas are non-residential structures and qualify for dry floodproofing (FMB-02-38, 10/14/02, ADM2002-00014); amendment to stipulated settlement agreement (3/30/01); stipulated settlement agreement resolving Bay Beach litigation (99-1042-CA-JBR, 2/23/01); legislative interpretation of LDC for Bay Beach (FMB-99-27, 7/1/99, 99-05-085.07S); administrative amendment to Bay Beach plan with site plan and conditions (PD-98-66, 9/22/98, 95-02-206.13A)
- 63 special exception for identification sign with conditions (ZB-83-401, 10/30/83, 83-10-40)
- 64 variance to allow accessory structures in front half of lot, with conditions (Z-81-402, 9/28/81, 81-9-4)
- 66 variance to 0' for dock setback to riparian property line, with conditions (90-8-9-V-6, 8/9/90)
- 69 variances to 19.5' for street setback and 3.4' for side setback, with conditions (FMB-97-20, 6/2/97, 97-03-250.05V)
- 76 variance to allow an open deck 4.7' seaward of the CCCL with conditions (FMB-00-13, 3/13/00, 99-07-176.05V)
- 80 variance to allow dock to extend 119', with conditions (90-1-25-V-1, 1/25/90)
- 82 variance to 17' for water setback with conditions (FMB-96-13, 5/16/96, 96-03-224.05V)
- 83 variance to 2.5' for water depth at dock, with conditions (90-8-9-V-7, 8/9/90)
- 85 variance to allow dock to extend 135', with conditions (89-10-26-V-2, 10/26/89)
- 86 variance to 2.5' for water depth at dock, with conditions (90-2-15-V-7, 2/15/90)
- 89 special exception for accessory apartment with conditions (95-02-276.01S, 4/27/95)
- 91 variance to 4.2' for side setback (FMB-00-29, 6/29/00, VAR2000-00023)
- 92 variance in lot dimensions (Z-75-185, 8/11/75, 75-7-20)
- 94 variance to 2.5' for rear setback (FMB-97-08, 3/17/97, 95-07-203.05V); variance to 12.5' for rear setback (95-07-203.05V, 9/21/95)
- 97 variance to 8.5' for street setback with conditions (FMB-96-28, 10/21/96, 96-08-244-05V)
- 100 variance to 90' for lot depth (Z-77-55, 3/14/77, 77-2-13)
- 101 administrative approval for COP in restaurant with conditions (COP2002-00019, 3/18/02)
- 106 administrative variance to 2.6' for street setback with conditions (ASV-95-023, 10/30/95, 95-02-108.09A)
- 108 variances to 8' & 16' for side setbacks, to 20' for rear setback, and a reduction in parking spaces to 21 spaces (Z-80-289, 9/22/80, 80-9-14)
- 114 rezoned to CPD (resort) with site plan and conditions (Z-95-085, 12/18/95, 95-07-137.02Z); special exception for COP with conditions (ZAB-85-271, 11/12/85, 85-9-38)
- 115 variance to 16.7' for street setback with conditions (FMB-01-39, 12/10/01, VAR2001-00030)
- 117 variance to 10' for street setback for lots 11-12 and 19-23 only (BZA-87-021, 1/26/87, 87-1-27)
- 118 special permit for COP granted (Z-78-12, 1/9/78, 77-12-9)
- 125 variance to allow apartment under a duplex (Z-72-18, 2/1/72, 71-12-8)
- 126 special permit for COP/bar & cocktail lounge denied; special permit for COP in conjunction with restaurant granted, with conditions (91-10-17-SP-4, 12/11/91)
- 127 variances to allow pool in front half of lot and to allow two on-site signs (Z-81-187, 5/4/81, 81-4-53)
- 128 special exceptions for church and related facilities and for a sign, variances to 39,000 SF for lot area and for a reduction in on-site parking spaces (ZB-84-95, 6/25/84, 84-4-10)

- 130 special permit for child care center (Z-77-150, 6/14/77, 77-5-38)
- 131 special exception for home occupation with conditions (Z-82-210, 6/28/82, 82-6-7)
- 132 variances to 13' for street setback and 4.7' for side setback with conditions (FMB-99-47, 12/13/01, 99-09-214.05V)
- 133 requested CPD zoning denied (FMB-96-31, 11/18/96, 95-07-032.02Z); requested CPD zoning denied (FMB-96-15, 2/9/96, 95-07-032.02Z)
- 134 variances to 0.5' for side setback and to 1' for rear setback for carports, with conditions (FMB-02-41, 11/4/02, VAR2002-00023)
- 135 variances to 7.5' for side setback and to 51.5' for lot width, with conditions (92-7-23-V-2, 7/23/92)
- 136 variances to 0' for street setbacks and to 1' for identification sign setback, with conditions (94-04-07-SP-02, 4/14/94)
- 141 administrative amendment to final PUD plan (resort) with site plan and conditions (PUD-98-29, 8/4/98, 95-01-034.13A); administrative amendment to final PUD plan (resort) with site plan and conditions (PUD-95-41, 12/22/95, 95-01-034.13A); rezoned to CPD (resort) with site plan and conditions (Z-95-017, 11/6/95, 95-01-034.03Z); amended final PUD plan (resort) with site plan and conditions (Z-93-057, 10/4/93, 83-9-12-DCI(d)); administrative amendment to final PUD plan (resort) with site plan and conditions (PUD-93-014/014A, 6/30/93, 83-9-12-DCI(c)); administrative amendment to final PUD plan (resort) with site plan and conditions (PUD-91-010/010A, 11/15/91, 83-9-12-DCI(b)); approved final PUD plan for phases II through V (resort) with site plan and conditions (ZAB-84-196/196A, 11/19/84, 83-9-12-DCI); rezoned to preliminary PUD (resort) with site plan and conditions (Z-82-170, 6/21/82, 82-3-28)
- 142 rezoned to amended CPD (to remove 7 approved units) with site plan and conditions (FMB-99-07, 2/22/99, 95-01-034.03Z 03.01); rezoned to CPD (resort) with site plan and conditions (Z-95-017, 11/6/95, 95-01-034.03Z)
- 144 rezoned to amended CPD on bay side (to remove 47 units) and amended PUD on gulf side (to add 47 units), both with site plans and conditions (FMB-00-07/07a, 1/10/00, 95-01-034.03Z 03.01); rezoned to amended CPD (to remove 7 approved units) with site plan and conditions (FMB-99-07, 2/22/99, 95-01-034.03Z 03.01); administrative amendment to final PUD plan (resort) with site plan and conditions (PUD-95-41, 12/22/95, 95-01-034.13A); rezoned to CPD (resort) with site plan and conditions (Z-95-017, 11/6/95, 95-01-034.03Z); administrative amendment to final PUD plan (resort) with site plan and conditions (PUD-91-010/010A, 11/15/91, 83-9-12-DCI(b)); approved final PUD plan for phases II through V (resort) with site plan and conditions (ZAB-84-196/196A, 11/19/84, 83-9-12-DCI); rezoned to preliminary PUD (resort) with site plan and conditions (Z-82-170, 6/21/82, 82-3-28)
- 146 administrative amendment to CPD (resort) with site plan and conditions (ADD2003-0086, 12/19/03); rezoned to MPD (resort) to reconstruct two existing buildings and transfer commercial space from bay side, with site plan and conditions (FMB-01-26, 08/27/01, DCI2000-00071)
- 147 rezoned to amended CPD and amended PUD (resort) to change orientation of 9-story building and revise size of units, with site plan and conditions (FMB-01-21, 6/25/01, DCI2001-00027); rezoned to amended CPD on bay side (to remove 47 units) and amended PUD on gulf side (to add 47 units), both with site plans and conditions (FMB-00-07/07a, 1/10/00, 95-01-034.03Z 03.01); administrative amendment to final PUD plan (resort) with site plan and conditions (PUD-98-29, 8/4/98, 95-01-034.13A); administrative amendment to final PUD plan (resort) with site plan and conditions (PUD-95-41, 12/22/95, 95-01-034.13A); amended final PUD plan (resort) with site plan and conditions (Z-93-057, 10/4/93, 83-9-12-DCI(d)); administrative amendment to final PUD plan (resort) with site plan and conditions (PUD-93-014/014A, 6/30/93, 83-9-12-DCI(c)); administrative amendment to final PUD plan (resort) with site plan and conditions (PUD-91-010/010A, 11/15/91, 83-9-12-DCI(b)); approved final PUD plan for phases II through V (resort) with site plan and conditions (ZAB-84-196/196A, 11/19/84, 83-9-12-DCI); rezoned to preliminary PUD (resort) with site plan and conditions (Z-82-170, 6/21/82, 82-3-28)
- 154 approved final PUD plan for phase I (resort) with site plan and conditions (ZAB-83-353, 11/14/83, 83-9-12 DCI); rezoned to preliminary PUD (resort) with site plan and conditions (Z-82-170, 6/21/82, 82-3-28)
- 155 variances to 45' & 50' for lot width, 13' for water setback, 4' for side setback, with conditions (FMB-01-20, 6/25/01, VAR2000-00076)
- 158 variance to allow accessory structures in front half of lot, with conditions (Z-81-58, 2/23/81, 81-2-13)
- 160 administrative variances to 5.8' for side (NW) setback and to 5' for side (SE) setback, with conditions (AA-ASV-96-006, 5/6/96, 96-03-107.09A)
- 161 administrative variances to 5.5' for rear setback and to 6.7' for side setback, with conditions (ASV-94-005, 11/21/94)
- 162 variance to 11' for rear setback with conditions (FMB-98-09, 4/20/98, 98-01-078.05V)
- 163 administrative variances to 5.6' for side (W) setback and to 6.2' for side (E) setback, with conditions (ASV-95-07, 3/1/95, 95-02-107.09A)
- 164 rezoned to amended CPD (to add 7 units to hotel from FMB-99-07), with site plan and conditions (FMB-99-08,

- 2/22/99, 95-07-043.02Z 02.01); rezoned to CPD and amended CPD (hotel) with site plan and conditions (Z-95-75, 11/6/95, 95-07-043.02Z); rezoned to CPD (motel) with site plan and conditions (Z-93-034, 8/2/93, 93-06-01-DCI-01)
- 165 variance to allow pool in front half of lot, with conditions (Z-82-51, 2/22/82, 82-2-33)
- 167 variances to 1' for rear setback and to 0' for side setback, with conditions (BZA-88-077, 4/18/88, 88-3-26)
- 169 variances to 4.2' for street setback, 6' for rear setback, 6' for side (S) setback, 42% lot coverage, 5,583 SF lot area, 50' lot depth, with conditions (FMB-02-27, 6/24/02, VAR2001-00032)
- 173 variance in lot size to allow division into 7 single-family lots (Z-76-212, 11/16/76)
- 174 variances on tract 4 to 4.5' for street setback, 10' for rear setback, 50' for lot width, 50' for lot depth, 5' for side setback, with conditions; variances on tract 6 to 4.5' for street setback, 10' for rear setback, 67.5' for lot width, 50' for lot depth, with conditions (BZA-88-140, 6/20/88, 88-5-33); variance in lot size to allow division into 7 single-family lots (Z-76-212, 11/16/76)
- 175 variances in lot size and to allow access by means of an easement (Z-76-163, 9/29/76, 76-9-29)
- 176 variances to 12' for street setback, 10' for rear setback, 60' for lot width, 50' for lot depth, with conditions (BZA-88-141, 6/20/88, 88-5-34); variances in lot size and to allow access by means of an easement (Z-76-163, 9/29/76, 76-9-29)
- 178 special permit for COP/outdoor seating with conditions (95-08-061.02S, 10/5/95)
- 179 variances to 12' for front setback and to 10' for rear setback (ZB-82-414, 10/25/82, 82-10-13); variances in lot size and to allow access by means of an easement (Z-76-163, 9/29/76, 76-9-29)
- 180 variance to 10.8' for side setback with conditions (Z-68-82, 5/22/68, 68-4-9)
- 185 variances to 4.5' for street setback, 7' for rear setback, 0' for side setback, with conditions (FMB-00-16, 4/10/00, VAR1999-00028)
- 186 variance in setbacks with conditions (Z-75-197, 9/8/75, 75-8-6)
- 188 rezoned to CPD (hotel, restaurant and retail building) with site plan and conditions (FMB-01-08, 4/9/01, DCI2000-00059); administrative approval for COP in restaurant with conditions (COP-94-013, 9/13/94)
- 192 rezoned to amended CPD (restaurant, retail and motel buildings) with site plan and conditions (FMB-03-35, 11/10/03, DCI2001-00067); administrative amendment to CPD (restaurant, retail and motel buildings) with site plan and conditions (ADD2002-00115, 10/4/02); rezoned to CPD and amended CPD (restaurant, retail and motel buildings) with site plan and conditions (FMB-99-05, 2/8/99, 95-01-003.02Z 02.01); rezoned to CPD (motel and restaurant) with site plan and conditions (Z-95-074, 11/6/95, 95-01-003.02Z); special permit for COP/outdoor seating with conditions (95-01-003.02S, 1/6/95); variance to allow existing roof sign to remain, with conditions (89-10-12-V-4, 10/12/89); special exception for COP (ZB-83-380, 10/24/83, 83-10-18)
- 193 variances to 55% for lot coverage and 4.5' for side setback, with conditions (FMB-01-33, 10/15/01, VAR2001-00023)
- 196 variance to 0' for water setback with conditions (94-02-10-V-02, 2/10/94)
- 198 variance in lot size to allow duplex (Z-71-29, 4/6/71, 71-2-2)
- 199 variance to 10' for rear setback (95-03-265.05V, 5/25/95)
- 201 variance to allow duplex on 5,000 SF lot (Z-70-67, 6/2/70, 70-4-14)
- 202 rezoned to amended CPD (restaurant, retail and motel buildings) with site plan and conditions (FMB-03-35, 11/10/03, DCI2001-00067); administrative amendment to CPD (restaurant, retail and motel buildings) with site plan and conditions (ADD2002-00115, 10/4/02); rezoned to CPD and amended CPD (restaurant, retail and motel buildings) with site plan and conditions (FMB-99-05, 2/8/99, 95-01-003.02Z 02.01); rezoned to CPD (motel and restaurant) with site plan and conditions (Z-95-074, 11/6/95, 95-01-003.02Z);
- 203 variances to 16.6' for street setback, to 15.6' for rear setback, and to 0' for side setback (FMB-99-38, 10/11/99, 99-07-194.05V 01.01)
- 206 variance to 0' for rear setback with conditions (FMB-02-21, 5/13/02, VAR2002-00003); administrative approval for COP in restaurant with conditions (COP-97-002, 3/6/97, 97-02-105.01A)
- 207 rezoned Parcel B to amended CPD to allow parking on open space, with site plan and conditions (FMB-01-14, 6/4/01, DCI2000-00002); special permit for COP with conditions (FMB-00-12, 3/13/00, SEZ1999-00028); rezoned to CPD (hotel and open space) with site plan and conditions (FMB-97-14, 4/7/97, 96-12-018.03Z)
- 208 administrative amendment to CPD with site plan and conditions (ADD2002-00089A, 12/19/03); administrative amendment to CPD denied (ADD2002-00089, 9/17/02); rezoned to CPD (retail and hotel buildings) with site plan and conditions (FMB-01-03, 1/22/01, DCI2000-00051); special exception for commercial parking lot with conditions ((FMB-99-40, 10/11/99, 98-12-212.01S 01.01)
- 210 rezoned to amended CPD (resort) with site plan and conditions (FMB-03-23, 6/30/03, DCI2003-00016); administrative amendment to CPD with site plan and conditions (ADD2001-00013, 3/5/01); rezoned to CPD

- (resort) with site plan and conditions (FMB-00-09, 2/14/00, 99-09-352.02Z); special permit for COP/outdoor seating with conditions (95-08-187.02S, 10/12/95)
- 211 variances to 10' for side setback, 5,000 SF for lot area, 50' for lot width (Z-80-361, 10/28/80, 80-10-49)
- 212 variances to 0' for rear and side setbacks (Z-80-284, 9/22/80, 80-9-7)
- 214 variances to allow commercial uses without additional parking spaces, to 10' for street setback, to 6' for rear setback, to 2' for side setback, to 2,925 SF for lot area, to 29' for lot width, with conditions (93-07-08-V-02, 7/8/93)
- 215 variances to 3.9' for street setback, 0' for rear setback, 0' for both side setbacks, 5,670 SF for lot area, 46' for lot width, with conditions (89-11-30-V-7, 12/21/89)
- 216 rezoned to amended CPD (restaurants, retail and hotel buildings) with site plan and conditions (FMB-04-08, 3/8/04, DCI2003-00065); administrative amendment to CPD with site plan and conditions (ADD2002-00130, 3/3/03); entered into development agreement for restaurants, retail and hotel buildings (OR-3646-2893, 4/15/02); rezoned to CPD and amended CPD (restaurants, retail and hotel buildings) with site plan and conditions (FMB-02-07, 4/15/02, DCI2000-00047); administrative amendment to CPD (restaurant and retail buildings) with site plan and conditions (ADD2000-00138, 10/17/00); administrative amendment to CPD (restaurant and retail buildings) with site plan and conditions (PD-95-38, 11/8/95, 95-10-207.13A); rezoned to CPD (restaurant and retail buildings) with site plan and conditions (Z-92-065, 2/1/93, 92-11-17); special permit for COP with conditions (SP-87-68, 11/23/87, 87-11-SP-3)
- 217 variances to 5' & 0' for street setback, 0' for side setback, 9' for rear setback, 63' for lot width, 81' for lot depth, 4,688 SF for lot area, 73% for lot coverage, reduce the number of parking spaces required to 0, with conditions (95-10-266.05V, 12/14/95)
- 218 variances to 0' for street setback, 0' for side setback, 0' for rear setback, 37' for lot width, 80' for lot depth, 5,074 SF for lot area, 75% for lot coverage, reduce the number of parking spaces required to 0, with conditions (95-05-217.05V, 7/13/95); special permit for COP (COP-83-13, 4/21/82, accepted into BOCC record 4/4/84)
- 219 variances to 3' for street setback, 5' for rear (E) setback, 3' for side (S) setback, 2,942 SF for lot area, 40' for lot width, 77' for average lot depth, reduce the number of parking spaces required to 0, with conditions (91-9-12-V-6, 12/12/91)
- 220 variances to 0' for street setback, 0' for side setback, 61.5' for lot depth, 2,460 SF for lot area, reduce the number of parking spaces required to 0, with conditions (95-04-193.05V, 6/15/95)
- 221 variances to 19' for street setback and to 5' for rear setback (93-02-04-V-02, 2/4/93)
- 222 variances to 0' for street setback, 0' for rear setback, 0' for side setback, reduce the number of parking spaces required to 0, with conditions (93-12-16-V-02, 12/16/93)
- 223 variances to 0' for side and rear setbacks and a reduction in parking spaces, with conditions (FMB-97-02, 2/3/97, 96-10-095.05V); variances to 10' and 12' for street setbacks, 15' for rear setback, 2' for side setback, with conditions (93-03-04-SP-01, 3/4/93)
- 224 rezoned to amended CPD (restaurants, retail and hotel buildings) with site plan and conditions (FMB-04-08, 3/8/04, DCI2003-00065); administrative amendment to CPD with site plan and conditions (ADD2002-00130, 3/3/03); entered into development agreement for restaurants, retail and hotel buildings (OR-3646-2893, 4/15/02); rezoned to CPD and amended CPD (restaurants, retail and hotel buildings) with site plan and conditions (FMB-02-07, 4/15/02, DCI2000-00047); administrative approval for COP/outdoor seating with conditions (COP2000-00064, 11/2/00); administrative approval for COP/outdoor seating with conditions (COP2000-00020, 6/22/00); special permit for COP/outdoor seating with conditions (92-2-6-SP-3, 2/6/92); administrative approval for COP in restaurant with conditions (COP-91-005, 2/26/91); variances to 20' for rear setback, to 0' for side setback, and to reduce the number of parking spaces required to 8 existing spaces, with conditions (BZA-88-341, 11/21/88, 88-11-24)
- 225 variance to allow an open trellis seaward of the CCCL, with conditions (FMB-99-39, 10/11/99, 99-08-007.05V)
- 226 variance to 0' for street setback for sign with conditions (FMB-97-43, 12/15/97, 97-08-145.03V)
- 227 variances to 48' for lot width and to 45' for lot depth (Z-80-278, 9/22/80, 80-9-1)
- 228 variance to 0' for identification sign setback (95-05-099.03V, 7/6/95)
- 229 variance to allow 4 instructional signs with conditions (FMB-97-44, 12/15/97, 97-04-188.03V); special permit for COP/bar & cocktail lounge, with conditions (91-8-8-SP-1, 8/8/91)
- 230 special permit for COP/outdoor seating and variance to allow increased commercial intensity without additional parking spaces, with conditions (95-07-161.02S, 9/28/95)
- 231 administrative amendment to CPD with site plan and conditions (ADD2002-00089A, 12/19/03); administrative interpretation of LDC overturned: CPD to be amended administratively, with dry floodproofing required only for new construction (FMB-03-10, 4/14/03, ADM2002-00017); administrative amendment to CPD denied (ADD2002-00089, 9/17/02); rezoned to CPD (retail and hotel buildings) with site plan and conditions (FMB-01-03, 1/22/01, DCI2000-00051)

- 232 variances to 41' for lot width and to 6,042 SF for lot area (91-4-25-V-1, 4/25/91)
- 233 variance to 5' for side setback (BZA-87-251, 12/21/87, 87-12-20)
- 234 variance to 62.5' for lot width (FMB-01-02, 1/22/01, VAR2001-00071)
- 235 variance to 57' for lot width (BZA-87-245, 12/21/87, 87-12-14)
- 236 variance to 15' for street setback with conditions (FMB-01-11, 5/14/01, VAR2001-00014)
- 238 administrative variance to 9.3' for water setback with conditions (ASV-94-006, 12/5/94); variance to 13.3' for water setback (94-06-16-V-01, 7/14/94); variance to 13.5' for water setback with conditions (92-9-10-V-2, 9/10/9)
- 240 variances to 2.5' for side setback, 5,670 SF for lot area, 53' for lot width, with conditions (92-12-17-V-2, 12/17/92); variance in lot size to allow one house (Z-76-178, 10/11/76, 76-9-18)
- 241 variances to 16' for street setback, 10' for corner lot setback, 6' for rear setback, with conditions (89-8-10-V-2, 8/10/89)
- 242 variances to 2.5' for side setback, 5,670 SF for lot area, 53' for lot width, with conditions (92-12-17-V-2, 12/17/92)
- 245 nonconformity of docking facility acknowledged as suitable for a submerged land lease, but expansion of docking facility denied (FMB-99-13, 3/8/99, 98-11-161.02V 01.01)
- 248 administrative variance to 2.3' for side setback with conditions (ASV-95-011, 6/6/95, 95-05-225.09A)
- 253 special permit for COP/outdoor seating with conditions (FMB-02-43, 12/9/02, COP2002-00106)
- 254 special permit for COP/outdoor seating with conditions (93-12-23-SP-01, 12/23/93); administrative approval for COP in restaurant with conditions (COP-93-007, 11/1/93)
- 255 variances to 14' for street setback and to 8.8' for side (S) setback (Z-70-113, 8/4/70, 70-6-10)
- 257 variances for lot area, to 4,450 SF for lots 15, 16, 17, 19, 20, to 5,000 SF for lot 18, to 4,000 SF for lots 8 & 9 (Z-81-68, 2/23/81, 81-2-24)
- 258 variance to lower by 2 the number of parking spaces required, with conditions (FMB-97-36, 9/9/97, 97-07-226.05V)
- 259 variances to 18.4' for rear setback and 5.8' for side setback, with conditions (FMB-01-34, 10/15/01, VAR2001-00037)
- 260 variance to 14' for street setback (92-12-10-V-2, 12/10/92); variances for lot area, to 4,450 SF for lots 15, 16, 17, 19, 20, to 5,000 SF for lot 18, to 4,000 SF for lots 8 & 9 (Z-81-68, 2/23/81, 81-2-24)
- 262 administrative approval for COP in restaurant with conditions (COP2003-00032) was revoked on 4/23/03; special permit for COP/outdoor seating with conditions (95-03-258.02S, 6/13/95)
- 263 special exception for shared permanent parking lot with conditions (FMB-03-40, 12/8/03, SEZ2003-00028); special exception for commercial parking lot with conditions, to expire on 3/9/2004 (FMB-99-11, 3/8/99, 98-05-223.01S); special exception for commercial parking lot and variance from parking lot design standards, with conditions (93-10-07-SE-02, 10/7/93)
- 264 variances for lot area, to 4,450 SF for lots 15, 16, 17, 19, 20, to 5,000 SF for lot 18, to 4,000 SF for lots 8 & 9 (Z-81-68, 2/23/81, 81-2-24)
- 265 variance to side setback with conditions (Z-79-94, 4/23/79, 79-4-22)
- 270 variances to 0' for fence setback to street and to 10' for front yard fence height, with conditions (FMB-02-28, 6/24/02, VAR2002-00010)
- 276 variance to 14' for street setback (93-11-18-V-03, 11/18/93); variances for lot area, to 4,450 SF for lots 15, 16, 17, 19, 20, to 5,000 SF for lot 18, to 4,000 SF for lots 8 & 9 (Z-81-68, 2/23/81, 81-2-24)
- 277 variances to 13.6' for street setback and to 12' for water setback, with conditions (93-08-12-V-02, 8/12/93)
- 278 variance to 2.5' for side setback with conditions (93-03-04-V-02, 3/4/93)
- 279 variances for lot area, to 4,450 SF for lots 15, 16, 17, 19, 20, to 5,000 SF for lot 18, to 4,000 SF for lots 8 & 9 (Z-81-68, 2/23/81, 81-2-24)
- 280 administrative variance to 4.3' for side setback with conditions (ASV-96-012, 3/19/97, 96-08-175.09A); special permit for COP/outdoor seating with conditions (FMB-97-09, 3/17/97, 96-08-175.02S)
- 286 special permit for COP/outdoor seating with conditions (FMB-02-44, 12/9/02, COP2002-00084); special permit for COP/outdoor seating with conditions (94-09-29-SP-04, 9/29/94)
- 288 variances to 11' for street setback, to 22' for rear setback, to 10' for side setback, and to allow vehicles to back out into Miramar Street, with conditions (90-9-27-V-4, 1/24/91)
- 289 variance to allow commercial uses without additional parking spaces, with conditions (92-12-3-V-1, 12/3/92)

- 290 special permit for COP/outdoor seating with conditions (FMB-96-27, 10/21/96, 96-07-178.04S); special exception for COP and variance to 80' for lot depth (ZB-84-229/229A, 10/22/84, 84-10-14)
- 291 variances to 1.2' for rear setback and 0.5' for side setback, with conditions (BZA-88-340, 11/21/88, 88-11-23)
- 292 special permit for COP/outdoor seating with conditions (FMB-00-14, 3/13/00, COP2000-00001)
- 293 special permit for COP/outdoor seating with conditions (95-10-232.04S, 12/21/95); variance to allow accessory structures in front half of lot (Z-81-300, 6/22/81, 81-6-38)
- 294 variance to allow commercial uses without additional parking spaces, with conditions (92-12-3-V-2, 12/3/92)
- 295 special exception for shared permanent parking lot with conditions (FMB-03-11, 4/14/03, DCI2002-00044); requested amended CPD zoning denied (FMB-00-41, 12/11/00, DCI2000-00060); rezoned to amended CPD (commercial parking lot; retail stores in future phase) with site plan and conditions (FMB-99-26, 6/21/99, 99-03-069.02Z); rezoned to CPD (commercial building) with site plan and conditions (Z-93-065, 10/4/93, 93-08-31-DCI-03)
- 297 special permit for COP/outdoor seating with conditions (95-10-173.02S, 12/7/95); variance to reduce the number of parking spaces required to 0, with conditions (BZA-88-339, 11/21/88, 88-11-22)
- 298 special permit for COP/outdoor seating with conditions (FMB-01-15, 6/4/01, COP2001-00044); administrative approval for COP in restaurant with conditions (COP-98-004, 10/19/98, 98-09-116.01A)
- 301 variances to 10' for street setback, 10' for water setback, 5,320 SF for lot area, 55' for lot depth, with conditions (95-04-056.05V, 6/8/95)
- 303 special exceptions for church and related facilities and for a sign, variances to 1.96 acres for lot area and for a reduction in on-site parking spaces, with conditions (ZAB-84-8, 2/20/84, 84-1-8)
- 305 variance to lower by 10 the number of parking spaces required (FMB-97-03, 2/3/97, 96-10-023.05V); variance to lower by 10 the number of parking spaces required (FMB-96-34, 12/2/96, 96-10-023.05V)
- 310 administrative approval for commercial antenna with conditions (ADD2003-00041, 5/27/03)
- 318 variances to 1' for side setback and to 20' for water setback (89-5-18-V-8, 5/18/89)
- 320 variances for lot area, lot width, and lot depth, see resolutions for complete list of lots and variance dimensions (ZB-84-119/119A/119AA, 6/4/84, 84-5-5)
- 324 variance to 50' for lot width with conditions (94-07-14-V-01, 7/14/94)
- 325 variances for lot area, lot width, and lot depth, see resolutions for complete list of lots and variance dimensions (ZB-84-119/119A/119AA, 6/4/84, 84-5-5)
- 329 variances for lot width and lot depth, see resolution for list of lots and variance dimensions (Z-82-180, 5/24/82, 82-5-12)
- 330 variances for lot area, lot width, and lot depth, see resolutions for complete list of lots and variance dimensions (ZB-84-119/119A/119AA, 6/4/84, 84-5-5)
- 332 variance to 90' for lot depth (Z-82-138, 4/26/82, 82-4-13); variance for lot size (Z-71-69, 6/1/71, 71-4-11)
- 333 variances for lot width and lot depth, see resolution for list of lots and variance dimensions (Z-82-180, 5/24/82, 82-5-12)
- 334 variances to 6.5' for side (SE) setback, to 6' for side (S) setback, to 7' for side (N) setback, to 7' for side (NW) setback, with conditions (94-04-14-V-01, 4/14/94); variance to 5' for dock setback to riparian property line, with conditions (92-12-17-VDK-1, 2/11/93)
- 335 variances for lot width and lot depth, see resolution for list of lots and variance dimensions (Z-82-180, 5/24/82, 82-5-12)
- 336 variances for lot area, lot width, and lot depth, see resolutions for complete list of lots and variance dimensions (ZB-84-119/119A/119AA, 6/4/84, 84-5-5); variance for lot size (Z-71-69, 6/1/71, 71-4-11)
- 337 variances for lot area, lot width, and lot depth, see resolutions for complete list of lots and variance dimensions (ZB-84-119/119A/119AA, 6/4/84, 84-5-5)
- 340 variances for lot area, lot width, and lot depth, see resolutions for complete list of lots and variance dimensions (ZB-84-119/119A/119AA, 6/4/84, 84-5-5); variance for lot size (Z-71-69, 6/1/71, 71-4-11)
- 341 variance to allow pool patio closer to street than the principal structure and variance to allow a 4' high fence (ZB-84-118, 5/29/84, 84-4-46)
- 342 administrative variance for front yard fence (ASV-95-022, 10/25/95, 95-10-024.09A)
- 346 special permit modified to allow expanded COP (FMB-97-06, 2/27/97, 96-02-186.02S); special permit not modified to allow expanded COP (FMB-96-20, 7/15/96, 96-02-186.02S); special permit not modified to allow expanded COP (FMB-96-11, 4/18/96, 96-02-186.02S); special permit for COP/outdoor seating with conditions (94-12-22-SP-1, 12/22/94)

- 347 variance to 22' for water setback (ZB-85-312, 10/29/85, 85-10-40)
- 348 special permit for 1 kitchen and 2 bathrooms upstairs and 1 kitchen and 3 bathrooms downstairs (Z-77-165, 7/11/77, 77-6-9)
- 349 administrative variance to 1.5' for street setback with conditions (ASV-94-002, 12/5/94)
- 351 variances to 15' for rear setback and to 82' for lot depth (ZB-82-518, 12/27/82, 82-12-32)
- 356 variance for apartment under piling home (Z-72-59, 4/4/72, 72-2-6)
- 359 special permit for accessory unit with conditions (Z-74-231, 7/8/74, 74-6-20)
- 360 rezoned to amended CPD (supermarket) to include signs, with site plan and conditions (FMB-01-06, 2/12/01, DCI2000-00078); rezoned to CPD (supermarket) with site plan and conditions (FMB-98-11/11A, 5/5/98, 96-02-186.02Z)
- 361 variance to 5' for water setback with conditions (90-11-15-V-4, 11/15/90)
- 362 variance to side setback with conditions (Z-79-298, 11/26/79, 79-11-5)
- 364 variance to 5' for water setback with conditions (89-4-13-V-3, 5/4/89); variance to 88' for average lot depth (BZA-87-243, 12/21/87, 87-12-12)
- 365 variance to 7.5' for street setback with conditions (FMB-00-37a, 10/9/00, VAR2000-00047)
- 369 special exception for home occupation with conditions (ZB-82-303, 8/23/82, 82-8-16)
- 371 rezoned to RPD with site plan and conditions (FMB-02-04, 1/14/02, DCI2001-00029)
- 372 variances to 4' for side (W) setback and to 5' for side (E) setback on Lot 18 only, with conditions (FMB-02-26, 6/24/02, VAR2002-00013)
- 373 variance to 7.5' for water setback with conditions (FMB-00-18, 5/8/00, VAR2000-00010)
- 374 variances to street setback, rear setback, and lot area (Z-79-351, 1/21/80, 79-12-29)
- 376 variances to 19.4' for street setback, 17.1' for rear setback, 2.5' for side (N) setback, with conditions (FMB-02-08, 2/11/02, VAR2001-00045)
- 377 variance to 4' for side setback, with conditions (89-6-1-V-2, 7/13/89); variance for lot size (less than 6,000 SF) (Z-72-130, 7/11/72, 72-5-12)
- 378 variance for lot size (less than 6,000 SF) (Z-72-130, 7/11/72, 72-5-12)
- 379 rezoned to CPD (hotel) with site plan and conditions (FMB-98-10/10A, 4/20/98, 95-04-118.02Z); requested CPD zoning denied (Z-95-072, 12/18/95, 95-04-118.02Z); special permit for COP/outdoor seating with conditions (93-12-09-SP-02, 12/23/93); variance to 90' for lot width (Z-77-31, 2/14/77, 77-1-7)
- 380 special permit for day care nursery with conditions (Z-76-127, 8/9/76, 76-7-4); variance to allow residence to be remodeled into a triplex (Z-69-149, 11/4/69, 69-6-18)
- 383 variance in lot size (Z-70-158, 11/3/70, 70-9-15)
- 384 variance to 5,000 SF for lot area (Z-77-271, 12/12/77, 77-11-3)
- 386 variance for duplex on substandard lot (Z-77-135, 6/13/77, 77-5-21)
- 388 variances to 50' for lot width and to 5,000 SF for lot area, with conditions (90-1-11-V-3, 1/11/90)
- 389 variance to 5,000' for lot area (Z-80-425, 12/22/80, 80-12-12)
- 390 variance to 5,000' for lot area (Z-80-433, 12/22/80, 80-12-21)
- 392 special permit for COP/outdoor seating with conditions (FMB-03-36, 11/10/03, SEZ2003-00023); special permit for COP/outdoor seating with conditions (FMB-02-40, 10/14/02, COP2002-00095); variance to 0' for street setback and variance to place required parking spaces in an off-site parking lot, with conditions (FMB-02-12, 9/17/02, VAR2001-00053)
- 395 requested CPD zoning denied (FMB-00-41, 12/11/00, DCI2000-00060)
- 400 addendum to stipulated settlement agreement (5/19/03); amendment to stipulated settlement agreement (3/30/01); stipulated settlement agreement resolving Bay Beach litigation (99-1042-CA-JBR, 2/23/01); legislative interpretation of LDC for Bay Beach (FMB-99-27, 7/1/99, 99-05-085.07S); administrative amendment to Bay Beach PD with site plan and conditions (PD-95-06, 3/20/95, 95-02-206.13A 02.01)
- 410 variances to 7' for street (NW) setback, 7' for rear (SE) setback, 15' for side (NE) setback, with conditions (replaces FMB-02-37) (FMB-03-09, 4/14/03, VAR2002-00014); variances to 7' for street (NW) setback, 7' for rear (SE) setback, 20' for side (NE) setback, with conditions (later amended by FMB-03-09) (FMB 02-37, 10/14/02, VAR2002-00014)
- 412 variances to 20' for street setback and 7.5' for side setback, with conditions (91-9-26-V-3, 11/7/91)
- 414 variance to 25' for lot frontage with conditions (BZA-87-043, 2/16/87, 87-2-19)

- 419 variance to 5.3' for side setback with conditions (FMB-01-05, 2/12/01, VAR2000-00077)
- 423 variance to allow deck seaward of CCCL denied (FMB-03-12, 4/14/03, VAR2002-00050)
- 433 variances to 0' for street setback and to allow a shed between principal building and street, with conditions (BZA-87-017, 1/26/87, 87-1-23)
- 436 administrative approval for COP in restaurant with conditions (COP2003-0220, 1/12/04); administrative variances to 20.8' for street setback, to 6' for rear setback, and to 2.6' for side setback, with conditions (ASV-98-009, 8/27/98, 98-07-260.09A)
- 437 variance to 7.5' for side setback with conditions (FMB-00-37b, 10/9/00, VAR2000-00029)
- 440 variance to 2' for side setback, variance to 0' for water setback, variance to allow a 6' fence, with conditions (FMB-97-37, 9/9/97, 97-08-046.05V)
- 445 special permit for COP/outdoor seating with conditions (90-1-18-SP-1, 1/18/90); variance to allow existing restaurant without additional parking spaces, with site plan and conditions (Z-89-074, 9/11/89, 89-7-25-2)
- 446 variances to 18' for street setback, 2.5' for side setback, 6,173 SF for lot area, 61.7' for lot width, with conditions (90-7-5-V-2, 7/5/90)
- 448 rezoned to amended CPD (headquarters building) with site plan and conditions (FMB-03-22, 6/9/03, DCI2002-00073); rezoned to CPD (headquarters building) with site plan and conditions (FMB-00-28, 6/29/00, DCI2000-00027)
- 449 variances to 55' for lot width and to 5,500 SF for lot area (Z-80-386, 11/24/80, 80-11-11)
- 450 variance to allow existing restaurant without additional parking spaces, with site plan and conditions (Z-89-074, 9/11/89, 89-7-25-2)
- 451 administrative variance to 16' for rear setback with conditions (ASV-95-016, 7/20/95, 95-07-001.09A)
- 453 variances to 68' for lot width and to 6,800 SF for lot area, with conditions (95-07-003.05V, 8/24/95)
- 457 variance to allow living area below flood elevation denied (FMB-00-25, 6/19/00, ADM2000-00005); variances for lot width and lot depth, see resolution for list of lots and variance dimensions (82-180, 5/24/82, 82-5-12)
- 461 variance for side setback denied (FMB-97-45, 12/15/97, 97-09-294.05V)
- 462 administrative interpretation of comprehensive plan correcting a "Wetlands" designation (FMB-01-06A, 3/12/01, ADD2000-00152); variance to 15' for street setback with conditions (89-7-13-V-4, 6/1/89)
- 463 variance to allow dock to extend 150', with conditions (90-11-15-V-5, 11/15/90)
- 465 variance to 90' for lot depth (Z-77-56, 3/14/77, 77-2-14)
- 466 variance to 90' for lot depth (Z 77-54, 3/14/77, 77-2-12)
- 468 variance to 5' for front yard fence height (BZA-88-232, 8/15/88, 88-8-27)
- 473 variance to 21' and to 18' for water setbacks, with conditions (BZA-88-367, 12/19/88, 88-12-22)
- 474 variances to 60' for lot width and to 7,200 SF for lot area (90-7-5-V-1, 7/5/90)
- 478 variance to legitimize existing shed, with conditions (89-1-HE-3, 1/12/89)
- 479 variance to 5' for side setback with conditions (91-3-14-V-3, 3/14/91)
- 480 variance to 25' for lot width with conditions (FMB-00-24, 6/5/00, VAR2000-00011)
- 482 special permit for COP/outdoor seating with conditions (93-04-29-SP-03, 4/29/93); special exception for COP with conditions (ZAB-85-271, 11/12/85, 85-9-38)
- 487 administrative interpretations of comprehensive plan vesting 5 stories over 1 story of parking up to 79.8' NGVD and invalidating two prior staff decisions (FMB-00-40, 11/13/00, CPA2000-00001); administrative interpretations of comprehensive plan correcting a "Wetlands" designation and finding final 64 dwelling units as approved in Exemption #83-09-120.00E to be consistent with the plan (FMB-00-39, 11/13/00, CPA2000-00001)
- 488 variance to 14' and 21.7' for water setbacks and variance to 7.5' for rear setback, as shown on site plan (FMB-00-25a, 6/12/00, VAR2000-00015)
- 489 administrative interpretation of LDC upheld: PD zoning required for new or expanded commercial activities (FMB-00-33, 9/11/00, ADM2000-00024)
- 490 variance to 21.5' for water setback (FMB-02-11, 3/11/02, VAR1999-00024)
- 491 variance from CCCL as shown on site plan (FMB-02-16, 4/8/02, VAR2002-00001)
- 492 administrative interpretation of LDC overturned: house permit to be issued after covenant is recorded (FMB-02-17, 4/8/02, ADM2002-00001)
- 493 rezoned to CPD (bed-and-breakfast inn) with site plan and conditions (FMB-04-04, 2/9/04, DCI2003-00051); administrative interpretation of LDC upheld (FMB-02-36, 9/16/02, ADM2002-00011)

- 494 variances to 15' for water setback and 1.5' for side setback, with conditions (FMB-97-23, 7/7/97, 97-08-063.05V)
- 495 addendum to stipulated settlement agreement (5/19/03); amendment to stipulated settlement agreement (3/30/01); stipulated settlement agreement resolving Bay Beach litigation (99-1042-CA-JBR, 2/23/01); legislative interpretation of LDC for Bay Beach (FMB-99-27, 7/1/99, 99-05-085.07S); variance to lower by 5 the number of parking spaces required (FMB-98-32, 12/14/98, 95-02-206.05V 02.01)
- 496 requested RM-2 zoning denied (FMB-99-12, 3/8/99, 98-12-279.01Z 01.01)
- 497 variance to 19.7 for water setback (FMB-99-25, 6/21/99, 99-05-096.05V 01.01)
- 498 variance to allow wet floodproofing for garage and public restrooms (FMB-99-30, 8/30/99, 99-09-158.12V)
- 499 variance to 5' for rear setback as shown on site plan (FMB-00-06, 1/10/00, VAR1999-00016)
- 500 variances to 10' for street setback and 9' for rear setback, with conditions (FMB-99-32, 7/20/99, 99-05-102-05V)
- 501 variance to eliminate required sprinkler system in existing portion of expanded three-story structure (FMB-02-10/10A, 4/15/02, ADM2001-00013); variances to 45' & 50' for lot width, 13' for water setback, 4' for side setback, with conditions (FMB-01-20, 6/25/01, VAR2000-00076)
- 502 variances to 15' for rear setback and to 5' for side setback (BoA-1, 5/9/77, 77-4-1)
- 503 addendum to stipulated settlement agreement (5/19/03); amendment to stipulated settlement agreement (3/30/01); stipulated settlement agreement resolving Bay Beach litigation (99-1042-CA-JBR, 2/23/01); legislative interpretation of LDC for Bay Beach (FMB-99-27, 7/1/99, 99-05-085.07S); administrative interpretation of LDC overturned: Waterside III can exceed current height limit based on equitable estoppel (Z-98-34, 12/14/98, 98-03-010.07S)
- 504 administrative approval for COP/outdoor seating with conditions (COP2002-00013, 3/13/02)
- 601 variances to 10' for setback (N) and to 27' for setback (S) for pool and deck, with conditions (FMB-03-04, 3/17/03, VAR2002-00042)
- 602 variance to 4.4' for side setback with conditions (FMB-03-14, 5/12/03, VAR2002-00054)
- 603 variance to 4.5' for side setback with conditions (FMB-03-15, 5/19/03, VAR2003-00004)
- 604 variances to 20' for water setback and 15' for rear setback, with conditions (FMB-03-16, 5/19/03, VAR2002-00048)
- 605 variance to 7.5' for water setback with conditions (FMB-03-17, 5/12/03, VAR2003-00002)
- 606 administrative interpretation of LDC upheld (FMB-03-18, 5/12/03, ADM2003-00003); administrative variance to 5' for side setback with conditions (ADD2002-00126, 10/11/02)
- 607 variance to 2' for boathouse side setback (FMB-03-19, 6/9/03, VAR2003-00015)
- 608 rezoned to RPD with site plan and conditions (FMB-03-20, 6/9/03, DCI2003-00006)
- 609 special exception for bed-and-breakfast inn with conditions (FMB-03-21, 6/9/03, SEZ2003-00007)
- 610 variance to 16.5' for water setback with conditions (FMB-03-24, 3/30/03, VAR2003-00023); variance to 62.5' for lot width (FMB-01-02, 1/22/01, VAR2001-00071)
- 611 variances to 1' for side (N) setback, to 2' for side (S) setback, and to 1' for rear setback for a deck, with conditions (FMB-03-37, 10/20/03, VAR2003-00042)
- 612 variance for street setback denied (FMB-03-39, 12/8/03, VAR2003-00040)
- 614 variances to allow resubdivision without meeting ROW and cul-de-sac requirements, with conditions (FMB-04-02, 1/26/04, VAR2003-00069)
- 615 variances to 21' for water setback and to 6' for side setback, with conditions (FMB-04-03, 2/9/04, VAR2003-00062)
- 616 administrative approval for designated historic resource to provide relief to 6' for side setback and to 17' for water setback, with conditions (ADD2003-00045, 6/24/03)

EXHIBIT B: DESCRIPTION OF ZONING DISTRICTS

<u>ZONING DISTRICT</u>	<u>DETAILS IN:</u>
<u>Conventional Zoning Districts:</u>	
RS – Residential Single-Family	§ 34-642
RC – Residential Conservation	§ 34-643
RM – Residential Multifamily	§ 34-644
CR – Commercial Resort	§ 34-645
CM – Commercial Marina	§ 34-646
CO – Commercial Office	§ 34-647
SANTOS	§ 34-648
IN – Institutional	§ 34-649
CF – Community Facilities	§ 34-650
BB – Bay Beach	§ 34-651
EC – Environmentally Critical	§ 34-652
<u>Redevelopment Zoning Districts:</u>	
DOWNTOWN	§ 34-671–680
SANTINI	§ 34-681–690
VILLAGE	§ 34-691–700
CB – Commercial Boulevard	§ 34-701–710
<u>Planned Development Zoning Districts:</u>	
RPD – Residential Planned Development	§ 34-941–950
CPD – Commercial Planned Development	§ 34-951–960

RESOLUTION OF THE TOWN COUNCIL OF
THE TOWN OF FORT MYERS BEACH, FLORIDA

RESOLUTION NUMBER 04-17

A RESOLUTION OF THE TOWN OF FORT MYERS BEACH ADOPTING A HISTORIC ZONING MAP THAT REFLECTS THE ZONING DISTRICTS THAT APPLIED TO ALL PROPERTY IN THE TOWN PRIOR TO THE APPROVAL OF ORDINANCE 03-03 ON MARCH 3, 2003, AND ALSO REFLECTING ALL OTHER ZONING RESOLUTIONS ADOPTED BY LEE COUNTY AND THE TOWN OF FORT MYERS BEACH THROUGH THAT DATE.

WHEREAS, the Town of Fort Myers has adopted Ordinance 03-03 providing a new zoning chapter (Chapter 34) for the town's land development code; and

WHEREAS, Division 1 of Article III of the zoning chapter provides the procedures for adopting zoning maps; and

WHEREAS, Section 34-614 of the new land development code mandates the adoption by resolution of an official zoning map to reflect the new zoning district boundaries adopted by Ordinance 03-03's "interim zoning map" and to also reflect past approvals of variances, special exceptions, special permits, and similar approvals that have not expired or believed to have become obsolete or unnecessary due to changed regulations or conditions; and

WHEREAS, public hearings were legally and properly advertised to consider the adoption of the Official Zoning Map; and

WHEREAS, a public hearing was held before the Local Planning Agency (LPA) on April 20, 2004, when the LPA gave full and complete consideration to the recommendations provided and to any public testimony; and

WHEREAS, as a result of that consideration the LPA recommended that the Town Council approve a resolution containing the Official Zoning Map (04-16) and also approve this second resolution containing a "Historic Zoning Map" that shows the zoning districts and other approvals that were in effect up until March 3, 2003; and

WHEREAS, public hearings were held by the Town Council on May 17, 2004, at which time the Town Council considered zoning approvals of Lee County and the Town of Fort Myers Beach prior to the adoption of Ordinance 03-03, the recommendations provided to the Town Council, and any public testimony.


NOW THEREFORE BE IT RESOLVED that the Town of Fort Myers hereby adopts Exhibit A as the Historic Zoning Map. This Historic Zoning Map shows the zoning districts that applied to all properties immediately prior to the adoption of Ordinance 03-03 and all variances, special exceptions, special permits, and similar approvals that had been approved by Lee County or the Town of Fort Myers Beach prior to the adoption of Ordinance 03-03. This map provides a historic record of past zoning actions and prior zoning status that may affect the nonconforming status of certain properties within the town. Exhibit A contains eleven map sheets that show the pre-existing zoning districts and additional key numbers that are explained by thirteen pages of notes that provide a history of prior rezonings, variances, special exceptions, special permits, and similar approvals that had been approved before Ordinance 03-03 was adopted on March 3, 2003.

The foregoing resolution was adopted by the Fort Myers Beach Town Council upon a motion by Council Member Rynearson which was seconded by Council Member Van Duzer. Upon being put to a vote, the result was as follows:

Bill Thomas	aye
Garr Reynolds	aye
Don Massucco	aye
Howard Rynearson	aye
W. H. "Bill" Van Duzer	aye

DULY PASSED AND ENACTED this 17th day of May, 2004.


ATTEST:

By: 
Marsha Segal-George, Town Clerk

TOWN OF FORT MYERS BEACH

By: 
Bill Thomas, Mayor

Approved as to form by:



Richard V.S. Roosa, Town Attorney



Display A - of part layers: District - District, Zoning Map
for other part: 100-1, 100-2

Zoning districts are in bold type
Map numbers are explained in table

CF-3



2. Plan of Fort Myers Beach Historic Zoning Map

Zoning districts are in light type
Key numbers are explained in text




Exhibit A - Fort Myers Beach Historic Zoning Map
(in effect until March 3, 2003)

-- Zoning districts are in bold type --
-- Key numbers are explained in table --






Exhibit A - Fort Myers Beach Historic Zoning Map

(in effect until March 3, 2003)

- Zoning districts are in bold type -
- Key numbers are explained in table -



AO-2




Exhibit A - West Haven Beach Historic Zoning Map
 to amend Ordinance 2003
 Zoning districts are in bold type
 Key numbers are explained in table.






Exhibit A - Fort Myers Beach Historic Zoning Map

(in effect until March 3, 2003)

- Zoning districts are in bold type -
- Key numbers are explained in table -



AG-2

AG-2





Exhibit A - Fort Myers Beach Historic Zoning Map
(in effect until March 1, 2003)






Exhibit A - Fort Myers Beach Historic Zoning Map
(in effect until March 3, 2003)

- Zoning districts are in bold type -
- Key numbers are explained in table -

- 0 ORIGINAL AG-2 ZONING, AFTER CONVERSION FROM AG & GU.
- 1 ASV-96-11, 9/4/96, 96-08-163.09A, ADM VAR FOR SB TO 14 FT PER SP.
- 2 ZB-85-248, 11/25/85, 85-9-15, VAR FM REQ MIN SB FM CANAL OR WTRBY TO 2', W/COND, STRUCT NOT BE CONNECTED TO BOAT HOUSE OR UTILIZED AS A SEPARATE ROOM.
- 3 FMB-99-46, 12/13/01, 99-09-245.01S 01.01, 2 COP FOR THE BCH MOVIE THEATER W COND; FMB-98-07, 4/6/98, 98-01-227.07S, ADMIN INTERP UPHELD; Z-79-313, 11/26/79, 79-11-20, DBC FM RM-2 TO CS, W/STIP THE ONLY ENTRANCE BE FM CURLEW ST W/NO ACCESS TO ESTERO BLVD. (CS-1, AS CONVERTED).
- 4 ORIGINAL RM-2 ZONING, AFTER CONVERSION FROM RU-3.
- 5 FMB-99-46, 12/13/01, 99-09-245.01S 01.01, 2 COP FOR THE BCH MOVIE THEATER W COND; Z-68-92, 68-7-5, 8/28/68, DBC FM RU-1 TO RU-3A (RS-1 & CT, AS CONVERTED).
- 6 93-11-04-V-01, 11/4/93, VAR IN THE RS-1 DIST FM ST SB TO 15 FT, SUBJ TO CONDS.
- 7 Z-64-29, 5/27/64, 64-4-2, DBC FM RU-2 TO RU-3 (TFC-2 & RM-2, AS CONVERTED).
- 8 Z-81-486, 11/23/81, 81-11-16, VAR FOR ACCESS STRUCT (TEN CTS) IN FR 50% OF PROP, W/STIP PROJECT CONSTRUCTED PER SP ON FILE; Z-64-29, 5/27/64, 64-4-2, DBC FM RU-2 TO RU-3 (TFC-2 & RM-2, AS CONVERTED).
- 9 ZB-83-59, 3/1/83, 83-2-33, SPEC EX FOR 1 MODH, LMTD TO 1 YR & VAR TO EXTEND TEMP SALES OFFICE PERMIT FOR 1 YR, W/COND NO REALES OR PERM MANAGEMENT OPERATIONS BE CONDUCTED FM THAT OFFICE; Z-71-116, 8/3/71, 71-6-18, DBC FM RU-3 TO RU-3A ON FIRST 250' FM ESTERO BLVD; REMAINING PROP WILL STAY RU-3 (RM-2 & CT, AS CONVERTED).
- 10 90-4-12-V-7, 4/12/90, VAR RS-1 DIST FM MIN REQ WAT SB OF 25FT TO 15FT.
- 13 FMB-97-21, 6/2/97, 97-03-111.05V, 6 FT SB VAR FOR GARAGE, VAR LOTS 33, 34.
- 14 Z-81-469, 10/26/81, 81-10-32, VAR FOR ACCESS STRUCTS W/ FR 50% OF LOT W/STIP PER SP-81-469.
- 15 ZB-83-59, 3/1/83, 83-2-33, SPEC EX FOR 1 MODH, LMTD TO 1 YR & VAR TO EXTEND TEMP SALES OFFICE PERMIT FOR 1 YR, W/COND NO REALES OR PERM MANAGEMENT OPERATIONS BE CONDUCTED FM THAT OFFICE; Z-71-116, 8/3/71, 71-6-18, DBC FM RU-3 TO RU-3A ON FIRST 250' FM ESTERO BLVD; REMAINING PROP WILL STAY RU-3 (RM-2 & CT, AS CONVERTED).
- 17 Z-69-3, 1/8/69, 68-10-10, DBC FM RU-1 TO RU-3, W/COND & RESTRICT (RS-1 & RM-2, AS CONVERTED).
- 18 FMB-97-34, 9/7/97, 97-08-063.05V, VARS SUBJ TO CONDS; FMB-97-10, 3/17/97, 96-09-166-02S, SPEC PER FOR COP, SUBJ TO CONDS (CT PER BOARD ACTION 10-20-82); Z-74-279, 9/9/74, 74-8-5, DBC FM RU-3 TO BU-1A (RM-2 & C-1A, AS CONVERTED).
- 19 ZAB-83-347, 11/14/83, 83-9-6, VAR FM REQ APVL 30' SB PER RESOL Z-79-206 TO AN ADDL 8' HGT PER ORD 72-9; ZAB-82-227, 9/20/82, 82-6-25, VAR FM REQ SB TO 3' ON TEN CT, VAR TO ALLOW PK ON SIDE SB (TO N OF PROP), VAR FOR SB OF WTRBY (POND) FM PVT BLDG STRUCT; Z-79-206, 8/20/79, 79-7-40, VAR FOR 30' SB ON N PROP LINE.
- 20 Z-70-119, 9/1/70, 70-7-4, VAR FOR SB FOR PROP.
- 21 VAR OF 4' FR & 1.5' SIDE, GRANTED 5-4-77.
- 22 Z-93-072, 11/15/93, 91-10-15-DCI-1(b), APVD AMEND TO RPD, SUBJ TO CONDS; Z-91-102, 12/9/91, 91-10-15-DCI-1, DBC FM RS-1 & CT TO RPD, SUBJ TO CONDS; Z-70-140/140A, 10/6/70, 70-8-8, SPEC PER FOR MED CNTR & SPEC PER FOR CONVALESCENT/NURSING HOME & COR TO DBC FM RU-1 TO RU-3A W/COND & BU-1A (RS-1, CT & C-1A, AS CONVERTED).
- 23 ORIGINAL RS-1 ZONING, AFTER CONVERSION FROM RU-1.
- 24 Z-93-072, 11/15/93, 91-10-15-DCI-1(b), AMEND RPD SUBJ TO CONDS; PD-92-020, 12/12/92, 91-10-15-DCI-1(a), ADMIN APVL TO AMEND RPD, SUBJ TO CONDS; Z-91-102, 12/9/91, 91-10-15-DCI-1, DBC FM RS-1 & CT TO RPD, SUBJ TO CONDS; Z-70-140/140A, 10/6/70, 70-8-8, SPEC PER FOR MED CNTR & SPEC PER FOR CONVALESCENT/NURSING HOME & COR TO DBC FM RU-1 TO RU-3A W/COND & BU-1A (RS-1, CT & C-1A, AS CONVERTED).
- 26 Z-81-448, 11/16/81, 81-10-8, DBC FM NONE TO PR (EC, AS CONVERTED) (INITIAL ZONING FOR LITTLE ESTERO ISLAND).
- 27 Z-70-140/140A, 10/6/70, 70-8-8, SPEC PER FOR MED CNTR & SPEC PER FOR CONVALESCENT/NURSING HOME & COR TO DBC FM RU-1 TO RU-3A W/COND & BU-1A (RS-1, CT, & C-1A, AS CONVERTED).
- 28 Z-70-140/140A, 10/6/70, 70-8-8, SPEC PER FOR MED CNTR & SPEC PER FOR CONVALESCENT/NURSING HOME & COR TO DBC FM RU-1 TO RU-3A W/COND & BU-1A (RS-1, CT, & C-1A, AS CONVERTED).
- 29 Z-70-115, 8/4/70, 70-6-13, DBC FM RU-1 TO BU-1A FOR MED CNTR & SUPPORTING RELATED

BUSINESS ENTERPRISES (RS- & C-1A, AS CONVERTED).

- 30 Z-82-12, 2/15/82, 82-1-19, VAR FOR PK AREA IN SIDE YARD SB & VAR FOR POOL/RESTROOM/TEN CT IN FR 50% OF LOT, PER SP-82-12; Z-71-86, 7/6/71, 71-5-3, DBC FM RU-1 TO BU-1 & RU-3 W/COND.
- 31 Z-82-12, 2/15/82, 82-1-19, VAR FOR PK AREA IN SIDE YARD SB & VAR FOR POOL/RESTROOM/TEN CT IN FR 50% OF LOT, PER SP-82-12; Z-71-86, 7/6/71, 71-5-3, DBC FM RU-1 TO BU-1 & RU-3 W/COND.
- 32 Z-88-291, 11/14/88, 88-10-10, DBC FM RM-2 TO CT; SPEC PER FOR COP, SPEC PER FOR BAR/COCKTAIL LOUNGE & VAR FM SEPARATION FM RES DWELLING FOR ESTABLISHMENTS SERVING ALCOHOLIC BEVERAGES, W/COND.
- 33 3/30/01, AMEND STIP SETTLE AGR; 99-1042-CA-JBR, 2/23/01, STIP SETTLE AGR; FMB-99-27, 7/1/99, 99-05-085.07S, LEG INTERP OF LDC; Z-72-243, 10/10/72, 72-9-27, DBC FM BU-1, RU-3, RU-3A RU-1 TO BU-4 & RU-4 TO OPERATE UNDER COMMUNITY UNIT PLAN, FOR SLO (C-1, RM-2, CT & RS-1, AS CONVERTED).
- 34 3/30/01, AMEND STIP SETTLE AGR; 99-1042-CA-JBR, 2/23/01, STIP SETTLE AGR; FMB-99-27, 7/1/99, 99-05-085.07S, LEG INTERP OF LDC; 94-08-11-V-01, 8/11/94, 94-08-11-V-01, VAR IN THE RM-2 DIST FM WAT SB TO 10 FT SUBJ TO CONDS; Z-72-243, 10/10/72, 72-9-27, DBC FM BU-1, RU-3, RU-3A RU-1 TO BU-4 & RU-4 TO OPERATE UNDER COMMUNITY UNIT PLAN, FOR SLO (C-1, RM-2, CT & RS-1, AS CONVERTED).
- 35 ZB-83-358, 9/26/83, 83-9-19, VAR FOR MIN SB FM CANAL TO 5' & VAR FOR MIN SB FM ST ROW TO 0', W/COND; Z-72-243, 10/10/72, 72-9-27, DBC FM BU-1, RU-3, RU-3A & RU-1 TO BU-4 & RU-4 TO OPERATE UNDER COMMUNITY UNIT PLAN, FOR SLO (C-1, RM-2, CT & RS-1, AS CONVERTED); Z-69-40, 3/5/69, 69-1-20, DBC FM RU-1 TO RU-3A & RU-3 (RS-1, CT & RM-2, AS CONVERTED).
- 36 ZB-83-69, 3/1/83, 83-2-45, SPEC EX FOR PUBLIC/PVT UTILITY SVC & RELATED FAC (WATER RESERVOIR); Z-72-243, 10/10/72, 72-9-27, DBC FM BU-1, RU-3, RU-3A & RU-1 TO BU-4 & RU-4 TO OPERATE UNDER COMMUNITY UNIT PLAN, FOR SLO (C-1, RM-2, CT & RS-1, AS CONVERTED); Z-69-40, 3/5/69, 69-1-20, DBC FM RU-1 TO RU-3A & RU-3.
- 37 AA-COP-94-011, 6/15/94, ADMIN APVL IN THE CPD DIST FOR COP, SUBJ TO CONDS; Z-92-017, 6/15/92, 92-3-17-DCI-1, DBC FM CN-1 TO CPD TO ALLOW RETAIL CMRL USES SUBJ TO CONDS; Z-86-75, 6/23/86, 86-6-1, DBC FM CT TO CN (CN-1, AS CONVERTED).
- 39 FMB-97-35, 10/27/97, 96-12-206.02Z, APPV ECKERDS DRUGS FOR 11,200 SF COMM; FMB-97-24, 7/7/97, 96-12-206.02Z 01.01, DBC FM CT TO CPD W/CONDS; Z-69-40, 3/5/69, 69-1-20, DBC FM RU-1 TO RU-3A & RU-2 (CT AND RM-2, AS CONVERTED).
- 42 3/30/01, AMEND STIP SETTLE AGR; 99-1042-CA-JBR, 2/23/01, STIP SETTLE AGR; FMB-99-27, 7/1/99, 99-05-085.07S, LEG INTERP OF LDC; ZB-83-358, 9/26/83, 83-9-19, VAR FOR MIN SB FM CANAL TO 5' & VAR FOR MIN SB FM ST ROW TO 0', W/COND; Z-72-243, 10/10/72, 72-9-27, DBC FM BU-1, RU-3, RU-3A RU-1 TO BU-4 & RU-4 TO OPERATE UNDER COMMUNITY UNIT PLAN, FOR SLO (C-1, RM-2, CT & RS-1, AS CONVERTED); Z-69-40, 3/5/69, 69-1-20, DBC FM RU-1 TO RU-3A & RU-3 (RS-1, CT & RM-2, AS CONVERTED).
- 43 ASV-95-24, 11/28/95. 95-11-147.09A, ADM APPV OF VAR TO ALLOW STAIRS, SUBJ TO SITE PLAN.
- 44 3/30/01, AMEND STIP SETTLE AGR; 99-1042-CA-JBR, 2/23/01, STIP SETTLE AGR; FMB-99-27, 7/1/99, 99-05-085.07S, LEG INTERP OF LDC; Z-81-142, 4/27/81, 81-4-9, SPEC EX FOR OS SIGN W/VAR FOR SB FM FR SIDE & REAR PROP LINES & FM WATER; Z-72-243, 10/10/72, 72-9-27, DBC FM BU-1, RU-3, RU-3A RU-1 TO BU-4 & RU-4 TO OPERATE UNDER COMMUNITY UNIT PLAN, FOR SLO (C-1, RM-2, CT & RS-1, AS CONVERTED).
- 47 3/30/01, AMEND STIP SETTLE AGR; 99-1042-CA-JBR, 2/23/01, STIP SETTLE AGR; FMB-99-27, 7/1/99, 99-05-085.07S, LEG INTERP OF LDC; PD-98-66, 9/22/98, 95-02-206.13A, ADM APPV MULTI CHANGES, W/CONDS, SEE RESO; Z-72-243, 10/10/72, 72-9-27, DBC FM BU-1, RU-3, RU-3A RU-1 TO BU-4 & RU-4 TO OPERATE UNDER COMMUNITY UNIT PLAN, FOR SLO (C-1, RM-2, CT & RS-1, AS CONVERTED).
- 49 FMB-01-13, 6/4/01, VAR2001-00020, VAR TO ALLOW A 32 SQ FT OFF SITE SIGN FOR A BUSINESS LOCATED ON AN ADJACENT PROPERTY W COND; COP-97-008, 7/3/97, 96-12-068.01A, ADM APPV 4-COP, SUBJ TO CONDS; ZB-85-15, 1/28/85, 85-1-16, S & N INC, SPEC EX FOR COP W COND; Z-76-141/141A, 9/1/76, 76-7-19, SPEC PER FOR NICOLAS LIQUORS FOR WINE TASTING & A SPEC PER FOR PIZZAS & CREAM FOR COP FOR BEER & WINE.
- 51 Z-94-048, 12/5/94, 94-10-18-DRI-1, APPV DRI/DO FOR MULTI-SLIP DOCK FACILITY.
- 52 Z-94-013, 5/16/94, 88-09-08-DCI(c), APVD AN AMEND FOR CPD, FOR ADDIT CMRL USES, SUBJ TO CONDS; Z-88-268/268A, 10/24/88, 88-9-8 DCI, DBC FM C-1 & CT TO CPD W/COND, & COR COND #16 OF Z-88-268.
- 54 Z-74-366, 12/9/74, 74-11-18, VAR FOR LOT SIZE & SB ON DUPLEXES, W/STIP.
- 58 Z-94-013, 5/16/94, 88-09-08-DCI(c), APVD AN AMEND FOR CPD, FOR ADDIT CMRL USES, SUBJ TO

- CONDS; 93-12-09-SP-05, 12/9/93, SPEC PER IN THE CPD DIST FOR OUTDOOR SEATING, SUBJ TO CONDS; PD-90-011, 4/18/90, 88-9-8 DCI (b), TO REUSE COURSE LAYOUT, RETENTION LOC & BLDG LAYOUT W/COND; Z-89-43, 6/12/89, 88-9-8(A)DCI, AMEND CPD TO ALLOW JOINT PK AGREEMENT, W/COND; Z-88-268/268A, 10/24/88, 88-9-8 DCI, DBC FM C-1 & CT TO CPD W/COND, & COR COND #16 OF Z-88-268.
- 59 Z-81-244, 6/1/81, 81-5-42, VAR FOR ACCESS STRUCT IN FR 50% OF PROP & VAR FOR QTR SLS TO 0', W/STIP; Z-72-243, 10/10/72, 72-9-27, DBC FM BU-1, RU-3, RU-3A & RU-1 TO BU-4 & RU-4 TO OPERATE UNDER COMMUNITY UNIT PLAN, FOR SLO.
- 61 FMB-02-38, 10/14/02, ADM2002-00014, DECISION REVRSD IN REF TO CABANAS AT WATERSIDE; 3/30/01, AMEND STIP SETTLE AGR; 99-1042-CA-JBR, 2/23/01, STIP SETTLE AGR; FMB-99-27, 7/1/99, 99-05-085.07S, LEG INTERP OF LDC; PD-98-66, 9/22/98, 95-02-206.13A, ADM APPV MULTI CHANGES, W/CONDS, SEE RESO; Z-72-243, 10/10/72, 72-9-27, DBC FM BU-1, RU-3, RU-3A RU-1 TO BU-4 & RU-4 TO OPERATE UNDER COMMUNITY UNIT PLAN, FOR SLO (C-1, RM-2, CT & RS-1, AS CONVERTED).
- 62 ORIGINAL C-1A ZONING, AFTER CONVERSION FROM BU-1A.
- 63 ZB-83-401, 10/30/83, 83-10-40, SPEC EX FOR SIGN (PROJECT ID) W/COND.
- 64 Z-81-402, 9/28/81, 81-9-4, VAR FOR ACCESS STRUCT (POOL/CABANA) IN FR 50% OF PROP.
- 66 90-8-9-V-6, 8/9/90, VAR FM DOCK ORD TO ALLOW A SB OF 0', W/COND.
- 68 Z-64-79, 9/30/64, 64-8-14, DBC FM RU-1 TO RU-3 (RS-1 & RM-2, AS CONVERTED).
- 69 FMB-97-20, 6/2/97, 97-03-250.05V, VAR LOT 224 ONLY FOR 5 FT.
- 70 SP-88-45, 7/11/88, 88-7-SP-7, SPEC PER FOR MODIF OF ST SB TO HALF ROW PLUS 33' (TOTAL SB FM C/L TO 73')
- 71 SP-88-2, 1/11/88, 88-1-SP-2, SPEC PER FOR MODIF OF ST SB TO HALF ROW PLUS 25'.
- 72 SP-88-14, 2/8/88, 88-2-SP-9, SPEC PER FOR MODIF OF ST SB TO HALF ROW PLUS 25'.
- 73 SP-88-11, 2/8/88, 88-2-SP-6, SPEC PER FOR MODIF OF ST SB TO HALF ROW PLUS 25'.
- 74 SP-88-12, 2/8/88, 88-2-SP-7, SPEC PER FOR MODIF OF ST SB TO HALF ROW PLUS 25'.
- 75 SP-87-58, 11/30/87, 87-10-SP-3, SPEC PER FOR MODIF OF ST SB TO 65' (HALF ROW PLUS 25').
- 76 FMB-00-13, 3/13/00, 99-07-176.05V, VAR IN THE CCCL W COND.
- 80 90-1-25-V-1, 1/25/90, VAR TO ALLOW 119' DOCK W/COND
- 81 Z-79-71, 3/26/79, 79-3-24, VAR FM REQ SLS; Z-74-140, 4/8/74, 74-2-35, DBC FM GU TO RU-4, SLO, W/LMTD HGT RESTRICT OF 29' & MAX DENS OF 5 UPA.
- 82 FMB-96-13, 5/16/96, 96-03-224.05V, WATER SB VAR FM 25 TO 17FT; Z-79-71, 3/26/79, 79-3-24, VAR FM REQ SLS; Z-74-140, 4/8/74, 74-2-35, DBC FM GU TO RU-4, SLO, W/LMTD HGT RESTRICT OF 29 OF 5 UPA.
- 83 90-8-9-V-7, 8/9/90, VAR FM REQ MIN DEPTH OF 3' MEAN LOW WAT FOR SLIP LOC TO APPROX 2.5' SUBJ TO COND; Z-74-140, 4/8/74, 74-2-35, DBC FM GU TO RU-4, SLO, W/LMTD HGT RESTRICT OF 29 OF 5 UPA.
- 84 Z-74-140, 4/8/74, 74-2-35, DBC FM GU TO RU-4, SLO W/LMTD HGT RESTRICTION OF 29' & MAX DENS OF 5 UPA. (AG-2 & RM-2, AS CONVERTED).
- 85 89-10-26-V-2, 10/26/89, VAR TO ALLOW A DOCK 135' ON A 104' LOT, W/CONDS; Z-74-140, 4/8/74, 74-2-35, DBC FM GU TO RU-4, SLO, W/LMTD HGT RESTRICT OF 29' & MAX DENS OF 5 UPA.
- 86 90-2-15-V-7, 2/15/90, VAR FM DOCK ORD (DEPTH) TO 2.5'; Z-74-140, 4/8/74, 74-2-35, DBC FM GU TO RU-4, SLO, W/LMTD HGT RESTRICT OF 29.
- 88 Z-71-12, 2/2/71, 70-12-3, DBC FM RU-2 TO RU-3A, W/STIP BLDGS BE NO HIGHER THAN 2 STORY.
- 89 95-02-276.01S, 4/27/95, SPEC EX TO ALLOW ACC APT, SUBJ TO CONDS.
- 91 FMB-00-29, 6/29/00, VAR2000-00023, VAR TO PERMIT A 4.2 FT SIDE SB TO RECONSTRUCT A CARPORT W COND.
- 92 Z-75-185, 8/11/75, 75-7-20, VAR OF LOT DIMEN FOR 7,503 SQ FT LOT.
- 94 FMB-97-08, 3/17/97, 95-07-203.05V, VAR FOR REAR SB OF 20 TO 2.5 FT; 95-07-203.05V, 9/21/95, VAR FM REAR SB OF 20 FT TO 12.5 FT, DENIES VAR TO 2.5 FT, REQUIRES REMOVAL OF SUNDECK.
- 95 Z-81-19, 1/26/81, 81-1-21, DBC FM AG TO RM-1 (AG-2 & TFC-2, AS CONVERTED).
- 96 Z-81-324, 6/25/81, 81-6-63, DBC FM AG TO RM-1 (AG-2 & TFC-2, AS CONVERTED).
- 97 FMB-96-28, 10/21/96, 96-08-244-05V, VAR W/COND.
- 99 Z-94-045, 10/30/95, 94-09-27-Z-1, DBC FM RS-1 TO TF-1.

- 100 Z-77-55, 3/14/77, 77-2-13, DBC FM GU TO RU-2; VAR IN LOT SIZE PERMITTING A 90' DEPTH, SLO.
- 101 COP2002-00019, 3/18/02, APVD 2-COP IN REST.
- 103 SP-88-48, 8/8/88, 88-8-SP-3, SPEC PER FOR MODIF OF ST SB (FOR ARTERIAL RD W/O FR RD) FM REQ TO HALF ROW (32.5') PLUS 27.19' (TOTAL SB FM C/L TO 59.69').
- 104 ORIGINAL TFC-2 ZONING, AFTER CONVERSION FROM RU-2 & RM-1.
- 105 ORIGINAL MH-2 ZONING, AFTER CONVERSION FROM MHRP.
- 106 ASV-95-023, 10/30/95, 95-02-108.09A, ADM VAR APPVD FOR SETBACK FM 15 FT TO 2.6 FT, SUBJ TO CONDS.
- 108 Z-80-289, 9/22/80, 80-9-14, VAR FOR SIDE SB FM REQ TO 8', VAR FOR SIDE SB FM REQ TO 16', VAR FOR REAR SB FM REQ TO 20', & VAR FOR OFF ST PK FM REQ TO 21 SPACES.
- 109 Z-69-24(1), 1/22/69, 68-12-6, DBC FM RU-1 TO RU-3A (RS-1 & CT, AS CONVERTED).
- 110 Z-71-40, 4/6/71, 71-2-16, DBC FM RU-1 TO RU-2 ON FIRST 150' OF PROP CLOSEST TO ESTERO BLVD, DIVIDED INTO TWO 75' FRONTAGE LOTS, REMAINING 4TH LOT REMAINS RU-1 (RS-1 & TFC-2, AS CONVERTED).
- 113 Z-69-23, 1/22/69, 68-12-5, DBC FM RU-1 TO RU-3A (RS-1 & CT, AS CONVERTED).
- 114 Z-95-085, 12/18/95, 95-07-137.02Z, DBC FM RM-2 TO CPD 5.4 AC 144 ROOMS, 10000 SQ FT COMM, OUTRIGGER RESORT, SUBJ TO CONDS; ZAB-85-271, 11/12/85, 85-9-38, SPEC EX FOR COP W/CONDS.
- 115 FMB-01-39, 12/10/01, VAR2001-00030, APVD ST SB OF 16.7 FT TO CONSTRUCT TWO CAR GAR W COND.
- 117 BZA-87-021, 1/26/87, 87-1-27, VAR FOR MIN ST SB TO 10'; Z-76-46, 3/8/76, 76-2-12, DBC FM RU-1 1200 TO RU-2 900 W/STIP (RS-1 1200 & TFC-2 900, AS CONVERTED).
- 118 Z-78-12, 1/9/78, 77-12-9, SPEC PER FOR COP OF BEER & WINE, W/STIP.
- 119 Z-76-46, 3/8/76, 76-2-12, DBC FM RU-1 1200 TO RU-2 900 W/STIP (RS-1 1200 & TFC-2 900, AS CONVERTED).
- 121 89-1-HE-6, 1/19/89, SPEC EX FOR DRIVE-THRU FAC, W/COND; SP-88-44, 7/11/88, 88-7-SP-6, SPEC PER FOR MODIF OF ST SB TO HALF ROW + 25' (TOTAL SB FM C/L TO 50').
- 122 89-1-HE-6, 1/19/89, SPEC EX FOR DRIVE-THRU FAC, W/COND; SP-88-44, 7/11/88, 88-7-SP-6, SPEC PER FOR MODIF OF ST SB TO HALF ROW + 25' (TOTAL SB FM C/L TO 50'); Z-75-234, 11/10/75, 75-10-15, SPEC PER FOR OVERNIGHT ACCOMMODATIONS FOR ANIMALS AFTER SURGERY ONLY, INCL A VETERINARY CLINIC & EXCLUDING BOARDING.
- 124 89-1-HE-6, 1/19/89, SPEC EX FOR DRIVE-THRU FAC, W/COND.
- 125 Z-72-18, 2/1/72, 71-12-8, VAR FOR AN APT UNDER A DUPLEX.
- 126 91-10-17-SP-4, 12/11/91, SPEC PER FOR COP, SUBJ TO CONDS.
- 127 Z-81-187, 5/4/81, 81-4-53, VAR FOR POOL IN FR 50% OF PROP & VAR FOR 2 OS SIGNS.
- 128 ZB-84-95, 6/25/84, 84-4-10, SPEC EX FOR A CHURCH & RELATED FAC, VAR FOR MIN LOT AREA TO 39,000 SQ FT, VAR FOR MIN PK SP TO 212 (JOINT USE OF OS/OFF STREET PK) & SPEC EX FOR A SIGN.
- 130 Z-77-150, 6/14/77, 77-5-38, SPEC PER FOR A CHILD CARE CNTR.
- 131 Z-82-210, 6/28/82, 82-6-7, SPEC EX FOR HOME OCC, W/STIP.
- 132 FMB-99-47, 12/13/01, 99-09-214.05V, VAR FM STREET SB & SIDE SB W COND.
- 133 FMB-96-31, 11/18/96, 95-07032.02Z, NYMAN CPD REZONE DENIED; FMB-96-15, 2/9/96, 95-07032.02Z, NYMAN CPD REZONE DENIED.
- 134 FMB-02-41, 11/4/02, VAR2002-00023, REAR SB VAR APRVD FOR ESTERO BEACH CLUB EAST, SUBJ TO CONDS.
- 135 92-7-23-V-2, 7/23/92, VAR FM SIDE SB TO 7.5 FT & FM LOT WIDTH TO 51.50 FT & 50 FT, SUBJ TO CONDS.
- 136 94-04-07-SP-02, 4/14/94, SPEC PER FM ST SB (FOR ART RD) TO 0 FT, ALONG ESTERO BLVD, SUBJ TO CONDS.
- 137 Z-81-187, 5/4/81, 81-4-53, VAR FOR POOL IN FR 50% OF PROP & VAR FOR (2) OS SIGNS.
- 139 Z-73-174, 10/3/73, 73-10-3, SPEC PER FOR MH AT REAR OF FMB LIBRARY FOR WORK/STORG AREA (CO COMM MINUTES BK 54 PG 100, 10/3/73).
- 140 Z-90-131, 1/14/91, 90-12-4-Z-5, DBC FM RM-2 TO CF-3.
- 141 PUD-98-29, 8/4/98, 95-01-034.13A, ADM APPV TO CODIFY ALL APPROVALS, SUBJ TO CONDS;

- PUD-95-41, 12/22/95, 95-01-034.13A, ADM APPV TO ELIMINATE PORTION OF PINK SHELL ON BAY SIDE, SUBJ TO CONDS; Z-95-017, 11/6/95, 95-01-034.03Z, DBC FM RM-2 TO CPD, SUBJ TO CONDS; Z-93-057, 10/4/93, 83-9-12-DCI(d), AMEND FINAL PUD, SUBJ TO CONDS; PUD-93-014/014A, 6/30/93, 83-9-12-DCI(c), ADM AMEND TO FINAL PUD TO RELOCATE A SWIM POOL & SPA, AMEND FINAL PUD & CONFIRM PK REQ AT MIN OF 1.5 SP PER UNIT, SB OF 25 FT BETWEEN OTHER BLDG IN PHASE III & A 5 FT BUFFER ON THE SOUTH END OF THE PROPERTY IN PHASE III, SUBJ TO CONDS; PUD-91-010/010A, 11/15/91, 83-9-12-DCI(b), ADMIN AMEND TO FINAL PUD FOR REQ PK, TRANSFER OF DWELLING UNITS. COP, & CORRECTION OF RESO Z-82-170 SUBJ TO CONDS; ZAB-84-196/196A, 11/19/84, 83-9-12-DCI, FINAL PUD FOR PHASES II THROUGH V SUBJ TO CONDS & COR OF RES ZAB-84-196; Z-82-170, 6/21/82, 82-3-28, DBC FM RM-2 TO PRELIM PUD, SUBJ TO CONDS.
- 142 FMB-99-07, 2/22/99, 95-01-034.03Z 03.01, AMEND THE CPD TO REMOVE 7 UNITS FOR TRANSFER TO CASA PLAYA, SUBJ TO CONDS; Z-95-017, 11/6/95, 95-01-034.03Z, DBC FM RM-2 TO CPD, SUBJ TO CONDS.
- 144 FMB-00-07/07a, 1/10/00, 95-01-034.03Z 03.01, AMEND CPD & PUD W COND; COR OF CPD LEGAL DESC; FMB-99-07, 2/22/99, 95-01-034.03Z 03.01, AMEND THE CPD TO REMOVE 7 UNITS FOR TRANSFER TO CASA PLAYA, SUBJ TO CONDS; PUD-95-41, 12/22/95, 95-01-034.13A, ADM APPV TO ELIMINATE PORTION OF PINK SHELL ON BAY SIDE, SUBJ TO CONDS; Z-95-017, 11/6/95, 95-01-034.03Z, DBC FM RM-2 TO CPD, SUBJ TO CONDS; PUD-91-010/010A, 11/15/91, 83-9-12-DCI(b), ADMIN AMEND TO FINAL PUD FOR REQ PK, TRANSFER OF DWELLING UNITS. COP, & CORRECTION OF RESO Z-82-170 SUBJ TO CONDS; ZAB-84-196/196A, 11/19/84, 83-9-12-DCI, FINAL PUD FOR PHASES II THROUGH V SUBJ TO CONDS & COR OF RES ZAB-84-196; Z-82-170, 6/21/82, 82-3-28, DBC FM RM-2 TO PRELIM PUD, SUBJ TO CONDS.
- 146 FMB-01-26, 08/27/01, DCI2000-00071, DBC FR RM-2 TO MPD SUBJ TO CONDS.
- 147 FMB-01-21, 6/25/01, DCI2001-00027, AMEND PUD & CPD SUBJ TO CONDS; FMB-00-07/07a, 1/10/00, 95-01-034.03Z 03.01, AMEND CPD & PUD W COND; COR OF CPD LEGAL DESC; PUD-98-29, 8/4/98, 95-01-034.13A, ADM APPV TO CODIFY ALL APPROVALS, SUBJ TO CONDS; PUD-95-41, 12/22/95, 95-01-034.13A, ADM APPV TO ELIMINATE PORTION OF PINK SHELL ON BAY SIDE, SUBJ TO CONDS; Z-93-057, 10/4/93, 83-9-12-DCI(d), AMEND FINAL PUD, SUBJ TO CONDS; PUD-93-014/014A, 6/30/93, 83-9-12-DCI(c), ADM AMEND TO FINAL PUD TO RELOCATE A SWIM POOL & SPA, AMEND FINAL PUD & CONFIRM PK REQ AT MIN OF 1.5 SP PER UNIT, SB OF 25 FT BETWEEN OTHER BLDG IN PHASE III & A 5 FT BUFFER ON THE SOUTH END OF THE PROPERTY IN PHASE III, SUBJ TO CONDS; PUD-91-010/010A, 11/15/91, 83-9-12-DCI(b), ADMIN AMEND TO FINAL PUD FOR REQ PK, TRANSFER OF DWELLING UNITS. COP, & CORRECTION OF RESO Z-82-170 SUBJ TO CONDS; ZAB-84-196/196A, 11/19/84, 83-9-12-DCI, FINAL PUD FOR PHASES II THROUGH V SUBJ TO CONDS & COR OF RES ZAB-84-196; Z-82-170, 6/21/82, 82-3-28, DBC FM RM-2 TO PRELIM PUD, SUBJ TO CONDS.
- 148 Z-77-104, 5/9/77, 77-4-15, DBC FM RU-2 TO RU-3 (TFC-2 & RM-2, AS CONVERTED).
- 154 ZAB-83-353, 11/14/83, 83-9-12 DCI, FINAL PUD SITE PLAN APVL FOR PHASE I; Z-82-170, 6/21/82, 82-3-28, DBC FM RM-2 TO PRELIM PUD, SUBJ TO CONDS
- 155 FMB-01-20, 6/25/01, VAR2000-00076, 3 VAR W COND.
- 158 Z-81-58, 2/23/81, 81-2-13, VAR FOR ACCESS USE W/I FR 50% OF PROP, W/STIPS.
- 160 ASV-96-006, 5/6/96, 96-03-107.09A, ADM VARS FOR SIDE SB, SUBJ TO CONDS.
- 161 ASV-94-005, 11/21/94, MULTI VARS FOR SB, SUBJ TO CONDS.
- 162 FMB-98-09, 4/20/98, 98-01-078.05V, VAR FOR DECK, W/CONDS.
- 163 ASV-95-07, 3/1/95, 95-02-107.09A, ADM SB VARS FROM 10 FT TO 5.6 AND 6.25 FT, SUBJ TO SITE PLAN; Z-64-54, 8/26/64, 64-7-1, DBC FM RU-1 TO EU (RS-1 & RS-2, AS CONVERTED).
- 164 FMB-99-08, 2/22/99, 95-07-043.02Z 02.01, AMEND CPD FOR 7 ADDT HOTEL UNITS, SUBJ TO CONDS; Z-95-075, 11/6/95, 95-07-043.02Z, CPD, DBC FM RM-2 AND CPD TO CPD, SUBJ TO CONDS; Z-93-034, 8/2/93, 93-06-01-DCI-01, DBC FM RM-2 TO CPD, SUBJ TO CONDS.
- 165 Z-82-51, 2/22/82, 82-2-33, VAR FOR ACCESS STRUCT (SWIM POOL) IN FR 50% OF LOT, W/COND.
- 166 ZB-84-290, 1/21/85, 84-12-19, SPEC EX FOR DAY CARE CNTR & SPEC EX FOR OS SIGN, W/STIP.
- 167 BZA-88-077, 4/18/88, 88-3-26, VAR FOR MIN REAR SB TO 1' & VAR FOR SIDE SB TO 0', W/COND.
- 169 FMB-02-27, 6/24/02, VAR2001-00032, APRVL OF VARIANCES, SUBJ TO CONDS.
- 173 Z-76-212, 11/16/76, VAR FOR MIN SQ FT IN LOT SIZE & ALLOW THIS LOT TO BE DIVIDED INTO (7) LOTS, W/STIP.
- 174 BZA-88-140, 6/20/88, 88-5-33, VAR FOR ST SB TO HALF ROW (7.5') + 4.5' (TOT SB TO 12') (TRACTS 4 & 6), MIN REAR SB TO 10' (TRACTS 4 & 6) MIN LOT WIDTH TO 50' (TRACT 4), MIN LOT WIDTH TO 67.5' (TRACT 6), MIN LOT DEPTH TO 50' (TRACTS 4 & 6) & MIN SIDE SB TO 5' (FOR EA SIDE TRACT 4), W/COND; Z-76-212, 11/16/76, VAR FOR MIN SQ FT IN LOT SIZE & ALLOW THIS LOT TO BE DIVIDED INTO (7) LOTS, W/STIP.

- 175 Z-76-163, 9/29/76, 76-9-29, VAR FOR MIN SQ FT, W/COND & VAR TO SUBD REG TO ALLOW ACCESS TO ST BY MEANS OF PERPETUAL ESMT, W/COND.
- 176 BZA-88-141, 6/20/88, 88-5-34, VAR FOR ST SB TO HALF ROW (7.5FT) + 4.5FT (TOT SB TO 12FT) VAR FOR MIN REAR SB TO 10', VAR FOR MIN LOT WIDTH TO 60' & VAR FOR MIN LOT DEPTH TO 50', W/COND; Z-76-163, 9/29/76, 76-9-29, VAR FOR MIN SQ FT, W/COND & VAR TO SUBD REG TO ALLOW ACCESS TO ST BY MEANS OF PERPETUAL ESMT, W/COND.
- 177 Z-80-232, 8/25/80, 78-2-13, UPHOLDING ORIG GRANT OF Z-78-53, 78-2-13; Z-78-53, 2/27/78, 78-2-13, DBC FM RM-1 TO RM-2 W/STIP & COND (TFC-2, AS CONVERTED).
- 178 95-08-061.02S, 10/5/95, SPEC PER W/ OUTDOOR SEATING, W/CONDS; Z-80-3, 2/18/80, 80-1-3, REMOVE STIP THAT PROP BE LMTD TO 6 UNITS; Z-79-279, 10/22/79, 79-10-13, DBC FM RS-1 TO RM-2, W/STIP.
- 179 ZB-82-414, 10/25/82, 82-10-13, VAR FOR MIN FR SB TO 12 FT & VAR FOR MIN REAR SB TO 10 FT; Z-76-163, 9/29/76, 76-9-29, VAR FOR MIN SQ FT W/COND & VAR TO SUBD REG TO ALLOW ACCESS TO ST BY MEANS OF PERPETUAL ESMT. W/COND.
- 180 Z-68-82, 5/22/68, 68-4-9, VAR ON SB, W/STIP.
- 181 95-08-061.02S, 10/20/95, SPEC PER FOR COP W/ OUTDOOR SEAT, SUBJ TO CONDS.
- 184 Z-73-39, 2/28/73, 73-1-5, UU FOR CONST OF 2 STEEL GRND LEVEL WAT STORG TANKS & METAL BLDGS W/WAT PUMPING FAC & CONTROLS.
- 185 FMB-00-16, 4/10/00, VAR1999-00028, SB VAR FOR SIDE YD TO 0 FT, REAR SB TO 7 FT, & STREET SB TO 4.5 FT W COND.
- 186 Z-75-197, 9/8/75, 75-8-6, VAR IN SETBACKS, W/STIPS.
- 188 FMB-01-08, 4/9/01, DCI2000-00059, DBC FM C-1 TO CPD W COND; COP-94-013, 9/13/94, ADMIN AMEND FOR COP IN REST, WITH CONDS.
- 189 Z-64-54, 8/26/64, 64-7-1, DBC FM RU-1 TO EU (RS-1 & RS-2, AS CONVERTED).
- 191 Z-62-28, 10/17/62, 62-9-3, VAR TO PERMIT REPAIRS OF PVT OWNED BOATS.
- 192 ADD2002-00115, 10/4/02, ADMIN APRVL TO AMEND CPD TO RELOCATE SWIM POOL, WITH CONDS; FMB-99-05, 2/8/99, 95-01-003.02Z 02.01, DBC FM CPD AND C-1 TO CPD, SUBJ TO CONDS; Z-95-074, 11/6/95, 95-01-003.02Z, DBC FM C-1, RM-2, CP TO CPD, APPV COP W/ OUTDR SEAT, SUBJ TO CONDS; 95-01-003.02S, 1/6/95, COP WITH OUTDR SEAT, W/CONDS; 89-10-12-V-4, 10/12/89, VAR TO PER MIT A ROOF SIGN, W/COND; ZB-83-380, 10/24/83, 83-10-18, SPEC EX FOR COP.
- 193 FMB-01-33, 10/15/01, VAR2001-00023, SEVERAL VAR W COND.
- 194 Z-71-71, 6/1/71, 71-4-13, DBC FM RU-2 TO RU-3 (TFC-2 & RM-2, AS CONVERTED).
- 196 94-02-10-V-02, 2/10/94, VAR FM WAT SB TO 0 FT, SUBJ TO COND; Z-62-28, 10/17/62, 62-9-3, VAR TO PERMIT REPAIRS OF PVT OWNED BOATS.
- 197 Z-69-24(2), 3/5/69, 69-1-2, DBC FM RU-2 TO RU-3, W/STIP (TFC-2 & RM-2, AS CONVERTED).
- 198 Z-71-29, 4/6/71, 71-2-2, VAR FOR LOT SIZE TO BUILD A DUPLEX.
- 199 95-03-265.05V, 5/25/95, VAR REAR SB FM 20 FT TO 10 FT, SUBJ TO CONDS.
- 201 Z-70-67, 6/2/70, 70-4-14, VAR TO BUILD A DUPLEX ON 5, 000 SQ FT LOT.
- 202 ADD2002-00115, 10/4/02, ADMIN APRVL TO AMEND CPD TO RELOCATE SWIM POOL, WITH CONDS; FMB-99-05, 2/8/99, 95-01-003.02Z 02.01, DBC FM CPD AND C-1 TO CPD, SUBJ TO CONDS; Z-95-074, 11/6/95, 95-01-003.02Z, DBC FM C-1, RM-2, CP TO CPD, APPV COP W/ OUTDR SEAT, SUBJ TO CONDS; Z-88-149, 6/27/88, 88-6-5, DBC FM C-1 TO CP; Z-62-33, 11/7/62, 62-10-7, VAR SB TO 20.
- 203 FMB-99-38, 10/11/99, 99-07-194.05V 01.01, 3 VARS W COND.
- 206 FMB-02-21, 5/13/02, VAR2002-00003, REAR SB VAR W COND; COP-97-002, 3/6/97, 97-02-105.01A, ADM APPV COP, APPLICANT SUBMITS TO FM BEACH OVERLAY, OR 2802/3244, 1/6/97, MUST DEVELOP PER SP.
- 207 FMB-01-14, 6/4/01, DCI2000-00002, AMEND CPD TO ALLOW PARKING ON PARCEL B W COND; FMB-00-12, 3/13/00, SEZ1999-00028, SPEC EX FOR COP W OUTDOOR SEATING W COND; FMB-97-14, 4/7/97, 96-12-018.03Z, DBC FM RM-2 & C-1 TO CPD FOR 24 UNIT MOTOR INN, SUBJ TO CONDS.
- 208 ADD2002-00089, 9/17/02, ADMIN AMENDMENT TO CPD DENIED; FMB-01-03, 1/22/01, DCI2000-00051, DBC FM C-1 TO CPD W COND; FMB-99-40, 10/11/99, 98-12-212.01S 01.01, SPEC EX FOR COMMERCIAL PARKING LOT W COND.
- 210 ADD2001-00013, 3/5/01, ADMIN APVL TO MOVE 2 UNITS FM PH II TO PH I W COND; FMB-00-09, 2/14/00, 99-09-352.02Z, DBC FM C-1 TO CPD W COND; 95-08-187.02S, 10/12/95, SPEC EX FOR COP W OUTDOOR SEAT W COND.
- 211 Z-80-361, 10/28/80, 80-10-49, VAR FOR LOT WIDTH TO 50FT, LOT SIZE TO 5,000 SQ FT & SIDE SB

ON RIGHT SIDE TO 10'.

- 212 Z-80-284, 9/22/80, 80-9-7, VAR FOR SIDE SB TO 0' & REAR SB TO 0'.
- 213 Z-87-151, 8/24/87, 87-8-3, DBC FM C-1 TO CF-2.
- 214 93-07-08-V-02, 7/8/93, VAR TO ALLOW 3 EXIST PK SP, SUBJ TO CONDS.
- 215 89-11-30-V-7, 12/21/89, VAR FOR ST SB TO HALF ROW +3.91FT, VAR FOR MIN SIDE SB TO 0 FT (BOTH SIDES), VAR FOR MIN REAR SB TO 0', VAR FOR MIN LOT WIDTH TO 46' & VAR FOR LOT AREA TO 5, 670.55 SQ FT; ALL W/STIP & COND.
- 216 ADD2002-00130, 3/3/03, RECONFIG PARKING & ADD GATES W CONDS; OR-3646-2893, 4/15/02, DEV AGR FOR SEAFARERS PLAZA; FMB-02-07, 4/15/02, DCI2000-00047, DBC FM CPD & C-1 TO CPD W COND; ADD2000-00138, 10/17/00, ADMIN APVL FOR ADDT PARKING W COND; PD-95-38, 11/8/95, 95-10-207.13A, ADM AMD TO CPD TO CORRECT LEGAL & ALLOW PORTABLE KIOSK, SUBJ TO CONDS; Z-92-065, 2/1/93, 92-11-17-DCI-2, DBC FM C-1 TO CPD FOR FAST FOOD REST W/DRIVE-THRU, SUBJ TO CONDS; SP-87-68, 11/23/87, 87-11-SP-3, SPEC PER FOR COP, W/COND.
- 217 95-10-266.05V, 12/14/95, VARS REGARDING SBS, LOT AREAS, AND PARKING, W/CONDS.
- 218 95-05-217.05V, 7/13/95, VARS FOR SBS, LOT SIZE AND COVERAGE, SUBJ TO COND; COP-83-13, 4/21/82, SPEC PER FOR COP, ACCEPTED IN BOCC RECORD 4/4/84.
- 219 91-9-12-V-6, 12/12/91, VAR FM SIDE SB TO 3 FT ON (SO SIDE), FM REAR SB TO 5 FT ON (EAST SIDE), FM LOT AREA TO 2, 942 SQ FT, FM REQ LOT WIDTH TO 40 FT, FM PK SP TO ALLOW 0 PK SP & APVD SPEC PER FM ART RD WITHOUT FRONTAGE RD TO 1/2 ROW PLUS 3 FT TOTAL SB FM CENT LINE 33 FT.
- 220 95-04-193.05V, 6/15/95, VARS FOR LOT AREA, PARKING, SIDE SB, STREET SB, LIMITED TO RETAIL SVCS GRP I.
- 221 93-02-04-V-02, 2/4/93, VAR FM REAR SB TO 5 FT & VAR FM ST SB TO 1/2 ROW PLUS 19 FT.
- 222 93-12-16-V-02, 12/16/93, VARS FM REQ PK, ST SB, SIDE SB & REAR SB, SUBJ TO COND, & VAR FM LOT AREA, WIDTH & DEPTH; Z-76-166, 10/11/76, 76-9-3, SPEC PER FOR SALE OF BEER & WINE & COP.
- 223 FMB-97-02, 2/3/97, 96-10-095.05V, VAR FOR 3 SBS, PARKING, SIDE, REAR SB, LTD TO PLAN D; 93-03-04-SP-01, 3/4/93, SPEC PER FOR MODIF OF ST SB (FOR ARTERIAL RD WITHOUT FRONTAGE RD) TO 1/2 ROW PLUS 10 FT (TOTAL SB FM CNTR LINE TO 40 FT), VAR FM ST SB (FOR A LOCAL RD) TO 1/2 ROW PLUS 12 FT, VAR FM SIDE SB TO 2 FT & VAR FM REAR SB TO 15 FT, ALL SUBJ TO CONDS.
- 224 ADD2002-00130, 3/3/03, RECONFIG PARKING & ADD GATES W CONDS; OR-3646-2893, 4/15/02, DEV AGR FOR SEAFARERS PLAZA; FMB-02-07, 4/15/02, DCI2000-00047, DBC FM CPD & C-1 TO CPD W COND; COP2000-00064, 11/2/00, ADMIN APVL FOR COP W OUTDOOR SEATING, LTD TO 3 RESTS, W COND; COP2000-00020, 6/22/00, ADMIN APVL FOR COP W OUTDOOR SEATING IN CONJ W A 4-COP, W COND; 92-2-6-SP-3, 2/6/92, SPEC PER FOR OUTDOOR SEATING W COND; COP-91-005, 2/26/91, ADMIN APVL FOR COP W COND; BZA-88-341, 11/21/88, 88-11-24, VAR FOR MIN SIDE SB TO 0 (EXIST BLDG) & VAR FOR PK SP TO 8 EXIST PK SP, W COND; SP-87-65, 11/30/87, 87-10-SP-10, SPEC PER FOR MODIF OF ST SB TO HALF ROW + 25'; Z-77-57, 3/14/77, 77-2-15, SPEC PER FOR COP OF BEER & WINE.
- 225 FMB-99-39, 10/11/99, 99-08-007.05V, VAR TO ALLOW TRELIS OVER EXISTING DECK 74 FT SEAWARD OF 1988 CCCL W COND.
- 226 FMB-97-43, 12/15/97, 97-08-145.03V, SIGN VAR W/CONDS.
- 227 Z-80-278, 9/22/80, 80-9-1, DBC FM C-1 TO CC, VAR FOR LOT WIDTH TO APPROX 48' & DEPTH TO APPROX 45'.
- 228 95-05-099.03V, 7/6/95, SIGN SB VAR TO ZERO FT.
- 229 FMB-97-44, 12/15/97, 97-04-188.03V, VARS FOR SIGNS, FOR SB, W/COND; 91-8-8-SP-1, 8/8/91, SPEC PER FOR COP, SUBJ TO COND.
- 230 95-07-161.02S, 9/28/95, SPEC PER FOR COP W/ OUT SEAT, VAR FOR 6 SPACES PARKING, ALL SUBJ TO CONDS.
- 231 ADD2002-00089A, 12/19/03, ADMIN AMENDMENT TO CPD DENIED; FMB-01-03, 1/22/01, DCI2000-00051, DBC FM C-1 TO CPD W COND
- 232 91-4-25-V-1, 4/25/91, VAR FOR LOT WIDTH TO 41' & VAR FOR LOT AREA TO 6,042 SQ FT.
- 233 BZA-87-251, 12/21/87, 87-12-20, VAR FOR MIN SIDE SB TO 5'.
- 234 FMB-01-02, 1/22/01, VAR2001-00071, VAR FOR MIN LOT WIDTH TO 62.5 FT W COND.
- 235 BZA-87-245, 12/21/87, 87-12-14, VAR FOR MIN LOT WIDTH TO 57'.
- 236 FMB-01-11, 5/14/01, VAR2001-00014, VAR TO ALLOW 15 FT ST SB FOR ADDITION W COND.

- 237 FMB-99-13, 3/8/99, 98-11-161.02V 01.01, NONCONFORMITY OF DOCKING FACILITY ACKNOWLEDGED, EXPANSION DENIED.
- 238 ASV-94-006, 12/5/94, ADM SB VAR, W/COND; 94-06-16-V-01, 7/14/94, VAR WAT SB TO 13'4"; 92-9-10-V-2, 9/10/92, VAR WAT SB TO 13.5 FT W/COND.
- 240 92-12-17-V-2, 12/17/92, VAR FOR LOT AREA TO 5670 SQ FT, FOR LOT WIDTH TO 53 FT & FOR SIDE SB TO 2.5 FT, ALL SUBJ TO CONDS; Z-76-178, 10/11/76, 76-9-18, VAR FOR LOT SIZE FOR ONE HOUSE, W/STIP.
- 241 89-8-10-V-2, 8/10/89, VAR FOR ST SB TO HALF ROW +16', VAR FOR MIN COR LOT (ABUTTING 2 STREETS) SB TO 10' & VAR FOR MIN REAR SB TO 6'.
- 242 92-12-17-V-2, 12/17/92, VAR DIST FOR LOT AREA TO 5670 SQ FT, FOR LOT WIDTH TO 53 FT & FOR SIDE SB TO 2.5 FT, ALL SUBJ TO CONDS.
- 245 FMB-99-13, 3/8/99, 98-11-161.02V 01.01, NONCONFORMITY OF DOCKING FACILITY ACKNOWLEDGED, EXPANSION DENIED.
- 248 ASV-95-011, 6/6/95, 95-05-225.09A, ADM SB VAR, LTD TO 5/26/95 SITE PLAN.
- 249 Z-77-134, 6/13/77, 77-5-19, SPEC PER FOR COP FOR BEER & WINE.
- 250 Z-70-151, 11/3/70, 70-9-3, DBC FM RU-1 TO RU-3A (RS-1 & CT, AS CONVERTED).
- 251 Z-79-87, 4/23/79, 79-4-14, DBC FM RS-1 TO CC, W/STIP.
- 253 FMB-02-43, 12/9/02, COP2002-00106, 2COP FOR REST, W CONDS; Z-76-211/211A 11/8/76, 76-10-20, SPEC PER FOR COP W/STIP & COR OF LEGAL DESC; 100 8-31-61 PASSED BY ZONING BOARD, PASSED BY BOCC 10/3/61, (RU-1 TO BU-1) (RS-1 & C-1, AS CONVERTED).
- 254 93-12-23-SP-01, 12/23/93, SPEC PER FOR OUTDOOR SEATING SUBJ TO CONDS; COP-93-007, 11/1/93, ADMIN APVL FOR COP FOR GROUP III REST & NO OUTDOOR SALES, SERVING OR CONSUMPTION.
- 255 Z-70-113, 8/4/70, 70-6-10, VAR FOR ST SB TO 14' & SOUTH SIDE SB TO 8.8'.
- 256 Z-69-81, 6/4/69, 69-4-10, DBC FM RU-1 TO BU-1A (RS-1 & C-1A, AS CONVERTED).
- 257 Z-81-68, 2/23/81, 81-2-24, VAR FOR LOT SIZE TO 4, 450 SQ FT (LOTS 15, 16, 17, 19 & 20), 5, 000 SQ FT (LOT 18) & 4000 SQ FT (LOTS 8 & 9), W/STIPS.
- 258 FMB-97-36, 9/9/97, 97-07-226.05V, PARKING VAR W COND.
- 259 FMB-01-34, 10/15/01, VAR2001-00037, VAR FM SIDE AND REAR YD SB W COND.
- 260 92-12-10-V-2, 12/10/92, VAR FOR ST SB TO 1/2 ROW PLUS 14 FEET; Z-81-68, 2/23/81, 81-2-24, VAR FOR LOT SIZE TO 4, 450 SQ FT (LOTS 15, 16, 17, 19 & 20), 5, 000 SQ FT (LOT 18) & 4000 SQ FT (LOTS 8 & 9), W/STIPS.
- 262 95-03-258.02S, 6/13/95, SPEC PER FOR OUT SEAT, SUBJ TO CONDS.
- 263 FMB-99-11, 3/8/99, 98-05-223.01S, SPEC EX FOR CMRL PK LOT W/CONDS; 93-10-07-SE-02, 10/7/93, SPEC EX FOR CMRL PK LOT, W/CONDS & VAR TO PK LOT LOC & DESIGN STAND TO USE TEMP PK LOT STDS; SP-87-64, 11/30/87, 87-10-SP-9, SPEC PER TO MODIF ST SB TO HALF ROW + 25.
- 264 Z-81-68, 2/23/81, 81-2-24, VAR FOR LOT SIZE TO 4, 450 SQ FT (LOTS 15, 16, 17, 19 & 20), 5, 000 SQ FT (LOT 18) & 4000 SQ FT (LOTS 8 & 9), W/STIPS.
- 265 Z-79-94, 4/23/79, 79-4-22, VAR FOR SIDE YARD SB W/STIP.
- 270 FMB-02-28, 6/24/02, VAR2002-00010, VAR FOR FENCE/WALL W CONDS.
- 275 Z-69-29, 3/5/69, 69-1-8, DBC FM RU-1 TO BU-1A W/STIPS (RS-1 & C-1A, AS CONVERTED).
- 276 93-11-18-V-03, 11/18/93, VAR FM REQ SB TO 14 FT; Z-81-68, 2/23/81, 81-2-24, VAR FOR LOT SIZE TO 4, 450 SQ FT (LOTS 15, 16, 17, 19 & 20), 5, 000 SQ FT (LOT 18) & 4000 SQ FT (LOTS 8 & 9), W/STIPS
- 277 93-08-12-V-02, 8/12/93, VAR FM ST SB TO 13.6 FT & VAR FM WAT SB TO 12 FT, SUBJ TO CONDS.
- 278 93-03-04-V-02, 3/4/93, VAR FM SIDE SB TO 2.5 FT, SUBJ TO CONDS.
- 279 Z-81-68, 2/23/81, 81-2-24, VAR FOR LOT SIZE TO 4, 450 SQ FT (LOTS 15, 16, 17, 19 & 20), 5, 000 SQ FT (LOT 18) & 4000 SQ FT (LOTS 8 & 9), W/STIPS.
- 280 ASV-96-012, 3/19/97, 96-08-175.09A, ADM SB VAR FOR DECK, SUBJ TO CONDS; FMB-97-09, 3/17/97, 96-08-175.02S, SPEC PER FOR COP/OUTDOOR SEATING, SUBJ TO CONDS;
- 281 Z-72-33, 3/7/72, 72-1-1, DBC FM RU-1 TO BU-1A (RS-1 & C-1A, AS CONVERTED).
- 282 Z-69-171, 12/2/69, 69-10-8, DBC FM RU-1 TO BU-1A (RS-1 & C-1A, AS CONVERTED).
- 283 Z-69-33, 3/5/69, 69-1-12, DBC FM RU-1 TO RU-2, W/STIP (RS-1 & TFC-2, AS CONVERTED).
- 284 Z-89-016, 2/27/89, 89-1-12, DBC FM TFC-2 & RS-1 TO CF-2.
- 286 FMB-02-44, 12/9/02, COP2002-00084, COP W/OUTDOOR SEAT W/COND; 94-09-29-SP-04, 9/29/94, COP

W/OUTDOOR SEAT W/COND.

- 288 90-9-27-V-4, 1/24/91, VAR FM REQ SIDE SB TO 10 FT, FM REQ REAR SB TO 22 FT, FM REQ PK SPACES, ALSO SPEC PER FOR MODIF OF ST SB ROW TO 1/2 ROW PLUS 11 FT (TOTAL SB FM CNTR LINE TO 36 FT) ALL VAR & SPEC PER SUBJ TO COND.
- 289 92-12-3-V-1, 12/3/92, VAR TO ALLOW EXISTING PARKING, SUBJ TO CONDS.
- 290 FMB-96-27, 10/21/96, 96-07-178.04S, SPEC PER FOR COP W/OUTDOOR SEAT SUBJ TO COND; ZB-84-229/229A, 10/22/84, 84-10-14, SPEC EX FOR COP & VAR FOR MIN DEPTH TO 80'.
- 291 BZA-88-340, 11/21/88, 88-11-23, VAR FOR MIN SIDE SB TO 6" & VAR FOR MIN REAR SB TO 1.2', W/COND.
- 292 FMB-00-14, 3/13/00, COP2000-00001, 2 COP W/OUTDOOR SEATING W COND.
- 293 95-10-232.04S, 12/21/95, SPEC PER FOR COP W/OUTDOOR SEATING, SUBJ TO CONDS; Z-81-300, 6/22/81, 81-6-38, VAR FOR ACCESS STRUCT IN FR 50% OF LOT.
- 294 92-12-3-V-2, 12/3/92, VAR TO ALLOW EXISTING PARKING, SUBJ TO CONDS.
- 295 FMB-00-41, 12/11/00, DCI2000-00060, AMENDED CPD DENIED; FMB-99-26, 6/21/99, 99-03-069.02Z, AMEND CPD TO ADD PARKING AS PERMITTED USE; Z-93-065, 10/4/93, 93-08-31-DCI-03, DBC FM RS-1 TO CPD, SUBJ TO CONDS.
- 297 95-10-173.02S, 12/7/95, SPEC PER FOR COP W/ OUTDOOR SEATING, SUBJ TO CONDS; BZA-88-339, 11/21/88, 88-11-22, VAR FOR MIN PK SP TO 0.
- 298 FMB-01-15, 6/4/01, COP2001-00044, SPEC PER FOR COP W/ OUTDOOR SEATING IN CONJ W AN EXISTING 4 COP, W/COND; COP-98-004, 10/19/98, 98-09-116.01A, ADM COP W/COND.
- 299 SP-88-43, 7/11/88, 88-7-SP-5, SPEC PER FOR MODIF OF ST SB TO HALF ROW + 25' (TOTAL SB FM C/L TO 50').
- 301 95-04-056.05V, 6/8/95, VARS FOR LOT AREA, DEPTH AND SBS, SUBJ TO COND.
- 303 ZAB-84-8, 2/20/84, 84-1-8, DBC FM C-1 & RM-2 TO RM-10, W/SPEC EX CHURCH/CHURCH RELATED FAC, VAR FOR MIN PK SP TO 258 (JOINT USE OF OS/OFF-ST PK), VAR FOR MIN AREA TO 1.96 AC & SPEC EX FOR A SIGN.
- 304 Z-69-41, 3/5/69, 69-1-21, DBC FM RU-1 800 TO BU-1A (RS-1 800 & C-1A, AS CONVERTED).
- 305 FMB-97-03, 2/3/97, 96-10-023.05V, VAR FOR PARK FOR DENTIST; FMB-96-34, 12/2/96, 96-10-023.05V, VARS FOR PARKING, SEE RESO.
- 307 ORIGINAL C-1 ZONING, AFTER CONVERSION FROM BU-1 & BU-2A.
- 310 Z-69-150, 11/4/69, 69-7-17, DBC FM RU-1 800 TO RU-3 1000 FOR GARDEN APTS; RESOL LEGAL AMENDED (RS-1 800 & RM-2 1000, AS CONVERTED).
- 318 89-5-18-V-8, 5/18/89, VAR FM MIN REQ SIDE SB TO 1' & VAR FM MIN REQ WTRBY SB TO 20'.
- 319 Z-66-32, 5/25/66, 66-4-1, DBC FM RU-1 1200 SQ FT TO RU-1 800 SQ FT & RU-2 1200 SQ FT (RS-1 800 & TFC-2 1200, AS CONVERTED).
- 320 ZB-84-119/119A/119AA, 6/4/84, 84-5-5, VAR FOR LOT DEPTH, FRONTAGE & AREA-PER EXHIBIT C & COR OF LEGAL DESC & REQ; Z-66-32, 66-4-1, DBC FM RU-1 1200 SQ FT TO RU-1 800 SQ FT & RU-2 1200 SQ FT (RS-1 800 & TFC-2 1200, AS CONVERTED).
- 323 Z-66-32, 5/25/66, 66-4-1, DBC FM RU-1 1200 SQ FT TO RU-1 800 SQ FT & RU-2 1200 SQ FT (RS-1 800 & TFC-2 1200, AS CONVERTED).
- 324 94-07-14-V-01, 7/14/94, VAR FOR LOT WIDTH TO 50 FT SUBJ TO CONDS.
- 325 ZB-84-119/119A/119AA, 6/4/84, 84-5-5, VAR FOR LOT DEPTH, FRONTAGE & AREA-PER EXHIBIT C & COR OF LEGAL DESC & REQ.
- 327 Z-66-32, 5/25/66, 66-4-1, DBC FM RU-1 1200 SQ FT TO RU-1 800 SQ FT & RU-2 1200 SQ FT (RS-1 800 & TFC-2 1200, AS CONVERTED).
- 329 Z-82-180, 5/24/82, 82-5-12, VAR FOR LOT DEPTH TO 97' ON LOTS 52.B08, 53.18, 53.11, 53.13, 53.24, 53.26 & 53.3, ALSO VAR FOR LOT WIDTH TO 68' ON LOT 53.17.
- 330 ZB-84-119/119A/119AA, 6/4/84, 84-5-5, VAR FOR LOT DEPTH, FRONTAGE & AREA-PER EXHIBIT C & COR OF LEGAL DESC & REQ.
- 331 Z-71-69, 6/1/71, 71-4-11, DBC FM RU-1 1200 TO RU-1 900 & RU-2, VAR ON LOT SIZE (RS-1 900 & TFC-2, AS CONVERTED).
- 332 Z-82-138, 4/26/82, 82-4-13, VAR FOR MIN LOT AREA TO 90'; Z-71-69, 6/1/71, 71-4-11, DBC FM RU-1 1200 TO RU-1 900 & RU-2, VAR ON LOT SIZE (RS-1 900 & TFC-2, AS CONVERTED).
- 333 Z-82-180, 5/24/82, 82-5-12, VAR FOR LOT DEPTH TO 97' ON LOTS 52.B08, 53.18, 53.11, 53.13, 53.24, 53.26 & 53.3, ALSO VAR FOR LOT WIDTH TO 68' ON LOT 53.17; Z-66-32, 5/25/66, 66-4-1, DBC FM RU-1 1200 SQ FT TO RU-1 800 SQ FT & RU-2 1200 SQ FT (RS-1 800 & TFC-2 1200, AS CONVERTED).

- 334 94-04-14-V-01, 4/14/94, CARPORT SB VAR FM 7.5 FT TO 3 FT SUBJ TO CONDS; 92-12-17-VDK-1, 2/11/93, RIPARIAN SETBACK VAR FOR DOCK FM 25 TO 5 FT SUBJ TO CONDS.
- 335 Z-82-180, 5/24/82, 82-5-12, VAR FOR LOT DEPTH TO 97' ON LOTS 52.B08, 53.18, 53.11, 53.13, 53.24, 53.26 & 53.3, ALSO VAR FOR LOT WIDTH TO 68' ON LOT 53.17.
- 336 ZB-84-119/119A/119AA, 6/4/84, 84-5-5, VAR FOR LOT DEPTH, FRONTAGE & AREA-PER EXHIBIT C & COR OF LEGAL DESC & REQ; Z-71-69, 6/1/71, 71-4-11, DBC FM RU-1 1200 TO RU-1 900 & RU-2, VAR ON LOT SIZE (RS-1 900 & TFC-2, AS CONVERTED).
- 337 ZB-84-119/119A/119AA; 6/4/84, 84-5-5, VAR FOR LOT DEPTH, FRONTAGE & AREA-PER EXHIBIT C & COR OF LEGAL DESC & REQ.
- 338 Z-74-27, 1/30/74, 69-8-8, SPEC PER FOR A DENTAL OFFICE, W/COND.
- 340 ZB-84-119/119A/119AA, 6/4/84, 84-5-5, VAR FOR LOT DEPTH, FRONTAGE & AREA-PER EXHIBIT C & COR OF LEGAL DESC & REQ; Z-71-69, 6/1/71, 71-4-11, DBC FM RU-1 1200 TO RU-1 900 & RU-2, VAR ON LOT SIZE (RS-1 900 & TFC-2, AS CONVERTED).
- 341 ZB-84-118, 5/29/84, 84-4-46, VAR TO ALLOW A POOL PATIO CLOSER TO ST ROW LINE THAN PRINCIPAL BLDG & VAR FM REQ FENCES OUTSIDE FR BLDG LINE LMTD TO MAX HGT OF 4'.
- 342 ASV-95-22, 10/25/95, 95-10-024.09A, ADM APPV FOR SB VAR TO FRONT 420 SQ FT OF PROPERTY (SEE LEGAL), SUBJ TO SP ONLY.
- 343 FMB-02-04, 1/14/02, DCI2001-00029, DBC FM RS-1 & RM-2 TO RPD SUBJ TO CONDS; Z-69-150, 11/4/69, 69-7-17, DBC FM RU-1 800 TO RU-3 1000 FOR GARDEN APTS, RESOL LEGAL AMENDED (RS-1 800 & RM-2 1000, AS CONVERTED).
- 345 Z-73-225, 12/10/73, 73-11-5, DBC FM RU-1 TO RU-4 FOR CONST OF CONDO UNITS, SLO (RS-1 & RM-2, AS CONVERTED); Z-64-80, 9/30/64, 64-8-15, SPEC PER FOR BOAT STORAGE, DRY DOCKING, EXTENSION OF BOAT RUNWAYS, MAKING REPAIRS & ERECTING 5' DECORATIVE WALL AROUND PROP FACING EXIST HOMES W/COND.
- 346 FMB-97-06, 2/27/97, 96-02-186.02S, SPEC PER MODIF APVD FOR EXPANDED COP; FMB-96-20, 7/15/96, 96-02-186.02S, SPEC PER MODIF DENIED FOR EXPANDED COP; FMB-96-11, 4/18/96, 96-02-186.02S, SPEC PER MODIF DENIED FOR EXPANDED COP; 94-12-22-SP-1, 12/22/94, SPEC PER FOR COP W/ OUTDOOR SEAT, SUBJ TO CONDS; Z-73-225, 12/10/73, 73-11-5, DBC FM RU-1 TO RU-4 FOR CONST OF CONDO UNITS, SLO (RS-1 & RM-2, AS CONVERTED); Z-64-80, 9/30/64, 64-8-15, SPEC PER FOR BOAT STORAGE, DRY DOCKING, EXTENSION OF BOAT RUNWAYS, MAKING REPAIRS & ERECTING 5' DECORATIVE WALL AROUND PROP FACING EXIST HOMES W/COND.
- 347 ZB-85-312, 10/29/85, 85-10-40, VAR FM REQ MIN SB FM CANAL OR WTRBY TO 22'.
- 348 Z-77-165, 7/11/77, 77-6-9, SPEC PER FOR 1 KITCHEN & 2 BATHROOMS UPSTAIRS, 1 KITCHEN & 3 BATHROOMS DOWNSTAIRS.
- 349 ASV-94-002, 12/5/94, ADM SB VAR, W/COND.
- 351 ZB-82-518, 12/27/82, 82-12-32, VAR FM REQ MIN LOT DEPTH TO 82' & FM REQ MIN REAR SB TO 15'.
- 352 Z-73-156, 9/10/73, 73-8-14, SPEC PER FOR 1 CHAIR BEAUTY SHOP & RENTAL OF 2 GUEST ROOMS, W/COND.
- 353 Z-76-99, 6/14/76, 76-5-22, DBC FM RU-1 800 TO RU-2 W/SP FOR A PROF OFFICE FOR RES DESIGN/CONST CONSULTANT (RS-1 800 & TFC-2, AS CONVERTED).
- 354 Z-75-172, 8/11/75, 75-7-5, DBC FM RU-1 TO RU-3 FOR A MOTEL (RS-1 & RM-2, AS CONVERTED).
- 355 Z-73-225, 12/10/73, 73-11-5, DBC FM RU-1 TO RU-4 FOR CONST OF CONDO UNITS, SLO (RS-1 & RM-2, AS CONVERTED); Z-64-80, 9/30/64, 64-8-15, SPEC PER FOR BOAT STORAGE, DRY DOCKING, EXTENSION OF BOAT RUNWAYS, MAKING REPAIRS & ERECTING 5 W/COND.
- 356 Z-72-59, 4/4/72, 72-2-6, VAR FOR APT UNDER PILING HOME.
- 358 Z-68-135, 12/11/68, 68-10-3, DBC FM RU-1 TO RU-3, SUBJ TO APVL OF FNL PLANS (RS-1 & RM-2, AS CONVERTED).
- 359 Z-74-231, 7/8/74, 74-6-20, SPEC PER TO BUILD ADDN, W/COND & NO RENTAL OF ANY KIND.
- 360 FMB-01-06, 2/12/01, DCI2000-00078, AMEND PUBLIX CPD W CONDS; FMB-98-11/11A, 5/5/98, 96-02-186.02Z, DBC FM RM-2 TO CPD FOR 28,000 SQ FT PUBLIX, SUBJ TO CONDS; Z-73-225, 12/10/73, 73-11-5, DBC FM RU-1 TO RU-4 FOR CONST OF CONDO UNITS, SLO (RS-1 & RM-2, AS CONVERTED); Z-64-80, 9/30/64, 64-8-15, SPEC PER FOR BOAT STORAGE, DRY DOCKING, EXTENSION OF BOAT RUNWAYS, MAKING REPAIRS & ERECTING 5 W/COND.
- 361 90-11-15-V-4, 11/15/90, VAR FM WAT SB TO 5 FT, LMT TO 2ND FLOOR OF RES ADJ TO SLIP.
- 362 Z-79-298, 11/26/79, 79-11-5, DBC FM RS-1 TO RM-2 & VAR FOR SIDE SB W/COND DENS SHALL NOT EXCEED 3 DWELLING UNITS.
- 363 Z-71-137, 9/7/71, 71-7-18, DBC FM RU-1 TO RU-3 (RS-1 & RM-2, AS CONVERTED).

- 364 89-4-13-V-3, 5/4/89, VAR FM MIN REQ WTRBY SB TO 5' W/COND; BZA-87-243, 12/21/87, 87-12-12, VAR FM REQ MIN LOT DEPTH TO AVG OF 88'.
- 365 FMB-00-37a, 10/9/00, VAR2000-00047, VAR FOR 7.5 FT SB FM ROW FOR SWIMMING POOL W COND.
- 369 ZB-82-303, 8/23/82, 82-8-16, SPEC EX FOR HOME OCC FOR MAIL DROP & TELEPHONE ONLY W/COND.
- 371 FMB-02-04, 1/14/02, DCI2001-00029, DBC FM RS-1 & RM-2 TO RPD SUBJ TO CONDS.
- 372 FMB-02-26, 6/24/02, VAR2002-00013, SB VARIANCES W CONDS.
- 373 FMB-00-18, 5/8/00, VAR2000-00010, VAR TO PERMIT A WATERBODY SB OF 7 FT 6 IN FOR ACCESS STR W CONDS.
- 374 Z-79-351, 1/21/80, 79-12-29, VAR FOR LOT SIZE & 10' FR & REAR SB.
- 375 Z-66-42, 6/15/66, 66-5-1, DBC FM RU-2 TO RU-3 (TFC-2 & RM-2, AS CONVERTED).
- 376 FMB-02-08, 2/11/02, VAR2001-00045, SB VARS TO 2.5 FT SIDE, 17.1 FT REAR, 19.4 FT FM PALMETTO ST, W CONDS.
- 377 89-6-1-V-2, 7/13/89, SIDE SB VAR TO 4' FOR EXIST STAIRS ONLY, W/COND; Z-72-130, 7/11/72, 72-5-12, VAR FOR LOT SIZE.
- 378 Z-72-130, 7/11/72, 72-5-12, VAR FOR LOT SIZE.
- 379 FMB-98-10/10A, 4/20/98, 95-04-118.02Z, DBC FM RM-2 TO CPD FOR SANDBAR, SUBJ TO CONDS; Z-95-072, 12/18/95, 95-04-118.02Z, DENIAL OF DBC FM RM-2 TO CPD, ORIG ZONING RM-2 REMAINS; 93-12-09-SP-02, 12/23/93, SPEC PER FOR COP & OUTDOOR SEATING, SUBJ TO CONDS; Z-77-31, 2/14/77, 77-1-7, VAR IN LOT SIZE, TO BE 90
- 380 Z-76-127, 8/9/76, 76-7-4, SPEC PER FOR A DAY CARE NURSERY W/COND; Z-69-149, 11/4/69, 69-6-18, VAR TO ALLOW EXIST SFR TO BE REMODELED INTO TRIPLEX.
- 383 Z-70-158, 11/3/70, 70-9-15, VAR IN LOT SIZE.
- 384 Z-77-271, 12/12/77, 77-11-3, VAR IN LOT SIZE FOR A DUPLEX.
- 386 Z-77-135, 6/13/77, 77-5-21, VAR FOR DUPLEX ON SUBSTD LOT, W/COND.
- 388 90-1-11-V-3, 1/11/90, VAR TO 50 FT FOR LOT WIDTH & TO 5,000 SQ FT FOR LOT AREA, W/COND..
- 389 Z-80-425, 12/22/80, 80-12-12, VAR TO 5,000 SQ FT LOT AREA FOR DUPLEX.
- 390 Z-80-433, 12/22/80, 80-12-21, VAR TO 5,000 SQ FT LOT AREA FOR DUPLEX.
- 392 FMB-02-40, 10/14/02, COP2002-00095, SPEC PER FOR COP & OUTDOOR SEATING, W CONDS; FMB-02-12, 9/17/02, VAR2001-00053, VAR FM REQ ST SB AND REQ PARKING.
- 395 FMB-00-41, 12/11/00, DCI2000-00060, DENIAL OF DBC TO CPD.
- 397 FMB-00-41, 12/11/00, DCI2000-00060, DENIAL OF DBC TO CPD.
- 400 3/30/01, AMEND STIP SETTLE AGR; 99-1042-CA-JBR, 2/23/01, STIP SETTLE AGR; FMB-99-27, 7/1/99, 99-05-085.07S, LEG INTERP OF LDC; PD-95-06, 3/20/95, 95-02-206.13A 02.01, SB DEVIATIONS FOR REAR & STREET; Z-72-243, 10/10/72, 72-9-27, DBC FM BU-1, RU-3, RU-3A RU-1 TO BU-4 & RU-4 TO OPERATE UNDER COMMUNITY UNIT PLAN, FOR SLO (C-1, RM-2, CT & RS-1, AS CONVERTED).
- 405 Z-76-37, 3/8/76, 76-2-1, DBC FM GU TO RU-2 (AG-2 & TFC-2, AS CONVERTED).
- 410 FMB 02-37, 10/14/02, VAR2002-00014, VAR FM STREET, REAR, SIDE SB W COND
- 412 91-9-26-V-3, 11/7/91, VAR FM SIDE SB TO 7.5 FT, VAR FM ST SB TO 1/2 ROW PLUS 20 FT & VAR FOR CORNER LOT TO ALLOW 7.5 FT SIDE SB, ALL SUBJ TO CONDS.
- 414 BZA-87-043, 2/16/87, 87-2-19, VAR FOR 25 FT LOT WIDTH W COND.
- 416 Z-75-77, 4/14/75, 75-3-19, DBC FM RU-1 1200 TO MHTP, VAR FOR INCREMENT AC FOR RELOC SPACES IN EXIST TRAILER PK, W/STIPS (RS-1 1200 & MH-2, AS CONVERTED).
- 417 Z-71-20, 2/2/71, 70-12-13, SPEC PER FOR REAL ESTATE OFFICE.
- 419 FMB-01-05, 2/12/01, VAR2000-00077, VAR TO ALLOW 5.3 FT SIDE SB W COND.
- 422 Z-65-4, 1/27/65, 64-12-2, SPEC PER FOR A TRAILER PK.
- 433 BZA-87-017, 1/26/87, 87-1-23 VAR TO ALLOW SHED CLOSER TO ROW THAN MAIN BLDG & VAR TO 0 FT FOR ST SB W/ CONDS.
- 436 ASV-98-009, 8/27/98, 98-07-260.09A, ADM SB VAR W/COND.
- 437 FMB-00-37b, 10/9/00, VAR2000-00029, VAR TO SIDE SB OF 7.5 FT W/ CONDS.
- 438 Z-65-45, 7/28/65, 65-6-7, DBC FM RU-2 TO BU-1 (TFC-2 & C-1, AS CONVERTED).
- 440 FMB-97-37, 9/9/97, 97-08-046.05V, VAR FOR FENCE W/CONDS.

- 442 Z-65-4, 1/27/65, 64-12-2, SPEC PER FOR A TRAILER PK.
- 445 90-1-18-SP-1, 1/18/90, SPEC PER FOR COP W/CONDS; Z-89-074, 9/11/89, 89-7-25-2, DBC FM MH-2 TO CT & VAR TO ALLOW 113 PK SP, W/COND ONLY FOR EXIST USE PER SP-89-74; Z-81-420, 10/19/81, 81-9-24, DBC FM MH-2 TO CT.
- 446 90-7-5-V-2, 7/5/90, VARS FM LOT AREA TO 6,173', FM LOT WIDTH TO 61.73', FM SIDE SB TO 2.5' & FM ST SB TO 1/2 ROW PLUS 18', SUBJ TO CONDS.
- 448 FMB-00-28, 6/29/00, DCI2000-00027, DBC FM TFC-2 TO CPD W COND.
- 449 Z-80-386, 11/24/80, 80-11-11, VAR FOR LOT WIDTH TO 55' & LOT SIZE TO 5,500 SQ FT.
- 450 Z-89-074, 9/11/89, 89-7-25-2, DBC FM MH-2 TO CT & VAR TO ALLOW 113 PK SP ONLY FOR EXIST USE PER SP-89-74, W/COND.
- 451 ASV-95-016, 7/20/95, 95-07-001.09A, ADM REAR SB VAR TO 16 FT, SUBJ TO COND.
- 452 FMB-98-27, 11/9/98, 98-06-228.01Z, DBC FROM MH-2 TO TF-1.
- 453 95-07-003.05V, 8/24/95, VARS FOR LOT WIDTH TO 68 FT & LOT AREA TO 6800 SQ FT, SUBJ TO COND.
- 455 Z-73-94, 6/11/73, 73-5-3, VAR TO BUILD A CHURCH.
- 456 Z-66-32, 5/25/66, 66-4-1, DBC FM RU-1 1200 SQ FT TO RU-1 800 SQ FT & RU-2 1200 SQ FT (RS-1 800 & TFC-2 1200, AS CONVERTED).
- 457 FMB-00-25, 6/19/00, ADM2000-00005, VAR DENIED TO ALLOW LIVING AREA BELOW MIN FLOOD ELEV; Z-82-180, 5/24/82, 82-5-12, VARS FOR LOT DEPTH AND WIDTH, SEE RESO FOR LIST
- 461 FMB-97-45, 12/15/97, 97-09-294.05V, SIDE SB VAR DENIED.
- 462 FMB-01-06A, 3/12/01, ADD2000-00152, CORRECTING WETLANDS BOUNDARY; 89-7-13-V-4, 6/1/89, VAR FM ST SB TO HALF ROW + 15; Z-74-140, 4/8/74, 74-2-35, DBC FM GU TO RU-4, SLO W/LMTD HGT RESTRICTION OF 29 UPA (AG-2 & RM-2, AS CONVERTED).
- 463 90-11-15-V-5, 11/15/90, VAR TO ALLOW 150' LONG DOCK, SUBJ TO COND; Z-74-140, 4/8/74, 74-2-35, DBC FM GU TO RU-4, SLO W/LMTD HGT RESTRICTION OF 29 UPA (AG-2 & RM-2, AS CONVERTED).
- 465 Z-77-56, 3/14/77, 77-2-14, DBC FM GU TO RU-2, VAR IN LOT DEPTH TO 90' (AG-2 & TFC-2, AS CONVERTED).
- 466 Z-77-54, 3/14/77, 77-2-12, DBC FM GU TO RU-2, VAR IN LOT SIZE PERMITTING A 90' DEPTH (AG-2 & TFC-2, AS CONVERTED).
- 468 BZA-88-232, 8/15/88, 88-8-27, VAR FM REQ FOR FENCE OR WALL LOCATED BETWEEN ST ROW OR ESMT & MIN REQ ST SB LINE TO 5'.
- 472 Z-90-083, 11/26/90, 90-9-4-Z-1 DBC FM MH-2 TO RSA.
- 473 BZA-88-367, 12/19/88, 88-12-22, VAR FM MIN REQ WTR SB TO 21' W/COND FOR PROPOSED EXPANSION & VAR TO ALLOW 18' SB FM WTRBY FOR CARPORT ONLY.
- 474 90-7-5-V-1, 7/5/90, VAR FM REQ LOT WIDTH TO 60'.
- 475 Z-71-40, 4/6/71, 71-2-16, DBC FM RU-1 TO RU-2 ON FIRST 150' OF PROP CLOSEST TO ESTERO BLVD, DIVIDED INTO TWO 75' FRONTAGE LOTS, REMAINING LOT STAYS RU-1 (RS-1 & TFC-2, AS CONVERTED).
- 476 Z-71-40, 4/6/71, 71-2-16, DBC FM RU-1 TO RU-2 ON FIRST 150' OF PROP CLOSEST TO ESTERO BLVD, DIVIDED INTO TWO 75' FRONTAGE LOTS, REMAINING LOT STAYS RU-1 (RS-1 & TFC-2, AS CONVERTED).
- 478 89-1-HE-3, 1/12/89, VAR FOR EXIST UTIL SHED, MAY NOT BE ENLARGED OR REBUILT.
- 479 91-3-14-V-3, 3/14/91, VAR FM SIDE SB TO 5', SUBJ TO COND.
- 480 FMB-00-24, 6/5/00, VAR2000-00011, VAR FOR 25 FT LOT WIDTH W/ CONDS.
- 481 Z-69-192, 1/6/70, 69-11-8, DBC FM RU-3 TO BU-1A FOR A RESTAURANT (RM-2 & C-1A, AS CONVERTED).
- 482 93-04-29-SP-03, 4/29/93, SPEC PER FOR COP, SUBJ TO CONDS; ZAB-85-271, 11/12/85, 85-9-38, SPEC EX FOR COP, W/CONDS.
- 483 Z-68-73, 7/3/68, 68-5-14, DBC FM RU-1 TO BU-1A (AG-2 & C-1A, AS CONVERTED).
- 487 FMB-00-40, 11/13/00, CPA2000-00001, COMP PLAN INTERP ON HEIGHT; FMB-00-39, 11/13/00, CPA2000-00001, COMP PLAN INTERP ON WETLANDS & VESTING; Z-70-140/140A, 10/6/70, 70-8-8, SPEC PER FOR MED CNTR & SPEC PER FOR CONVALESCENT/NURSING HOME & COR TO DBC FM RU-1 TO RU-3A W/COND & BU-1A (RS-1, CT, & C-1A, AS CONVERTED).
- 488 FMB-00-25a, 6/12/00, VAR2000-00015, VAR FM WATER SB & REAR SB W COND.

- 489 FMB-00-33, 9/11/00, ADM2000-00024, ADMIN INTERP UPHELD, PD REQUIRED FOR NEW COMM L ACTIVITIES.
- 490 FMB-02-11, 3/11/02, VAR1999-00024, VAR FM WATER SB TO 21.5'.
- 491 FMB-02-16, 4/8/02, VAR2002-00001, VAR FM CCCL PER SITE PLAN, W COND.
- 492 FMB-02-17, 4/8/02, ADM2002-00001, ADMIN INTERP OVERTURNED W COND.
- 493 FMB-02-36, 9/16/02, ADM2002-00011, LDC ADMIN INTERP UPHELD.
- 494 FMB-97-23, 7/7/97, 97-08-063.05V, VAR FM WATER SB TO 15' & SIDE SB TO 1.5' W COND.
- 495 3/30/01, AMEND STIP SETTLE AGR; 99-1042-CA-JBR, 2/23/01, STIP SETTLE AGR; FMB-99-27, 7/1/99, 99-05-085.07S, LEG INTERP OF LDC; FMB-98-32, 12/14/98, 95-02-206.05V 02.01, VAR FM REQUIRED PARK SP; Z-72-243, 10/10/72, 72-9-27, DBC FM BU-1, RU-3, RU-3A RU-1 TO BU-4 & RU-4 TO OPERATE UNDER COMMUNITY UNIT PLAN, FOR SLO (C-1, RM-2, CT & RS-1, AS CONVERTED).
- 496 FMB-99-12, 3/8/99, 98-12-279.01Z 01.01, DBC FM RS-1 TO RM-2 DENIED.
- 497 FMB-99-25, 6/21/99, 99-05-096.05V 01.01, VAR FM WATER SB TO 19.7'.
- 498 FMB-99-30, 8/30/99, 99-09-158.12V, VAR FOR WET FLOODPROOFING.
- 499 FMB-00-06, 1/10/00, VAR1999-00016, VAR FM REAR SB TO 5' W COND.
- 500 FMB-99-32, 7/20/99, 99-05-102-05V, VAR FM FRONT & REAR SBS TO 10' & 9'.
- 501 FMB-02-10/10A, 4/15/02, ADM2001-00013, VAR TO ELIM SPRINKLER SYSTEM; FMB-01-20, 6/25/01, VAR2000-00076, 3 VARS W COND.
- 502 BoA-1, 5/9/77, 77-4-1, VAR FOR MIN SIDE SB TO 5 FT, VAR FOR MIN REAR SB TO 15 FT.
- 503 3/30/01, AMEND STIP SETTLE AGR; 99-1042-CA-JBR, 2/23/01, STIP SETTLE AGR; FMB-99-27, 7/1/99, 99-05-085.07S, LEG INTERP OF LDC; Z-98-34, 12/14/98, 98-03-010.07S, ADMIN INTERPRET IN REF TO HGT OVERTURNED; Z-72-243, 10/10/72, 72-9-27, DBC FM BU-1, RU-3, RU-3A RU-1 TO BU-4 & RU-4 TO OPERATE UNDER COMMUNITY UNIT PLAN, FOR SLO (C-1, RM-2, CT & RS-1, AS CONVERTED).
- 504 COP2002-00013, 3/13/02, ADMIN APVL FOR COP W OUTDOOR SEATING IN CONJ W A 4-COP W COND
- 610 FMB-01-02, 1/22/01, VAR2001-00071, VAR FOR MIN LOT WIDTH to 62.5 FT W COND.
- 613 ORIGINAL AG-2 ZONING, AFTER CONVERSION FROM AG & GU.

RESOLUTION OF THE LOCAL PLANNING AGENCY OF THE
TOWN OF FORT MYERS BEACH, FLORIDA
RESOLUTION NUMBER 2009-24

WHEREAS, the existence of the Local Planning Agency (LPA) is mandated by Florida Statutes Section 163.3174; and

WHEREAS, the Local Planning Agency is statutorily responsible under Chapter 163, Florida Statutes, and the Town of Fort Myers Land Development Code (LDC) Section 34-120 for the review of proposed land development regulations, land development codes, or amendments thereto, and for making recommendations to the Town Council with regard thereto; and

WHEREAS, LDC Section 34-112 provides that the broad objectives of town planning and the Town's creation of the LPA are to further the welfare of the citizens of the town by helping to promote a better, more helpful, convenient, efficient, healthful, safe, and attractive community environment and to insure that the unique and natural characteristics of the island are preserved; and

WHEREAS, LDC Section 34-120 provides that the functions, powers, and duties of the LPA include preparing principles and policies for guiding land use and development in the town in order to preserve the unique and natural characteristics of the island, to overcome the islands present handicaps, and to prevent or minimize future problems; and aid town officials charged with the direction of projects or improvements embraced within the comprehensive plan and generally promote the realization of the comprehensive plan; and

WHEREAS, the Town Comprehensive Plan provides that Goal 4 is "to keep Fort Myers Beach a healthy and vibrant "small town," while capitalizing on the vitality and amenities available in a beach-resort environment and minimizing the damage that a hurricane could inflict"; and

WHEREAS, the Gulf beaches factor significantly throughout the comprehensive plan as an important natural resource, the preservation of which is of the highest importance, according to Comprehensive Plan Policy 4-A-5; and

WHEREAS, Comprehensive Plan Policy 4-A-6 provides that the beaches provide incomparable recreational and environmental benefits to the town; and

WHEREAS, the vast majority of the Gulf beaches are within the "Recreation" Future Land Use Map (FLUM) category of the comprehensive plan; and

WHEREAS, the Recreation Element of the Comprehensive Plan indicates: "The vision for the future of the Town of Fort Myers Beach is a result of the beautiful natural surroundings of beaches and dunes, wildlife habitat, historic and archaeological sites, boating opportunities, and places for people to come together for recreation, visiting, dining, and shopping within the park-like setting of the entire island. The Community Design Element describes how the town can ensure that the physical components of the community (natural areas, open spaces, buildings, streets, paths) can work together to achieve a coherent whole, reinforcing and enhancing its small-town character and as a place where permanent residents coexist comfortably with tourism. Policies emphasize

walkability, promote streets as the neighborhood realm, plan for interconnected foot paths throughout the island, and improve linkages to the town's natural resources and active recreation areas. These linkages and "people-gathering places" become part of the town's system of recreation, open space, and cultural amenities"; and

WHEREAS, Objective 4-B of the Comprehensive Plan is to "reduce the potential for further overbuilding through a new future land use map that protects remaining natural and historic resources, preserves the small-town character of Fort Myers Beach, and protects residential neighborhoods against commercial intrusions"; and

WHEREAS, the LPA finds that the expansion of on-premises consumption of alcoholic beverages onto the Gulf beaches **does not** protect remaining natural resources, and **does not** preserve the small-town character of the Town, and **does not** protect residential neighborhoods against commercial intrusions; and therefore would not accord with Comprehensive Plan Objectives 4-A, 4-B, 4-C, and the applicable policies following thereunder.

NOW THEREFORE BE IT RESOLVED that the LPA **recommends** that the Town Council of the Town of Fort Myers Beach:

does restrict further expansion of on-premises consumption of alcoholic beverages on the Gulf beaches within the Town of Fort Myers Beach.

The foregoing Resolution was adopted by the LPA upon a motion by LPA Member Kay and seconded by LPA Member Weimer and upon being put to a vote, the result was as follows:

Joanne Shamp, Chair	<u>aye</u>	Bill Van Duzer, Vice Chair	<u>aye</u>
Carleton Ryffel	<u>aye</u>	Rochelle Kay	<u>aye</u>
Dennis Weimer	<u>aye</u>	Alan Mandel	<u>nay</u>

DULY PASSED AND ADOPTED THIS 10th day of November, 2009.

LPA of the Town of Fort Myers Beach

By: Joanne Shamp
Joanne Shamp, LPA Chair

Approved as to legal sufficiency:

By: Anne Dalton
Anne Dalton, Esquire
LPA Attorney

ATTEST:

By: Michelle Mayher
Michelle Mayher, Town Clerk

MINUTES
FORT MYERS BEACH
Local Planning Agency Meeting

Town Hall – Council Chambers
2523 Estero Boulevard
Fort Myers Beach, FL 33931

Tuesday, November 10, 2009

I. CALL TO ORDER

Meeting was called to order at 10:42 AM by Chairperson Dennis Weimer. All members were present:

Joanne Shamp
Dennis Weimer
Rochelle Kay
Alan Mandel
Bill Van Duzer
Carleton Ryffel

Staff present: LPA Attorney Anne Dalton; Community Development Director Dr. Frank Shockey. There were no members of the press or public present.

II. PLEDGE OF ALLEGIANCE

III. INVOCATION-Ms. Kay

IV. ADMINISTRATIVE AGENDA

A. Discussion of the Residential ROW Connections

Mr. Van Duzer reported that he and Ms. Shamp met with Cathy Lewis to discuss this issue. Ms. Lewis drafted the document presented to the LPA. Ms. Shamp asked for LPA comments.

Mr. Mandel complimented the report and agreed with the draft. Mr. Van Duzer commented on the portion which refers to permit application fees and pointed out what he thought was an error regarding stake-out of the property. He stated that the fee would not include that but rather the inspection of the stake out. The correction would be that the permit fee would not include the stake-out itself but only the inspection of it. He also commented about the “hold harmless” clause and questioned the need for it in the LDC. Ms. Dalton agreed that it does not need to be in the LDC. Ms. Kay referred to page 2 about “expiration exceptions- permits for apron driveways to be constructed as part of a residential house, construction is exempted” and asked why this particular item is exempted from the expiration exception. Mr. Van Duzer explained and short discussion ensued.

Mr. Ryffel had comments regarding page 3 and commented that the draft is a good job. He referred to the top of the page, specifically the word “separation,” and

thought that it was not needed. He was confused by the wording pertaining to driveway aprons and the distance involved, and stated that the draft does not a method for measuring that distance. Mr. Weimer agreed and some discussion ensued about a method of measure for this.

Ms. Dalton asked if the draft was meant as a policy direction, with staff crafting the exact language. She commented as well about the variance measurement item. Mr. Van Duzer advised that this is just that, a draft for direction. Ms. Dalton then reserved comment for a later time but added that the draft was well done and commended Ms. Shamp and Mr. Van Duzer.

Dr. Shockey commented about the policy about the separation between driveway connections and intersections, pointing out that there are always exceptions and the policy should be in place for that process to be handled administratively, making it easier for the applicant. He also had some comments and concerns about the dimensions of the apron and driveway and a discussion ensued. It was clarified that that 20% referred to in the draft is the maximum, with a minimum of 10%.

Ms. Dalton asked if the LPA will allow the driveway aprons to be made of porous material. Mr. Van Duzer said that this was discussed but that this draft was not the proper place to address this. Mr. Ryffel suggested that that the measurements should include the distance from the centerline of the driveway to the side property line.

After clarification, he retracted this suggestion.

Ms. Shamp commented about “permitting process” on page 1, and is concerned about the use of the word “maintenance” there. There was some discussion about the general maintenance of the driveways.

Ms. Shamp asked for public comment; no public comment. She asked for a general consensus to guide Dr. Shockey for moving ahead with the draft. The first item was the permit fees and Mr. Van Duzer recommended changing page 1 as he previously mentioned. All other members agreed to change the wording. On page 2, #G, “hold harmless” clause, the recommendation was to make reference to an addendum but not to set it out specifically; again, all members agreed. On page 3, remove the word “separation” and then renumbering of 2, 3 4 and 5; all members agreed. As mentioned earlier by Mr. Ryffel, the measuring of the driveway dimensions to be reconsidered by Dr. Shockey. The administrative procedures for variances on narrow lots were discussed and it was agreed that there should be something in place for this; all members agreed. The last point was review of wording regarding handling non-conforming issues; all members agreed.

B. Recommendations to Council regarding Alcoholic Beverage Regulations (Resolution 2009-24)

Ms. Shamp thanked Dr. Shockey for his work on this and asked him to address the meeting. Dr. Shockey referred to the consultant’s report, included in the packets, and stated that it points out that the Town’s LDC contains policy that has not actually been reviewed by the Council but follows the county’s regulations in place at the time LDC Chapter 34 was adopted. He explained that there are things in those guidelines that typically do not actually apply to the beach and that much of it is outdated, needing revision. He said that the Council had specifically asked what the LPA would

recommend about possibly allowing COP on the beach and whether this is something the LPA wants to take action on or let it stay as is. Ms. Dalton referred to a comment about inconsistency between the LDC and state law and pointed out that the state law supersedes Town ordinance.

Ms. Shamp asked for a general consensus for direction of the resolution as a whole. There was a majority consensus that the expansion of COP onto the beach should not be allowed, and Ms. Shamp then asked for individual comments.

Mr. Ryffel said that he would like to see an exemption for the Times Square area and he suggested changing the language in the second page, wherein it states “now therefore be it resolved that the LPA recommends that the Town Council of FMB...” where it has “does and does not,” to say “restrict or not restrict.” Ms. Dalton helped clear this up and there was brief discussion about it.

Mr. Van Duzer said he is in favor of moving this on.

Mr. Mandel stated that the concern was the lack of consistency in handling the issue of approving COP uses in the past and said this should be handled as a whole package, not just the question of COPs on the beach. He feels that the resolution they are talking about would only address a piece of that. Ms. Shamp agreed but reminded that Council advised there were other groups handling some of the other issues such as noise.

Mr. Weimer commented that he is in favor of this resolution but agrees that this only addresses a specific issue. He too realizes that the LPA should be working on additional issues to fairly address the problem.

Ms. Shamp added that this would be taking a step in creating the policy.

She asked Ms. Dalton if the LPA has the authority to continue to establish the policy further. Ms. Dalton researched this.

Ms. Kay disagreed and feels that the LPA has been trying to look at the whole thing as a package and fix it when it is an issue that needs to be revised one piece at a time.

Mr. Van Duzer understands that the Council wants the LPA to take one item at a time, as directed by them, give their recommendations and send it back to be looked at by them. He agrees that this is the way it should be done.

Ms. Dalton now referred to the LDC sections which apply to the authority to establish the policy, as she read the sections. She then explained what each section means to the LPA authority and responsibilities and reminded that the code does not preclude the LPA from initiating policy, but that if not given specific direction to do so by the Council, then it may turn out to be unnecessary effort. Discussion ensued regarding authority, consultants, etc.

Mr. Weimer stated that this item has been on the agenda for more than 2 years, to review the LDC modifications that had not yet been addressed. Last year there was a consultant actually hired to take a look and give recommendations, with additional items included by the town manager at the time. He said the initiative came from the Town Council, originally, over 2 years ago.

Ms. Shamp asked for public comment; no public comment.

Motion: Ms. Kay moved to accept the resolution, changing the words on the second page

wherein it states “whereas the LPA finds that the expansion of the on premises consumption of alcoholic beverages onto the gulf beaches does not protect remaining natural resources and does not preserve the small town character of the Town, and does not protect residential neighborhoods against commercial intrusions, and therefore would not accord the comprehensive plan objectives, etc.” “Now therefore be it resolved that the LPA recommends that the Town Council for the Town of Fort Myers Beach does restrict further expansion of on premises consumption of alcoholic beverages on the gulf beaches in the Town of Fort Myers Beach.”

Seconded by Mr. Weimer;

Vote: Motion passed 5-1 with Mr. Mandel opposing.

V. ADJOURN AS LPA; RECONVENE AS HPB

Adjourned as LPA at 11:52 am

Motion: Mr. Weimer moved to adjourn as the LPA and reconvene as the HPB.

Seconded by Mr. Van Duzer;

Vote: Motion passed 6-0

Ms. Kay called the meeting to order at 11:52 with all members present.

Ms. Kay advised the Historic Committee will meet next week to discuss the next step on the plaque program and other ongoing matters. She also reported that there is no news regarding budget suggestions they are developing.

With no further comment, the meeting was adjourned.

Motion: Mr. Van Duzer moved to adjourn as the HPB and reconvene as the LPA;

Seconded by Mr. Weimer;

Vote: Motion passed 6-0

Meeting adjourned at 11:54 PM

VI. ADJOURN AS HPB; RECONVENE AS LPA

Ms. Shamp reconvened the meeting at 11:54 PM with all members present.

VII. LPA MEMBER ITEMS AND REPORTS

Mr. Weimer, nothing to report.

Mr. Mandel, nothing to report.

Mr. Van Duzer asked if anyone has applied for the available positions on the LPA.

Ms. Dalton advised that there is an item about this on the Council agenda but didn't know exactly what it means, whether it is a placeholder or if there are actually applicants. Mr. Van Duzer said he had 3 interested people and wanted to follow up with them. After checking, Ms. Dalton advised that Chuck Moorefield has applied and is under consideration.

Ms. Kay, nothing to report.

Mr. Ryffel, nothing to report.

Ms. Shamp asked Dr. Shockey about the Newton demolition item on the Council agenda. He said this is a part of the process for demolition that the HPB included as a condition in the resolution for the certificate of appropriateness and the Council will

be looking at taking that step.

VIII. LPA ATTORNEY ITEMS

Nothing to report except that the next meeting will be the Christmas lunch. Ms. Kay will do an ornament for the LPA for the trees.

IX. COMMUNITY DEVELOPMENT DIRECTOR ITEMS

Dr. Shockey reported that he put together a schedule of LPA meeting dates and times, second Tuesday of the month at 9:00 AM from now on, except the next meeting on December 15, which is the third Tuesday.

X. LPA ACTION ITEMS

Resolutions to Town Council:

- Animal Control-long term - Mr. Mandel: January 4, 2010
- Gulfview TBD sometime after vacation ordinance
- Vacation ordinance, continuation of first hearing-December 21, 2009 at 6:30 PM
- Pink Shell-12/7/09 at 9:00 AM - Mr. Weimer or Ms. Kay
- Alcoholic beverages-COP expansion on the beach-Ms. Kay

Continued LPA hearings:

- Shipwreck - Jan. 12, 2010

Future Work Activites:

- Resolution LPA 2009-XX Recognition of Dennis Weimer's service
- Present ROW resolution to Council-2/9/2010
- Storm Water-pending; Dr. Shockey/Kay/Van Duzer-TBD
- Seasonal Parking- 12/15/09; final review
- Alcoholic Beverages-Dr. Shockey/Mr. Weimer (Discussion ensued as to whether or not to proceed on the other items in this issue other than the COP on the beach – Ms. Shamp polled the members to see who agrees that this should be removed from the list unless asked to proceed by Council. All agreed to temporarily remove this item until directed by Council.
- HPB Vistas – Budget Proposal - Ms. Shamp; 12/15/09

XI. PUBLIC COMMENT

Mr. Melsek expressed his disappointment in the LPA's "timidity" in not continuing with the COP discussion. He stated that the LPA has a responsibility to recommend these changes for the beach and he was especially concerned with the issue of the noise connected with this problem. He opined that the LPA should address this.

Ms. Shamp asked for a motion to adjourn.

Motion: Mr. Ryffel moved to adjourn.

Seconded by Ms. Kay;

Vote: Motion carried 6-0.

XII. ADJOURNMENT

Adjourned at 12:17 PM.

Next meeting December 15, 2009 at 9:00 AM

Adopted _____ with/without changes. Motion by _____
(DATE)

Vote: _____
Joanne Shamp, LPA Chair

- End of document